


\$73.75



2014 NATIONAL HOME IMPROVEMENT ESTIMATOR

Edited by Ray F. Hicks



Includes inside the back cover:

Inside the back cover of this book you'll find a software download certificate. To access the download, follow the instructions printed there. The download includes the National Estimator, an easy to-use estimating program with all the cost estimates in this book. The software will run on PCs using Windows XP, Vista, 7 or 8 operating systems.

Quarterly price updates on the Web are free and automatic all during 2014. You'll be prompted when it's time to collect the next update. A connection to the Web is required.

Download all of Craftsman's most popular costbooks for one low price with the Craftsman Site License. <http://CraftsmanSiteLicense.com>



- Turn your estimate into a bid.
- Turn your bid into a contract.
- ConstructionContractWriter.com



Craftsman Book Company
6058 Corte del Cedro, Carlsbad, CA 92011

Acknowledgments

Portions of chapters 8, 9 and 15 first appeared in the book *Renovating & Restyling Older Homes* by Lawrence Dworin. Mr. Dworin served as a resource in the development of this manuscript and contributed many valuable insights from his years of experience in the industry. An order form for *Renovating & Restyling Older Homes*, and his other construction reference *Profits in Buying & Renovating Homes* appears on the final pages of this manual.

Looking for other construction reference manuals?

Craftsman has the books to fill your needs. **Call toll-free 1-800-829-8123** or write to Craftsman Book Company, 6058 Corte del Cedro, Carlsbad, CA 92011 for a **FREE CATALOG** of over 100 books, including how-to manuals, annual cost books, and estimating software. Visit our Web site: <http://www.craftsman-book.com>

SAMPLE

Contributing Editor: *Walter James O'Brien*
Cover design by: *Bill Grote*
Graphics by: *Devona Quindoy and Christal Stimpson*
Production Manager: *Christine Bruneau*
Layout by: *Christine Bruneau*
Software production: *Timothy Campbell*

© 2013 Craftsman Book Company
ISBN 978-1-57218-294-3
Published November 2013 for the year 2014.


Contents

1 Pricing Home Improvement Jobs5	7 Roofing and Flashing117
This book works two ways8	Flashing leaks118
Craft codes and crews15	Roof repairs121
Area modification factors18	Roofing material122
2 Demolition27	<i>Cost estimates</i>
Before you begin27	Roof repairs129
<i>Cost estimates</i>	Composition shingles130
Equipment rental28	Built-up roofing131
Sitework demolition29	Roof patching134
Building demolition30	Wood shingle roofing137
Wood framing demolition33	Slate and tile roofing139
3 Foundations and Slabs37	Roof flashing141
Pre-construction checklist38	Gutters and downspouts146
<i>Cost estimates</i>	8 Windows147
Equipment rental39	Window repair149
Concrete flatwork40	Sash repair151
Concrete finishing49	Counterweighted windows152
4 Rough Carpentry53	Adding or moving a window153
Floor beams53	<i>Cost estimates</i>
Wood floor repairs56	Window repairs156
Wall framing57	Vinyl windows157
Roof repairs58	Aluminum windows161
<i>Cost estimates</i>	Wood windows164
Framing repairs62	Storm windows166
Framing room additions64	Window accessories166
Subflooring66	Window glazing170
Wall and ceiling changes70	Skylights173
Roof framing changes75	9 Doors175
5 Insulation and Moisture Control79	Door repair and replacement175
Ceiling insulation79	Adding or moving a door182
Wall and floor insulation80	Hanging a slab door184
Attic and roof ventilation83	Door terms188
<i>Cost estimates</i>	<i>Cost estimates</i>
Fiberglass insulation84	Exterior doors191
Panel insulation85	Prehung doors197
Vapor barrier87	Screen and storm doors202
Vents and louvers88	Interior doors206
Roof ventilators91	Patio doors214
6 Siding and Trim93	Closet doors218
Vinyl siding installation96	Garage doors223
Wood siding installation97	10 Walls and Ceilings227
Estimating procedure for siding104	Drywall installation228
Masonry fireplaces104	Wood paneling235
<i>Cost estimates</i>	Removing partitions239
Siding and soffit repairs105	<i>Cost estimates</i>
Vinyl siding107	Drywall242
Wood board siding108	Textured finishes for drywall244
Texture 1-11 plywood siding111	Drywall bead and tools247
Fiber cement siding112	Wall paneling251
Aluminum siding and soffit113	Suspended ceilings255
Stucco and masonry siding114	Moldings259
	Partition walls270

11 Floors and Tile	271	16 Porches and Decks	445
Wood flooring installation	272	Adding a porch	446
Ceramic tile installation	276	Elevated decks	448
<i>Cost estimates</i>		<i>Cost estimates</i>	
Wood strip and plank flooring	278	Deck lumber	452
Laminate plank flooring	283	Alternative deck materials	454
Vinyl flooring	286	Porch and deck stairs	457
Ceramic tile	293	Pool replastering	459
Natural stone and slate flooring	298	Spa replastering	460
Ceramic field wall tile	301	17 Painting and Finishing	461
Carpet	308	Paint application techniques	464
12 Kitchens	309	<i>Cost estimates</i>	
Kitchen cabinet standards	312	Labor estimates for painting	466
<i>Cost estimates</i>		Stains and finishes	487
Kitchen demolition	315	Wood preservatives	490
Cabinets and countertops	317	Interior paints	492
Cabinet knobs, pulls and hinges	324	Exterior paints	494
Sinks and faucets	328	18 Earthquake Damage	497
Appliances	339	Types of damage	497
13 Bathrooms	345	What FEMA recommends	499
Bathroom additions	345	When making alterations	504
<i>Cost estimates</i>		When adding a room	505
Tubs, enclosures and shower stalls	352	Checking for earthquake damage	505
Tub and shower faucets	360	Repair of foundations and floor slabs	506
Toilets	362	Framing repairs	508
Lavatory sinks	367	Cracks in plaster and stucco	509
Vanity cabinets and countertops	374	Fireplaces and chimneys	510
Bath exhaust fans	378	Mechanical, electrical, and plumbing systems	511
Medicine cabinets	382	<i>Cost estimates</i>	
Bathroom accessories	385	Foundation anchors and brackets	512
14 Plumbing and HVAC	391	Cripple wall bracing	512
Heating types and considerations	391	Hold-down anchors	512
Framing for plumbing and HVAC	394	Bracing a water heater	512
<i>Cost estimates</i>		Framing straps and braces	512
Furnace replacement	396	Concrete repairs	513
Chimney flue components	399	Straighten a frame wall	514
Water heaters	405	Straighten a window opening	514
DWV pipe replacement	407	Plaster and stucco repair	514
15 Electrical	409	19 Water Damage and	
Wiring residences	411	Mold Remediation	515
Adding outlets and switches	414	Building Dryout	515
<i>Cost estimates</i>		Mold Remediation	525
Non-metallic cable	417	<i>Cost estimates</i>	
PVC conduit and fittings	420	Water extraction	529, 531
EMT conduit and fittings	422	Pre-drying	529
Flex conduit and fittings	426	Remove appliances	530
Rigid and IMC conduit and fittings	429	HVAC system cleaning	530
Switches and receptacles	434	Carpet removal	531
Distribution panels	436	Drywall repairs	532
Lighting	440	Demolition	532-534
Smart home electrical mgmt. system	444	Cleanup after water extraction	534
		Mold inspection and remediation protocol	535
		Containment structure	536
		Remove mold by abrading	537
		Encapsulation	537
		Personal protection equipment	538
		Air movers, dryers and drying systems	539
		Other dryout and mold equipment	540
		Index	541

Pricing Home Improvement Jobs

1



Estimating home improvement costs requires specialized skills. You can't price home improvement work the same way you'd price new construction. The proportion of labor expense is greater. There's far more risk because there are far more variables and unknowns. An example will make this clear.

Hanging doors in new construction is a 1-2-3 affair. You know ahead of time exactly what's required. You built the wall, installed the frame and know each door will fit right the first time. There won't be any surprises. An experienced estimator can forecast the cost of hanging a door in a new home with a high degree of certainty.

Now let's look at the same task on a home improvement project. First, remember that you may be hanging only one door. There's no chance to improve the production rate on second or later doors. Installing this door is probably different from the last door you installed on a similar project and will be different from your next door installation.

Work starts with removing the old door. That's probably not too hard — once you break through six coats of accumulated paint on the hinges. Let's assume you work carefully and don't damage the casing or trim. The next step is to install a blind Dutchman where the original hinges were attached. If the frame's badly chewed up from years of neglect and abuse, you'll have to remove and replace the entire frame. Don't forget that the building has settled over the years. The frame has probably twisted out of plumb. More time will be needed to shim and level the frame.

Finally the door is installed and swings smoothly. But the job still isn't finished. You have to paint the door to match and will certainly have to haul away the old door and the debris.

Every home improvement cost estimate comes with dozens of chances to make an expensive mistake. Surprises are inevitable and nearly all surprises will add to the cost, not reduce the cost. Estimating new construction is a snap by comparison.

All home improvement has similar problems:

- ❖ No chance for economies of scale (mass production),
- ❖ Difficulty in removing just enough of the old,
- ❖ Work doesn't follow the normal (from the ground, up) sequence of construction,
- ❖ Difficulty adding new materials to deteriorated or nonstandard existing materials,
- ❖ The need to match designs, colors and textures,
- ❖ Covering up for another contractor's mistakes,
- ❖ Struggling to get access to the place where the work is to be done,
- ❖ Protecting adjacent surfaces and pathway to the work area,
- ❖ Initial uncertainty about how much work is needed.

If you're an experienced home improvement contractor, you understand this already. Whether experienced or not, you know full well that accurate pricing is crucial to survival in the home improvement business. Unfortunately, most home improvement specialists have far less experience in pricing their work than in getting the work done. No wonder so many home improvement companies sink into obscurity.

But it doesn't have to be that way.

The chapters that follow explain how to price each type of home improvement work. Emphasis will be on avoiding risk — pricing pitfalls that can turn any home improvement contract into a financial nightmare.

No Price Fits All Jobs

There's no single way to arrive at the correct price for home improvement work. Neither is there a single correct price for most home improvement projects. But there are both good and bad ways to estimate prices and there are good and bad prices for any proposed job. Your task as a home improvement estimator is to produce consistently good estimates on most jobs. If you're already doing that, congratulations. You don't need this book. Return it where you bought it and get a refund. But if you're not, information in the following chapters will make or save you many times what you paid for the book.

It's accepted wisdom among home improvement specialists that salespeople need authority to quote prices when closing a sale. When trying to wrap up a deal, there's no substitute for having current cost information at your fingertips. That's especially true on larger jobs where you've prepared detailed plans and a written estimate. The owner will have questions and suggestions that change the job specs. If you want to close the sale then and there, you'd better know how much to add or subtract for each change the owner wants.

Most home improvement companies authorize salespeople to quote prices from an approved list in a price book. That simplifies the salesperson's job, eliminates most major errors, and saves the owner of the company from approving every item in every estimate. In our opinion, quoting from a price book is the only way to build sales volume in the home improvement business. That means every home improvement contractor needs a good price book.

Of course, the best price book for your company would be based on your actual cost experience — work done by your crews on your jobs with materials from your dealers and installed by your subcontractors. Since every contractor uses different crews, subcontractors and suppliers, every price book should be different. And, of course, prices in the company price book should be revised regularly to reflect current labor and material costs.

Having admitted that there's no substitute for developing your own price book, we'll suggest that you not bother. Most home improvement contractors don't have the time or patience to maintain current installed prices for thousands of repair and

remodeling items. Even if you did, spending hundreds of hours a year keeping a price book current would be a waste of time. Prices for home improvement work are usually negotiated on site. There's little value in keeping a book of exact costs if you have to cut a special deal to close each sale.

Instead, we suggest that you let this manual serve as your company price book. Using the prices in this book (and on the disk in the back of this manual) will eliminate most of the common estimating mistakes. If your labor costs are higher or if your crews aren't as skilled as most tradesmen, you may have to increase the selling prices listed here to make a reasonable profit. And, of course, sometimes you're going to have a job with costs that exceed what any reasonable estimate could have predicted. This manual isn't a substitute for the exercise of good judgment. That's always your job.

Cost Plus Markup Equals Selling Price

The figures in this manual show both costs to the contractor and a recommended selling price. The difference between your cost and your selling price is your markup. Markup varies widely, far more than either material cost or labor cost. You're the final authority on markup. You decide what markup fits best — based on market conditions, your client, and the profit you feel is reasonable. Once you decide on the "right" markup, it's easy to plug that percentage into the bid, assuming you use National Estimator.

Every construction contractor needs to distinguish between "markup" and "profit." Markup is what you add to estimated labor and material costs (usually called "hard costs") to find the selling price. Profit is what you have left when all bills have been paid. The two are very different. Profit is just the frosting on the cake.

Markup is also different from "margin." Figure 1-1 shows percentages of markup for various levels of hard costs. For example, if your markup on a \$20,000 job is 50 percent, the selling price will be \$30,000. The margin on that job is 33 percent, \$10,000 divided by the selling price of \$30,000. (Note the bottom row in Figure 1-1.) Margin is what's left after hard costs are recovered, and includes profit.

Markup vs. Margin				
Hard Cost	Price at 50% Markup	Price at 70% Markup	Price at 100% Markup	Price at 150% Markup
\$50	\$75	\$85	\$100	\$125
\$100	\$150	\$170	\$200	\$250
\$200	\$300	\$340	\$400	\$500
\$300	\$450	\$510	\$600	\$750
\$400	\$600	\$680	\$800	\$1,000
\$500	\$750	\$850	\$1,000	\$1,250
\$1,000	\$1,500	\$1,700	\$2,000	\$2,500
\$2,000	\$3,000	\$3,400	\$4,000	\$5,000
\$3,000	\$4,500	\$5,100	\$6,000	\$7,500
\$4,000	\$6,000	\$6,800	\$8,000	\$10,000
\$5,000	\$7,500	\$8,500	\$10,000	\$12,500
\$6,000	\$9,000	\$10,200	\$12,000	\$15,000
\$7,000	\$10,500	\$11,900	\$14,000	\$17,500
\$8,000	\$12,000	\$13,600	\$16,000	\$20,000
\$9,000	\$13,500	\$15,300	\$18,000	\$22,500
\$10,000	\$15,000	\$17,000	\$20,000	\$25,000
\$11,000	\$16,500	\$18,700	\$22,000	\$27,500
\$12,000	\$18,000	\$20,600	\$24,000	\$30,000
\$13,000	\$19,500	\$22,100	\$26,000	\$32,500
\$14,000	\$21,000	\$23,800	\$28,000	\$35,000
\$15,000	\$22,500	\$25,500	\$30,000	\$37,500
\$16,000	\$24,000	\$27,200	\$32,000	\$40,000
\$17,000	\$25,500	\$28,900	\$34,000	\$42,500
\$18,000	\$27,000	\$30,600	\$36,000	\$45,000
\$19,000	\$28,500	\$32,300	\$38,000	\$47,500
\$20,000	\$30,000	\$34,000	\$40,000	\$50,000
\$30,000	\$45,000	\$51,000	\$60,000	\$75,000
\$40,000	\$60,000	\$68,000	\$80,000	\$100,000
\$50,000	\$75,000	\$85,000	\$100,000	\$125,000
Hard Cost	33% Margin	41% Margin	50% Margin	60% Margin

Figure 1-1

Markup (based on cost) vs. Margin (based on selling price)

Many successful home improvement contractors find they can stay in business if hard costs are 59 percent of selling price. Hard costs include material expense, subcontract costs and labor (including taxes and insurance). The other 41 percent of selling price (“margin”) compensates the sales staff, covers overhead, supervision and contingency, and should yield a modest profit. From Figure 1-1, you can see that markup on hard costs has to be 70 percent to yield a margin of 41 percent.

To put this formula to work in your home improvement company, add 70 percent to your hard costs to find the selling price. Of course, some jobs need more markup and others can get by on less. A smaller job with more risk done for a demanding client may require greater markup. A larger job done mostly by subcontractors can usually carry a smaller markup.

Home improvement contractors have all the overhead of any business: office rent, telephone, owner’s salary, office salaries, legal and accounting expense, insurance, auto and truck expense, and more. But unlike other contractors, home improvement specialists routinely deal with high risk from both the unknown and the unknowable — at least until work actually begins. Since most of what you didn’t or couldn’t anticipate will inflate your costs, you’re assuming significant risk. That’s why markups for home improvement work have to be higher than for new construction.

Naturally, competition dictates markup. If you’re not getting enough work at 70 percent markup, maybe 70 percent is too much for your area. But remember that you shouldn’t have to bid remodeling work on a level playing field. New construction usually goes to the lowest responsible bidder. A creative salesman who follows the recommendations in this book has an advantage over lowball bidders who rely on price alone to sell their services.

If you have trouble using National Estimator, we’ll be glad to help, and we don’t charge you for it.

Free telephone assistance is available from 8 a.m. until 5 p.m. Pacific time Monday through Friday (except holidays). Call 760-438-7828, Ext. 2.



This Book Works Two Ways

The disk in the back of this book has all the information that appears in the printed book, but with one advantage. The National Estimator program makes it easy to copy and paste these costs into an estimate (or bid) and then add whatever markup you select. **Quarterly price updates on the Web are free** and automatic all during 2014. You’ll be prompted when it’s time to collect the next update. A connection to the Web is required. To get started with the National Estimator disk, insert it into any computer that uses Microsoft Windows. Then follow instructions on the screen.

Before installation is complete, you’ll be invited to watch ShowMe, an interactive video guide to the National Estimator program. ShowMe is designed to speed your mastery of National Estimator. You can start ShowMe at any time while using National Estimator. Click “**Help**” on the National Estimator menu bar. Then click “**Launch The Tutorial.**” The disk has to be in your computer when ShowMe is running.

Estimates That Work Two Ways

This manual is designed for use by both the owner of a home improvement business and by company sales staff. Prices shown in this manual include both hard costs (labor and material) and a recommended selling price (usually based on 70 percent markup). Sales staff will use the selling price.

Figure 1-2 shows the last page of an estimate for the Stillwel room addition, including 70 percent markup. The company estimator created this estimate from a job survey prepared by a sales representative. Figure 1-2 is for company use and was created in the National Estimator program.

Qty	Craft@Hours	Unit	Material	Labor	Equipment	Total
Roll & brush 1 coat of water base undercoat on interior flush doors						
Medium .3 MH/Door, 11.5 Doors/Gal						
3.00	2P@.9000	Ea	5.07	21.36	0.00	26.43
Roll & brush 1st finish coat of water base enamel on interior flush doors						
Medium .25 MH/Door, 12.5 Doors/Gal						
3.00	2P@.7500	Ea	5.39	17.80	0.00	23.18
Roll & brush 1 coat water base undercoat on vanity cabinet						
Medium 93 SF/MH, 250 SF/Gal						
0.90	2P@.9720	CSF	6.99	23.06	0.00	30.05
Roll & brush 1st finish coat of water base enamel on vanity cabinet						
Medium 103 SF/MH, 288 SF/Gal						
0.90	2P@.8740	CSF	7.02	20.70	0.00	27.72
Roll 1st coat of water base stain on rough sawn or resawn wood siding						
Medium 225 SF/MH, 213 SF/Gal						
17.00	2P@7.548	CSF	157.08	178.50	0.00	335.58
Roll 2nd coat of water base stain on rough sawn or resawn wood siding						
Medium 275 SF/MH, 273 SF/Gal						
17.00	2P@6.188	CSF	122.63	146.73	0.00	269.36
**Subtotal: Painting						
	40.7		1,014.54	973.46	0.00	1,988.00
Total Manhours, Material, Labor, and Equipment:						
	456.0		18,641.82	11,675.42	540.29	30,857.53
Total Only (Subcontract) Costs:						
						4,028.33
Subtotal:						34,885.85
70.00% Markup:						24,420.10
Estimate Total:						59,305.95

Figure 1-2

Estimate with a 70 percent markup shown

Figure 1-3 shows the last page of a proposal for the same job. This is what the customer sees. It was created by the Job Cost Wizard program. Both National Estimator and Job Cost Wizard are on the disk in the back of this book. Notice that the total is the same in both documents, \$59,305.95. Figure 1-2, the estimate, shows 70 percent markup on hard costs. Figure 1-3, the proposal, doesn't show the markup at all. Instead, markup has been distributed proportionately throughout each cost item in the job. Job Cost Wizard does this distribution at the click of a button.

Craftsman Construction		Proposal	
6058 Corte del Cedro Box 6600 Fairfield, GA 30456 856-3806		Date	Estimate #
		8/3/14	494
		Customer	Job
		Bill Stillwel	Room Addition
Description	Qty	Rate	Amount
Roll & brush 1st finish coat of water base enamel on vanity cabinet. Medium 103 SF/MH, 288 SF/Gal			
Material, per CSF	0.90	13.26	11.94
Labor, per CSF	0.90	39.09	35.18
Roll 1st coat of water base stain on rough sawn or resawn wood siding. Medium 225 SF/MH, 213 SF/Gal			
Material, per CSF	17	15.71	267.04
Labor, per CSF	17	17.85	303.45
Roll 2nd coat of water base stain on rough sawn or resawn wood siding. Medium 275 SF/MH, 273 SF/Gal			
Material, per CSF	17	12.26	208.47
Labor, per CSF	17	14.67	249.44
*Painting subtotal			3,379.60
*Project Subtotal			59,305.96
*Project Total			59,305.96

Figure 1-3

Proposal for the same job not showing the markup

Once an estimate is finished in the National Estimator program and saved to computer disk, press **Ctrl** on your keyboard and tap the letter **J** to convert the estimate into a proposal in Job Cost Wizard. You can't make changes in the Job Cost Wizard screen. But it's easy to toggle back to National Estimator program (press **Alt** and tap the **Tab** key), make a change, and then press **Ctrl-J** once again.

Job Cost Wizard offers dozens of choices on what you show and don't show in written proposals. Your bids can be long (full description for everything in the estimate) or short (only a summary of each category). You can show or hide labor and material cost detail. You can show or hide markup and profit.

Once work begins, you'll want to monitor job expenses to be sure actual costs remain consistent with estimated costs. If you use QuickBooks to pay bills and figure payroll, let QuickBooks do the comparisons for you. Job Cost Wizard exports the proposal to QuickBooks, where you can prepare progress invoices and track expenses against estimates.

The National Estimator program lets you change anything in the costbook or even add your own estimated costs. Make the *National Home Improvement Estimator* your collection point for all estimating and pricing information. Anything you add to the costbook shows up in red and can be migrated to later editions of this manual when available. The *National Home Improvement Estimator* starts out as your most useful estimating reference. What you add to the costbook will make it even more valuable.

Job Survey (Scope of Work)

Of course, neither a good price book nor a computer estimating program will solve all of your estimating problems. Computers seldom make mistakes in addition or multiplication. But nothing prevents you from making expensive estimating mistakes on your own. By far the most common estimating mistake will be omitting something essential to the job.

Get in the habit of completing an exhaustive job survey before beginning any estimate for home improvement work. Some of your estimates on a job may be too high. Other estimates on a job may be too low. With any luck, your over-estimates will roughly balance with your under-estimates, leaving the job total about where it should be. But the estimated price for anything omitted from a job survey is always zero. That's a 100 percent miss. It's hard to balance a complete miss with anything. A few of those can create a financial disaster.

Material Costs in This Book

Material costs for each item are listed in the column headed Material. These are neither retail nor wholesale prices. They are estimates of what most contractors who buy in moderate volume will pay suppliers as of mid-2014. Discounts may be available for purchases in larger volumes.

Add Delivery Expense to the material cost for other than local delivery of reasonably large quantities. Cost of delivery varies with the distance from source of supply, method of transportation, and quantity to be delivered. But most material dealers absorb the delivery cost on local delivery (5 to 15 miles) of larger quantities to good customers. Add the expense of job site delivery when it's a significant part of the material cost.

Add Sales Tax when sales tax will be charged to the contractor buying the materials. In some states, contractors have to collect sales tax based on the contract price. No matter what your state (or county) requires, National Estimator can handle the task. Click **Edit** on the National Estimator menu bar. Then click **Sales Tax**.

Waste and Coverage Loss is included in the installed material cost. The cost of many materials per unit after installation is greater than the purchase price for the same unit because of waste, shrinkage or coverage loss during installation. For example, about 120 square feet of nominal 1" x 4" square edge boards will be needed to cover 100 square feet of floor or wall. There's no coverage loss with plywood sheathing, but waste due to cutting and fitting will average about 6 percent.

Costs in the Material column of this book assume normal waste and coverage loss. Small and irregular jobs may require a greater waste allowance. Materials priced without installation (with no labor cost) don't include an allowance for waste and coverage except as noted.

Labor Costs for installing the material or doing the work described are listed in the column headed Labor. The labor cost per unit is the labor cost per hour multiplied by the manhours per unit shown after the @ sign in the Craft@Hrs column. Labor cost includes the basic wage, the employer's contribution to welfare, pension, vacation and apprentice funds, and all tax and insurance charges based on wages.

Supervision Expense to the general contractor isn't included in the labor cost. The cost of supervision and non-productive labor varies widely from job to job. Calculate the cost of supervision and non-productive labor and add this to the estimate.

Payroll Taxes and Insurance are included in the labor cost. See the following section for more on the "contractor's burden."

Manhours per Unit and the Craft performing the work are listed in the Craft@Hrs column. To find the units of work done per worker in an 8-hour day, divide 8 by the manhours per unit. To find the units done by a crew in an 8-hour day, multiply the units per worker per 8-hour day by the number of crew members.

Manhours include all productive labor normally associated with installing the materials described.

This will usually include tasks such as:

- ❖ Unloading and storing construction materials, tools and equipment on site.
- ❖ Moving tools and equipment from a storage area or truck on site at the beginning of the day.
- ❖ Returning tools and equipment to a storage area or truck on site at the end of the day.
- ❖ Normal time lost for work breaks.
- ❖ Planning and discussing the work to be performed.
- ❖ Normal handling, measuring, cutting and fitting.
- ❖ Keeping a record of the time spent and work done.
- ❖ Regular cleanup of construction debris.
- ❖ Infrequent correction or repairs required because of faulty installation.

Adjust the Labor Cost to the job you're figuring when your actual hourly labor cost is known or can be estimated. The labor costs listed in Figure 1-5 will apply within a few percent on many jobs. But labor costs may be much higher or much lower on the job you're estimating.

If the hourly wage rates listed in Figure 1-5 aren't accurate, divide your known or estimated cost per hour by the listed cost per hour. The result is your adjustment for any figure in the Labor column for that craft.

Adjust for Unusual Labor Productivity. Costs in the Labor column are for normal conditions: experienced craftsmen working on reasonably well-planned and managed home improvement projects with fair to good productivity. Labor estimates assume that materials are standard grade, appropriate tools are on hand, work done by other crafts is adequate, layout and installation are relatively uncomplicated, and working conditions don't slow progress.

Working conditions at the jobsite have a major effect on labor cost. Estimating experience and careful analysis can help you predict the effect of most changes in working conditions. Obviously, no single adjustment will apply on all jobs. But the adjustments that follow should help you produce more accurate labor estimates. More than one condition may apply on a job.

Jobsite conditions affect labor costs

- ❖ Add 10% to 15% when working temperatures are below 40 degrees or above 95 degrees.
- ❖ Add 30% to 35% when temperatures are below 20 degrees. Materials and tools are hard to handle. Bulky clothing restricts freedom of movement.
- ❖ Add 15% to 25% for work on a ladder or a scaffold, in a 36" crawl space, in a congested area, or remote from the material storage point.
- ❖ Add 50% for work in an 18" to 36" crawl space. Allow extra time for cleaning out the area before work begins.
- ❖ Add 200% if portions of the crawl space are less than 18". Allow extra time for passing tools and materials. Few contractors bid on work like this.
- ❖ Deduct 10% when the work is in an open area with excellent access and good light.
- ❖ Add 1% for each 10 feet that materials must be lifted above ground level.
- ❖ Add 5% to 50% for tradesmen with below-average skills. Deduct 5% to 25% for highly-motivated, highly-skilled tradesmen.
- ❖ Deduct 10% to 20% when an identical task is repeated many times for several days at the same site.
- ❖ Add 20% to 50% on small jobs where fitting and matching of materials is required, adjacent surfaces have to be protected and the job site is occupied during construction.
- ❖ Add 25% to 50% for work done following a major flood, fire, earthquake, hurricane or tornado while skilled tradesmen are not readily available. Material costs may also be higher after a major disaster.
- ❖ Add 10% to 35% for demanding specs, rigid inspections, unreliable suppliers, a difficult owner or an inexperienced architect.

Use an Area Modification Factor from pages 18 through 26 if your material, hourly labor or equipment costs are unknown and can't be estimated. Here's how: Use the labor and material costs in this manual without modification. Then add or deduct the percentages shown for labor, material and equipment.

Equipment Costs for small tools and expendable supplies (such as saws and tape) are usually considered overhead expense and are covered by your markup. Equipment costs for larger equipment (such as a compressor or backhoe) should be

based on the rental rate for the period needed. Equipment rental costs are included in sections where heavy equipment may be needed.

Labor and Material Costs Change. These costs were compiled in the fall of 2013 and projected to mid-2014 by adding a small percentage. This projection will be accurate for some materials and inaccurate for others. No one can predict material price changes accurately.

How Accurate Are These Figures? They're as accurate as possible considering that the estimators who wrote this book don't know your subcontractors or material suppliers, haven't seen the plans or specifications, don't know what building code applies or where the job is, had to project material costs at least six months into the future, and had no record of how much work the crew that will be assigned to the job can handle.

You wouldn't bid a job under those conditions. And we don't claim that all construction is done at these prices.

Estimating Is an Art, not a science. On many jobs the range between high and low bid will be 20 percent or more. There's room for legitimate disagreement on what the correct costs are, even when complete plans and specifications are available, the date and site are established, and labor and material costs are identical for all bidders.

No cost fits all jobs. Good estimates are custom-made for a particular project and a single contractor through judgment, analysis and experience.

This book isn't a substitute for judgment, analysis and sound estimating practice. It's an *aid* in developing an *informed opinion* of cost. If you're using this book as your sole cost authority for contract bids, you're reading more into these pages than the editors intend.

Use These Figures to compile preliminary estimates, when a "snap" bid is needed to close the deal, and when no actual costs are available. This book will reduce the chance of error or omission on bid estimates, speed "ball park" estimates, and be a good guide when there's no time to get a quote.

Where Do We Get These Figures? From the same sources all professional estimators use: material suppliers, material price services, analysis of plans, specifications, estimates and completed project costs, and both published and unpublished cost studies compiled by both private and government agencies. In addition, we conduct nationwide mail and phone surveys and have the use of several major national estimating databases.

We'll Answer Your Questions about any part of this book and explain how to apply these costs. Free telephone assistance is available from 8 a.m. until 5 p.m. Pacific time Monday through Friday except holidays. Phone 760-438-7828, Ext. 2. We don't accept collect calls and can't estimate the job for you. But if you need clarification on something in this manual, we can help.

Labor Costs and Crews

Throughout this manual you'll see a column headed *Craft@Hrs.* Letters and numbers in this column show our estimates of:

- ❖ Who will do the work (the craft code)
- ❖ An @ symbol which means at
- ❖ How long the work will take (manhours).

For example, in Chapter 4, page 70, you'll find estimates for installing BC plywood wall sheathing by the square foot. The *Craft@Hrs* column opposite 1/2" plywood wall sheathing shows:

B1@.016

That means we estimate the installation rate for crew B1 at 0.016 manhours per square foot. That's the same as 16 manhours per 1,000 square feet.

Figure 1-4 is a table that defines each of the craft codes used in this book. Notice that crew B1 is composed of two craftsmen: one laborer and one carpenter. To install 1,000 square feet of 1/2" BC wall sheathing at 0.016 manhours per square foot, that crew would need 16 manhours (one 8-hour day for a crew of two).

Notice also in the table that the cost per manhour for crew B1 is listed as \$32.59. That's the average for a laborer (listed at \$29.13 per hour) and a carpenter (listed at \$36.05 per hour): \$29.13 plus \$36.05 is \$65.18. Divide by 2 to get \$32.59, the average cost per manhour for crew B1.

In the table, the cost per manhour is the sum of hourly costs of all crew members divided by the number of crew members. That's the average cost per manhour.

Costs in the Labor column in this book are the product of the installation time (in manhours) multiplied by the cost per manhour. For example, in Chapter 4, the labor cost listed for 1/2" BC wall sheathing is \$0.52 per square foot. That's the installation time (0.016 manhours per square foot) multiplied by \$32.59, the average cost per manhour for crew B1.

Figure 1-5 shows hourly labor costs components — base wage, typical fringe benefits, payroll taxes, insurance and the total hourly cost.

The labor costs shown in Column 6 were used to compute the manhour costs for crews and the figures in the Labor column.

Craft Codes		
Craft Code	Cost Per Manhour	Crew Composition
B1	\$32.59	1 laborer, 1 carpenter
B2	\$33.74	1 laborer, 2 carpenters
B3	\$31.44	2 laborers, 1 carpenter
B4	\$35.64	1 laborer, 1 operating engineer, 1 reinforcing iron worker
B5	\$35.40	1 laborer, 1 carpenter, 1 cement mason, 1 operating engineer, 1 reinforcing iron worker
B6	\$31.58	1 laborer, 1 cement mason
B7	\$29.51	1 laborer, 1 truck driver
B8	\$35.03	1 laborer, 1 operating engineer
B9	\$31.96	1 bricklayer, 1 bricklayer's helper
BB	\$36.59	1 bricklayer
BC	\$36.05	1 carpenter
BE	\$39.04	1 electrician
BF	\$32.51	1 floor layer
BG	\$34.77	1 glazier
BH	\$27.32	1 bricklayer's helper
BL	\$29.13	1 laborer
BR	\$34.89	1 lather
BS	\$31.66	1 marblesetter
CF	\$34.02	1 cement mason
CT	\$33.90	1 mosaic & terrazzo worker
D1	\$35.27	1 drywall installer, 1 drywall taper
DI	\$34.91	1 drywall installer
DT	\$35.62	1 drywall taper
HC	\$28.43	1 plasterer helper
OE	\$40.93	1 operating engineer
P1	\$35.39	1 laborer, 1 plumber
PM	\$41.65	1 plumber
PP	\$32.87	1 painter, 1 laborer
PR	\$36.42	1 plasterer
PT	\$36.60	1 painter
R1	\$34.80	1 roofer, 1 laborer
RI	\$36.86	1 reinforcing iron worker
RR	\$40.46	1 roofer
SW	\$40.50	1 sheet metal worker
T1	\$31.55	1 tile layer, 1 laborer
TL	\$33.96	1 tile layer
TR	\$29.88	1 truck driver

Figure 1-4

Craft codes used in this manual

Hourly Labor Cost						
	1	2	3	4	5	6
Craft	Base wage per hour	Taxable fringe benefits (5.15% of base wage)	Insurance and employer taxes (%)	Insurance and employer taxes (\$)	Non-Taxable fringe benefits (4.55% of base wage)	Total hourly cost used in this book
Bricklayer	\$26.84	\$1.38	25.34%	\$7.15	\$1.22	\$36.59
Bricklayer's Helper	20.04	1.03	25.34	5.34	0.91	27.32
Building Laborer	20.21	1.04	32.73	6.96	0.92	29.13
Carpenter	25.21	1.30	31.63	8.39	1.15	36.05
Cement Mason	25.38	1.31	23.15	6.18	1.15	34.02
Drywall Installer	25.96	1.34	23.57	6.43	1.18	34.91
Drywall Taper	26.49	1.36	23.57	6.56	1.21	35.62
Electrician	29.90	1.54	19.84	6.24	1.36	39.04
Floor Layer	24.13	1.24	23.82	6.04	1.10	32.51
Glazier	25.41	1.31	25.78	6.89	1.16	34.77
Lather	26.42	1.36	21.28	5.91	1.20	34.89
Marble Setter	23.96	1.23	21.36	5.38	1.09	31.66
Millwright	25.64	1.32	21.24	5.73	1.17	33.86
Mosaic & Terrazzo Worker	25.65	1.32	21.36	5.76	1.17	33.90
Operating Engineer	30.04	1.55	25.22	7.97	1.37	40.93
Painter	26.93	1.39	24.88	7.05	1.23	36.60
Plasterer	26.06	1.34	28.58	7.83	1.19	36.42
Plasterer Helper	20.34	1.05	28.58	6.11	0.93	28.43
Plumber	30.80	1.59	24.27	7.86	1.40	41.65
Reinforcing Ironworker	26.37	1.36	28.61	7.93	1.20	36.86
Roofer	25.92	1.33	44.14	12.03	1.18	40.46
Sheet Metal Worker	29.56	1.52	26.01	8.08	1.34	40.50
Sprinkler Fitter	30.25	1.56	25.08	7.98	1.38	41.17
Tile Layer	25.70	1.32	21.36	5.77	1.17	33.96
Truck Driver	21.77	1.12	26.22	6.00	0.99	29.88

Figure 1-5

Components of hourly labor costs

It's important that you understand what's included in the figures in each of the six columns in the table. Here's an explanation:

Column 1, the base wage per hour, is the craftsman's hourly wage. These figures are representative of what many contractors will be paying craftsmen working on home improvement jobs in 2014.

Column 2, taxable fringe benefits, includes vacation pay, sick leave and other taxable benefits. These fringe benefits average 5.15 percent of the base wage for many construction contractors. This benefit is in addition to the base wage.

Column 3, insurance and employer taxes in percent, shows the insurance and tax rate for construction trades. The cost of insurance in this column includes workers' compensation and contractor's casualty and liability coverage. Insurance rates vary

widely from state to state and depend on a contractor's loss experience. Note that taxes and insurance increase the hourly labor cost by 30 to 35 percent for most trades. There is no legal way to avoid these costs.

Column 4, insurance and employer taxes in dollars, shows the hourly cost of taxes and insurance for each construction trade. Insurance and taxes are paid on the costs in both columns 1 and 2.

Column 5, non-taxable fringe benefits, includes employer paid non-taxable benefits such as medical coverage and tax-deferred pension and profit sharing plans. These fringe benefits average 4.55 percent of the base wage for many construction contractors. The employer pays no taxes or insurance on these benefits.

Column 6, the total hourly cost in dollars, is the sum of columns 1, 2, 4 and 5.

These hourly labor costs will apply within a few percent on many jobs. But wage rates may be much higher or lower in the area where you do business. We recommend using your actual labor cost rather than national averages. That's easy with the National Estimator program. When copying and pasting any cost to your estimate, adjust the assumed hourly labor cost to your actual cost. You need do this only once for each trade. And you can make this adjustment at any time. Any change you make is applied to that trade throughout the estimate.

Abbreviations			
4WD	four-wheel drive	EPA	Environmental Protection Agency
ABS	acrylonitrile butadiene styrene	F	Fahrenheit
AC	alternating current	GFCI	ground fault circuit interrupter
ACQ	Alkaline Copper Quat	GRS	galvanized rigid steel
ADA	Americans with Disabilities Act	H	height
ANSI	American Nat. Standards Institute	HOM	higher order mode
APP	atactic polypropylene	HP	horsepower
ASTM	Amer. Society for Testing Materials	HVAC	heating, ventilating & air cond.
AWG	American Wire Gauge	ID	inside diameter
BF	board foot	IMC	intermediate metal conduit
Btr	better	KD	kiln dried
Btu(s)	British thermal unit(s)	KO	knockout
C	Celsius/Centigrade	kW	kilowatt(s)
CF	cubic foot	L	length
CFM	cubic feet per minute	Lb(s)	pound(s)
CLF	100 linear feet	LF	linear foot
CPM	cycles per minute	LS	lump sum
CSF	100 square feet	MBF	1,000 board feet
CY	cubic yard	MDF	medium density fiberboard
d	penny	mm	millimeter(s)
D	depth	Mo	month
DWV	drain, waste & vent	MPH	miles per hour
Ea	each	MSF	1,000 square feet
EMT	electric metallic tube	NEC	National Electrical Code
NEMA	National Electrical Manufacturer's Assoc.	OC	spacing from center to center
OD	outside diameter	OSB	oriented strand board
OSHA	Occupational Safety & Health Admin.	oz.	ounce(s)
PSI	pounds per square inch	PVC	polyvinyl chloride
R	thermal resistance	S4S	surfaced 4 sides
SBS	styrene butadiene styrene	SF	square foot
SFCA	(per) square foot of contact area	Sq	100 square feet
Std	standard	SY	square yard
T	thick	T&G	tongue & groove edge
UL	Underwriter's Laboratory	USDA	United States Dept. of Agriculture
UV	ultraviolet	W	width
X	by or times		

Figure 1-6

Abbreviations used in this manual

Area Modification Factors

Construction costs are higher in some areas than in other areas. Add or deduct the percentages shown on the following pages to adapt the costs in this book to your jobsite. Adjust your cost estimate by the appropriate percentages in this table to find the estimated cost for the site selected. Where 0% is shown, it means no modification is required.

Modification factors are listed by state and province. Areas within each state are listed by the first three digits of the postal zip code. For convenience, one representative city is identified in each three-digit zip or range of zips. Percentages are based on the average of all data points in the table. Factors listed for each state and province are the average of all data in that state or province. Figures for the zips are the average of all information in that area. And figures in the Total column are the weighted average of factors for Labor, Material and Equipment.

The National Estimator program will apply an area modification factor for any five-digit zip you select. Click Utilities. Click Options. Then select the Area Modification Factors tab.

These percentages are composites of many costs and will not necessarily be accurate when estimating the cost of any particular part of a building. But when used to modify costs for an entire structure, they should improve the accuracy of your estimates.

Area Modification Factors

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Alabama Average		-1	-11	0	-6%
Anniston	362	-3	-19	-1	-10%
Auburn	368	0	-14	0	-6%
Bellamy	369	-2	-7	-1	-4%
Birmingham	350-352	-3	10	-1	3%
Dothan	363	-1	-13	0	-7%
Evergreen	364	-1	-25	0	-12%
Gadsden	359	-4	-21	-1	-12%
Huntsville	358	1	-8	0	-3%
Jasper	355	-1	-23	0	-11%
Mobile	365-366	-1	-5	0	-3%
Montgomery	360-361	-1	-6	0	-3%
Scottsboro	357	0	-13	0	-6%
Selma	367	-1	-14	0	-7%
Sheffield	356	0	-3	0	-1%
Tuscaloosa	354	1	-11	0	-5%
Alaska Average		14	29	5	21%
Anchorage	995	17	37	6	26%
Fairbanks	997	16	31	5	23%
Juneau	998	18	24	6	21%
Ketchikan	999	3	20	1	11%
King Salmon	996	16	31	5	23%
Arizona Average		1	-11	0	-4%
Chambers	865	1	-9	0	-4%
Douglas	855	0	-14	0	-6%
Flagstaff	860	2	-21	1	-9%
Kingman	864	1	-14	0	-6%
Mesa	852	1	2	0	1%
Phoenix	850	1	2	0	1%
Prescott	863	3	-17	1	-6%
Show Low	859	1	-22	0	-10%
Tucson	856-867	0	-15	0	-7%
Yuma	853	0	1	0	0%
Arkansas Average		-2	-11	0	-6%
Batesville	725	0	-20	0	-9%
Camden	717	-4	-3	-1	-3%
Fayetteville	727	1	-10	0	-4%
Fort Smith	729	-1	-12	0	-6%
Harrison	726	0	-28	0	-13%
Hope	718	-3	11	-1	3%
Hot Springs	719	-2	-29	-1	-14%
Jonesboro	724	-1	-13	0	-7%
Little Rock	720-722	-1	-5	0	-3%
Pine Bluff	716	-4	3	-1	-1%

Area Modification Factors

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Russellville	728	0	-15	0	-7%
West Memphis	723	-3	-8	-1	-5%
California Average		2	13	1	7%
Alhambra	917	3	13	1	8%
Bakersfield	932-933	0	7	0	3%
El Centro	922	1	-2	0	0%
Eureka	955	1	-5	0	-2%
Fresno	936-938	0	-3	0	-1%
Herlong	961	2	-5	1	-1%
Inglewood	902-905	3	14	1	8%
Irvine	926-927	3	23	1	12%
Lompoc	934	3	10	1	6%
Long Beach	907-908	3	15	1	8%
Los Angeles	900-901	3	12	1	7%
Marysville	959	1	-2	0	0%
Modesto	953	1	-3	0	-1%
Mojave	935	0	10	0	5%
Novato	949	3	23	1	12%
Oakland	945-947	3	34	1	17%
Orange	928	3	21	1	11%
Oxnard	930	3	6	1	4%
Pasadena	910-912	3	14	1	8%
Rancho Cordova	956-957	2	10	1	6%
Redding	960	1	-5	0	-2%
Richmond	948	2	35	1	17%
Riverside	925	1	7	0	4%
Sacramento	958	1	10	0	5%
Salinas	939	3	1	1	2%
San Bernardino	923-924	0	9	0	4%
San Diego	919-921	3	10	1	6%
San Francisco	941	3	55	1	27%
San Jose	950-951	3	34	1	17%
San Mateo	943-944	4	36	1	19%
Santa Barbara	931	3	10	1	6%
Santa Rosa	954	3	10	1	6%
Stockton	952	1	2	0	1%
Sunnyvale	940	3	38	1	19%
Van Nuys	913-916	3	12	1	7%
Whittier	906	3	13	1	8%
Colorado Average		1	0	1	1%
Aurora	800-801	2	7	1	4%
Boulder	803-804	3	1	1	2%
Colorado Springs	808-809	2	-5	1	-1%
Denver	802	2	9	1	5%
Durango	813	1	-1	0	0%
Fort Morgan	807	1	-1	0	0%
Glenwood Springs	816	2	3	1	2%
Grand Junction	814-815	1	-4	0	-1%
Greeley	806	2	5	1	3%
Longmont	805	3	-1	1	1%
Pagosa Springs	811	0	-9	0	-4%
Pueblo	810	-1	5	0	2%
Salida	812	1	-12	0	-5%

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Connecticut Average		1	28	0	13%
Bridgeport	066	1	28	0	13%
Bristol	060	1	24	0	12%
Fairfield	064	2	31	1	15%
Hartford	061	0	31	0	14%
New Haven	065	1	28	0	13%
Norwich	063	0	26	0	12%
Stamford	068	4	35	1	18%
Waterbury	067	1	28	0	13%
West Hartford	062	1	20	0	10%
Delaware Average		1	1	0	1%
Dover	199	1	-13	0	-5%
Newark	197	2	9	1	5%
Wilmington	198	0	8	0	4%
District of Columbia Average		3	21	1	11%
Washington	200-205	3	21	1	11%
Florida Average		-1	-15	0	-7%
Altamonte Springs	327	-1	-12	0	-6%
Bradenton	342	0	-18	0	-8%
Brooksville	346	-1	-21	0	-10%
Daytona Beach	321	-2	-24	-1	-12%
Fort Lauderdale	333	2	-5	1	-1%
Fort Myers	339	0	-20	0	-9%
Fort Pierce	349	-2	-26	-1	-13%
Gainesville	326	-1	-19	0	-9%
Jacksonville	322	-1	-8	0	-4%
Lakeland	338	-3	-16	-1	-9%
Melbourne	329	-2	-19	-1	-10%
Miami	330-332	2	-5	1	-1%
Naples	341	3	-14	1	-5%
Ocala	344	-2	-26	-1	-13%
Orlando	328	0	-3	0	-1%
Panama City	324	-2	-16	-1	-8%
Pensacola	325	0	-17	0	-8%
Saint Augustine	320	-1	-13	0	-7%
Saint Cloud	347	0	-10	0	-5%
St Petersburg	337	-1	-14	0	-7%
Tallahassee	323	0	-19	0	-9%
Tampa	335	-1	-7	0	-4%
West Palm Beach	334	1	-7	0	-3%
Georgia Average		-1	-9	0	-5%
Albany	317	-2	-19	-1	-10%
Athens	306	0	-12	0	-6%
Atlanta	303	3	24	1	13%
Augusta	308-309	-2	-6	-1	-4%
Buford	305	0	-9	0	-4%
Calhoun	307	-1	-21	0	-10%
Columbus	318-319	-1	-13	0	-7%
Dublin/Fort Valley	310	-3	-15	-1	-8%
Hinesville	313	-2	-10	-1	-6%
Kings Bay	315	-2	-9	-1	-5%

Area Modification Factors

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.	Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Macon	312	-2	-8	-1	-5%	Indiana Average		-2	0	-1	-1%
Marietta	300-302	1	7	0	4%	Aurora	470	-1	-6	0	-3%
Savannah	314	-1	-11	0	-6%	Bloomington	474	1	-4	0	-1%
Statesboro	304	-2	-21	-1	-11%	Columbus	472	0	-8	0	-4%
Valdosta	316	-1	-7	0	-4%	Elkhart	465	-2	-4	-1	-3%
Hawaii Average		17	30	6	23%	Evansville	476-477	-2	14	-1	5%
Aliamanu	968	17	32	6	24%	Fort Wayne	467-468	-3	-3	-1	-3%
Ewa	967	17	29	6	22%	Gary	463-464	-4	48	-1	20%
Halawa Heights	967	17	29	6	22%	Indianapolis	460-462	-1	14	0	6%
Hilo	967	17	29	6	22%	Jasper	475	-1	-16	0	-8%
Honolulu	968	17	32	6	24%	Jeffersonville	471	-1	-3	0	-2%
Kailua	968	17	32	6	24%	Kokomo	469	-2	-13	-1	-7%
Lualualei	967	17	29	6	22%	Lafayette	479	-1	-10	0	-5%
Mililani Town	967	17	29	6	22%	Muncie	473	-4	-15	-1	-9%
Pearl City	967	17	29	6	22%	South Bend	466	-4	-1	-1	-3%
Wahiawa	967	17	29	6	22%	Terre Haute	478	-4	0	-1	-2%
Waianae	967	17	29	6	22%	Iowa Average		-1	-5	0	-2%
Wailuku (Maui)	967	17	29	6	22%	Burlington	526	0	-8	0	-4%
Idaho Average		0	-17	0	8%	Carroll	514	-3	-18	-1	-10%
Boise	837	1	-5	0	-2%	Cedar Falls	506	-1	-6	0	-3%
Coeur d'Alene	838	0	-21	0	-10%	Cedar Rapids	522-524	0	4	0	2%
Idaho Falls	834	-1	-15	0	-7%	Cherokee	510	-2	-3	-1	-2%
Lewiston	835	0	-26	0	-12%	Council Bluffs	515	-2	-8	-1	-5%
Meridian	836	0	-18	0	-8%	Creston	508	-3	-12	-1	-7%
Pocatello	832	-1	-17	0	-8%	Davenport	527-528	-1	5	0	14%
Sun Valley	833	-1	-15	0	-7%	Decorah	521	-2	-12	-1	1%
Illinois Average		-1	11	0	4%	Des Moines	500-503	-2	10	-1	4%
Arlington Heights	600	1	30	0	14%	Dubuque	520	-1	0	0	-2%
Aurora	605	2	28	1	14%	Fort Dodge	505	-2	-8	-1	-5%
Belleville	622	-2	5	-1	1%	Mason City	504	0	-6	0	-3%
Bloomington	617	1	0	0	1%	Ottumwa	525	0	-17	0	-4%
Carbondale	629	-3	-8	-1	-5%	Sheldon	512	0	-16	0	-7%
Carol Stream	601	2	29	1	14%	Shenandoah	516	-3	-26	-1	-14%
Centralia	628	-3	-5	-1	-4%	Sioux City	511	-2	4	-1	1%
Champaign	618	-1	1	0	0%	Spencer	513	-1	-14	0	-7%
Chicago	606-608	2	34	1	17%	Waterloo	507	-4	-7	-1	-5%
Decatur	623	-2	-14	-1	-8%	Kansas Average		-2	-11	-1	-6%
Galesburg	614	-2	-9	-1	-5%	Colby	677	-1	-16	0	-8%
Granite City	620	-3	9	-1	3%	Concordia	669	-1	-29	0	-14%
Green River	612	-2	11	-1	4%	Dodge City	678	-2	-4	-1	-3%
Joliet	604	0	33	0	15%	Emporia	668	-3	-15	-1	-8%
Kankakee	609	-2	5	-1	1%	Fort Scott	667	-2	-11	-1	-6%
Lawrenceville	624	-4	-7	-1	-5%	Hays	676	-2	-28	-1	-14%
Oak Park	603	3	38	1	19%	Hutchinson	675	-3	-9	-1	-6%
Peoria	615-615	-1	14	0	6%	Independence	673	-3	0	-1	-2%
Peru	613	0	7	0	3%	Kansas City	660-662	0	11	0	5%
Quincy	602	3	34	1	17%	Liberal	679	-2	-16	-1	-8%
Rockford	610	-2	11	-1	4%	Salina	674	-3	-15	-1	-8%
Springfield	625-627	-2	0	-1	-1%	Topeka	664-666	-3	-2	-1	-3%
Urbana	619	-3	-4	-1	-3%	Wichita	670-672	-2	-7	-1	-4%

Area Modification Factors

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.	Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Kentucky Average						Massachusetts Average					
Ashland	411-412	-3	-12	-1	-7%	Ayer	015-016	1	12	0	6%
Bowling Green	421	0	-12	0	-6%	Bedford	017	3	33	1	17%
Campton	413-414	-1	-16	0	-8%	Boston	021-022	3	72	1	35%
Covington	410	-1	2	0	0%	Brockton	023-024	2	40	1	19%
Elizabethtown	427	-1	-16	0	-8%	Cape Cod	026	2	2	1	2%
Frankfort	406	1	-6	0	-2%	Chicopee	010	1	16	0	8%
Hazard	417-418	-1	-10	0	-5%	Dedham	019	3	33	1	17%
Hopkinsville	422	-2	-14	-1	-8%	Fitchburg	014	2	23	1	12%
Lexington	403-405	1	3	0	2%	Hingham	020	3	38	1	19%
London	407-409	-1	-9	0	-5%	Lawrence	018	2	30	1	15%
Louisville	400-402	-1	1	0	0%	Nantucket	025	3	17	1	9%
Owensboro	423	-2	-8	-1	-5%	New Bedford	027	2	21	1	11%
Paducah	420	-2	-6	-1	-4%	Northfield	013	1	-2	0	0%
Pikeville	415-416	-3	-3	-1	-3%	Pittsfield	012	1	-1	0	0%
Somerset	425-426	0	-23	0	-11%	Springfield	011	-1	21	0	9%
White Plains	424	-3	-4	-1	-3%	Michigan Average					
Louisiana Average						Battle Creek	490-491	-3	1	-1	-1%
Alexandria	713-714	-3	-8	-1	-5%	Detroit	481-482	0	19	0	9%
Baton Rouge	707-708	0	18	0	8%	Flint	484-485	-3	-7	-1	-5%
Houma	703	-2	14	-1	5%	Grand Rapids	493-495	-1	2	0	0%
Lafayette	705	0	3	0	1%	Grayling	497	1	-14	0	-6%
Lake Charles	706	-2	-1	-1	-2%	Jackson	492	-3	2	-1	-1%
Mandeville	704	0	-2	0	-1%	Lansing	488-489	0	1	0	0%
Minden	710	-2	-9	-1	-5%	Marquette	489-499	-1	2	0	0%
Monroe	712	-2	-15	-1	-8%	Pontiac	483	-3	21	-1	8%
New Orleans	700-701	0	4	0	2%	Royal Oak	480	-2	19	-1	8%
Shreveport	711	-2	-4	-1	-3%	Saginaw	486-487	-2	-8	-1	-5%
Maine Average						Traverse City	496	-1	3	0	1%
Auburn	042	-1	-12	0	-6%	Minnesota Average					
Augusta	043	-1	-16	0	-8%	Bemidji	566	-1	-9	0	-5%
Bangor	044	-2	-16	-1	-8%	Brainerd	564	0	0	0	0%
Bath	045	0	-14	0	-6%	Duluth	556-558	-2	0	-1	-1%
Brunswick	039-040	1	-7	0	-3%	Fergus Falls	565	-1	-13	0	-7%
Camden	048	-1	-22	0	-11%	Magnolia	561	0	-17	0	-8%
Cutler	046	-1	-22	0	-11%	Mankato	560	0	-6	0	-3%
Dexter	049	-2	-14	-1	-8%	Minneapolis	553-555	1	21	0	10%
Northern Area	047	-2	-18	-1	-9%	Rochester	559	0	-4	0	-2%
Portland	041	2	-3	1	0%	St Cloud	563	-1	12	0	5%
Maryland Average						St Paul	550-551	1	22	0	11%
Annapolis	214	3	12	1	7%	Thief River Falls	567	0	-2	0	-1%
Baltimore	210-212	-1	15	0	6%	Willmar	562	-1	-3	0	-2%
Bethesda	208-209	3	23	1	12%	Mississippi Average					
Church Hill	216	2	-10	1	-4%	Clarksdale	386	-3	-16	-1	-9%
Cumberland	215	-4	-17	-1	-10%	Columbus	397	-1	-7	0	-4%
Elkton	219	2	-3	1	0%	Greenville	387	-4	-24	-1	-13%
Frederick	217	1	6	0	3%	Greenwood	389	-3	-22	-1	-12%
Laurel	206-207	2	16	1	8%	Gulfport	395	-2	-9	-1	-5%
Salisbury	218	1	-12	0	-5%	Jackson	390-392	-3	-7	-1	-5%
						Laurel	394	-3	-12	-1	-7%

Area Modification Factors

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.	Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
McComb	396	-2	-20	-1	-10%	New Hampshire Average		1	-1	0	0%
Meridian	393	-2	-9	-1	-5%	Charlestown	036	1	-9	0	-4%
Tupelo	388	-1	-21	0	-10%	Concord	034	1	-5	0	-2%
						Dover	038	0	5	0	2%
Missouri Average		-1	-8	0	-4%	Lebanon	037	2	-6	1	-2%
Cape Girardeau	637	-2	-4	-1	-3%	Littleton	035	-1	-6	0	-3%
Caruthersville	638	-1	-12	0	-6%	Manchester	032-033	0	5	0	2%
Chillicothe	646	-2	-17	-1	-9%	New Boston	030-031	2	7	1	4%
Columbia	652	1	-11	0	-5%						
East Lynne	647	-1	-9	0	-5%	New Jersey Average		1	33	0	16%
Farmington	636	-3	-16	-1	-9%	Atlantic City	080-084	-2	26	-1	11%
Hannibal	634	1	-9	0	-4%	Brick	087	2	17	1	9%
Independence	640	-1	12	0	5%	Dover	078	1	35	0	17%
Jefferson City	650-651	1	-11	0	-5%	Edison	088-089	1	38	0	18%
Joplin	648	-2	-17	-1	-9%	Hackensack	076	3	32	1	16%
Kansas City	641	-2	15	-1	6%	Monmouth	077	3	35	1	18%
Kirksville	635	0	-26	0	-12%	Newark	071-073	2	35	1	17%
Knob Noster	653	0	-12	0	-6%	Passaic	070	2	36	1	18%
Lebanon	654-655	-2	-20	-1	-10%	Paterson	074-075	2	31	1	15%
Poplar Bluff	639	-1	-11	0	-6%	Princeton	085	-2	38	-1	16%
Saint Charles	633	1	-2	0	0%	Summit	079	3	45	1	22%
Saint Joseph	644-645	-3	8	-1	2%	Trenton	086	-3	33	-1	14%
Springfield	656-658	-2	-16	-1	-8%						
St Louis	630-631	-2	15	-1	6%	New Mexico Average		0	-20	0	-9%
						Alamogordo	883	-1	-25	0	-12%
Montana Average		0	-7	0	-3%	Albuquerque	870-871	2	-9	1	-3%
Billings	590-591	0	0	0	0%	Clovis	881	-2	-23	-1	-12%
Butte	597	1	-10	0	-4%	Farmington	874	2	-4	1	-1%
Fairview	592	-1	2	0	0%	Fort Sumner	882	-3	-2	-1	-3%
Great Falls	594	-1	-3	0	-2%	Gallup	873	1	-12	0	-5%
Havre	595	-1	-14	0	-7%	Holman	877	2	-26	1	-11%
Helena	596	0	-4	0	-2%	Las Cruces	880	-2	-24	-1	-12%
Kalispell	599	1	-15	0	-6%	Santa Fe	875	3	-22	1	-9%
Miles City	593	-1	-6	0	-3%	Socorro	878	1	-37	0	-17%
Missoula	598	1	-15	0	-6%	Truth or Consequences	879	-2	-29	-1	-14%
						Tucumcari	884	-1	-25	0	-12%
Nebraska Average		-1	-17	0	-8%						
Alliance	693	-1	-19	0	-9%	New York Average		0	22	0	10%
Columbus	686	0	-13	0	-6%	Albany	120-123	0	16	0	7%
Grand Island	688	0	-18	0	-8%	Amityville	117	2	34	1	17%
Hastings	689	0	-16	0	-7%	Batavia	140	-3	2	-1	-1%
Lincoln	683-685	0	-9	0	-4%	Binghamton	137-139	-3	3	-1	0%
McCook	690	0	-26	0	-12%	Bronx	104	2	33	1	16%
Norfolk	687	-3	-19	-1	-10%	Brooklyn	112	3	30	1	15%
North Platte	691	0	-21	0	-10%	Buffalo	142	-4	4	-1	0%
Omaha	680-681	-1	-3	0	-2%	Elmira	149	-4	3	-1	-1%
Valentine	692	-2	-29	-1	-14%	Flushing	113	3	50	1	25%
						Garden City	115	3	46	1	23%
Nevada Average		2	9	1	5%	Hicksville	118	3	42	1	21%
Carson City	897	2	-14	1	-5%	Ithaca	148	-4	-3	-1	-3%
Elko	898	1	54	0	25%	Jamaica	114	3	48	1	24%
Ely	893	2	4	1	3%	Jamestown	147	-4	-7	-1	-5%
Fallon	894	2	3	1	2%	Kingston	124	0	0	0	0%
Las Vegas	889-891	2	4	1	3%	Long Island	111	3	76	1	37%
Reno	895	2	1	1	2%						

Area Modification Factors

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.	Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Montauk	119	1	31	0	15%	Lima	458	-3	-7	-1	-5%
New York (Manhattan)	100-102	3	78	1	37%	Marietta	457	-2	-9	-1	-5%
New York City	100-102	3	78	1	37%	Marion	433	-3	-6	-1	-4%
Newcomb	128	-1	2	0	0%	Newark	430-431	-1	7	0	3%
Niagara Falls	143	-4	-10	-1	-7%	Sandusky	448-449	-1	1	0	0%
Plattsburgh	129	1	-1	0	0%	Steubenville	439	-3	-3	-1	-3%
Poughkeepsie	125-126	0	9	0	4%	Toledo	434-436	-1	17	0	7%
Queens	110	4	53	1	26%	Warren	444	-4	-1	-1	-3%
Rochester	144-146	-3	6	-1	1%	Youngstown	445	-5	7	-2	1%
Rockaway	116	3	38	1	19%	Zanesville	437-438	-2	1	-1	-1%
Rome	133-134	-3	-3	-1	-3%	Oklahoma Average		-3	-9	-1	-5%
Staten Island	103	3	29	1	15%	Adams	739	-2	-16	-1	-8%
Stewart	127	-1	-1	0	-1%	Ardmore	734	-3	-11	-1	-7%
Syracuse	130-132	-3	5	-1	1%	Clinton	736	-3	-4	-1	-3%
Tonawanda	141	-4	0	-1	-2%	Durant	747	-4	-22	-1	-12%
Utica	135	-4	-5	-1	-4%	Enid	737	-4	-6	-1	-5%
Watertown	136	-2	15	-1	6%	Lawton	735	-3	-22	-1	-12%
West Point	109	1	22	0	11%	McAlester	745	-4	-15	-1	-9%
White Plains	105-108	3	39	1	20%	Muskogee	744	-2	-17	-1	-9%
North Carolina Average		1	-10	0	-4%	Norman	730	-2	-4	-1	-3%
Asheville	287-289	1	-18	0	-8%	Oklahoma City	731	-2	-2	-1	-2%
Charlotte	280-282	1	10	0	5%	Ponca City	746	-3	2	-1	-1%
Durham	277	2	0	1	1%	Poteau	749	-2	-17	-1	-9%
Elizabeth City	279	1	-18	0	-8%	Pryor	743	-2	-21	-1	-11%
Fayetteville	283	-1	-14	0	-7%	Shawnee	748	-4	-21	-1	-12%
Goldsboro	275	1	-5	0	-2%	Tulsa	740-741	-1	-1	0	-1%
Greensboro	274	1	-11	0	-5%	Woodward	738	-4	6	-1	1%
Hickory	286	-1	-17	0	-8%	Oregon Average		1	-14	1	-6%
Kinston	285	-1	-19	0	-9%	Adrian	979	-1	-23	0	-11%
Raleigh	276	3	-2	1	1%	Bend	977	1	-14	0	-6%
Rocky Mount	278	-1	-15	0	-7%	Eugene	974	2	-7	1	-2%
Wilmington	284	1	-15	0	-6%	Grants Pass	975	2	-16	1	-6%
Winston-Salem	270-273	0	-10	0	-5%	Klamath Falls	976	2	-21	1	-9%
North Dakota Average		-1	9	0	4%	Pendleton	978	0	-10	0	-5%
Bismarck	585	0	6	0	3%	Portland	970-972	2	17	1	9%
Dickinson	586	-1	20	0	9%	Salem	973	2	-7	1	-2%
Fargo	580-581	0	5	0	2%	Pennsylvania Average		-3	0	-1	-1%
Grand Forks	582	0	0	0	0%	Allentown	181	-2	10	-1	4%
Jamestown	584	-1	-7	0	-4%	Altoona	166	-3	-12	-1	-7%
Minot	587	-1	20	0	9%	Beaver Springs	178	-3	-8	-1	-5%
Nekoma	583	-1	-17	0	-8%	Bethlehem	180	-1	12	0	5%
Williston	588	-1	43	0	19%	Bradford	167	-4	-11	-1	-7%
Ohio Average		-2	2	-1	0%	Butler	160	-4	0	-1	-2%
Akron	442-443	-2	7	-1	2%	Chambersburg	172	-1	-13	0	-7%
Canton	446-447	-2	-1	-1	-2%	Clearfield	168	2	-6	1	-2%
Chillicothe	456	-2	-8	-1	-5%	DuBois	158	-2	-19	-1	-10%
Cincinnati	450-452	-1	8	0	3%	East Stroudsburg	183	0	-9	0	-4%
Cleveland	440-441	-3	8	-1	2%	Erie	164-165	-3	-9	-1	-6%
Columbus	432	0	9	0	4%	Genesee	169	-4	-6	-1	-5%
Dayton	453-455	-3	-1	-1	-2%	Greensburg	156	-4	1	-1	-2%
						Harrisburg	170-171	-2	6	-1	2%

Area Modification Factors

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.	Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Hazleton	182	-3	-8	-1	-5%	Sioux Falls	570-571	0	-5	0	-2%
Johnstown	159	-4	-15	-1	-9%	Watertown	572	-1	-16	0	-8%
Kittanning	162	-4	-10	-1	-7%	Tennessee Average		-1	-4	0	-2%
Lancaster	175-176	-2	3	-1	0%	Chattanooga	374	-1	1	0	0%
Meadville	163	-4	-20	-1	-11%	Clarksville	370	1	4	0	2%
Montrose	188	-3	0	-1	-2%	Cleveland	373	-1	-2	0	-1%
New Castle	161	-4	0	-1	-2%	Columbia	384	-1	-15	0	-7%
Philadelphia	190-191	-3	29	-1	12%	Cookeville	385	0	-20	0	-9%
Pittsburgh	152	-4	14	-1	4%	Jackson	383	-1	-6	0	-3%
Pottsville	179	-4	-12	-1	-8%	Kingsport	376	0	-10	0	-5%
Punxsutawney	157	-4	-4	-1	-4%	Knoxville	377-379	-1	-2	0	-1%
Reading	195-196	-4	8	-1	2%	McKenzie	382	-1	-11	0	-6%
Scranton	184-185	-2	-3	-1	-2%	Memphis	380-381	-2	5	-1	1%
Somerset	155	-4	-12	-1	-8%	Nashville	371-372	1	10	0	5%
Southeastern	193	0	20	0	9%	Texas Average		-2	-1	-1	-2%
Uniontown	154	-4	-7	-1	-5%	Abilene	795-796	-4	-4	-1	-4%
Valley Forge	194	-3	32	-1	13%	Amarillo	790-791	-2	-6	-1	-4%
Warminster	189	-1	23	0	10%	Arlington	760	-1	3	0	1%
Warrendale	150-151	-4	14	-1	4%	Austin	786-787	1	5	0	3%
Washington	153	-3	24	-1	9%	Bay City	774	-2	50	-1	22%
Wilkes Barre	186-187	-3	-6	-1	-4%	Beaumont	776-777	-3	22	-1	9%
Williamsport	177	-3	0	-1	-2%	Brownwood	768	-3	-17	-1	-9%
York	173-174	-3	5	-1	1%	Bryan	778	0	-10	0	-5%
Rhode Island Average		1	15	0	7%	Childress	792	-3	-26	-1	-14%
Bristol	028	1	16	0	8%	Corpus Christi	783-784	-2	11	-1	4%
Coventry	028	1	16	0	8%	Dallas	751-753	-1	11	0	5%
Cranston	029	1	10	0	5%	Del Rio	788	-3	-14	-1	-8%
Davisville	028	1	16	0	8%	El Paso	798-799	-3	-21	-1	-11%
Narragansett	028	1	16	0	8%	Fort Worth	761-762	-2	3	-1	0%
Newport	028	1	16	0	8%	Galveston	775	-3	22	-1	9%
Providence	029	1	10	0	5%	Giddings	789	0	-3	0	-1%
Warwick	028	1	16	0	8%	Greenville	754	-3	10	-1	3%
South Carolina Average		0	-9	0	-4%	Houston	770-772	-1	24	0	11%
Aiken	298	0	6	0	3%	Huntsville	773	-2	23	-1	10%
Beaufort	299	-1	-14	0	-7%	Longview	756	-2	-2	-1	-2%
Charleston	294	-1	-3	0	-2%	Lubbock	793-794	-3	-12	-1	-7%
Columbia	290-292	0	-11	0	-5%	Lufkin	759	-3	-9	-1	-6%
Greenville	296	0	-8	0	-4%	McAllen	785	-3	-26	-1	-14%
Myrtle Beach	295	0	-20	0	-9%	Midland	797	-3	18	-1	7%
Rock Hill	297	0	-15	0	-7%	Palestine	758	-2	-13	-1	-7%
Spartanburg	293	-1	-6	0	-3%	Plano	750	-1	12	0	5%
South Dakota Average		-1	-15	0	-7%	San Angelo	769	-3	-13	-1	-8%
Aberdeen	574	-1	-12	0	-6%	San Antonio	780-782	-3	0	-1	-2%
Mitchell	573	0	-14	0	-6%	Texarkana	755	-3	-17	-1	-9%
Mobridge	576	-1	-22	0	-11%	Tyler	757	-1	-13	0	-7%
Pierre	575	-1	-23	0	-11%	Victoria	779	-3	1	-1	-1%
Rapid City	577	-1	-14	0	-7%	Waco	765-767	-3	-10	-1	-6%
						Wichita Falls	763	-3	-20	-1	-11%
						Woodson	764	-3	-10	-1	-6%

Area Modification Factors

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.	Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Utah Average		1	-10	1	-4%	Wenatchee	988	1	-13	0	-5%
Clearfield	840	2	-1	1	1%	Yakima	989	0	-10	0	-5%
Green River	845	1	-5	0	-2%	West Virginia Average		-2	-9	-1	-5%
Ogden	843-844	0	-22	0	-10%	Beckley	258-259	1	-15	0	-6%
Provo	846-847	2	-21	1	-9%	Bluefield	247-248	-1	2	0	0%
Salt Lake City	841	2	0	1	1%	Charleston	250-253	1	7	0	4%
Vermont Average		1	-12	0	-5%	Clarksburg	263-264	-3	-6	-1	-4%
Albany	058	1	-15	0	-6%	Fairmont	266	0	-23	0	-11%
Battleboro	053	1	-11	0	-5%	Huntington	255-257	-1	-2	0	-1%
Beecher Falls	059	1	-17	0	-7%	Lewisburg	249	-2	-31	-1	-15%
Bennington	052	-1	-16	0	-8%	Martinsburg	254	-1	-9	0	-5%
Burlington	054	2	3	1	2%	Morgantown	265	-3	-9	-1	-6%
Montpelier	056	2	-10	1	-4%	New Martinsville	262	-2	-17	-1	-9%
Rutland	057	-1	-15	0	-7%	Parkersburg	261	-3	5	-1	1%
Springfield	051	-1	-14	0	-7%	Romney	267	-4	-11	-1	-7%
White River Junction	050	1	-14	0	-6%	Sugar Grove	268	-3	-12	-1	-7%
Virginia Average		0	-10	0	-5%	Wheeling	260	-3	-2	-1	-3%
Abingdon	242	-2	-16	-1	-8%	Wisconsin Average		-1	1	0	0%
Alexandria	220-223	3	18	1	10%	Amery	540	0	-3	0	-1%
Charlottesville	229	1	-15	0	-6%	Beloit	535	0	9	0	4%
Chesapeake	233	0	-4	0	-2%	Clam Lake	545	-1	-12	0	-6%
Culpeper	227	2	-11	1	-4%	Eau Claire	547	-1	-2	0	-1%
Farmville	239	-2	-26	-1	-13%	Green Bay	541-543	0	4	0	2%
Fredericksburg	224-225	1	-11	0	-5%	La Crosse	546	-2	-2	-1	-2%
Galax	243	-2	-19	-1	-10%	Ladysmith	548	-2	-2	-1	-2%
Harrisonburg	228	1	-19	0	-8%	Madison	537	2	13	1	7%
Lynchburg	245	-2	-16	-1	-8%	Milwaukee	530-534	0	13	0	6%
Norfolk	235-237	0	-3	0	-1%	Oshkosh	549	-1	5	0	2%
Petersburg	238	-2	-7	-1	-4%	Portage	539	0	6	0	3%
Radford	241	-1	-21	0	-10%	Prairie du Chien	538	-2	-6	-1	-4%
Reston	201	3	14	1	8%	Wausau	544	-1	-5	0	-3%
Richmond	232	-1	1	0	0%	Wyoming Average		0	-6	0	-3%
Roanoke	240	-1	-21	0	-10%	Casper	826	-2	8	-1	3%
Staunton	244	0	-22	0	-10%	Cheyenne/ Laramie	820	1	-11	0	-5%
Tazewell	246	-3	-11	-1	-7%	Gillette	827	-1	4	0	1%
Virginia Beach	234	0	-9	0	-4%	Powell	824	0	-15	0	-7%
Williamsburg	230-231	0	-9	0	-4%	Rawlins	823	0	2	0	1%
Winchester	226	0	-11	0	-5%	Riverton	825	-1	-10	0	-5%
Washington Average		1	-2	0	0%	Rock Springs	829-831	0	2	0	1%
Clarkston	994	0	-12	0	-6%	Sheridan	828	0	-12	0	-6%
Everett	982	2	3	1	2%	Wheatland	822	0	-18	0	-8%
Olympia	985	2	-7	1	-2%	UNITED STATES TERRITORIES					
Pasco	993	0	2	0	1%	Guam	53	-21	-5	18%	
Seattle	980-981	3	20	1	11%	Puerto Rico	2	-47	-5	-21%	
Spokane	990-992	0	-6	0	-3%	VIRGIN ISLANDS (U.S.)					
Tacoma	983-984	1	4	0	2%	St. Croix	18	-15	-4	2%	
Vancouver	986	2	4	1	3%	St. John	52	-15	-4	20%	
						St. Thomas	23	-15	-4	5%	

Canadian Area Modification Factors

To find the cost in Canada in Canadian dollars, increase the costs in this book by the appropriate percentage listed below. These figures convert costs to Canadian dollars based on \$1.00 Canadian to \$0.95 U.S.

Location	Mat.	Lab.	Equip.	Total Wtd. Avg.
Alberta Average	20	5	7	13%
Calgary	20	7	7	14%
Edmonton	19	8	7	14%
Fort McMurray	22	-1	7	11%
British Columbia Average	20	-9	7	7%
Fraser Valley	20	-10	7	6%
Okanagan	21	-12	7	6%
Vancouver	20	-5	7	8%
Manitoba Average	14	-16	5	0%
North Manitoba	14	-16	5	0%
South Manitoba	14	-16	5	0%
Selkirk	14	-16	5	0%
Winnipeg	14	-16	5	0%
New Brunswick Average	10	-41	3	-14%
Moncton	10	-41	3	-14%

Location	Mat.	Lab.	Equip.	Total Wtd. Avg.
Nova Scotia Average	11	-30	4	-8%
Amherst	10	-30	3	-9%
Nova Scotia	11	-29	4	-8%
Sydney	11	-31	4	-8%
Newfoundland/Labrador Average	13	-29	4	-6%
Ontario Average	16	-5	5	6%
London	16	-4	5	7%
Thunder Bay	18	-8	6	6%
Toronto	15	-3	5	7%
Quebec Average	13	-18	4	-1%
Montreal	13	-18	4	-1%
Quebec City	13	-18	4	-1%
Saskatchewan Average	17	-12	5	3%
La Ronge	18	-15	6	3%
Prince Albert	16	-14	5	2%
Saskatoon	16	-8	5	5%

Demolition

2



Nearly all home improvement projects require some breaking out and removing of existing materials and disposal of debris. Most will require protection of adjacent surfaces, taking safety precautions (such as setting up barricades), closing off doorways or windows, and normal cleanup. The demolition figures in this chapter include these tasks and will apply on most home improvement jobs that don't involve unusual conditions or complications. Costs will be higher when access to the work is limited, when your crew doesn't have complete control of the construction site, or when debris must be moved longer distances or around obstacles. All figures assume that debris is piled on site or in a bin. Add the cost of hauling to the nearest disposal site and tippage charges, if required. No salvage value is assumed except as noted.

Many of the following chapters include estimated costs to remove the old and replace with new materials of a similar description. For example, you'll find costs for removing shingles and replacing shingles in the roofing chapter. That's appropriate because they're part of the same task and usually performed by the same contractor. The estimates in this chapter are for demolition only and don't consider the cost of replacing what has been removed.

Of all construction tasks, demolition is probably the most difficult to estimate with any certainty. You're never sure what's in a wall to be demolished until the job begins. That's why it's best to exclude from your demolition bid what isn't in your estimate. Use the checklist to the right to help identify potential problems before they develop.

Demolition Checklist

- Can you anticipate any problem getting a demolition permit for this job?
- Is there a noise ordinance which will limit hours of operation or selection of equipment?
- Can the debris box be located close to the work?
- Can a trencher get to the job site?
- Is the site accessible to wheeled equipment?
- Will the debris have to be hand-carried to the roll-off box or gondola?
- Is there a direct route from the demolition site to the debris box?
- Will you need to re-route any plumbing, electrical, phone or gas lines?
- Will you need to remove and replace lawn sprinklers?
- Will you need to cut back or remove any bushes or trees?
- Will you have to remove and re-install a fence or gate?
- Does a septic tank or drain field extend into the site of construction?
- Can (must) materials generated from your project be recycled or salvaged?

	Day	Week	Month
Equipment Rental for Demolition.			
Air compressors, wheel-mounted			
16 CFM, shop type, electric	65.50	156.00	467.00
30 CFM, shop type, electric	41.40	214.00	644.00
80 CFM, shop type, electric	83.60	254.00	760.00
100 CFM, gasoline unit	104.00	312.00	877.00
125 CFM, gasoline unit	130.00	390.00	1,170.00
Paving breakers (no bits included) hand-held, pneumatic			
To 40 lb	29.00	84.00	226.00
41 - 55 lb	35.00	85.00	250.00
56 - 70 lb	34.00	105.00	275.00
71 - 90 lb	38.00	110.00	305.00
Paving breakers jackhammer bits			
Moil points, 15" to 18"	6.00	14.00	30.00
Chisels, 3"	7.00	17.00	44.00
Clay spades, 5-1/2"	10.00	23.00	62.00
Asphalt cutters, 5"	8.00	24.00	51.00
Pneumatic chippers, medium weight, 10 lb	35.00	95.00	250.00
Air hose rental, 50 LF section			
5/8" air hose	6.00	15.00	40.00
3/4" air hose	7.00	20.00	51.00
1" air hose	10.00	29.00	62.00
1-1/2" air hose	18.00	58.00	149.00
Dump truck rental rate plus mileage			
3 CY	250.00	740.00	1,730.00
5 CY	315.00	895.00	2,720.00
Hammer rental			
Electric brute breaker	60.00	232.00	725.00
Gas breaker	65.00	255.00	760.00
Demolition hammer, electric	53.00	210.00	600.00
Roto hammer, 7/8", electric	55.00	220.00	620.00
Roto hammer, 1-1/2", electric	54.00	187.00	535.00
Stump grinder, 9 HP	113.00	450.00	1,310.00
Brush chipper, trailer-mounted 40 HP	222.00	866.00	1,940.00
Chain saw, 18", gasoline	55.00	255.00	650.00
Chop saw, 14", electric	37.00	150.00	440.00
Backhoe/loader, wheel-mounted, diesel or gasoline			
1/2 CY bucket capacity, 55 HP	210.00	625.00	1,770.00
1 CY bucket capacity, 65 HP	310.00	980.00	2,810.00
1-1/4 CY bucket capacity, 75 HP	240.00	650.00	1,900.00
1-1/2 CY bucket capacity, 100 HP	300.00	850.00	2,320.00
Wheel loader, front-end load and dump, diesel			
3/4 CY bucket, 4WD, articulated	210.00	600.00	1,700.00
1 CY bucket, 4WD, articulated	290.00	840.00	2,420.00
2 CY bucket, 4WD, articulated	370.00	1,090.00	3,300.00

	Craft@Hrs	Unit	Material	Labor	Total	Sell
Sitework Demolition						
Debris disposal and removal. Tipping charges for solid waste disposal at the dump vary from \$30 to \$120 per ton. For planning purposes, estimate waste disposal at \$75 per ton, plus the hauling cost. Call the dump or trash disposal company for actual charges. Typical costs are shown below.						
Dumpster, 3 CY trash bin, emptied weekly	—	Mo	—	—	330.00	—
Dumpster, 40 CY solid waste bin (lumber, drywall, roofing)						
Hauling cost, per load	—	Ea	—	—	230.00	—
Add to per load charge, per ton	—	Ton	—	—	55.00	—
Low-boy, 14 CY solid waste container (asphalt, dirt, masonry, concrete)						
Hauling cost, per load (7 CY maximum load)	—	Ea	—	—	230.00	—
Add to per load charge, per ton	—	Ton	—	—	55.00	—
Recycler fees. Recycling construction waste materials can substantially reduce disposal costs. Recycling charges vary from \$95 to \$120 per load, depending on the type of material and the size of the load. Add the cost of hauling to a recycling facility.						
Greenwaste	—	Ton	—	—	30.00	—
Asphalt, per load (7 CY)	—	Ea	—	—	100.00	—
Concrete, masonry or rock, per load (7 CY)	—	Ea	—	—	100.00	—
Dirt, per load (7 CY)	—	Ea	—	—	100.00	—
Mixed loads, per load (7 CY)	—	Ea	—	—	100.00	—
Bush and tree removal. Includes cutting into manageable pieces with power hand tools and dumping debris in a trash bin on site. Add the cost of power equipment rental, if needed.						
Shrubs and bushes, including stump removal.						
4' high, per each	BL@.750	Ea	—	21.80	21.80	37.10
Tree removal. Costs will vary widely depending on the condition, size, location and accessibility of the tree. Includes cutting into manageable pieces with power hand tools and dumping debris in a trash bin or chipper on site. Does not include stump removal or grinding. Add the cost of power equipment rental, bucket truck, and other specialized equipment if needed. Large shade tree removal may require a crew of 5 or more. Use \$2,000 as a minimum job charge for trees with a 36" diameter trunk and larger.						
8" to 12" diameter trunk	B8@2.50	Ea	—	87.60	87.60	149.00
13" to 18" diameter trunk	B8@3.50	Ea	—	123.00	123.00	209.00
19" to 24" diameter trunk	B8@5.50	Ea	—	193.00	193.00	328.00
25" to 36" diameter trunk	B8@7.00	Ea	—	245.00	245.00	417.00
Stump grinding, using a 9 HP wheel-mounted stump grinder						
6" to 10" diameter stump	B8@.800	Ea	—	28.00	28.00	47.60
11" to 14" diameter stump	B8@1.04	Ea	—	36.40	36.40	61.90
15" to 18" diameter stump	B8@1.30	Ea	—	45.50	45.50	77.40
19" to 24" diameter stump	B8@1.50	Ea	—	52.50	52.50	89.30
Fencing demolition. Remove chain link fence and cemented posts for disposal. These figures assume fencing is removed by cutting ties at posts and rails and rolling the fabric. These rolls can be heavy. A larger crew will be needed on larger jobs.						
To 6' high	BL@.100	LF	—	2.91	2.91	4.95
Remove chain link fence and cemented posts for salvage,						
To 6' high	BL@.120	LF	—	3.50	3.50	5.95
Remove board fence and cemented posts for disposal,						
To 6' high	BL@.100	LF	—	2.91	2.91	4.95

	Craft@Hrs	Unit	Material	Labor	Total	Sell
Building Demolition						
Single-story room demolition. Includes breaking out a concrete or masonry foundation using pneumatic tools, breaking materials into manageable pieces with hand tools and handling debris to a trash bin on site. Includes the cost of erecting a temporary vapor barrier to seal the wall opening in the existing structure. Add the cost of wall patching on the remaining structure. Add the cost of equipment rental.						
Demolish a wood-frame addition built on a concrete slab, including grade beams. Use these figures to estimate the cost of demolishing an attached garage.						
Per square foot of floor area demolished	BL@.100	SF	—	2.91	2.91	4.95
Demolish a wood-frame addition built on a conventional foundation, including wood deck, stairs to grade, and the concrete or concrete block foundation.						
Per square foot of floor area demolished	BL@.120	SF	—	3.50	3.50	5.95
Detached garage demolition. Includes breaking materials into manageable pieces with hand tools and handling debris to a trash bin on site. No slab or foundation demolition included. No salvage of materials assumed.						
Frame garage with wood or aluminum siding						
One-car garage, to 10' wide by 22' deep	BL@16.5	Ea	—	481.00	481.00	818.00
Two-car garage, to 20' wide by 28' deep	BL@23.0	Ea	—	670.00	670.00	1,140.00
Frame garage with stucco siding						
One-car garage to 12' wide by 22' deep	BL@23.5	Ea	—	685.00	685.00	1,160.00
One-car to 16' wide by 22' deep	BL@28.5	Ea	—	830.00	830.00	1,410.00
Two-car garage to 22' wide by 28' deep	BL@42.5	Ea	—	1,240.00	1,240.00	2,110.00
Brick or block garage						
One-car garage to 12' wide by 22' deep	BL@23.0	Ea	—	670.00	670.00	1,140.00
One-car garage to 16' wide by 22' deep	BL@28.0	Ea	—	816.00	816.00	1,390.00
Two-car garage to 20' wide by 22' deep	BL@33.0	Ea	—	961.00	961.00	1,630.00
Gutting a building. Interior finish stripped back to the structural walls. Building structure to remain. No allowance for salvage value. These costs include loading and hauling up to 6 miles but no dump fees. Costs are per square foot of floor area based on 8' ceiling height. Add the cost of equipment rental. Figures in parentheses show the approximate "loose" volume of materials after demolition.						
Residential building (125 SF per CY)	BL@.100	SF	—	2.91	2.91	4.95
Building Component Demolition. Itemized costs for demolition of building components when building is being remodeled, repaired or rehabilitated and not completely demolished. Costs include protecting adjacent areas and normal clean-up. Costs are to break out the items listed and pile debris on site or in a bin.						
Brick wall demolition. Cost per square foot removed measured on one face. Removed using a pneumatic breaker. Add the cost of equipment rental. Figures in parentheses show the volume before and after demolition and weight of the materials after demolition.						
4" thick walls (60 SF per CY and 36 lbs. per SF)	BL@.061	SF	—	1.78	1.78	3.03
8" thick walls (30 SF per CY and 72 lbs. per SF)	BL@.110	SF	—	3.20	3.20	5.44

	Craft@Hrs	Unit	Material	Labor	Total	Sell
Brick sidewalk demolition. Cost per square foot removed. Add the cost of Bobcat rental. Larger jobs will require a crew of 2 or more. Figures in parentheses show the volume before and after demolition and weight of materials after demolition.						
2-1/2" thick brick on sand base, no mortar bed, removed using hand tools (100 SF per CY and 28 lbs. per SF)	BL@.010	SF	—	.29	.29	.49
Brick pavers up to 4-1/2" thick with mortar bed, removed using a pneumatic breaker (55 SF per CY and 50 lbs. per SF)	BL@.050	SF	—	1.46	1.46	2.48

Concrete masonry wall demolition. Cost per square foot of wall removed measured on one side. Removed using a pneumatic breaker. Add the cost of equipment rental. Figures in parentheses show the volume before and after demolition and weight of materials after demolition.

4" thick walls (60 SF per CY and 19 lbs. per SF)	BL@.066	SF	—	1.92	1.92	3.26
6" thick walls (40 SF per CY and 28 lbs. per SF)	BL@.075	SF	—	2.18	2.18	3.71
8" thick walls (30 SF per CY and 34 lbs. per SF)	BL@.098	SF	—	2.85	2.85	4.85
12" thick walls (20 SF per CY and 46 lbs. per SF)	BL@.140	SF	—	4.08	4.08	6.94
Reinforced or grouted walls add	—	%	—	—	50.0	—

Concrete foundation demolition (footings). Steel reinforced, removed using a pneumatic breaker. Add the cost of equipment rental. Figures in parentheses show the volume before and after demolition.

Cost per CY (.75 CY per CY)	BL@3.96	CY	—	115.00	115.00	196.00
Cost per LF with width and depth as shown						
6" W x 12" D (35 LF per CY)	BL@.075	LF	—	2.18	2.18	3.71
8" W x 12" D (30 LF per CY)	BL@.098	LF	—	2.85	2.85	4.85
8" W x 16" D (20 LF per CY)	BL@.133	LF	—	3.87	3.87	6.58
8" W x 18" D (18 LF per CY)	BL@.147	LF	—	4.28	4.28	7.28
10" W x 12" D (21 LF per CY)	BL@.121	LF	—	3.52	3.52	5.98
10" W x 16" D (16 LF per CY)	BL@.165	LF	—	4.81	4.81	8.18
10" W x 18" D (14 LF per CY)	BL@.185	LF	—	5.39	5.39	9.16
12" W x 12" D (20 LF per CY)	BL@.147	LF	—	4.28	4.28	7.28
12" W x 16" D (13 LF per CY)	BL@.196	LF	—	5.71	5.71	9.71
12" W x 20" D (11 LF per CY)	BL@.245	LF	—	7.14	7.14	12.10
12" W x 24" D (9 LF per CY)	BL@.294	LF	—	8.56	8.56	14.60

Concrete sidewalk demolition. To 4" thick, cost per SF removed. Figures in parentheses show the volume before and after demolition.

Non-reinforced, removed by hand with sledge (60 SF per CY)	BL@.050	SF	—	1.46	1.46	2.48
Reinforced with wire mesh. Mesh cut into manageable pieces, then removed using pneumatic breaker. Add the cost of equipment rental.						
(55 SF per CY)	BL@.060	SF	—	1.75	1.75	2.98

	Craft@Hrs	Unit	Material	Labor	Total	Sell
Porch and deck demolition. Includes breaking materials into manageable pieces with hand tools and handling debris to a trash bin on site.						
Demolish an enclosed wood-frame porch. Includes breaking out the concrete or masonry pier foundation. Per square foot of floor.						
One story	BL@.250	SF	—	7.28	7.28	12.40
Two story	BL@.225	SF	—	6.55	6.55	11.10
Three story	BL@.196	SF	—	5.71	5.71	9.71
Demolish a screened porch built on a concrete slab. Includes demolition of one concrete or wood frame step to grade. Per square foot of floor area.						
Porch and one step (no slab demolition)	BL@.100	SF	—	2.91	2.91	4.95
Demolish a wood deck with railing or kneewall. Includes demolition of the wood deck and up to 7 steps to grade.						
Deck to 150 SF	BL@18.5	Ea	—	539.00	539.00	916.00
Add per SF for deck over 150 SF	BL@.100	SF	—	2.91	2.91	4.95

Concrete slab demolition. Break up and remove concrete slab using a compressor and pneumatic hammer.

Includes loosening concrete with a pick and handling debris to a trash bin on site. Costs for demolition of reinforced concrete slab include burning off rebars with an acetylene torch. Add the rental cost of a compressor, pneumatic hammer and a torch, as required. Figures in parentheses show the volume before and after demolition.

4" non-reinforced concrete (60 SF per CY)	BL@.057	SF	—	1.66	1.66	2.82
4" reinforced concrete (60 SF per CY)	BL@.071	SF	—	2.07	2.07	3.52
6" non-reinforced concrete (45 SF per CY)	BL@.083	SF	—	2.42	2.42	4.11
6" reinforced concrete (45 SF per CY)	BL@.103	SF	—	3.00	3.00	5.10
8" non-reinforced concrete (30 SF per CY)	BL@.109	SF	—	3.18	3.18	5.41
8" reinforced concrete (30 SF per CY)	BL@.122	SF	—	3.55	3.55	6.04

Asphalt pavement demolition. Asphaltic concrete (bituminous) 3" thick, removed using a pneumatic spade. Add the cost of equipment rental and dump fees. Figures in parentheses show the volume before and after demolition and weight of debris.

Break up and shovel on to a truck (4 SY per CY and 660 lbs. per SY)	BL@.140	SY	—	4.08	4.08	6.94
--	---------	----	---	------	------	------

Concrete wall demolition. Steel reinforced, removed using a compressor and pneumatic breaker. Add the cost of equipment rental. Figures in parentheses show the volume before and after demolition.

Cost per CY (1.33 CY per CY)	BL@4.76	CY	—	139.00	139.00	236.00
Cost per SF with thickness as shown						
3" wall thickness (80 SF per CY)	BL@.045	SF	—	1.31	1.31	2.23
4" wall thickness (55 SF per CY)	BL@.058	SF	—	1.69	1.69	2.87
5" wall thickness (45 SF per CY)	BL@.075	SF	—	2.18	2.18	3.71
6" wall thickness (40 SF per CY)	BL@.090	SF	—	2.62	2.62	4.45
8" wall thickness (30 SF per CY)	BL@.120	SF	—	3.50	3.50	5.95
10" wall thickness (25 SF per CY)	BL@.147	SF	—	4.28	4.28	7.28
12" wall thickness (20 SF per CY)	BL@.176	SF	—	5.13	5.13	8.72

	Craft@Hrs	Unit	Material	Labor	Total	Sell
Wood Framing Demolition. Typical costs for demolition of wood frame structural components using hand tools. Normal center-to-center spacing (12" thru 24" OC) is assumed. Includes breaking materials into manageable pieces with hand tools and handling debris to a trash bin on site. Costs include removal of Romex cable as necessary, protecting adjacent areas, and normal clean-up. Costs do not include temporary shoring to support structural elements above or adjacent to the work area. (Add for demolition of flooring, roofing, sheathing, etc.) Figures in parentheses give the approximate "loose" volume and weight of the materials after being demolished.						
Ceiling joist demolition. Per in-place SF of ceiling area removed.						
2" x 4" (720 SF per CY and 1.18 lbs. per SF)	BL@.009	SF	—	.26	.26	.44
2" x 6" (410 SF per CY and 1.76 lbs. per SF)	BL@.013	SF	—	.38	.38	.65
2" x 8" (290 SF per CY and 2.34 lbs. per SF)	BL@.018	SF	—	.52	.52	.88
2" x 10" (220 SF per CY and 2.94 lbs. per SF)	BL@.023	SF	—	.67	.67	1.14
2" x 12" (190 SF per CY and 3.52 lbs. per SF)	BL@.027	SF	—	.79	.79	1.34
Floor joist demolition. Per in-place SF of floor area removed.						
2" x 6" (290 SF per CY and 2.04 lbs. per SF)	BL@.016	SF	—	.47	.47	.80
2" x 8" (190 SF per CY and 2.72 lbs. per SF)	BL@.021	SF	—	.61	.61	1.04
2" x 10" (160 SF per CY and 3.42 lbs. per SF)	BL@.026	SF	—	.76	.76	1.29
2" x 12" (120 SF per CY and 4.10 lbs. per SF)	BL@.031	SF	—	.90	.90	1.53
Rafter demolition. Per in-place SF of actual roof area removed.						
2" x 4" (610 SF per CY and 1.42 lbs. per SF)	BL@.011	SF	—	.32	.32	.54
2" x 6" (360 SF per CY and 2.04 lbs. per SF)	BL@.016	SF	—	.47	.47	.80
2" x 8" (270 SF per CY and 2.68 lbs. per SF)	BL@.020	SF	—	.58	.58	.99
2" x 10" (210 SF per CY and 3.36 lbs. per SF)	BL@.026	SF	—	.76	.76	1.29
2" x 12" (180 SF per CY and 3.94 lbs. per SF)	BL@.030	SF	—	.87	.87	1.48
Stud wall demolition. Interior or exterior, includes allowance for plates and blocking, per in-place SF of wall area removed, measured on one face.						
2" x 3" (430 SF per CY and 1.92 lbs. per SF)	BL@.013	SF	—	.38	.38	.65
2" x 4" (310 SF per CY and 2.58 lbs. per SF)	BL@.017	SF	—	.50	.50	.85
2" x 6" (190 SF per CY and 3.74 lbs. per SF)	BL@.025	SF	—	.73	.73	1.24
Stud wall demolition, salvage condition. Remove wall cover (nailed hardboard or fiberboard) from partition wall and salvage the stud framing. Per linear foot of stud wall.						
2" x 4" x 8', 16" on center	BL@.156	LF	—	4.54	4.54	7.72
Roof cover demolition. Includes breaking materials into manageable pieces with hand tools and handling debris to a trash bin on site. Cost per Sq or "square". (1 square = 100 square feet.) Figures in parentheses show the approximate "loose" volume and weight of materials after being demolished.						
Built-up, 5 ply (2.5 Sq per CY and 250 lbs per Sq)	BL@1.50	Sq	—	43.70	43.70	74.30
Shingles, asphalt, single layer (2.5 Sq per CY and 240 lbs per Sq)	BL@1.33	Sq	—	38.70	38.70	65.80
Shingles, asphalt, double layer (1.2 Sq per CY and 480 lbs per Sq)	BL@2.00	Sq	—	58.30	58.30	99.10
Shingles, slate. Weight ranges from 600 lbs. to 1,200 lbs. per Sq (1 Sq per CY and 900 lbs per Sq)	BL@1.79	Sq	—	52.10	52.10	88.60

	Craft@Hrs	Unit	Material	Labor	Total	Sell
Shingles, wood (1.7 Sq per CY and 400 lbs per Sq)	BL@2.02	Sq	—	58.80	58.80	100.00
Clay or concrete tile (.70 Sq per CY)	BL@1.65	Sq	—	48.10	48.10	81.80
Remove gravel stop or flashing	BL@.070	LF	—	2.04	2.04	3.47
Interior and exterior finish demolition. Includes breaking materials into manageable pieces with hand tools and handling debris to a trash bin on site. Figures in parentheses show the approximate "loose" volume and weight of the materials after being demolished. Demolition for disposal. No salvage of materials included.						
Plywood sheathing, up to 1" thick, cost per in-place SF (200 SF per CY and 2 lbs. per SF)						
	BL@.017	SF	—	.50	.50	.85
Wood board sheathing (250 SF per CY and 2 lbs. per SF)						
	BL@.030	SF	—	.87	.87	1.48
Metal siding, using hand tools (200 SF per CY and 2 lbs. per SF)						
	BL@.027	SF	—	.79	.79	1.34
Stucco on walls or soffits, cost per in-place SF, removed using hand tools (150 SF per CY and 8 lbs. per SF)						
	BL@.036	SF	—	1.05	1.05	1.79
Wallboard 1/2" thick, cost per in-place SF, removed using hand tools. Add 50% to labor costs for 1" wallboard.						
Gypsum, walls or ceilings (250 SF per CY and 2.3 lbs. per SF)						
	BL@.010	SF	—	.29	.29	.49
Including strip furring						
	BL@.015	SF	—	.44	.44	.75
Plywood or insulation board (200 SF per CY and 2 lbs. per SF)						
	BL@.018	SF	—	.52	.52	.88
Insulation, fiberglass batts or rolls, cost per square foot removed (500 SF per CY and .3 lb per SF)						
	BL@.003	SF	—	.09	.09	.15
Plaster on walls, cost per square foot removed by hand (150 SF per CY and 8 lbs. per SF)						
	BL@.015	SF	—	.44	.44	.75
Remove baseboard molding						
Single member base, no salvage						
	BL@.022	LF	—	.64	.64	1.09
Base and base shoe, no salvage						
	BL@.038	LF	—	1.11	1.11	1.89
Remove and salvage single member base						
	BL@.025	LF	—	.73	.73	1.24
Remove and salvage base and base shoe						
	BL@.044	LF	—	1.28	1.28	2.18

Ceiling demolition. Knock down with hand tools at heights to 9' and handle debris to a trash bin on site. Building structure to remain. No allowance for salvage value. Costs shown are per square foot of ceiling. Figures in parentheses show the approximate "loose" volume after demolition.

Plaster ceiling (typically 175 to 200 SF per CY)						
Including lath and furring						
	BL@.025	SF	—	.73	.73	1.24
Including suspended grid						
	BL@.020	SF	—	.58	.58	.99
Acoustic tile ceiling (typically 200 to 250 SF per CY)						
Including suspended grid						
	BL@.010	SF	—	.29	.29	.49
Including grid in salvage condition						
	BL@.019	SF	—	.55	.55	.94
Tile glued or stapled to ceiling						
	BL@.015	SF	—	.44	.44	.75
Tile on strip furring, including furring						
	BL@.025	SF	—	.73	.73	1.24
Drywall ceiling (typically 250 to 300 SF per CY)						
Nailed or attached with screws to joists						
	BL@.010	SF	—	.29	.29	.49

	Craft@Hrs	Unit	Material	Labor	Total	Sell
Floor cover demolition. Includes breaking materials into manageable pieces with hand tools and handling debris to a trash bin on site. Cost per square yard of floor removed. (1 square yard = 9 square feet.) Figures in parentheses show the approximate "loose" volume and weight of the materials after demolition.						
Ceramic tile (25 SY per CY and 34 lbs. per SY)	BL@.263	SY	—	7.66	7.66	13.00
Hardwood, nailed (25 SY per CY and 18 lbs. per SY)	BL@.290	SY	—	8.45	8.45	14.40
Hardwood, glued (25 SY per CY and 18 lbs. per SY)	BL@.503	SY	—	14.70	14.70	25.00
Linoleum, sheet (30 SY per CY and 3 lbs. per SY)	BL@.056	SY	—	1.63	1.63	2.77
Resilient tile (30 SY per CY and 3 lbs. per SY)	BL@.300	SY	—	8.74	8.74	14.90
Terrazzo (25 SY per CY and 34 lbs. per SY)	BL@.286	SY	—	8.33	8.33	14.20
Carpet on tack strip (40 SY per CY and 5 lbs. per SY)	BL@.028	SY	—	.82	.82	1.39
Glue-down carpet with rubber backing (35 SY per CY and 1.7 lbs. per SY)	BL@.160	SY	—	4.66	4.66	7.92
Add for each LF of room perimeter	BL@.008	LF	—	.23	.23	.39
Carpet pad (35 SY per CY and 1.7 lbs. per SY)	BL@.014	SY	—	.41	.41	.70
Removal of interior items. Includes breaking materials into manageable pieces with hand tools and handling debris to a trash bin on site. Items removed in salvageable condition do not include an allowance for salvage value. Figures in parentheses give the approximate "loose" volume of the materials after demolition. Removed in non-salvageable condition (demolished) except as noted.						
Windows, typical cost to remove window, frame and hardware, cost per SF of window						
Metal (36 SF per CY)	BL@.058	SF	—	1.69	1.69	2.87
Wood (36 SF per CY)	BL@.063	SF	—	1.84	1.84	3.13
Wood stairs, cost per in-place SF or LF						
Risers (25 SF per CY)	BL@.116	SF	—	3.38	3.38	5.75
Landings (50 SF per CY)	BL@.021	SF	—	.61	.61	1.04
Handrails (100 LF per CY)	BL@.044	LF	—	1.28	1.28	2.18
Posts (200 LF per CY)	BL@.075	LF	—	2.18	2.18	3.71
Hollow metal door and frame in a masonry wall. (2 doors per CY)						
Single door to 4' x 7'	BL@1.00	Ea	—	29.10	29.10	49.50
Two doors, per opening to 8' x 7'	BL@1.50	Ea	—	43.70	43.70	74.30
Wood door and frame in a wood frame wall (2 doors per CY)						
Single door to 4' x 7'	BL@.500	Ea	—	14.60	14.60	24.80
Two doors, per opening to 8' x 7'	BL@.750	Ea	—	21.80	21.80	37.10
Metal door and frame in masonry wall, salvage condition						
Hollow metal door to 4' x 7'	BL@2.00	Ea	—	58.30	58.30	99.10
Wood door to 4' x 7'	BL@1.00	Ea	—	29.10	29.10	49.50

Index

- A**
- Abbreviations17
 - ABS pipe408
 - Absorber, water surge407
 - ABTCO251
 - AC cable419
 - AC quiet rocker switch, Decora434
 - AC quiet toggle switch434
 - Access door248
 - Access doors, foundation88
 - Accessories, ridge vents90
 - Acid cleaning
 - masonry115
 - wash50, 115
 - Acid wash, manhours466
 - Acknowledgments2
 - Acoustic ceiling texture, labor469
 - Acoustic roll-on493
 - Acoustic tile
 - demolition34, 315
 - Acoustical ceiling
 - ceiling tile253
 - demolition254
 - panel255-257
 - patch245
 - suspended256
 - texture touch-up kit244
 - tile adhesive254
 - Acousti-Tex ceiling texture245
 - Acrylic
 - latex paint492
 - mirrored sheet171
 - mortar admix307
 - paint40
 - roof coating137
 - sheet171
 - skylights173
 - stain487
 - suspended lighting
 - panel258
 - tape291
 - wood filler281
 - Actuating devices, garage doors225
 - Adapter, box421
 - Additive
 - feather edge286
 - resilient flooring285
 - Additives
 - coloring47
 - concrete47
 - Perlite paint texturing493
 - Adhesive
 - acoustical ceiling tile254
 - bond133
 - cold process133
 - cove base290
 - field134
 - flooring282
 - marble & granite306
 - modified bitumen133
 - nozzle291
 - primer282
 - resilient tile290
 - sheet flooring290
 - spray249
 - tile293-294
 - vinyl tile290
 - white silicon171
 - wood flooring282
 - Adhesive caulk, ceramic tile307
 - Adhesive remover282
 - flooring285
 - Admix, acrylic mortar307
 - Admixtures
 - coloring47
 - concrete47
 - Aggregate
 - base40, 46
 - roofing132
 - Aggregate sealer495
 - Air compressor, rental28
 - Air conditioner398
 - Air gap
 - cover334
 - Air hose, rental28
 - Air mover539
 - Air scrubber539
 - Alkyd gloss enamel493
 - All-season storm doors204-205
 - All-season storm doors, triple-track204
 - Alpine ceiling panel257
 - Aluminum
 - door bottom196
 - drip edge141
 - fascia114
 - foil88
 - patio cover459
 - patio doors215
 - roll flashing141
 - roof coating137
 - screen rolls168
 - siding113
 - siding removal106
 - siding repair105
 - soffit114
 - storm windows165
 - thermal door sill195
 - windows, fixed162
 - Aluminum conduit, threaded431
 - Aluminum siding93
 - painting482
 - Aluminum wiring411
 - Amber shellac490
 - American Flexible Conduit419
 - American Marazzi296-298
 - American Molding262
 - American Shower & Bath336-337, 357-358
 - American Standard330, 332-334, 338, 353-354, 360-363, 366-372, 385-386
 - Anchor clip458
 - Anchor, foundation512
 - Anchor, hold-down512
 - Andersen214, 216
 - Angle flashing142
 - Angle bay windows164
 - Angle valve364
 - Ann Arbor birch paneling252
 - Anti-fracture membrane kit307
 - membrane water-proofing305
 - tile membrane305
 - Antimicrobial536
 - Anti-siphon toilet fill valve364
 - Appliance receptacle435
 - Appliance removal530
 - Appliances
 - connect417
 - disconnect417
 - kitchen, removal315
 - new connection417
 - remove & replace cable417
 - Apron
 - roof143
 - whirlpool tub354
 - Aqua Mix307
 - Aqua-Tough tile
 - underlayment295
 - Arch, bullnose drywall247
 - Architectural laminate shingles130-131
 - Area modification factors18
 - Area modification factors, Canadian26
 - Area walls, sheet metal389
 - Ariston407
 - Arlington Industries422
 - Armstrong254-257, 285-291, 293
 - Asceri Hi-Arc lavatory faucet373
 - Ashland sink329
 - Asphalt
 - base51
 - fiberglass shingles130
 - paving51
 - paving, demolition32, 51
 - recycling29
 - Asphalt roofing132
 - built-up132
 - emulsion133
 - fabric131
 - saturated cotton roof patch136
 - SEBS135
 - Asphalt shingles
 - fiberglass131
 - repair130
 - Association of Bay Area Governments500
 - Astragal, T-194
 - Attachments, skid steer equipment39
 - Attic conversions57
 - Attic fans, belt drive91
 - Attic ventilation83
 - Attic vents91
 - Avenite counters322
 - Awning, remove & replace106
 - Awning windows
 - aluminum162
 - operators166
 - vinyl-clad wood160
- B**
- Bacharach kitchen faucet331
 - Backer, tile245
 - Backer tape, tile249
 - Backerboard
 - ceramic tile295
 - RhinoBoard295
 - tile295
 - Wonderboard295
 - Backfill, concrete excavation40
 - Backhoe, rental28
 - Backing, carpentry73
 - Backplate knob326
 - Backsplash322
 - Baffle, sound340
 - Baffle light kit440
 - Bahama pedestal lavatory, bowl366
 - Balance, sash166
 - Ballista range hood343
 - Baluster
 - deck rail456
 - Bamboo
 - flooring trim280
 - hardwood flooring280
 - plank flooring280
 - Banner329
 - Bar doors209
 - Bar faucet
 - single handle338
 - two-handle338-339
 - Bar kit, QO load center, ground440
 - Bar light fixture441
 - Bar sink
 - composite338
 - Manchester composite338
 - polycast338
 - single bowl337
 - stainless steel338
 - Bar, towel305, 385-386, 388
 - Barn & fence paint496
 - Barrier, foil88
 - Base
 - adhesive290
 - asphalt51
 - ceramic tile295
 - lavatory367
 - rubber wall292
 - self-stick wall293
 - shower, one-piece358
 - slab49
 - vinyl wall292-293
 - wall, thermoplastic292
 - Base cabinets318
 - end panel317
 - finished320-321
 - oak320
 - unfinished birch317
 - unfinished oak318
 - Base cap molding, primed finger joint260
 - Base corner molding259
 - MDF primed261
 - Base molding263
 - colonial263
 - combination264

MDF colonial	261	Bath light bar	441	drywall	248	Blue Board insulation	85
paperwrap colonial	263	Bath Unlimited	387-388	drywall corner	247	Blueboard	245
paperwrap ranch base	264	Bath vent kit	382	glazing	170	Board	
polystyrene colonial	264	Bathrobe hook .385-386, 388		inside corner	247	blue	245
primed finger joint	260	Bathroom accessories		L-trim	248	forming	44
shoe	264	ceramic tile soap dish .304		metal J-trim	248	sheathing	66
Victorian hardwood	259	towel bar, ceramic	305	outside corner	247	Board insulation	80, 85
Base plate cover, toilet	364	Bathroom sink	367-369	plastic	248	fire resistance	80
Base sheet, fiberglass	133	cadet	368	tape on	247	polystyrene	80
Base shoe molding,		drop-in	367-368	Bead molding	263	polyurethane	80
primed finger joint	260	Farmington	367	primed finger joint	260	Board siding	
Baseboard demolition,	34	Laurel	368	Bead, corner, spray		cedar	108
painting labor	468	Lucerne	369	adhesive	249	pine	108
Baseboard heater,		Memoirs	369	Beaded baseboard		repair	105
electric	404	Miami	369	molding	259	Board, cement	245
Baseboard molding		Minette	369	Beaded Cape Cod plank .252		Bobcats	39
beaded	259	Murro	369	Beaded paneling	251	Boiler, hydronic heating	
MDF	261	oval	368	Beadex flex metal tape .248		system	398
Basement doors	226	Ovalyn	368	Beadex paper faced		Boiler breeching	401-403
Basement HVAC		Radiant	368	metal	247	Bolt	
restoration	92	Renaissance	367	Beams		bolt kit	324
Basement post removal . .63		round	368	ceiling	68	foundation	512
Basement storm		Seychelle	367-368	collar	75	toilet tank	364
windows	165	steel	368	grade	48	Bolt-on AType	
Basin strainer, remove &		under counter mount .368		needle	62	universal hub	438
replace	352	wall hung	369	Bed molding	263	Bolts, double-hung	
Basket strainer		wall hung, corner	369	Bedding mortar,		window	166
garbage disposal	335	wall hung, corner	369	CustomFloat	306	Bond adhesive,	
junior	338	Bathroom vanity top	376	Behr	487, 490, 492-495	permanent	133
kitchen sink	335-336	Bathrooms		Bell wire	433	Bonding mortar	305-306
Basket strainer washer,		additions	345	Bemis Mfg.	365-366	flexible	306
kitchen sink	336	conversions	346	Berm	530	Bonding primer,	
Basswood molding	259	exterior additions	348	Bestview Ltd	298	concrete	493
Bath accessories . . .385-388		floor plans	349	Bevel siding		Bookcase, painting labor .468	
black finish	388	in basements	347	cedar	108	Boone International	293
brass	386-388	in garages	348	pine	108	Bosch	407
brass & chrome . .386-388		naming conventions	345	western red cedar	108	Boston polish	491
ceramic & chrome	387	space minimums	350	Beveled mirror bath bar .441		Bottle jacks	62
ceramic tile	294	Bathtub	353	Bidet, hot & cold	362	Bow window roof . . .164-165	
chrome	386-388	acrylic soaker	353	Bidet faucet set	362	Bowl, lavatory	366
chrome & brass	386	enameled steel	352	Bi-fold doors	219-221	Bowl sink, utility	337
chrome & porcelain	386	Princeton	353	hardware	221	Bowling alley wax	491
economy	386	recessed	353	metal	220	Box	
nickel	388	removal	352	mirrored	221	drawn 2-device switch .425	
Bath accessory set,		soaker	353	Binco	226	drawn handy	424
porcelain	305	soaker with skirt	353	Bin, trash	29	drawn octagon	425
Bath cabinet		surround	355	Biocidal coating	92	multi-gang switch	425
framed	382	surround kit	355	Birch doors	192,	non-metallic old work	
stainless steel	382	three-piece tile kit	355	.206-207, 210		switch	422
storage	383	tile kit	355	Birch paneling	252	non-metallic round	
swing door	383	tile wall kit	355	Birdstop	140	conduit	428
top lighted	383	Villager	353	Bitumen adhesive,		rectangular weather-	
Bath ceiling blower	378	wall surround kit	355	modified	133	proof	427
Bath fan	378-380	whirlpool	353-354	Bitumen cold process		Super Blue non-	
ceiling	381	Bathtub & shower		adhesive, modified	133	metallic three-gang . . .422	
ceiling & wall	378	units	356-357	Bituminous roofing	132	Super Blue non-	
ceiling or wall	379	Bathtub door	356	Blank cover		metallic two-gang	422
chain-operated	380	bypass	355	handy box	424	2-gang weatherproof	
Designer Series	381	sliding	356	2-gang	428	electrical	427
exhaust	380	Bathtub filler	354	weatherproof	428	welded square	425
exhaust with heater	381	Bathtub framing	395	Blasting, dry ice	537	Box adapter	421
exhaust with light	380	Bathtub wall	354	Bleach kit, wood	487	Box cover	426
Heat-A-Lamp	381	one-piece with shelf	354	Blinds, painting	481-482	blank handy	424
QuieTTTest	380	Bathtub, molded	352	Block furniture	529	finished	425
solitaire	381	Bathtub, wall kit, three-		Block masonry painting . .476		square surface	425
timer switch	382	piece	354	Block molding		Box for ceiling fan	425
Ultra Silent	379	Batt insulation	84	corner	262	pancake	425
vertical discharge	379	Batten tileboard	251	rosette	259	Box room contents	529
with heater, infrared	381	Bay vent channel, rafter . .88		Blocking		Boxes, cardboard	538
with light	380-381	Bay window roof	164	fire	66	Brace plate installation . .92	
Bath heater		Bay windows	158, 164	fireblocks	68	Braces, wall	513
exhaust fan	381	Bead		Blow-in cellulose		Bracing	
Heat-A-Lamp	381	bullnose corner	247	insulation	85	carpentry	67
infrared bulb	381	corner	248				

- cripple wall512
 temporary67
 Bracket
 foundation512
 non-metallic low
 voltage mounting422
 Bracket, hanger, lavatory .369
 Brass storm doors205
 Brass Craft334, 337,
362, 364
 Breaker
 arc fault, HomeLine . . .437
 GFCI437
 ground fault interrupter
 plug-on circuit440
 HomeLine437
 main circuit438
 QO miniature circuit . .439
 tandem circuit439
 Breaker box, ground
 bar kit440
 Breaker, paving, rental . .28
 Brick
 cleaning115
 demolition30
 painting477-478
 pointing115
 repointing115
 Brick masonry,
 painting labor476
 Brick molding195
 Brick molding set,
 primed finger joint . . .260
 Brick paver tile300
 Bridging, carpentry65
 Broan Manufacturing . . .344,
378-382
 Brookfield cast iron
 kitchen sink330
 Brookstone birch
 paneling252
 Broom finish, concrete . .49
 Brown coat plaster114
 Bruce278, 282
 Brush
 painting labor468
 wire50
 Brush chipper, rental . . .28
 Brushes
 crow's foot250
 drywall texture250
 Bubble wrap538
 Buggies, rental39
 Building dryout, interior
 work
 appliances516
 basement517
 ceiling516
 flooring516
 furniture516
 heavy items517
 lamps516
 mud & debris517
 outlets516
 valuables, securing . .516
 vents & registers . . .517
 wall switches516
 walls516
 Building paper87, 134
 Building wire, Type
 THHN432
 Built-up girders, carpentry .62
 Built-up roofing . . .132, 134
 Cold-Ap cement133
 demolition33
 insulation131-132
 patch131
 tear-off129
 torch & mop system . .134
 Bulb heater & fan,
 Heat-A-Lamp381
 Bulkhead light fixture,
 outdoor443
 Bull float, rental39
 Bullnose
 ceramic tile301
 corner bead247
 corner tile302
 drywall arch247
 outside corner247
 plastic corner247
 Bulls Eye shellac490
 Bumper, garage door . .225
 Buried cable419
 Burn off paint, labor . . .466
 Bush removal29
 Bushing
 insulated metallic
 grounding430
 non-metallic reducer . .420
 rigid or IMC reducing .430
 thermoplastic
 insulating430
 Butcher's491
 BX cable, flexible
 armored419
 Bypass doors218
 accessories219
 bathtub355
 beveled mirror218
 closet218
 hardware222
 mirrored218-219
 shower356
C
 Cabinet demolition, wet . .534
 Cabinet door316
 Cabinet drawer front . .316
 Cabinet hinge
 overlay327
 self-closing328
 semi-concealed328
 Cabinet knobs324-326
 Cabinet trim320
 Cabinets
 base317-318, 320-321
 bath382-383
 bathroom vanity . .374-375
 corner383
 door trim316
 end panel316-318
 filler strip318-319
 finished320
 frameless383
 kitchen, unfinished
 birch317
 medicine382-384
 oak320-321
 painting labor469
 pantry319-321
 removal315
 trim320
 trim, finished322
 utility317-321
 vanity378
 wall317-321
 Cable
 AC419
 appliance connection .417
 appliance re-connect .417
 appliance, remove &
 replace417
 BX419
 coaxial433
 data communication . .433
 fish through stud wall .417
 flexible armored BX . .419
 thermostat433
 Type NM-B Romex
 sheathed417-418
 Type UF-B sheathed .419
 underground419
 Cable coupling, EMT to
 non-metallic sheathed .424
 Cable Snake flat wire
 fish tape417
 Cadet Series bar faucet .338
 Cafe doors209
 Calcium chloride47
 Cal-Flor accessory
 systems291
 Cambay vinyl sheet
 flooring287
 Cambria countertop . .323
 Can, ceiling light440
 Canopy, remove &
 replace106
 Cant strips137
 roofing86
 Cap146
 ceramic surface302
 chimney146
 PVC service entrance .422
 service entrance432
 Cap molding, colonial . .264
 Cap sheet, roofing133
 Cap, post456-457
 Cape Cod plank252
 Carbon monoxide alarm,
 battery powered436
 Carborundum rub50
 Cardboard boxes538
 Carflex liquid-tight
 flexible conduit427
 fitting427
 Carlon420-422, 427-428
 Carol Cable433
 Carpentry
 backing & nailers73
 beams & girders62
 bridging or blocking . .65
 ceiling beams68
 ceiling joists73
 door openings69
 dormer studs76
 fascia board76
 fireblocks68
 floor joists64-65
 floor repairs62
 furring72
 plates67
 posts63
 rafters75
 roof sheathing77
 roof trusses76
 room additions64
 sheathing70
 sill plates64
 studs66
 subflooring66
 wall assemblies70
 wall framing66
 window openings69
 Carpet308
 cleaning532
 demolition35
 removal278, 531
 roller, extendable291
 transition strip292
 water extraction531
 Cartridge, disposal . . .340
 Casement windows . . .164
 lock handle166
 operator handle166
 vinyl-clad wood160
 Casing263
 aluminum siding114
 colonial260
 colonial door195
 door191, 206
 economy265
 MDF261
 paperwrap colonial . . .264
 paperwrap ranch265
 polystyrene266
 polystyrene colonial . .264
 polystyrene fluted . . .265
 polystyrene ranch . . .265
 prefinished colonial . .264
 prefinished fluted . . .265
 ranch260, 265
 Caspian sheet vinyl
 flooring286
 Cast iron
 pipe, remove &
 replace408
 radiator, remove &
 replace398
 water closet flange . .364
 Cast iron kitchen
 sink329-330
 Cast molding262
 chair rail262
 Cast-in-place concrete . .47
 Cat doors216
 Catalina Lighting443
 Caulk
 ceramic tile307
 ceramic tile adhesive .307
 removal157
 roof136
 window exterior157
 Caulking, manhours . . .466
 Cedar
 panels, sidewall
 shingle113
 roofing137
 shingles138
 siding108-109
 Cedar louvered vents . .90
 Cedar mill112
 Ceiling
 beams68
 demolition242
 demolition, wet533

joists73	Ceiling, suspended237	Chair rail		Cleaning	
painting470	cross tee255	cast polyurethane262	after water extraction534
painting manhrs.469-470	installation254	Clearwood PS266	antimicrobial536
repair244	main beam255	MDF261	brick115
staining manhours470	wall molding255	paperwrap266	carpet532
texture manhours469	CeilingMAX255	polymer263	HVAC530
tile adhesive254	Cellar doors, steel194	polystyrene266	masonry115
touch-up kit244	Cement		prefinished266	pressure wash468
Ceiling & wall panel,		board245	primed finger joint260	stone115
FRP253	coloring47	Chalk line, self chalking291	terra cotta115
Ceiling fan		joint compound245	Chandeliers442	Ultrasonic530
bath378	mixer, rental39	Channel vent, rafter bay88	Clear cedar siding108
bath heater & fan381	siding113	Chesapeake floor tile289	Clear wood	
gazebo444	soffit, fiber112	Chime kit, door436	preservative491
QuieTTest380	tile139	Chimneys399-403	protector490
San Marino444	underlayment285	A vent402-403	Clearshield488
Ceiling fan box425	white114	all fuels402-403	Clip, anchor458
non-metallic422	Cement, roofing		aluminum399-400	Clips & screws,	
pancake425	cold process133	B vent401	sink mounting329
Ceiling fixture440	flashing135	base tee400-402	Clips, drywall repair249
drum441	Kool Patch135	C vent399-400	Closers, door217
fluorescent441	lap roof133	cap146	Closet, painting labor470
flush mount441	rubber wet patch135	double wall401-402	Closet doors210
glass globe442	Wet-Stick135	double wall		bi-fold219-220
incandescent flush		Center, HomeLine		insulated402-403	bypass218
mount442	indoor main lug load437	elbow400-403	mirrored bypass218-219
mushroom flush		Central air conditioning397	flue399-403	Closet pole molding263
mount442	Central air filtration		flue rain cap399	Closure strips, horizontal141
remove & replace441	retrofit, HEPA398	gas or propane399-402	CMU, painting477
Sunburst flush mount442	Central humidifier397	L vent401-402	CO/ALR duplex	
swirl dome light442	Ceramic tile		liner399	receptacle435
Ceiling insulation		accessories304	liner (flue), aluminum399	Coal furnace404
batt and roll blanket79	accessory set305	liner rain cap399	Coated glass fabric136
Kraft-faced79	adhesive293	masonry, repair104	yellow resin136
loose-fill79	adhesive caulk307	rain cap400-403	Coating	
R-value79	backer295	repairing earthquake		fibered roof137
Ceiling latex paint492	backerboard295	damage510	floor, epoxy495
Ceiling lighting panel		bullnose301	roof flashing400-403	foundation and roof129
acrylic258	bullnose corner302	single wall399-400	roof137
styrene258	caulk307	stack401-402	roof & foundation129
Ceiling panel256	definitions276	storm collar400-403	weather-resistant488
acoustical256	demolition35, 315	supports & brackets403	wood488
classic fine-textured256	floor276, 295-298	termination		Coating kit	
fiberglass257	floor warming system305	assembly400-403	seam291
Firecode Fifth Avenue257	glazed303	Chlorinated rubber paint496	corrosion92
fissured257	installation293	C-hook, garage door225	Coatings	
fissured fire guard256	mosaic accent304	Chop saw, rental28	concrete495
Grenoble256	mosaic octagon304	Chrome light fixture441	epoxy gloss496
gypsum lay-in257	Natura296	Circuit breaker		epoxy primer496
mineral fiber257	removal278	arc fault, HomeLine437	specialty496
plain white256	Saltillo299	GFCI437	Coaxial cable433
Prestige256	sink rail302	ground fault interrupter		wall plate433
random textured255	soap dish304	plug-on440	Coaxial F-connector	
Sahara256	surface cap302	HomeLine437	for RG6433
suspended255-257	surface cap corner302	main438	Cobra Rigid ridge vent145
textured257	threshold301	main, all-in-one438	Cofair Products135
Ceiling panel, fiberglass256	toilet tissue holder304	QO miniature439	Coffer dam92
Ceiling repair245	tool291	tandem439	Coil, kickplate459
Ceiling texture246	toothbrush & tumbler		Circular windows, half		Cold process adhesive,	
Acousti-Tex245	holder305	circle, vinyl159	modified bitumen133
patch245	wall297, 301, 303	Civic Square290	Cold process cement133
popcorn patch245	window sill301	Clamp		Collar beams, carpentry75
spray244-245	Ceramic tile flooring,		ground rod432	Collar ties75
touch-up kit244	tips on277	Snap Strap PVC		Colonial base molding263
Ceiling tile254	Chain link fence		conduit420	MDF261
acoustical253	demolition29	wood floor281	paperwrap263
tin design254	Chain saw, rental28	Clamp connector,		polystyrene264
wood fiber254	Chain-operated wall		two-piece419	Colonial cap	
Ceiling tile grid system,		exhaust fan380	Classic faucet handle370	paperwrap molding264
zero-clearance tile grid255			Clay roofing tile139	Colonial casing	
Ceiling tile, wet533					finger jointed260
Ceiling wire hanging kit255					paperwrap264
						polystyrene264
						prefinished264

Colonial crown paperwrap molding268	grinding513	steel425	Cork roll293
Colonial door casing195	grout mix46	three-gang non- metallic422	tile flooring275
Colonial outside corner molding267	grouting50	two-gang non-metallic .422	tile, natural293
Colonial stop molding269	high early strength47	Conduit bushing, rigid . . .430	Corner MDF primed base261
Colonial storm doors, triple-track205	joints46	Conduit clamp, Snap Strap PVC420	plastic bullnose247
Colonnade kitchen faucet332	keyway48	Conduit connector 90-degree426	Corner & cove molding inside266-267
Colorant, grout307	lightweight46	flex427	paperwrap266
Coloring agents, concrete47, 49	mix46	Conduit coupling, rigid429-430	prefinished267
Column, porch455	patching50	Conduit elbow 45-degree rigid steel . .429	Corner bead bullnose247
Combination base molding264	planing513	rigid or IMC steel429	drywall247
Combination coupling . . .424	plasticized47	Conduit fitting Carflex427	flex248
Combination service entrance device438	protective coating495	non-metallic421	inside247
Combination service entrance load center . .437	pump mix46	Conduit fitting Carflex427	outside248
Commercial Electric . . .440	pumping39	Conduit hub, watertight . .430	spray adhesive249
Communication cable, Category 5E433	ready-mix46	Conduit installation, confined area429	Corner block, polyurethane262
Composite kitchen sink .338	recycling29	Conduit locknut430	Corner cabinet, frameless383
bar338	reinforcing steel44	Conduit nipple431	Corner entry shower kit . .358
Beaumont331	repair513	Conduit sill plate, service entrance432	Corner molding inside267
double bowl330	retaining walls47	Conduit strap431	paperwrap outside . . .267
Forsyth330	sawing50	Connector 90-degree flexible426	polystyrene inside . . .267
Greenwich330	sealer495	dishwasher340-341	polystyrene outside . .267
single bowl330	shingles140	EMT compression423	prefinished inside . . .267
60/40 bowl331	sidewalk49	EMT offset screw423	prefinished outside . .267
Composition tile, vinyl289-290	slab demolition32	EMT set screw423	Corner shelf, ceramic . .304
Compound glazing170	slabs49	EMT-to-box offset compression424	Corner tape, flexible metal249
latex glazing170	specialty finishes50	flex screw-in426	Corner trowel250
Compression conduit coupling, rigid or IMC .430	stain495	flex squeeze427	Cornices, painting480
Compression connector EMT423	stamped finish50	non-metallic UF compression419	Corrosion coatings92
EMT-to-box offset424	tile139	two-piece clamp419	Corrugated fiberglass140
non-metallic UF419	tile roofing140	Containment dust536	metal roofing138
Compression faucet, repair352	topping50	mold536	metal siding113
Compression inlet, dishwasher connector .341	walks49	Contents3	CorStone330-331
Compressor, rental28	wall demolition32	Continuous vents89	Cost plus markup equals selling price7
Concrete additives47	wall form43	Contractors Wardrobe . .359	Cotton insulation87
architectural47	walls47	Contractors, state license dryout515	Cotton roof patch, asphalt saturated136
bonding primer493	waterproof495	mold remediation515	Counter edge, oak268
coatings495	waterproofing sealer . .495	Control switch, fan382	Counterflashing144
coloring47	Concrete & masonry waterproof495	Convection heating, baseboard398	Countertops322
curb44	Concrete block demolition31	Cooktop electric342	Corian322
delivery charges46	painting476-478	electric ceramic glass .342	granite323
driveways46	Concrete conveyor, rental .39	gas342	laminated plastic . .323-324
embossed finish50	Concrete deck, patch built-up roofing131	Cooling system, patio . .458	marble vanity376
enamel495	Concrete pier replacement63	Copper formed flashing142	miter bolt kit324
epoxy floor coating . . .495	Concrete saws, rental . . .39	roll flashing141	plastic laminate323
expansion joints46	Conditioner, wood491	window roofs164	setting with adhesive . .294
exposed aggregate49	Conduit Carflex liquid-tight . . .427	Copper pipe DWV408	setting with mortar . . .294
finishing50	EMT422, 426	water408	solid surface322
flatwork40	EMT, removal422	Copper step flashing . . .142	stone, engineered . . .323
floor painting, labor474-475	ENT427	Copper wire, Type THHN432	tile295
footings, demolition . . .31	flex appliance connection417	Copper wood preservative491	Coupling, combination . .424
form stripping43	flexible aluminum . . .426	Cord, disposal accessory kit340	EMT to non-metallic sheathed cable424
forms42, 48	flexible steel426	Corian countertops322	non-metallic standard .421
foundations48	galvanized IMC429		rigid conduit429
grade beams48	GRS429		rigid or IMC compression conduit .430
granite aggregate46	IMC429		Cove & corner molding inside266-267
	installation, rigid429		paperwrap266
	removal, rigid429		
	Schedule 40 PVC420		
	Schedule 80 PVC420		
	Conduit body421		
	PVC Type T421		
	threaded aluminum . .431		
	Conduit box adapter421		
	cover, steel424, 426		
	installation424		
	non-metallic round . . .428		

Cove base	Data communication	porch	32, 452	Door
adhesive	cable, Category 5E	shower stall	357	cabinet
adhesive nozzle	Deadbolts	sidewalks	31	demolition, wet
Cove molding	Debris removal	skylight, poly dome	172	framing
spring	Deck	slab	30	hinges, brass
Cover	demolition	stairs	35	kick plates
faucet hole	lumber	suspended ceiling	254, 315	knockers
patio, aluminum	lumber, Fiberon	wall	270	openers
Covers	lumber, Thompsonized	wall cover	316	painting labor
blank handy box	misting system	walls	30, 31	peep sights
dual weatherproof	painting	wet materials	532	pull plates
lampholder	post & beam	windows	35, 156	push plates
GFCI wet location	post cap	wood framing	30	touch bar exit hardware
receptacle	posts	DensArmor gypsum		Door accessories,
horizontal duplex	railing	board	243	bypass
weatherproof recept.	railing, turned spindle	DensShield tile backer	245	Door bell, wireless
receptacle	repair	Dentil cast molding	262	Door bottom
steel conduit box	roof	Dentil chair rail	262	aluminum & vinyl
switch	screws	Designer panel		drip cap
2-gang blank	staining	wallcovering	252	Door casing
weatherproof blank	stairs	Designer Series bath fan	381	colonial
Crack filler, siliconizer	Deck & siding stain	Detaching membrane	308	ranch
Crack repair	Deck Plus stain	Detector		ranch, pine
mesh	Deck, roof	dual-ionization smoke	436	Door chime builder's kit
Craft Codes	removal	smoke	436	Door closers
Crawlspace ventilation,	repair	Devoe Coatings	496	hinge pin
free circulation area	walking	DeWalt	249	hydraulic
Cribbing	Deck, roofing, patching	DeWaters	529	installation
built-up	built-up	DeWitts	135	pneumatic
Cripple wall	Decora AC quiet rocker	Difficulty factors, painting		Door frame, painting
Cross bridging	switch	manhours	466	labor
Cross head cast	Decora wall plate, single	overhang	480	Door frames
molding	gang	Diffuser fixture,		fire-rated
Crow's foot brush	Deflect-O	fluorescent	441	pocket
Crown molding,	Dehumidifiers	Diffusers, duct,		removal
paperwrap colonial	Delta	installation	397	Door grille
Crown molding	Dimmer		Door handles, patio
cabinet	Demolition	illuminated slide	436	Door hangers
MDF	acoustic tile ceiling	incandescent slide	436	Door hardware
MDF ultralite	acoustical ceiling	Dirt, recycling	29	track
polystyrene	asphalt paving	Disconnect		Door hinge, remove
prefinished	baseboard	appliances	417	Door installation
primed finger joint	brick sidewalk	distribution panel	437
Crystalite countertop	brick wall	Dish, soap	304	Door jambs
Curb mount fixed	building components	Dishwasher	341	exterior
skylights	carpet	compression inlet	341	garage
Curbs, concrete	ceiling	connector	340-341	interior
Cure-Seal concrete	checklist	removal	315	patio door
sealer	concrete block	Dispenser		pocket
Curing & sealing	concrete sidewalk	hot water	336	remove & replace
compound	concrete slab	soap	335	Door kit
Curved glass wall	concrete wall	Disposal, garbage	339-340	Door lever, privacy
lantern	decks, wood	basket strainer	335	Door locks
Custom Building	doors	batch feed	339	patio
Products	drywall	cartridge	340	Door locksets
CustomBlend	drywall ceiling	cord accessory kit	340	.183, 201-202
Thin-Set Mortar	equipment rental	food waste	339-340	Door exit push bar
CustomFloat	estimating	mounting assembly	340	Door roller
bedding mortar	fence	septic system	339	Door stop
Cutter	floor cover	sink flange	340	Door sweep,
glass	flooring	sink stopper	340	Flex-O-Matic
vinyl tile	framing	waste	29
Cutting slabs	garage	Distribution box, electric	540	Door threshold
	guardrail	Distribution panel,	
	joists	disconnect & remove	437	Door track hardware
	kitchen cabinets	Ditching	41	Door trim
	kitchen fixtures	Ditra	308	painting labor
	masonry	Dock & fence post		Doors
	molding	preservative	490	4-panel
	paneling	Dome light ceiling fixture	442	6-panel
	plaster			adding or removing
	plaster ceiling			bar
				basement
				bathtub
				bi-fold
				.219-221
				bi-fold, louvered
				.220-221

D

Dado partition	demolition	316
Dal-Tile	297, 303-304	
Danco	336	
Danish Oil	488	
DAP	170	

- birch192, 210
 birch, prehung197
 bypass, closet218
 bypass, mirrored .218-219
 cafe209
 camber top199
 casing195
 cellar194
 closers217
 closet .186, 210, 218-219
 closet, bypass218
 demolition35
 Douglas fir193
 entrance194
 entry193, 198-200
 entry, decorative fan .200
 entry, decorative
 half lite200
 exterior .192-193, 197-198
 exterior fan lite197
 exterior flush197
 exterior prehung .197-199
 exterior prehung,
 with mini-blind198
 exterior, installation .191
 fiberglass200-201
 fir193
 fire192
 fire-rated197
 flush219
 flush closet219
 flush closet, lauan .219
 folding, accordion217
 foundation access88
 French193
 French, interior208
 garage223-224
 garage, extension
 spring225
 garage, jamb hinge .224
 handle sets202
 hanging slab184
 hardboard192, 209
 hardware221
 hardware, exit226
 hemlock197
 installation191, 197,
 206, 209
 interior .207-208, 211-212
 interior cafe209
 interior slab206
 interior, birch206
 interior, colonial211
 interior, colonist211
 interior, fir208
 interior, French .212-213
 interior, full louver,
 pine212
 interior, hardboard .207
 interior, hardboard,
 colonist207
 interior, lauan206-207
 interior, oak .206, 208, 212
 interior, pine208
 interior, pine louver .212
 interior, prehung .209-210
 interior, prehung,
 knotty alder212
 interior, solid core .207
 lauan210
 lever latchset213
 lockset repair201
 metal, reversible194
 mirrored221
 mirrored, frameless .221
 mobile home222
 molded face207-208
 oak210
 pantry212
 patio214
 patio grille216
 patio handle216
 patio lock216
 patio roller216
 patio threshold216
 patio, aluminum215
 patio, double215
 patio, fiberglass215
 patio, gliding214
 patio, hinged214
 patio, sliding214
 aluminum215
 patio, steel215
 patio, swinging .214-215
 patio, vinyl215
 pet216
 pocket222
 prehung186, 197
 removal35, 197
 repair175, 191
 replacement175
 procedure185
 screen203
 screen, installation .202
 screen, metal203
 screen, pine203
 screen, replace .203, 216
 screen, steel203
 screen, vinyl203
 screen, wood203
 security205
 security, Paradise-
 style205
 security, with screen,
 heavy-duty205
 setting trim184
 shower .356, 359-360
 sidelites198
 slab192-193
 solid core192, 197
 steel198
 steel exterior199
 steel, 6-panel198
 steel, entry198
 steel, exterior199
 steel, prehung198
 steel, prehung, with
 mini-blind198
 stile & rail208
 storm204-205
 storm, all-season .204
 storm, aluminum204
 storm, aluminum
 & wood204
 storm, removal .204
 storm, self-storing .204
 storm, triple-track .204
 storm, woodcore205
 terms188
 weatherstripping196
 Doors, entry175
 antiquing176
 reassembling179
 rebuilding178
 refinishing176
 repairing holes177
 Doors, exterior,
 framing & replacing .179
 Doors, interior181
 Dormer
 studs75-76
 vents90, 144
 Double bowl kitchen
 sink329
 cast iron329
 stainless steel .328
 Double cylinder door
 handle202
 Double doors211-212
 Double oven, wall342
 Double-hung windows
 insulated159
 replacement157
 screens160
 vinyl-clad159
 wood163
 Double-track storm
 windows165
 Downlight ceiling fixture .440
 Downspouts
 acid wash466
 galvanized steel .146
 painting labor .476
 remove & replace .106
 residential146
 Drain connector,
 garbage disposal
 to dishwasher341
 Drain stopper336
 flat sink336
 Drain, waste & vent
 lines, plumbing for .393
 Drainboards, counters .295
 Drawer front cabinet .316
 Drawn box
 2-device switch425
 handy424
 octagon425
 Drip cap141
 door bottom seal .196
 molding, wood114
 Drip edge142
 aluminum141
 Driveway forms43, 49
 Driveways, concrete .49
 Drop ceiling
 panel255-257
 soffit316
 Drop-in lavatory sink .367
 Drum mushroom
 ceiling fixture441
 Dry ice blasting537
 Dry rot remediation .92
 Dry tile grout,
 non-sanded307
 Dryback vinyl wall base .292
 Dryer, wall cavity539
 Dry-out529
 Drywall
 arch, bullnose247
 ceiling, demolition .315
 ceilings232
 corner bead247
 corner tape249
 demolition .34, 242, 316
 demolition, wet532
 dustless sanding
 system251
 finish244
 fire code Type X .243
 fire-resistant243
 flexible244
 greenboard244
 hand sander250
 hanging228
 installation242, 244
 J-bead248
 joint compound .245-246
 joint tape246
 J-trim248
 L-trim248
 mildew resistant .243
 moisture resistant .243
 mold resistant243
 nails249
 outside corner trowel .250
 painting483-484
 panel lift250
 patch242
 primer246
 repair242
 repair clips249
 repair kit248
 repair patch248
 repair sheet244
 repairing234
 sander kit250
 sanding respirator .250
 sanding sponge250
 screws249
 sound deadening .243
 spray texture244
 tape246
 tape, white, fiberglass .246
 taping & finishing .230
 texture244
 texture spray244
 textured finishes .232
 topping compound .246
 vinyl outside corner
 bead248
 Drywall tools
 electronic stud sensor .249
 hammer250
 sander251
 screw gun, battery-
 powered249
 screwdriver249
 screwdriver bit250
 screws, collated .249
 stilts250
 texture brush250
 trowel250
 trowel, corner250
 T-square250
 Dual sensing smoke
 alarm436
 Dual weatherproof
 lampholder & cover .428
 Dual-ionization
 smoke detector436
 Duct
 heating, removal .396
 runs, installation .397
 Duct tape538
 Dumont kitchen sink .329
 Dump fees29

Dump trucks, rental28	foundations & slabs . . .507	Electric space heaters . . .392	End panel
Dumpster538	framing508	Electric wall oven342	base cabinets317
rental29	gypsum drywall510	Electric water	cabinets316, 318
trash29	mechanical systems . . .511	heater406-407	wall cabinets319
Duplex receptacle	plaster509	PowerStar™407	Energy-efficient
CO/ALR435	plumbing systems . . .511	tankless407	electrical upgrades . . .444
commercial grade . . .435	stucco509	Electrical management	ENT conduit427
handy box cover424	Earthquake damage,	system, smart home . . .444	Entertainment sink338
straight blade434	checking for	Electrical non-metallic	Entrance cap, PVC422
waterproof cover428	before making repairs .506	tubing conduit427	Entry doors193, 198-200
Durabase358	jobsite walk506	Electrical systems	deco fan lite193
Durastall358	structural engineer . . .506	licensing & code	fiberglass200-201
Duratemp panel siding . .111	Earthquake damage,	compliance410	oak194
Durock backerboard . . .295	cosmetic497	<i>National Electrical</i>	Epoxy crack repair513
Durock cement board . .245	Earthquake damage,	<i>Code (NEC)</i>410	Epoxy floor coating495
Dust control536	increased risk	power shortfall409	Epoxy gloss coating . . .496
Dustless drywall	when adding a room . .504	repairing earthquake	Epoxy mortar306
sanding system251	when making	damage511	Epoxy primer496
DWV pipe, remove &	alterations504	service upgrade410	Equipment costs13
replace408	when removing wall	Eliane ceramic tile297	Equipment rental
	bracing505	Eljer329	demolition28
E	Earthquake damage,	Eljer Plumbingware367	foundations and slabs . .39
E.L. Mustee336, 358	structural497	Elkay Mfg.328-329, 338	Escape window172
Earthquake anchor . . .512	Easysills165	Embossed basswood	Estimating home
Earthquake damage	Eave closure140	molding259	improvement costs
IBC seismic safety	Eave vents90	Embossed concrete50	hanging doors5
standards497	Decomesh89	Embossed decorative	price book6
IPMC seismic safety	Eaves, painting480	molding259	problems5
standards497	Edeck452	Embossed polystyrene	Estwing250
IRC seismic safety	composite deck454	casing265	Eternit139
standards497	Edge	Embossed polystyrene	Excavation41
structural	counter268	molding	backfilling40
improvements498	drip141-142	base263	fine grading40
structural	flashing, roof143	chair rail266	footings40
improvements, <i>IRC</i> .498	Edge forms, concrete .40, 43	crown268	rock40
structural	Edge protection tile . . .303	Embossed prefinished	spreading41
improvements,	Edge pulls222	molding	tamping41
permits for498	Edge V-plank252	chair rail266	topsoil41
Earthquake damage	Efficiency cast iron	Embossed tileboard251	Excelon vinyl
prevention	kitchen sink329	Embossing leveler285	composition tile . . .289-290
anchors, hold-down . .500	Egg & dart cast molding .262	Emergency dry-out	Exhaust fan380
bracing hillside homes .502	Egg knob locksets . . .202	service529	bath378-381
bracing, cripple walls .500	Eggshell wall paint, latex .492	Emser International298	bath, vertical discharge .379
bracing, open front . .501	Elastocaulk136	EMT conduit422, 426	ceiling379
foundation bolting . . .499	Elastomastic136	45-degree elbow423	QuietTest380
masonry chimneys,	Elastomeric	90-degree elbow423	timer switch382
anchoring503	roof coating137	combination coupling .424	utility, vertical discharge .379
tension ties on	Elastomeric water-	compression connector .423	ValueTest with light . .380
split-level homes . . .503	proofing paint494	coupling424	vertical discharge . . .379
Earthquake damage	Elastotape136	offset compression	wall379
prevention, FEMA	Elbow	connector424	with heater381
recommendations . . .499	45-degree plain end . .421	offset screw connector .423	with infrared heater . .381
bracing hillside homes .502	90-degree423	set screw connector . .423	Exhauster, roof145
cripple wall bracing . .500	90-degree standard	strap424	Exit bar226
foundation bolting . . .499	radius421	EMT conduit, removal . .422	Expansion bolt512
hold-down anchors . .500	EMT 45-degree423	EMT strap424	Expansion joints, concrete .46
masonry chimneys,	EMT 90-degree423	Emulsion, asphalt133	Exposed aggregate finish .49
anchoring503	pulling423	Enamel	Exposed aggregate
open front bracing . . .501	rigid or IMC steel	floor & porch495	sealer495
tension ties on	conduit429	interior & exterior . . .493	Exposed round conduit
split-level homes . . .503	rigid steel conduit . . .429	latex492	box, non-metallic428
Earthquake damage repair	rigid steel conduit . . .429	oil-based496	Extendable roller291
chimneys510	service entrance432	painting483-484	Extension kit, jamb216
concrete cracks507	Electric baseboard	wall & trim492	Exterior & interior stain,
cracks in plaster &	heaters404	Enamel undercoater,	acrylic487
stucco509	Electric cooktop342	interior491	Exterior clear finish . . .489
drywall510	Electric metallic tube	Encapsulate mold537	Exterior door jambs194
electrical systems511	conduit422, 426	Encapsulated fiberglass	Exterior doors193
epoxy injection507	Electric metallic tube	roll insulation85	fir192
fireplaces510	conduit removal422	Enclosure, shower356	flush192
	Electric service panel . . .439	pivot door359	prehung197
			Exterior jambs, kerfed . .194

- Exterior paint, satin flat .494
 Exterior painting .466
 Exterior sanding,
 manhours .467
 Exterior stain .487
 Plus 10 .487
 Exterior trim, painting .463
 Exterior wall assemblies .71
 Exterior window shutters .167
 Extraction, water .529
 Extruded polymer
 molding .263
 Eyeball trim light kit .440
- F**
- F channel .459
 F connector for
 RG6 coaxial cable .433
 Fabbback acrylic
 mirrored sheet .171
 Fabric
 asphalt roofing .131
 polyester stress-block .136
 Factors
 high time painting .466
 painting difficulty .480
 Fairfax faucet,
 two-handle .374
 Fairfax kitchen faucet .333
 Fan lite doors .197, 201
 Fans .444
 attic exhaust .91
 bath .378-381
 bath exhaust .378, 380-381
 bath exhaust & heater .381
 bath exhaust,
 QuietTest .380
 bath exhaust, vertical
 discharge .379
 bath, premium .379
 SensAire control
 switch .382
 utility exhaust, vertical
 discharge .379
 utility, thru-the-wall .380
 wall exhaust,
 chain-operated .380
 Fascia
 aluminum .114
 board .76
 staining .473
 vinyl .108
 Fashion Series .252
 Fasteners .458-459
 deck screws .459
 Fast-setting patch .285
 Faucet hole cover .335
 Faucets
 bar .338
 bar, single handle .338
 bar, 2-handle .338-339
 bidet .362
 compression, repair .352
 kitchen .331-333
 kitchen, 2-handle .333-334
 kitchen, 2-handle,
 with spray .334
 laundry, 2-handle .337
 lavatory .370-372
 lavatory, adjustable
 center .374
 lavatory, center set .371-374
 lavatory, infrared .371
 lavatory, two-handle .372
 pressure balanced .361
 Roman tub .354
 shower & tub .360
 supply .374
 tub & shower .360-362
 Feather edge additive .286
 Federal Emergency
 Management Agency
 (FEMA)
 recommendations .499
 structural improvements .498
 Fees, recycling .29
 Felt
 roofing .133
 roofing, glass fiber .134
 scribing .291
 Fence
 demolition .29
 staining labor .474
 Fence & barn paint .496
 Fence post preservative .490
 Fernco .341
 Fiber cement
 lap siding .112
 roofing .139
 siding .113
 siding panel .112
 soffit .112
 trim for siding .112
 Fibered aluminum
 roof coating .137
 Fibered roof coating .137
 Wet-Stick .137
 Fiberglass
 base sheet .133
 bathtubs .357
 panels .140
 reinforcing membrane .136
 screen rolls .168
 shower stall .358
 window trim, bath .355
 Fiberglass asphalt
 shingles .131
 Fiberglass ceiling
 panel .256-257
 Fiberglass entry
 doors .200-201
 Fiberglass insulation
 batt .84
 Kraft-faced .84
 roll .84-85
 unfaced .84
 Fiberglass mat roof patch .135
 Fiberglass reinforced
 plastic panels .253
 Fiberon .452, 454
 Field adhesive, SBS .134
 Field tile
 setting with adhesive .294
 setting with mortar .294
 Fill, excavation .40
 Filler, crack .136
 Filler strip .317-319
 oak .321
 wood .138
 Film, polyethylene .87
 Finish carpentry
 countertops .322
 siding .107
 Finish sealer, high-gloss .307
 Finished box cover .425
 Finishes
 exterior clear .489
 flat latex .492
 floor, oil-based .489
 interior classic clear .489
 log home gloss .489
 rust-resistant .496
 stain gel, non-wood .488
 wood .487
 Finishing concrete .49-50
 Finishing compound,
 wallboard .246
 Finishing putty, Pergo .283
 Fink truss .76
 Fir doors .192-193
 Fire doors .192
 Fireblocks .68
 Firebrick .115
 Fireplaces
 demolition .115
 masonry, repair .104
 prefabricated .116
 repair .115
 repairing earthquake
 damage .510
 Fire-rated door frames .194
 Fire-rated doors .197
 Fire-resistant drywall .243
 First Alert .436
 Fish tape .413
 cable snake .417
 Fissured ceiling
 panel .256-257
 Fixed skylights .172-173
 Fixture removal .530
 Fixture gasket removal .352
 Fixture supply lines .374
 Fixture valve lines .374
 Fixture, light
 ceiling .442
 chandelier .442
 chrome bath bar .441
 fluorescent ceiling .441
 flush mount ceiling .441
 jelly jar .443
 motion sensing .443
 mushroom flush mount .442
 outdoor bulkhead .443
 outdoor wall lantern .443
 remove & replace .441
 wave bath .441
 Fixtures
 troffer fluorescent .258
 U-lamp troffer
 fluorescent .258
 Flange kit, load center .437
 Flashing
 aluminum roll .141
 aluminum siding .113
 angle .142
 copper formed .142
 counterflash .144
 galvanized .142
 gravel stop .142
 lead .143, 145
 patch .135
 pipe .143, 145
 removal .129
 repair .129
 roll valley .141, 143
 roof .134
 roof edge .143-144
 roof, removal .134
 roof-to-wall .144
 service entrance roof .432
 shingle .144
 step .144
 W-valley .144
 Flashing cement,
 pro-grade .135
 Flashing leaks .118
 Flashing paper, roof .88
 Flashing, pipe, tile roof .145
 Flat masonry & stucco
 paint .494
 Flat paint .492
 exterior, satin .494
 interior .492
 latex .494
 Flat sink drain stopper .336
 Flex conduit appliance
 connection .417
 Flex screw-in connector .426
 FlexBond bonding
 mortar .306
 Flexible aluminum
 conduit .426
 Flexible armored BX
 cable .419
 Flexible bonding mortar .306
 Flexible connector
 90-degree .426
 90-degree insulated .426
 Flexible metal corner
 tape .249
 Flexible steel conduit .426
 Flip locks, window .171
 Float, carpet .531
 Float finish, concrete .49
 Floating floor
 installation kit .280
 Flood abatement .531
 Flood Company, The .490
 Flooding, effects of .515
 Floor
 beam .62
 beam, shimming .62
 clamp .281
 decking, subflooring .66
 demolition .35
 furring .72
 joists .64-65
 repairs, framing .62
 slab, concrete .49
 staining .475
 Floor & porch enamel .495
 Floor & porch oil gloss .495
 Floor & wall tile, ceramic .297
 Floor beams
 decay .53
 reinforcement with
 jack posts .55
 repair .53
 Floor coating, epoxy .495
 Floor covering
 tile, resilient .271
 wood .271
 Floor drying system .539
 Floor enamel .495
 Floor finish, oil-based .489
 Floor furnace, gas .404
 Floor insulation .80

Floor jacks	54	underlayment & patch	286	Fluted casing embossed polystyrene molding	265	demolition	33, 270
Floor joists		underlayment skimcoat	286	Fluted casing		estimating, problems with	53
demolition	33	vinyl roll	286-287	prefinished molding	265	interior doors	206, 209
repair	54-55	vinyl sheet	287	Foam insulation	85	partitions, wood	66-67
Floor molding, hardwood	278	vinyl wall base	293	Foam underlayment	283-284	repairs	62
Floor plank choices		water extraction	531	Foam weatherstripping	196	room additions	64
for porches & decks	450	white oak strip	281	Foamular XAE	85	straightening	514
Floor primer	285	wood	281	Foil		wall studs	66
Floor tile		wood laminate	283	aluminum	88	Framing lumber	452
ceramic	295-298	wood plank	280	barrier	88	Framing straps	512
granite	299	wood, installation tools	281	Folding doors		Franklin Brass	386-387
marble	298	Flooring installation system, laminate floor	284	locks	217	French doors	193, 208
natural stone	299	Flooring over concrete	276	accordion	217	interior, double	212-213
parquet	282	Flooring trim	284	Footings	48	painting labor	471-472
Place n Press	289	bamboo	280	concrete	46, 48	Frenchwood	214, 216
Saltillo ceramic	299	heart pine	281	continuous	48	Frieze cast molding	262
slate	299	Flooring, resilient, sheet vinyl	274	demolition	31	FRP panel molding	253
travertine	299	Flooring, tile		excavation	40	FRP wall & ceiling panel	253
vinyl	288-289	ceramic	276	keyway	48	Full-view storm doors	205
vinyl, slip-retardant	289	ceramic, tips on	277	Forced air furnace	397	Fungicide	92
wood	282	cork	275	remove & replace	397	Furnace	
Floor trim, wood	279	granite	275	Forced-air heating	391	coal	404
Floor warming system	305	marble	275	Foremost International	363	counterflow, gas	397
thermostat	305	Flooring, wood		Formica countertops	322	flue	399-403
Flooring		hardwood	272	Forms		gas	398
adhesive for rubber tile	290	laminate	274	board	43	gas, duct	396
adhesive for vinyl sheet	290	softwood	272	curb	44	gas, floor	404
adhesive for wood	282	strip	272	footings	44	gas, thru-wall	404
adhesive remover	285	Floors, sagging	54	foundation	43-44	gas, wall	404
bamboo plank	280	Floors, wood, fixing squeaks	56	keyway	44	horizontal flow, gas	397
carpet	308	Flue		plywood stripping	44	low boy, gas	396
ceramic tile	294	chimney	399	wall	43	oil fired	397
demolition	35, 278, 315	chimney, aluminum	399	Formwork, stripping	44	remove & replace	397-398
demolition, wet	533	furnace	399-403	Forsyth composite sink	330	wood burning	404
hardwood plank	280	Fluidmaster	364	Foundation		Furniture	
hardwood, sanding	281	Fluorescent ceiling fixture	441	access doors	88	blocking	529
heart pine plank	280	Fluorescent diffuser fixture, low profile	441	anchor	512	moving	529
Hevea parquet	282	Fluorescent fixtures		bracket	512	Furniture pad	538
installation spacer	283	parabolic troffer	258	crack repair	513	Furring	
laminate floor		troffer	258	demolition	31	floor	72
underlayment	284	U-lamp troffer	258	vents	88	wood	72
laminate strip	284	Flush doors	219	Foundation & roof coating, non-fibered	129		
maple hardwood	279	bi-fold closet	219	Foundation & slab pre-construction checklist	38	G	
maple strip, unfinished	281	birch exterior	192, 197	Foundation bolt	512	Gable, truss	76
molding, laminate	284	birch interior	206-207, 210	Foundation insulation	86	Gable louver, metal	90
molding, wood		fire-rated	192	Foundations		Gable vents	89
laminate	283	hardboard	192	concrete	46-47	metal	90
Northwoods hardwood	278	hardboard exterior	197	cracks (active or dormant)	37	power attic	92
oak	279	hardboard interior	206-209	equipment rental	39	redwood	90
oak parquet	282	hardwood exterior	192, 197	footings	48	Gabrielle Comfort	
oak self-stick parquet	282	lauan exterior	192	forms	43	Height toilet	363
oak, solid hardwood	278	lauan interior	206-207, 210	leaky basement walls	37	GAF	131, 134, 145
Pergo	283	oak entry	194	repair	37	GAFGLAS	
Pergo underlayment	283	oak interior	206, 210	Frame		ply 4 glass felt	134
red oak, strip	281	painting labor	471-472	painting labor	471	Torch & Mop System	134
removal	278	red oak interior	210	sink	334	Galvanized bullnose corner bead	247
repairs	62	steel exterior	198-199	Frame wall, aligning	514	Galvanized flashing	142
rustic oak plank	280	steel utility	198	Framed bypass door, bathtub	356	Galvanized rigid steel conduit	429
sealant, laminate	283	Flush mount ceiling fixture	441-442	Frameless corner cabinet	383	Galvanized roofing	138
setting with adhesive	294	Flush mount light fixture	442	Frames, door	194	louver	145
setting with mortar	294	Flush valve		Framing		Galvanized steel rain gutters	146
sheet vinyl	286-287	Sloan Royal	363	cut window opening	156	Garage demolition	30
strips, natural wood	279	urinal, Sloan Royal	363	damage	53	Garage doors	223
surface preparation	284	Flute & reed molding	261			bonded steel	224
teak	279					bottom seal	223
TrafficMaster laminate	284					extension springs	225
transition reducer strip	292						
transition strip	292						
trim, hardwood	281						
underlayment	285						

- hardware 225
 installation 223
 insulated 224
 jamb hinge 224
 locks 225
 low headroom kit 225
 operators 225
 raised panel 223
 replacement 223
 steel 223
 steel, non-insulated 224
 torsion spring 223
 trollies, installation 223
 weather seal 224
- Garage slabs 42
- Garbage disposal . . . 339-340
 basket strainer 335
 connector, dishwasher
 drain 341
 cord kit 340
 mounting assembly 340
 mounting gasket 340
 removal 315
 sink flange 340
 sink stopper 340
 switch, sink top 340
- Garden windows 158
- Gardner 135-136
- Gardner Bender 417
- Gas breaker, rental 28
- Gas cooktop 342
- Gas furnace
 counterflow 397
 exterior wall duct 396
 horizontal flow 397
 interior wall duct 396
 low boy 396
 remove and replace 397
- Gas water heater 405
 AquaStar 407
 power vent 407
 tankless 407
- Gasket
 fixture, remove
 & replace 352
 mounting 340
 wax, toilet bowl 364
- Gates, security 205
- Gazebo ceiling fan 444
- GE Appliances 341-342
- Gel stain 488
- General requirements 29
- Generator 540
- Genesis kitchen faucet 332
- Georgetown lavatory
 faucet 373
- Georgia-Pacific .245, 251-253
- GFCI circuit breaker 437
 plug-on 440
- GFCI receptacle . . 425, 435
 duplex waterproof 428
 hospital grade 435
 vertical 428
 wet location cover 428
- Girders, carpentry 62
- Glacier Bay 331, 333,
 337, 360, 370-372
- Glacier Extensa
 kitchen faucet 332
- Glaslock interlocking
 shingles 130
- Glass
 jalousie 169
 measure & cut 170
- Glass block mortar mix . . 306
- Glass cutters 171
- Glass felt, ply 4 134
- Glass globe ceiling
 fixture 442
- Glazing bead 170
- Glazing compound 170
 latex 170
- Glazing points 170
- Glazing putty, remove
 and replace 170
- Glazing tool 171
- Glidden 492-495
- Gloss, polyurethane oil . 495
- Gloss & seal, tile 308
- Gloss enamel, alkyd . 493
- Gloss finish, log home . 489
- Glue, Pergo laminate
 floor 283
- Grade beams
 concrete 48
 formwork 44
- Granite
 aggregate concrete . . 46
 countertop 323
 floor tile 299
 mortar mix 306
 setting adhesive 306
 tile, natural 299
 tile flooring 275
 vanity top 377
- Granules, roofing 136
- Gravel stop 142
- Gravity heating 391
- Gray Board insulation . . 85
- Grecian cast molding 262
- Greek key chair rail 262
- Greenboard 71
- Greenhouse panels 140
- Greenwaste, recycling . 29
- Greenwich kitchen sink . 330
- Grilles, door, patio 216
- Ground bar kit
 breaker box 440
 QO load center 440
- Ground fault interrupter,
 plug-on circuit breaker . 440
- Ground rod clamp 432
- Grounding bushing,
 insulated metallic 430
- Grout
 colorant 307
 Saltillo 307
 sanded 307
 sealer 308
 tile 294
 tile, non-sanded dry . . 307
- Grout mix concrete 46
- Grouting, concrete 50
- GRS conduit 429
 removal 429
- Guard, window 167
- Guardrail, demolition . . 29
- Gutters
 acid wash 466
 aluminum 146
 flashing cement 135
 galvanized steel 146
 painting labor 476
 patching material 135
 remove and replace . . 106
 roof caulk 136
 vinyl 146
- Gutting, demolition 30
- Gypboard, painting . . 483-484
- Gypsum
 demolition 34
 greenboard 71
 Type X 71
- Gypsum base, Imperial . 245
- Gypsum board,
 DensArmor 243
- Gypsum lay-in ceiling
 panel 257
- Gypsum panel lift 250
- Gypsum wallboard
 demolition 242
 fire code 243
 flexible 244
 installation 242, 244
 joint cement 246
 joint tape 246
 mold resistant 243
 primer 246
 repair 242
 spray texture 244
 water resistant 243
- H
 Hammer, drywall 250
- Hampton Bay 441-444
- Hand sander 251
 drywall 250
- Handle sets 216
 double cylinder 202
 entry door 202
- Handrail
 painting 481
 patio deck 455
- Handy box
 cover, blank 424
 drawn 424
 welded 424
- Hanger bracket, lavatory . 369
- Hangers, pocket door . . 222
- Harbour Collection 289
- Hardboard
 lap siding 112
 panel siding 111
- Hardboard doors 192,
 207, 209
 fire-rated 197
- Hardboard siding 100
- Hardibacker 295
- Hardie 112
- Hardipanel 112
- Hardiplank 112
- Hardisoffit 112
- Hardware
 bi-fold door 221
 door, patio 216
 garage door 224-225
 pocket door 222
 screen door 203
- Hardwood
 flooring demolition . . 315
 molding, embossed . . 259
 molding, Victorian base . 259
 paneling 251
- Hardwood doors 192
 fire-rated 192
 prehung 197
- Hardwood flooring
 demolition 35
 maple 279
- molding 278, 280
- oak 278-279
- removal 278
- rosewood 279
- sanding 281
- strip 278
- TapTight 280
- trim 281
- Hardwood molding . . . 259,
 278, 280
 Bruce parquet 282
- Harris-Tarkett . 278, 280-281
- Hartland cast iron
 kitchen sink 330
- Hazel 358
- HazMat protection 538
- Headers, carpentry 68
- Headroom kit 225
- Heart pine
 flooring trim 281
 plank flooring 280
- Heat recovery ventilator
 retrofit 406
- Heat-A-Lamp bulb
 heater & fan 381
- Heat-A-Ventlite heater . . 382
- Heaters
 baseboard, electric . . 404
 water, gas 405
 whirlpool bath
 EZ-Install 354
- Heath Zenith 443
- Heating duct, removal . . 396
- Heating system
 component removal . . 396
- Heating systems
 electric space heaters . 392
 hot water, radiant
 heating 392
- Heating systems, warm air
 forced-air 391
 gravity 391
- Heating, hydronic 398
- Helmsman spar
 urethane 488
- Hemlock doors 212
- Henry 133, 135-136,
 254, 285-286, 290
- HEPA central air
 filtration retrofit 399
- HEPA vacuum 540
- Hevea parquet flooring . 282
- High boy threshold, oak . 195
- High early strength
 concrete 47
- High time factors 466
- High-gloss enamel 493
- High-gloss finish sealer . 307
- Hilti 250
- Hinges
 cabinet 328
 cabinet, Euro 327
 door 196
 garage door 224
 solid brass 196
- Hip & ridge shingles . . 130
- Hip shingles 131
- Hold-down anchor 512
- Hole cover, faucet 335
- Hollow core doors 207
- Hollow metal doors 194
- Homax 245, 493

HomeLine	Indoor main lug load	heater closet 210	Jelly jar fixture 443
circuit breaker 437	center 438	hemlock, prehung 212	Jenn-Air 341
indoor main lug load	Homeline 437	knotty alder 212	Job Cost Wizard 9
center 437	Industrial hygienist 535	lauan 207	Job survey (scope of
HomeStyle	Infiltration barrier 88	lauan, flush 206-207	work) 11
suspended ceiling 256	Infrared bulb heater	oak 208, 212	Joint cement, lightweight . 245
Hood	& fan 381	oak, flush 206	Joint compound 246
range 343-344	Ingenium Flushing	pine 208, 212	Joint repair, concrete . . . 513
range, quiet 343	System 363	pine louver 212	Joint tape 246
range, vented 343	Innovations lavatory	prehung 211, 212	drywall 246
Hooks	faucet 373	Interior flat paint 492	Joints, expansion 46
robe 385-386, 388	Inside corner & cove	Interior latex	Joists
Hopper gun, ceiling	molding 266	eggshell 492	bridging 65
finish 244	Inside corner bead,	flat finish 492	ceiling 73
Hopper vinyl window . . . 159	metal 247	paint, semi-gloss 493	demolition 33
Hospital grade	Inside corner molding	Interior paint 492	floor 64-65
receptacle, GFCI 435	polystyrene 267	Interior painting 466	TJI 65
Hot mix, spreading 51	prefinished 267	Interior sanding, labor . . 466	J-trim, metal 248
Hot water dispenser . . . 336	In-Sink-Erator . . 336, 339-340	Interior trim	Jubilee White Ice
Hot water heating	Insl-X 496	baseboard 238	beaded paneling 251
systems 392	Installation kit	casing 238	Junction box 424
Hotmopping, roofing . . . 132	floating floor 280	molding 238	Junior basket strainer . . 338
House wrap 88	Pergo 283	Interior wall assemblies . . 70	
Hub	Installation system,	Interlocking shingles . . . 130	
bolt-on A Type	laminated flooring 284	Intermatic 436	
universal 438	Insulated grounding	Intermediate metal	K
watertight conduit . . . 430	bushing, metallic 430	conduit 429	Karnak 136
Humidifier, central 397	Insulating bushing,	International	Key locks, sliding
HVAC	high-impact	Thermocast 331, 338,	window 171
central air conditioning . 398	thermoplastic 430	368-369	Keystone 356, 359
cleaning 530	Insulation	In-wall spring wound	Keyway form 44
component removal . . 396	blow-in cellulose 85	timer 436	Kick plates, door 213
hydronic heating	board 80, 85	Island sink, polycast . . . 338	Kicker, garage door 225
system 398	board, demolition . . 34, 316		Kickplate channel 459
radiator, cast iron . . . 398	built-up roofing,		Kickplate coil 459
radiator, relocation . . . 398	patch 131-132		Kidde 436
removal of	ceiling 79		KILZ
components 396	FBX 86		sealer, primer
restoration 92	fiberglass 84-85	J	& stainblocker 492
Hydraulic door closers . . 217	fiberglass batt 84	J A Manufacturing 334,	exterior sealer primer
Hydraulic jacks 62	fiberglass, unfaced . . . 84	.339, 361, 371, 374	stainblocker 494
Hydronic heating 398	floor 80	Jack roof 145	Kitchen
Hydro-X Vacuum 531	foam 85	Jack posts 63	appliance removal 315
Hygienist, industrial 535	foundation 86	Jackhammer, rental 28	cabinets, removal 315
	masonry 87	Jalousie windows	countertop 323-324
	natural fiber 87	aluminum 163	cabinet doors 316
	polystyrene 85	operators 166	Kitchen cabinets
	pouring 87	replacement glass . . . 169	base 317-318
	R-Gard 86	vinyl 159	wall 317-319
	rockwool 86-87	Jamb extension kit 216	Kitchen countertop
	roof, perlite 86	Jamb sets	miter bolt kit 324
	SAFB 87	finger joint 209	Kitchen faucet
	sill gasket 86	interior 209	deck spray 333-334
	sound control 86	solid clear pine 209	pull-out spout 331-332
	urethane sheathing . . . 86	with hinges 209	single-handle 331-333
	vapor barrier 81	Jamb	two-handle 333-334
	vermiculite 87	exterior 194	Kitchen sink 329-330
	wall 80	exterior door 194	Beaumont 331
	Interior pressure wash . . 530	exterior, remove &	cast iron 329-330
	Interior & exterior stain	replace 191	Charleston 329
	acrylic 487	interior, remove &	composite 330-331
	Interior acrylic latex	replace 206	double bowl 328-329
	paint 492	pocket door 222	Iveness 331
	Interior doors 212-213	Jameco 335	Newport 331
	birch, flush 206-207	James Hardie 112, 295	polycast 330
	cafe 209	Jasco 282, 490-491, 495	single bowl 328
	fir 208	J-bead	stainless steel 328
	fire-rated 211	metal 248	Kitchen sink basket
	flush 207, 209-210	plastic 248	strainer 335-336
	half louver 208	J-channel	Spin-N-Lock 335
	hardboard 207	thermoplastic 108	washer 336
	hardboard, colonist . . . 207	vinyl 107	
	hardboard, flush . . 206-207	Jeffrey Court 300	

- Kitchens
 appliances313
 cabinets & counters . . .310
 cabinets & counters,
 costs311
 cabinets & counters,
 custom-made312
 cabinets & counters,
 refinishing311
 design309
 electrical service
 checklist314
 remodeling checklist . .313
 work triangle310
 Klean-Strip487
 Knob & tube wiring . . .411
 Knobs, cabinet324-326
 Knock down door
 frames194
 Knockdown ceiling . . .245
 Knockdown drywall
 texture244
 Knockdown stucco . . .493
 Knockers, door213
 Kohler328-330,
 . . .332-333, 353-354, 363,
 . . .366-369, 371, 374
 Kool Patch acrylic roof
 patching cement . . .135
 Kool Seal135
 Kraft-faced fiberglass
 roll insulation84
- L**
- Labor costs12
 hourly16
 jobsite conditions . . .13
 Labor, manhours
 acid wash gutters
 & downspouts . . .466
 apply acoustic ceiling
 texture469
 apply masonry block
 filler476
 burn off paint466
 caulking466
 cutting-in466
 high time painting . . .466
 masking466
 paint, stripping467
 painting aluminum . . .482
 painting baseboard . . .468
 painting bookcases
 & shelves468
 painting cabinets . . .469
 painting closet shelf
 & pole470
 painting concrete
 floor474-475
 painting CMU . . .477-478
 painting decorative
 wood handrail . . .481
 painting door frame
 & trim471
 painting exterior
 French door . . .471
 painting exterior louver
 door471
 painting exterior panel
 (entry) door471
 painting exterior plaster
 or stucco480-481
 painting flush exterior
 door471
 painting gutters &
 downspouts476
 painting gypsum
 drywall ceiling . . .484
 painting gypsum
 drywall walls . . .483
 painting interior flush
 door471-472
 painting interior French
 door472
 painting interior louver
 door472
 painting interior panel
 door472-473
 painting molding or
 trim479
 painting roof
 overhang479-480
 painting shutters or
 blinds481-482
 painting smooth brick
 masonry477
 painting tongue &
 groove ceiling . . .469-470
 painting windows . .486-487
 painting wood deck
 or floor475
 painting wood paneled
 walls485
 pressure washing
 (waterblasting) . . .468
 repaint home exterior .466
 repaint home interior .466
 sandblasting . . .467
 sanding, exterior . . .467
 sanding, interior . . .466
 staining fascia . . .473
 masonry & stucco . .494
 semi-gloss . . .493
 waterproofing . . .494
 Latex primer
 PVA491
 resilient flooring . . .285
 Lattice molding . . .269
 Luan doors . . .206-207, 210
 flush . . .192
 Laundry faucet
 two-handle . . .337
 wall mount . . .337
 Laundry tub
 double bowl . . .337
 overflow tube . . .337
 single bowl . . .336
 Utilatub . . .336
 utility kit . . .336
 Lavatory base . . .367
 Lavatory bowl . . .366
 Lavatory faucet
 adjustable center . . .374
 decorator . . .373
 hands free . . .371
 hi-arc . . .373
 single-handle . . .370-371
 single-handle, zinc . .370
 two-handle . . .371-374
 two-handle, acrylic . .371
 two-lever . . .371
 Lavatory hanger bracket .369
 Lavatory leg set . . .367
 Lavatory sink . . .367-369
 above counter . . .369
 Cadet . . .368
 drop-in . . .367-368
 Farmington . . .367
 Laurel . . .368
 Magnolia . . .369
 Miami . . .369
 Murro . . .369
 oval . . .368
 Ovalyn . . .368
 pedestal . . .366
 Radiant . . .368
 Reminiscence . . .369
 removal . . .367
 Renaissance . . .367
 round . . .368
 Seychelle . . .367-368
 Summit . . .368
 under counter mount .368
 wall hung . . .369
 wall hung, corner . .369
 Lavatory trap, remove
 & replace . . .352
 Lay-in ceiling panel,
 gypsum . . .257
 LB conduit body, PVC,
 Type LB . . .421
 LDR Industries . . .334-335
 Lead flashing . . .143, 145
 Leak Sentry toilet fill
 valve . . .364
 Leak Stopper rubberized
 roof patch . . .135
 Leaks, roof penetrations .120
 LED lighting system
 retrofit . . .444
 Ledgers . . .73
 Leg set, pedestal
 lavatory . . .367
 Lenape . . .304-305
 Let-in bracing . . .67
 Let-in ribbons . . .73
 Leveler, embossing . . .285
 Lever locksets . . .202
 Leviton . . .434-435
 Lexan XL-10 . . .171
 L-flashing . . .143
 Lift sash . . .166
 Light bar
 beveled . . .384
 medicine cabinet . .384-385
 Light fixture
 ceiling . . .440
 chandelier . . .442
 chrome bath bar . . .441
 drum, mushroom . . .441
 jelly jar . . .443
 mushroom flush mount .442
 outdoor bulkhead . . .443
 remove & replace . . .441
 wave bath . . .441
 Light kit
 mini can . . .440
 mini can recessed
 eyeball . . .440
 recessed . . .440
 recessed non-IC baffle .440
 slot aperture . . .440
 Light-emitting diodes . .444
 Lighting
 motion sensor . . .443
 recessed . . .440
 Lighting fixtures, soffit,
 kitchen . . .316
 Lighting panel
 acrylic . . .258
 styrene . . .258
 Lights, suspended troffer
 fixture . . .258
 Lightweight concrete . . .46
 Linoleum, sheet,
 demolition . . .35
 Liquid underlayment . .285
 Liquid-tight flexible
 conduit, Carflex . . .427
 Listello tumbled marble
 tile . . .300
 Litex . . .493
 Lithonia Lighting . . .441
 Load center
 combination ring type .437
 flange kit . . .437
 ground bar kit . . .440
 HomeLine indoor
 main lug . . .437
 indoor main lug . . .438
 outdoor . . .439
 Loading trucks . . .40
 Locknut steel sealing
 conduit . . .430
 Locks
 deadbolt . . .202
 door, folding . . .217
 garage door . . .225
 installation . . .201
 patio door . . .216
 sash . . .166
 sliding window . . .171
 window flip . . .171
 Locksets
 and deadbolt . . .202
 colonial knob . . .202
 egg knob . . .202
 installation . . .201
 keyed entry . . .201-202
 lever . . .202
 Log cabin siding . . .110
 Log home gloss finish . .489
 Log lap siding . . .110
 Longstrip oak flooring . .279
 Louver
 gable . . .90
 roof . . .145
 roofing . . .145
 Louver doors
 painting . . .471-472
 Louver windows . . .163
 Louvered doors . . .212
 Louvered exterior
 window shutters . . .167
 Louvered vents . . .90
 Louvers
 midget . . .91
 roof . . .91
 wall . . .91
 Low voltage wiring . . .414
 Low-Boy toilet kit . . .364
 Low-Boy trash disposal . .29
 Low-sound bath fan,
 QuieTTest . . .380
 Low-voltage light kit . . .440
 L-straps . . .512
 L-trim, drywall . . .248

Lug load center, HomeLine indoor	437	Mayfield sink	329	Miniature circuit breaker		crown polystyrene	268
Lumber		Maytag	341-342	QO	439	crown prefinished	268
alternative building materials	457	MDF		Minwax	487-489, 491	demolition	34
deck	453-454	casing	261	pickling stain	488	embossed basswood	259
pressure treated	452	chair rail	261	polycrylic	489	embossed decorative	
recycled plastic	457	molding, base corner	261	polyshades	488	hardwood	259
Thompsonized	454	molding, colonial base	261	polyurethane	489	extruded polymer	263
Luna ceiling panel	257	molding, crown	262	spar urethane	488	hardwood	259, 280
		molding, plinth block	262	Miracle Sealants Co.	307	hardwood floor	278
		molding, ultralite crown	262	Mirror bath light bar	441	hardwood parquet	282
		paneling	251	Mirrored doors		heart pine	281
		Mechanical systems,		bi-fold	221	inside corner	266-267
		repairing earthquake		bypass	218	laminite flooring	284
		damage	511	Mirrored sheet	171	lattice	269
M		Medicine cabinet		Mirrors		MDF	261
Magna	251	beveled edge	383-384	frosted	382	MDF, colonial base	261
Magnetic weatherstrip	196	bi-view	384	oval	382	MDF, crown	262
Magnolia Brick & Tile	300	etched glass	383	vanity	382	MDF ultralite crown	262
Mahogany doors	193	framed	383	Mission tile roofing	139	oak, unfinished	281
Main circuit breaker	438	framed door	382	Miter bolt kit	324	outside corner	267
Main load center,		frameless	383-384	Mobile home doors	222	painting labor	479
combination	437	light bar	384-385	Modified bitumen		panel	253
Main lug load center	439	lighted	383	adhesive	133	paperwrap	263, 264
HomeLine indoor	437	mirrored	383	Moen	332, 360, 362, 370, 373-374	polystyrene	263-265
indoor	438	octagonal	383	Moisturbloc poly-		prefinished casing	264
Mallet, rubber	291	oval	383	ethylene film	284	primed finger joint	
Man-O-War marine		single door	383	Moisture barrier,		base	260
spar varnish	488	sliding door	383	polyethylene	284	quarter round	261
Maple plank flooring	280	swing door	383	Moisture-resistant		reversible flute & reed	261
Maple hardwood		tri-view	384	drywall	243	rosette block	259
flooring, solid	279	Medium density fiberboard		Mold		round edge stop	261
molding	279	molding	261	abrading	537	spring cove	268
Maple strip flooring	281	Medley sheet vinyl		blasting	537	stool	261
Marble		flooring	286	containment structure	536	stop	195, 269
countertop	376	Megatrade	297	encapsulation	537	stop paperwrap	269
floor tile	298	Melard	367	inspection	535	stop polystyrene	269
Listello tumbled tile	300	Membrane		protective equipment	538	stucco	196
mortar mix	306	anti-fracture	305	removal	537	T-astragal	194
setting adhesive	306	fiberglass reinforcing	136	sampling	535	Victorian hardwood	
threshold	300	polyethylene	308	testing	535	base	259
tile	298	tile, anti-fracture	305	Mold & mildew		vinyl tileboard	270
tile flooring	275	Memoirs pedestal		sanitizer	531	wall base	284
Margin notch trowel	291	lavatory bowl	366-367	Mold remediation	535	wall, suspended	
Marine spar varnish,		Mesh, crack repair	248	by job size	526	ceiling	255
Man-O-War	488	Metal conduit		cleaning methods	528	Molding set, brick	260
Marine varnish	488	flexible	426	industrial hygienist	526	Molding, crown	261
Markup vs. margin	7	galvanized	429	insurance coverage	525	Molding, hardwood	279
Masco	361, 372-373	Metal corner bead	247, 249	sampling and protocol	527	rosewood	279
Mask, safety	250	Metal doors	194	Mold remediation		Monticello lavatory	
Masonite Corp	253	bi-fold	220	protocol	535	faucet	373
Masonry		Metal primer	496	Mold retarder	92	Mop, roof	136
chimneys, repair	104	rust converting	496	Molded face closet		Mortar	
cleaning	115	Metal screen doors	203	doors	220	acrylic admix	307
demolition	30	Metallic grounding		Molded sectional		bedding	306
fireplace demolition	115	bushing, insulated	430	shower stall	357	bonding	305-306
fireplaces	115	Meter main load center	437	Molding		CustomBlend thin-set	306
fireplaces, repair	104	Meter socket	437	base	263-264	epoxy	306
furring	72	Metro sheet vinyl		base cap	260	flexible bonding	306
insulation	87	flooring	287	base corner	259	porcelain	306
joints	115	Microwave oven		base shoe	260, 264	thin-set	306
painting labor	476-478	Advantium	342	bead	260	thin-set tile	293
pointing	115	over-the-range	342	beaded baseboard	259	tile	294
protective coating	495	Midget louvers	91	brick	195	tile repair	306
recycling	29	Milban	531	casing	264-265	underwater tile repair	307
repointing	115	Milban 1-2-3	536	casing paperwrap	265	Mortar mix	
veneer	103	Mildew resistant drywall	243	casing polystyrene	265	glass block	306
walls, waterproofing	130	Mineral fiber ceiling		cast	262	marble & granite	306
Masonry & concrete		panel	257	chair rail	260, 262, 266	Mosaic ceramic tile	304
waterproof	495	Mineral siding	93	colonial crown		Motion sensor security	
Masonry & stucco paint	494	asbestos cement	94	paperwrap	268	light	443
Masterchem	492, 494	asbestos testing	94	cove	268	heavy-duty	443
Mastic, tile	294	Mineral surface roll		crown	259	lantern	443
Material costs	11	roofing	133	crown embossed		Moulding, hardwood	259
		Mini can recessed light		polystyrene	268	Mount Vernon paneling	251
		kit	440				

- Mounting assembly, disposal 340
- Mounting bracket, non-metallic low voltage . . . 422
- Mounting kit, sink 334
- Mud
 joint cement 245
 wallboard 246
- Mullions, window 166
- Multi gang switch box . . . 425
- Mushroom light fixture . . . 442
- N**
- Nail plate, stud 419
- Nailer strip, carpentry . . . 73
- Nailers 73
- Nailite siding 107
- Nails
 drywall 249
 vinyl siding 107
- National Electrical Code (NEC)* 410
- National Estimator 8
- Natural Images floor tile . . 289
- Natural stone floor tile . . . 299
- Needle beams 62
- Negative air scrubber 539
- Neo-angle shower kit 358
- Neptune 328
- Neptune marble countertop 376
- New wood treatment 490
- Nipple, rigid conduit 431
- NM-B Romex sheathed cable, indoor & outdoor . . 418
- NM-B Romex sheathed indoor cable 417
- Non-fibered roof & foundation coating . . . 129
- Non-metallic
 ceiling fan box 422
 conduit fitting 421
 low voltage device mounting bracket . . . 422
 old work switch box . . . 422
 reducer bushing 420
 sheathed cable 418
 standard coupling 421
 UF compression connector 419
- Non-metallic cable 417
- Non-metallic sheathed cable (Romex) 412
- Northwoods hardwood flooring 278
- Notched trowels 291
- NuTone 343, 378-382
- Nylon carpet 308
- Nylon paneling rivets 253
- O**
- Oak
 counter edge molding . . . 268
 hardwood flooring 278
 molding, unfinished . . . 281
 parquet flooring 282
 plank flooring 280
 strip flooring 278, 281
- Oak doors 192, 206, 210
- entry 194
- Oak fill strip 321
- Oak threshold 195
- OakCrest Products 282
- Octagon box, drawn 425
- Octagonal windows 163
- Offset compression connector, EMT-to-box . . 424
- Offset screw connector, EMT 423
- Oil, Danish 488
- Oil fired furnace 397
- Oil gloss, polyurethane . . . 495
- Oil, teak 491
- Oil, tung 491
- Oil-based enamel 496
- Oil-based floor finish, Varathane 489
- Oil-based primer sealer . . . 493
- Oil-fired water heater 405
- Old work switch box, non-metallic 422
- Olefin carpet 308
- Opal glass wall light 441
- Open light kit 440
- Openers, garage door 225
- Opening, breakthrough wall 72
- Operators, window 166
- Orange peel
 ceiling 245
 drywall texture 244
- Oriental carpet, hang dry . . 531
- Oriented strand board siding 111
- OSB
 roof sheathing 77
 shear wall 512
 sheathing 66, 70
 siding 111
 subfloor 66
- Outdoor ceiling fan 444
- Outdoor wall lantern 443
- Outlet box
 connecting appliance . . . 417
 re-connect appliance . . . 417
- Outside corner bead, drywall 248
- Outside corner molding 263, 267
- colonial 267
- paperwrap 267
- polystyrene 267
- polystyrene colonial . . . 267
- prefinished 267
- Outside corner trowel, drywall 250
- Oval light fixture, outdoor bulkhead 443
- Oven
 double wall 342
 microwave 342
 microwave, above range 342
 wall 342
- Overhang, painting 479-480
- difficulty 480
- Overhead doors, garage . . . 223
- Owens Corning 130, 144
- P**
- Pad, furniture 538
- Paint
 acrylic latex 492
 alkyd 493
- barn & fence 496
- ceiling 492
- elastomeric 494
- flat 492, 494
- floor & porch 495
- gloss 493
- house & trim 494
- interior 492
- latex 494
- latex ceiling 492
- latex interior 492
- masonry & stucco 494
- polyurethane oil gloss . . . 495
- satin flat 494
- semi-gloss 493
- semi-gloss latex 493
- swimming pool 496
- texture 493
- wall & trim 492-493
- waterproofing 494
- Paint additive, Perlite texturing 493
- Paint seal removal 156
- Painting
 burn off, manhours 466
 high-time difficulty factors 466
- Painting & finishing
 application methods 464
 exterior trim 463
 paint color & gloss 462
 penetrating stains 463
 recoating 461
 surface preparation 461
 wood preservatives 463
- Painting labor, manhours
 acid wash 466
 baseboard 468
 blinds 481-482
 bookcases 468
 brick masonry 477
 burn off paint 466
 cabinets 469
 caulking 466
 ceiling texture 469
 ceilings 469-470
 closet shelf & pole 470
 CMU 477-478
 concrete floor 474-475
 cutting-in 466
 door frame & trim 471
 drywall 483, 484
 eaves & cornices 480
 entry doors 471
 exterior doors 471
 French doors 471-472
 gutters & downspouts 476
 handrail 481
 houses 466
 interior doors 471-473
 louver doors 471
 masking 466
 molding 479
 paneled walls 485
 plaster or stucco 480-481
 pressure washing 468
 roof overhang 479-480
 shutters 481-482
 siding 482
 stripping paint 467
 trim 479
 windows 486-487
 wood deck 475
- Paling, rail 455
- Pan, shower 359
- Pancake box, ceiling fan . . 425
- Panel molding, FRP 253
- Panel siding 98
- cedar shingle 113
- fiber cement siding 112
- fiber-overlaid plywood . . . 99
- hardboard 98, 111
- MDO 99
- OSB 111
- particleboard 98
- plywood 98, 111
- Panel wallcovering, designer 252
- Panel, ceiling 253
- acoustical 256
- lay-in 257
- lighting 258
- suspended 255-257
- Panel, distribution, disconnect & remove . . . 437
- Panel, electric service . . . 439
- Paneling
 beaded 251
- birch 252
- demolition 252
- fiberboard 251
- FRP 253
- hardboard 251
- hardwood 252
- hardwood plank 251-252
- MDF 251
- oak print 251
- pine plank 252-253
- plywood 251-253
- prefinished 252
- rivets 253
- tileboard 251-252
- trim pack 252-253
- wainscot 253
- Panelized shingles 113
- Panels
 fiberglass 140
- greenhouse 140
- sun 140
- Panic bar, door 226
- Panic door hardware 226
- Pantry
 cabinets 319-321
- doors 212
- Paper
 Aquabar 87
- building 134
- Moistop 88
- Pyro-Kure 88
- roof flashing 88
- roof underlay 88
- Seekure 88
- vapor barrier 87
- Paper holder, toilet tissue 304
- Paper-faced metal trim . . . 247
- Paperwrap molding
 base 263
- casing 264-265
- chair rail 266
- colonial cap 264
- colonial crown 268
- inside corner & cove . . . 266
- outside corner 267
- stop 269
- Parabolic troffer fluorescent fixture 258

Parisa faucet	370	Pedestal lavatory		Place n Press floor tile	289	Plywood	
Parks Corporation	489	Bahama	366	Plain end 45-degree		roof sheathing	77
Parquet molding	282	Classic base	367	elbow	421	sheathing	66, 70
Parquet flooring		leg set	367	Planing concrete	513	siding, T 1-11	111
Hevea	282	Memoirs	366	Plank floor clamp	281	subfloor	66
oak	282	Memoirs base	367	Plank flooring		Plywood cap molding	263
oak, self-stick	282	metal leg set	367	bamboo	280	Plywood siding	99, 111
tile	282	removal	367	heart pine	280	pre-finished	99
Parting stop molding	269	Repertoire	366	rustic oak	280	Pneumatic breaker,	
Partition walls		Seychelle	366	wood	280	rental	28
adding	270	Williamsburg	366	Plank paneling	252-253	Pocket doors	
removal	70	Peel & Patch water-		beaded	252	edge pull	222
Pass & Seymour/		proofing	135	Edge-V	252	hangers	222
Legrand	435	Peep sights	214	Plaster		hardware	222
Passage latch, knob	213	Pellets, dry ice	537	demolition	34, 242, 316	jamb	222
Paste wax	491	Penetrating stains	463	demolition, wet	533	kit, converging	222
Patch		Penetrating wood finish,		painting	480-481	Pointing trowel	291
built-up roofing	131-132	Preserva-Wood	487	repair	514	Pointing, masonry	115
drywall	248	Pergo	283	veneer	246	Points, glazing	170
Elastocaulk roof patch	136	finishing putty	283	Plaster of Paris	246	Pole sander	251
Elastomastic roof		flooring	283	Plastering		Polish, Boston	491
patch	136	flooring sealant	283	pool	460	Poly bags	538
flashing	135	flooring underlayment	283	spa	460	Poly sheeting	536
Kool Patch cement	135	installation	283	Plastic		Polyblend ceramic tile	
PondPatch	136	installation kit	283	conduit	420	caulk	307
popcorn	245	lamine glue	283	gutters	146	Polycarbonate sheet	171
roof caulk	136	Presto floor molding	283	lumber	457	Polycast kitchen sink	330
roof cement	135	Presto laminate flooring	283	siding	107	Polycrylic protective	
roofing	134-135	Pergola patio cover	459	Plasticized concrete	47	finish	489
roofing, cotton	136	Perimeter berm	530	Plate		Polyester stress-block	
roofing, wood shingle	137	Perimeter wall insulation	86	service entrance		fabric	136
underlayment	285-286	Perlite texturing paint		conduit sill	432	Polyester carpet	308
vinyl	285	additive	493	single gang Decora		Polyethylene film	40, 87
wet patch roof cement	135	Permanent Bond		wall	435	moisture barrier	284
Wet-Stick roof cement	135	Adhesive	133	single gang plastic		Polyethylene membrane,	
Patching		Perma-Shield	216	wall	435	Schluter Ditra	308
cement, roof	135	Pet doors	216	stud nail	419	Polymer molding	263
concrete	50	Phone wall plate	433	Plate cover, toilet base	364	Polyshades polyurethane	
Patio cover, aluminum	459	Picket fence, staining		Plate straps	513	stain	488
Patio doors	214-216	labor	474	Plate, splash	344	Polystyrene casing	264-265
aluminum	214-215	Pickling stain, white		Plates		reversible	266
aluminum, double	214	wash	488	carpentry	64	Polystyrene insulation	85-86
fiberglass, swinging	215	Picture windows	162	carpentry piecework		Polystyrene molding	
gliding, vinyl	214	Pier, concrete	63	rates	67	base	264
grille	216	Pine		Platinum lavatory faucet	373	base embossed	263
handles	216	door casing	195	Plexiglas	171	chair rail	266
hardware	216	door casing, fluted	195	Plinth	455	crown	268
hinged, vinyl-clad	214	flooring trim	281	Plinth block	259	crown embossed	268
installation	214	plank flooring	280	MDF primed	262	embossed	265
jamb extension kit	216	screen doors	203	Plug		inside corner	267
locks	216	siding	108-110	connecting appliance	417	lattice	269
roller	216	Pine doors	208	ground fault interrupter	440	outside corner	267
screen	216	Pine jamb sets	209	Plug-on circuit breaker,		spring cove	268
screen & track	216	Pine planking	252-253	Plumb bob	291	stop	269
swinging, double	214	Pine square rosette		Plumb Shop	336, 341	Polyurethane	
threshold	216	molding	259	Plumbing and HVAC		fast-drying	489
vinyl	215	Pipe		bathtub framing	395	oil gloss	495
Patio roof	455	ABS	408	framing for improve-		stain	488
Patio screens,		ABS replacement of		ments	394	Polyurethane cast	
replacement	216	cast iron	408	repairs, cutting floor		molding	262
Pavement		copper replacement		joists	394	chair rail	262
concrete	46, 49	of cast iron	408	repairs, pricing	394	corner block	262
demolition	32	copper replacement		repairs, utility walls	395	cross head	262
Paver tile	299	of galvanized	408	Plumbing drain, waste		frieze	262
brick	300	PVC DWV	408	and vent lines	393	rope	262
Paving		PVC replacement of		Plumbing systems, repair		PondPatch	136
asphalt	51	cast iron	408	earthquake damage	511	Pool paint	496
concrete	46, 49	Pipe flashing	143-145	Plumbing vent	389	Pool replastering	460
demolition	32	tile roof	145	relocate	389	Popcorn ceiling	
Paving breaker, rental	28	Pitch pan	129	Plus 10 Exterior Stain	487	patch	245
Pea gravel, concrete	46	Pitch pocket	129	Ply 4 glass felt	134	spray	244
		Pits, excavation	40			spray texture	244

- Porcelain
 bath accessory set . . . 305
 mortar 306
 towel bar 305
- Porcelain, glazed floor
 tile 296
- Porch
 columns 455
 columns, aluminum . . . 455
 demolition 452
 enclosure screen 458
 misting system 458
 repair 452
 roof framing 455
 screen frame 458
 support posts 455
- Porch & floor enamel . . . 495
- Porches
 additions 446
 balustrades 448
 columns & posts 447
 elevated decks 448
- Porches & decks
 choices in floor plank . . 450
 inspecting for decay . . . 445
 maintenance 451
- Portland cement, stucco . 114
- Portrait whirlpool bath . . 354
- Post base, plinth 455
- Posts
 basement 63
 cap 456-457
 carpentry 63
 deck 452-456
 jack posts 63
 porch 452, 455
 wood 455
- Pouring insulation 87
- Power attic gable vents . . 92
- Power distribution box . . 540
- Power massage shower
 head 362
- Power vent, gas water
 heater 407
- Power ventilators
 attic gable 92
 roof-mount 92
- Power washing 468
- PowerStar 407
- PowerStream 407
- Power-vent, water heater . 405
- PPE 538
- Pre-drying 529
- Prefinished molding
 casing 264-265
 chair rail 266
 crown 268
 inside corner 267
 inside corner & cove . . 267
 outside corner 267
- Prefinished paneling . . . 252
- Prehung doors 209-211
 double 212
 exterior 198
 fire-rated 197, 211
 French 212-213
 hardboard 197
 heater closet 210
 installation 197
 interior 212
 oak 212
 pantry 212
- patio, steel 215
 steel 199-200
 steel, exterior, with
 mini-blind 198
 steel, half lite 198
 steel, installation 197
- Prelude 255
- Premium Plus 495
 interior flat paint 492
 primer sealer 493
 satin flat exterior paint . 494
- Preservaproducts 487
- Preservative
 dock & fence post . . . 490
 wood 490-491
- Preserva-Wood
 penetrating finish 487
- Pressure wash interior . . 530
- Pressure washer 540
 manhours 468
- Price Pfister 332-333,
 337, 360-362,
 370-371, 373
- Primed finger joint casing
 colonial 260
 ranch 260
- Primed finger joint molding
 base 260
 base cap 260
 base shoe 260
 bead 260
 brick 260
 chair rail 260
 crown 261
 flute & reed 261
 quarter round 261
 stool 261
- Primed tilt double-hung
 windows 163
- Primer
 adhesive 282
 bonding 493
 clean metal 496
 concrete 493
 epoxy 496
 flooring 285
 gypsum wallboard . . . 246
 latex 491
 metal 496
 resilient flooring 285
 rusty metal 496
 water-based 492
 Primer sealer 494
 oil-based 493
 stainblocker 494
- Privacy latchsets 213
- Pro Finisher 489
- Propane-fired water
 heater 405
- Protection, tile edge . . . 303
- Protector, wood 490
- ProtectoWrap 307
- Protocol, mold
 remediation 535
- Provisa range hood 343
- Pro-Wall 3 354
- P-trap, remove &
 replace 352
- Pull
 brass-plated spoon-foot . 327
 cabinet 326-327
- S swirl 327
 wire 327
 wire, solid brass 327
- Pull bar 281
- Pull plates, door 213
- Pulling elbow, 90-degree . 423
- Pulls, edge, pocket door . 222
- Pump, water 540
- Pump mix concrete 46
- Pumps, sewer 389
- Purity siding 113
- Purlins, carpentry 76
- Push bar, door 226
- Push plates, door 213
- Pushbutton garage door . 225
- Putty, finishing 283
- PVA latex primer 491
- PVC faucet supply 374
- PVC conduit
 coupling 421
 elbow 421
 Schedule 40 420
 Schedule 80 420
- PVC conduit body 421
- PVC conduit clamp,
 Snap Strap 420
- PVC pipe 408
 DWV 408
- PVC service entrance
 cap 422
- Pyro-Kure paper 88
- Q**
- QO circuit breaker
 GFI plug-on 440
 main 438
 miniature 439
 tandem 439
- QO load center ground
 bar kit 440
- QO main lug load
 center 438-439
- Quarry tile 299
- Quarrybasics 299
- Quarter round
 bamboo 280
 floor molding . 278-280, 284
 molding 263
 primed finger joint . . . 261
- Quick Roof 135
- QuickBooks 10
- QuietTest bath fan 380
- Quietzone 86
- Quik-Tape 248
- Qwik-Gard 440
- R**
- RACO 424-426
- RADAR Illusion
 ceiling panel 257
- Radiant heating systems . 392
- Radiator
 cast iron 398
 hot water 398
 relocating 398
- Rafter
 bay vent channel 88
 spacing 88
- Rafters
 demolition 33
 rough carpentry 75
- Ragione 296
- Rail
 deck 456
 painting 481
 sink 302
- Rail molding
 chair 266
 embossed polystyrene . 266
 embossed prefinished . 266
 paperwrap 266
 prefinished chair 266
- Railing, patio deck 455
- Rain cap, chimney 400
- Rain gutters 146
 aluminum 146
 galvanized steel 146
- Ranch base paperwrap
 molding 264
- Ranch casing 195, 265
- Clearwood PS 265
- paperwrap 265
- polystyrene 265
- primed finger joint . . . 260
- Ranch door casing,
 primed finger joint 195
- Ranch stop molding 269
- Random textured
 ceiling panel 255
- Range hood 343
 Ballista 343
 custom 344
 Provisa 343
 vented 343
- RCA 433
- Ready-mix concrete 46
- Rebar 44
- Rebond 308
- Receptacle
 appliance flush mount . 435
 CO/ALR duplex 435
 duplex 435
 duplex straight blade . 434
 GFCI 435
 GFCI, hospital grade . . 435
 remove 434
 side-wired single 435
- Receptacle cover
 GFCI, wet location . . . 428
 horizontal duplex
 weatherproof 428
- Recessed bathtub,
 Princeton 353
- Recessed light kit 440
- Recessed lighting 440
- Recoating 461
- Rectangular weather-
 proof box 427
- Recycler fees 29
- Red cedar, western,
 siding 108
- Red Dot 427-428
- Red oak
 plank flooring 280
 strip flooring 278, 281
- Red rosin sheathing 87
- RedGard waterproofing
 membrane 305
- Reducer
 bamboo 280
 carpet 284

floor molding	278-279	Resilient tile	455	concrete tile	140
laminated flooring	284	adhesive	290	demolition	33
Reducer floor		demolition	35	felt	133
molding	279-280	removal	278	fiber-cement slate	139
Reducer strip		Resin siding	107	fiberglass panels	140
tile	304	Respirator	538	flashing	134
vinyl flooring	292	sanding drywall	250	flashing, self-adhesive	134
Reducing window		Retaining wall forms	47	insulation	86
opening size	156	Reversible doors	194	louver	91, 145
Reducing bushing		Reversible flute & reed		membrane	132
non-metallic	420	molding		patch	135
rigid or IMC	430	primed finger joint	261	patch, shingle	137
Redwood		Reversible polystyrene		patio	455
siding	109	casing	266	patio cover	459
vents	90	R-Gard insulation	86	sagging ridge board	59
Reed & flute molding	261	RhinoBoard	295	sheathing, OSB	70, 77
Refinishing in-ground		Ribbons, carpentry	73	sheathing, plywood	77
spa	460	Ridge & hip shingles	130-131	tile, clay	139
Reinforcing		Ridge & hip shingles	130-131	tile, concrete	140
bars	44	Ridge vent	144	trusses	76
membrane, fiberglass	136	aluminum	90	underlay	88
slab	47	Cobra Rigid	145	urethane spray foam	140
steel	44	coil	90	Roof & foundation	
steel, galvanized	45	rigid	145	coating, non-fibered	129
Reliant kitchen faucet	332	shingle-over	145	Roof apron	143
Remediation		VentSure	144	Roof caulk	136
dry rot	92	Rigid conduit		Roof cement	135
mold	535	coupling	429	wet patch	135
Removal		strap	431	Wet-Stick	135
appliance	530	Rigid insulation	85	Roof coating	137
carpet	531	Rigid steel conduit		Roof covers	164
fixture	530	elbow	429	Roof deck	
glazing putty	170	galvanized	429	removal	129
skylight	172	installation	429	repair	129
window glass	170	removal	429	walking	140
windows	156	Ring type meter socket	437	Roof edge flashing	143-144
Remover		Rings, towel	385-386, 388	Roof exhaust vent, T-top	145
adhesive	282	Rivets	255	Roof flashing	
flooring adhesive	285	paneling	253	chimney	400-401
Rental		Robe hook	385-386, 388	service entrance	432
air mover	539	Roberts	282	Roof framing	75
dehumidifiers	538	Rock, recycling	29	jacking	75
dry ice blaster	537	Rocker switch, Decora	434	Roof jack	145
floor drying system	539	AC quiet	434	Roof loading	140
generator	540	Rockwool insulation	87	Roof openings, cut	
gypsum panel lift	250	Rod clamp, ground	432	for skylights	172
negative air scrubber	539	Roll, screen	168	Roof overhang	
remediation equipment	538	Roll flashing		adding	61
wall cavity dryer	539	aluminum	141	painting	479-480
Repainting a home	466	copper	141	Roof patch	
Repair shingles, tin	144	Roll roofing	134	cotton	136
Repair clips, drywall	249	mineral surface	133	rubberized	135
Repair kit		Roll valley flashing	143	Roof patching cement,	
drywall	248	Roller		white	135
toilet	364	extendable	291	Roof sheathing	60
Repair mesh, crack	248	painting labor	468	Roof turbine vents	91, 146
Repair patch, drywall	248	Roller spline tool	168	Roof vent	
Repairs, door	191	Rollers, patio door	216	repair	130
Repertoire pedestal		Roll-on		waterproofing	130
lavatory bowl	366	texture, acoustic	493	Roof vent kit, bath	382
Replace-A-Vent	89	texture, stucco	493	Roof ventilation	83
Replacement screen		Rollup doors, garage	223	Roof waterproofing	135
doors	203	Roman tub		repair	129
Replacement windows		filler	354	replace	130
vinyl	157	trim & rough-in	354	Roofing	
vinyl double-hung	157	Romex sheathed cable	412	asphalt	132
vinyl single-hung	158	indoor	417-418	base sheet	133
Replastering		indoor & outdoor	418	broom with scraper	136
pool	460	Roof		built-up	132, 134
spa	460	bay window	164	built-up, patch	131-132
Resilient flooring, sheet		bow window	164	built-up, tear-off	129
vinyl	274	built-up	132	cement trowel	136
		cant strips	86	clay tile	139

girders	62	Sash	high-gloss finish	307	Shear wall	512
joists	68	balance	oil-based	493	Sheathed cable	
ledger strips	73	cord repair	painting	483-484	indoor	418
plates	67	lift	primer	493	indoor & outdoor	
posts	63	locks	sanding	489	Romex	418
purlins	76	springs, wood window	sill86	Type NM-B Romex	417-418
rafters	75	window, repair	tile	308	Sheathing	
ribbons	73	Saturated cotton roof	tile & stone	307	board	66, 70
roof trusses	76	patch, asphalt	water-based	492	carpentry	66
sill plates	64	Savannah lavatory faucet	waterproofing	495	demolition	34
studding	66-67	Sawing concrete slab	Sealer primer		insulated	85
subflooring	66	SBS field adhesive	stainblocker	494	plywood	70, 77
trimmers	75	ScapeWel window	water-base	494	roof	70, 77
wall openings	72	Schedule 40 PVC	Sealer's Choice 15 Gold	307	T 1-11	111
wall studs	66	conduit	Sealing conduit locknut,		Sheathing paper	87
window openings	72	Schedule 80 PVC	steel	430	Sheet	
Round conduit box,		conduit	Seal-Krete	495	acrylic	171
non-metallic	428	Schluter Ditra poly-	Seam coating kit	291	mirrored	171
Round edge stop		ethylene membrane	Seats, toilet	365-366	Plexiglas	171
molding	261	Schluter Systems	SEBS (styrene-ethylene-		Sheet flooring	
Royal Mouldings	263-270	Scotchguard	butylene-styrene)		adhesive	290
Royelle vinyl sheet		Scratch coat, plaster	asphalt	135	removal	278
flooring	287	Screed, rental	Security doors	205	vinyl	286-287
Rub, carborundum	50	Screen	Security gates, folding	205	Sheet metal	
Rubber		aluminum rolls	Security light, motion		gutters, downspouts	146
mallet	291	fiberglass rolls	sensor	443	roofing	138
roof jack	145	frame kit	Security storm doors	205	Sheetrock	
wall base	292	patch	Seekure paper	88	ceiling panel	257
wet patch roof cement	135	porch enclosure	Seismic safety standards,		demolition	242
Rubber studded tile	290	screws	earthquakes	497	fire code	243
Rubber tile adhesive	290	spline	Self-stick		flexible	244
Rubberized roof patch	135	window	parquet flooring, oak	282	installation	242, 244
Rust Destroyer	496	Screen doors	vinyl wall base	293	painting	483-484
Rust-resistant finish	496	hardware	wall base	293	repair	242
Rustic oak plank flooring	280	installation	Self-storing storm doors	204	water resistant	243
Rustic siding, pine	108, 110	metal	Self-tapping screws	141	Sheets, roofing	138
Rust-Oleum	488-489, 496	pine	Semco	305	Shelf	
S		replacement	Semi-gloss		bath, with glass	385
Sack finish	50	security, steel	latex paint	493	bathroom	388
Saddle & sill	300	steel, replacement	wall enamel	492	corner	304
Safety, respirator mask	250	vinyl	Senco	249	glass	388
Safety Zone vinyl floor		wood	SensAire wall control		painting	468
tile	289	Screen frame	switch	382	Shellac, amber	490
Sahara ceiling panels	256	Screen vents	Sentinel Products	285	ShellGard RTU	92
Salttillo		Screen wire	Sentinel sheet vinyl		Shelves, painting labor	468
ceramic floor tile	299	Screens	flooring	287	Sherwin-Williams	490
grout mix	307	patio door	Septic disposal cartridge	340	Shield, ice & water	88
Salvage, demolition	35	window	Sequentia	253	Shim shingles	138
Sampling, mold	535	Screw gun, drywall	Service entrance		Shims	
San Marino ceiling fan	444	Screwdriver, drywall	cap	432	flooring	62
Sand, fill	40, 49	Screwdriver bit, drywall	cap, PVC	422	stud	67
Sand & Kleen	251	Screw-in connector, flex	device, combination	438	Shingle flashing	144
Sandblasting		Screws	elbow	432	Shingle & shake siding	100
manhours	467	deck	meter main load center	437	furring, estimating	100
masonry	115	drywall	roof flashing	432	Shingle panels	113
Sanded grout	307	drywall to steel	Service entrance conduit		Shingle siding	113
Sander		drywall to wood	sill plate	432	cedar	113
drywall	250	lag, drill tip	Service panel, electric	439	Shingle starter strip	131
gypsum wallboard	251	screen enclosure	Set screw connector,		Shingles	
Sanding hardwood floor	281	self-tapping	EMT	423	algae-resistant	130
Sanding sealer,		Screws & clips, sink	Setting adhesive, marble		architectural	131
waterborne	489	mount	& granite stone	306	asphalt	130
Sanding sponge	250	Scribing felt	Seychelle pedestal		asphalt, repair	130
Sanding system		Scrubber, negative air	lavatory bowl	366	cedar	138
drywall	251	Seal, garage door	Shake felt	137	demolition	33
dustless	251	Seal & tile gloss	Shakertown siding	113	fiberglass asphalt	131
Sanding, paint prep,		Sealant, laminate flooring	Shakes		hip & ridge	131
manhours	466-467	Sealer	siding, replacement	105	interlocking	130
Sand-Texture wall texture	493	concrete	cedar	137	laminated	130
		exposed aggregate	Shank nut sink strainer	336	panelized	113
		grout	Shaping slopes	41	roofing	130
			Shaw HardSurfaces	284	siding	113

siding, replacement . . .105	panel98	Sinks	Soaker bathtub353
slate139	paneled shingles . . .113	bar337-338	acrylic353
tin repair144	pine108	bowl337	with skirt353
wood137	pine rustic108, 110	Breckenridge331	Soap dish386-388
wood, repair137	pine shiplap110	Cambridge331	ceramic304
ShockWave536	plywood99, 111	cast iron329-330	porcelain305
Shoe molding, base . . .264	redwood109	composite . . .330-331, 338	Soap dispenser335
Shower & bathtub	removal106	double bowl328-330	Soffit
units356-357	repair105	double bowl composite .331	painting479-480
Shower & tub faucet	resin107	entertainment338	wood73
single control360	shingle113	kitchen329-331	Soffit vents, louvered . .89
single-knob360	shingle & shake100	kitchen, basket strainer .335	Soffits
Shower base358	shingles, replacement .105	mounting clips329	aluminum114
Shower curtain rod,	southern yellow	polycast330	demolition34
permanent389	pine109-110	Silhouette polycast . . .330	fiber cement112
Shower door356	staining482	single bowl328-330	kitchen316
bypass360	T 1-11 plywood111	stainless steel328-329	pendent lighting316
hinged359	thermoplastic107	stainless steel kitchen .328	refrigerator, under
pivot359	touch up paint108	stainless steel single	counter316
swinging359	trim114	bowl328	removal106
Shower faucet360-362	vinyl96, 107	utility337	stucco114
lever handle361	western red cedar . . .108	Sinks, lavatory	vinyl108
single-knob360	wood93	Hydra369	Soil compaction41
Shower head	wood, diagonal97	Magnolia369	Solar lens172
power massage362	wood, horizontal97	Morning369	Solid core doors
remove & replace . . .352	wood, vertical97	Reminiscence369	birch exterior192, 197
Sunflower362	Siding & deck stain . . .487	Skid steer loaders, rental .39	entry193
Shower pan359	Siding & roofing, metal .247	Skimcoat patch &	fir entry193
Shower stall357	Siding installation,	underlayment286	hardboard exterior .192, 197
demolition357	removing old siding . . .95	Skylight removal172	hardboard interior . . .207
smooth wall357	Siding, estimating	Skylights	hardwood exterior . . .192
three-piece358	procedure104	acrylic173	lauan exterior192
Shower stall kit	Signature kitchen faucet .332	cut roof opening172	prehung exterior197
neo-angle358	SilentStep283	fixed172-173	red oak192
round358	Silestone countertop .323	trimmers75	red oak exterior192
Showers356-357	Silhouette polycast	tubular172	Solid surface countertop .322
corner entry kit358	kitchen sink330	venting173	Solitaire bath fan381
fiberglass357	Silicone sealant window	Slab doors .192-194, 206-207	Sound baffle, removable .340
stall357	caulk157	installation191	Sound control86
stall kit357	Siliconizer crack filler .136	Slab leveling513	Soundbloc foam
stall kit, add-on362	Sill	Slabs	underlayment283
ShowMe8	door, thermal195	base49	Southern yellow pine
Shutters	window165	calculating area42	siding109-110
painting481-482	window, ceramic301	concrete46	Spa replastering460
remove & replace . . .106	Sill & saddle300	finishes49	Spacer, laminate flooring .283
window167	Sill plate, service	forms43	Spacing, rafter88
Sidelites, steel door . . .198	entrance conduit432	garage42	Spanish tile roofing . . .139
Sidewalk demolition . . .31	Sill plate gasket.86	on grade49	Spar urethane,
Sidewalks, concrete .46, 49	Sill plates64	repair37	Helmsman488
Side-wired receptacle,	removal63	Slate	Spar varnish, marine . . .488
single435	Sill sealer86	floor tile, natural299	Spatter ceiling245
Siding107-112	Single bowl kitchen sink,	roofing139	Spatter drywall texture .244
accessories, mounting .107	stainless steel328	tile, tumbled300	Speaker wire433
aluminum93, 114	Single gang wall plate . .435	Sleepers, carpentry73	Speed-Wall
aluminum corrugated .113	Single receptacle, side-	Slide dimmer	interior latex enamel . .493
cedar108	wired435	illuminated436	PVA latex primer491
cedar T&G109	Single-hung windows . .158,	incandescent436	Spider box, electric540
corrugated113	160-161	Sliding windows161-162	Spin-N-Lock sink strainer .335
demolition34	Single-texture drywall	Sloan Royal flush valve .363	Splash plate344
fiber cement112	brush250	Slopes, shaping41	Spline
fiber cement shingles .113	Sink	Slot aperture light kit . .440	screen, porch459
hardboard100	bathroom367-369	Smart home electrical	tool168
hardboard lap112	frame334	management system . .444	window screen168
hardboard panel111	hardware329	Smoke alarm, dual	Split system, remove . .398
lap110	lavatory367-369	sensing436	Sponge, sanding, drywall .250
log cabin110	mounting kit334	Smoke & CO Alarm . . .436	Spray adhesive249
mineral93-94	removal315	Smoke detectors416	Spray painting, labor . . .468
mounting block, fixture .107	strainer shank nut . . .336	basic436	Spray texture244-246
Nailite107	under counter mount .368	dual sensing436	ceiling244
OSB111	Sink rail, ceramic302	dual-ionization436	wallboard244
painting482	Sink trap, remove &	Snap Strap PVC conduit	Spreading soil41
	replace352	clamp420	Spring cove molding . . .268

- Spring wound timer, in-wall 436
- Springs
garage door 223
garage, extension 225
window sash 166
- Spruce lap siding 110
- Square box
surface cover 425
welded 425
- Square D 437-440
- Square rosette molding 259
- Squeeze connector, flex 427
- Stain
acrylic interior & exterior 487
concrete 495
deck 487
deck & siding 487
Deck Plus 487
exterior 487
gel 488
Plus 10 487
polyurethane 488
siding 487
white wash 488
wood 488
- Stainblocker
primer sealer 494
water-based 492
- Staining labor, manhours
ceiling 470
fascia 473
paneled walls 485
picket fence 474
siding 482
wood deck 475
- Stainless steel sink 328-329
double bowl 328
single bowl 328
- Stair nose 284
bamboo 280
molding 278-280
- Stair stringers, basement 226
- Stairs
basement 226
deck 457-458
demolition 35
porch 457-458
stringers 458
- Stall kit, shower 357
add-on 362
corner entry 358
neo-angle 358
round 358
- Stall, shower 357
fiberglass 358
- Stamped concrete 50
- Stanadyne 334, 360
- Standard coupling, non-metallic 421
- Standard radius elbow 421
- Starter strip 131
- Starter strip, aluminum siding 114
- Steam cleaning, masonry 115
- Steam heat, radiator, hot water 398
- Steel conduit
elbow 429
elbow, rigid or IMC 429
galvanized rigid 429
- Steel doors
entry 199-200
exterior 198-199
exterior, with mini-blind 198
frames 194
garage 223
installation 197
screen 203
- Steel octagon box cover 426
- Steel sealing conduit
locknut 430
- Stem wall 48
- Step flashing 142, 144
copper 142
- Sterling Plumbing 354-355, 359
- Stile & rail doors 208
- Stilts, drywall 250
- Stone
base 49
cleaning 115
countertops 323
floor tile 299
roofing 139
sealer 307
setting adhesive 306
slate 139
tile, travertine 298
tile, tumbled 300
- Stonit 139
- Stool molding primed
finger joint 261
- Stop, gravel 142
- Stop fixture supply 364
- Stop molding 195
colonial 269
paperwrap colonial 269
parting 269
polystyrene colonial 269
polystyrene ranch 269
ranch 269
round edge 261
- Stopper, drain 336
- Stops Rust 496
- Storage, off site 538
- Storage cabinet
bath 383
etched glass 383
- Store-in-Door 204
- Storm collar, chimney 400-401
- Storm doors 204-205
aluminum 205
full-view 205
removal 204
security 205
self-storing 204
triple-track 204
woodcore 205
- Storm windows 149, 165
remove & replace 106
- StormGuard 88
- Straight blade receptacle, duplex 434
- Straightening framing 514
- Strainer
junior basket 338
sink shank nut 336
- Strainer, basin, remove & replace 352
- Strap
EMT 424
rigid conduit 431
- Straps
framing 512
hardware 513
T 513
tie 513
Stress-block fabric 136
- Stretch wrap 538
- Stringers, deck stair 458
- Strip, transition 292
- Strip flooring
laminated 284
maple, unfinished 281
natural wood 279
red oak 281
white oak 281
- Stripping
forms 44
soil 41
- Stripping paint, labor 467
- Strips
asphalt roofing starter 131
cant 137
shingle starter 131
- Structoglas 253
- Stucco
knockdown 493
molding, redwood 196
paint 494
painting 480-481
plastering 114
portland cement 114
removal 106
repair 103, 105, 514
soffit vents 89
texture 493
wall assembly, wood framed 71
- Stud sensor, electronic 249
- Stud straightening 67
- Stud wall, demolition 33
- Studding 66
- Studs
carpentry piecework rates 66
dormer 76
straps 513
wall assemblies 66
- Stump grinder, rental 28
- Stump grinding 29
- Stylistik II floor tile 289
- Styrene suspended lighting panel 258
- Styrene-ethylene-butylene-styrene asphalt 135
- Subfloor
board sheathing 66
OSB 66
plywood 66
- Subflooring
installation 66
piecework rates 66
- Sump pump 389
- Sundial vinyl sheet flooring 287
- Sunflower shower head 362
- Supply lines 374
toilet 364
- Supply stop 364
- Surface box cover, square 425
- Surface preparation
flooring 284
labor 466
manhours 466
- Surface preparation for painting or finishing 461
- Surround, bathtub 355
- Surround kit
bathtub 355
tub wall 355
- Suspended ceiling
demolition 34, 254, 315
installation 254
installation kit 255
light kit 440
lighting panel 258
panel 255-257
panel, acoustical 256
- Suspended ceiling
panel 256
systems 255
- Suspended ceilings 237
- Sweep, door 196
- Swimming pools
paint 496
refinishing 460
- Switch
AC quiet toggle 434
Decora AC quiet rocker 434
remove 434
sink top 340
- Switch & cover 428
- Switch box
drawn 2-device 425
multi gang 425
non-metallic old work 422
- Switches
fan control 382
timer, exhaust fan 382
- T**
- T 1-11 plywood siding 111
- T-astragal 194
- T molding 284
wood floor 278
- Tall boy water heater 405
- Tall Elite 355
- Tamping, excavation 41
- Tandem circuit breaker 439
- Tank, thermal expansion 406
- Tape
acrylic 291
corner bead 249
drywall 246
drywall joint 246
fish 417
tile backer 249
Tape-on bead 247
- Tapping block 281
- TapTight
hardwood flooring 280
hardwood molding 280
- Tar, roofing 132
- Teak flooring 279
- Teak oil 491
- Tear-off, roofing 129
- Temporary wall bracing 67
- Termin-8 wood preservative 490
- Terrazzo, demolition 35
- Testing, mold 535

Textolite counters	322	ceramic floor	295-298	Tile repair	glazing	171
Texture		ceramic floor & wall	297	mortar	roof repair	136
paint	493	ceramic wall	301-303	mortar, underwater	spine	168
paint additive	493	ceramic, demolition	35	Tile tool, ceramic	Toothbrush & tumbler	
roll-on	493	clay, roofing	139	Tile tub wall	holder	305
Sand-Texture wall	493	concrete roof	140	Tile underlayment,	Toothbrush holder	385-386,
stucco	493	demolition	315	Aqua-Tough	388
Texture 1-11 plywood		edge protection	303	Tile wall kit	porcelain	305
siding	111	finish	307	Tile, ceiling, zero	Top, laminated	
Texture brushes, drywall	250	floor	299	clearance grid system	plastic	323-324
Texture spray, gypsum		glazed ceramic	303	Tileboard	Topping compound,	
board	244	glazed porcelain	296	batten	wallboard	246
Texture touch-up kit,		gloss & seal	308	embossed	Topping, concrete	50
acoustic ceiling	244	granite	299	Tileboard molding, vinyl	Topsoil, excavation	41
Texture, drywall	244	granite floor	299	Tilt double-hung windows	Torsion springs	223
ceiling	245	grout	294	Timberline Ultra	Touch control lavatory	
spray	244, 246	grout, sanded	307	Timbertex	faucet	371
Textured ceiling panels	257	installation	293	Timer, in-wall, spring	Touch-up kit	
Textured lap siding	111	marble	298	wound	spray texture	244
Texturing paint additive,		marble floor	298	Timer switch	wood floor	278
Perlite	493	mortar	306	Tin repair shingles	Towel bar	385-388
Themes sheet vinyl		mosaic ceramic	304	Tissue holder	ceramic	305
flooring	287	natural cork	293	TJI joists	porcelain	305
Thermal expansion tank	406	non-sanded dry grout	307	T-molding	Towel ring	385-388
Thermal sill	195	parquet floor	282	bamboo	Track, patio door	216
Thermoplastic siding	107	paver	299	hardwood	TrafficMaster laminate	
Thermostat, floor		Place n Press floor	289	wood floor	flooring	284
warming system	305	polyethylene mem-		Toggle switch, AC quiet	Transit mix concrete	46
Thermostat cable	433	brane	308	Toilet base plate cover	Transition reducer strip,	
THHN copper wire,		quarry	299	Toilet bowl	vinyl flooring	292
gauge	432	reducer strip	304	gasket	Transition strip	
Thin-set mortar	306	repair, mortar	306	reset	carpet to tile	292
CustomBlend	306	resilient, demolition	35	Toilet fill valve	oak to tile	292
Thompson's	490	roofing	140	anti-siphon	Trap, lavatory, remove	
Thompsonized decking		rubber studded	290	remove & replace	& replace	352
lumber	454	Saltillo ceramic floor	299	Toilet flange, cast iron	Trash bins	29
Thoro	495	sealer	307	Toilet paper holder	Trash compactor removal	315
Thoroseal protective		sealer, high-gloss	307	Trash pump	540
coating	495	setting with adhesive	294	recessed	Travertine	
Threaded conduit body	431	setting with mortar	294	Toilet repair kit	floor tile	299
Three-gang box		slate floor	299	Toilet seat	stone tile	298
Super Blue, non-		thin-set mortar	293	cushioned vinyl	Treads, concrete, finishing	49
metallic	422	travertine floor	299	molded wood	Treatment, wood	490
Threshold		travertine stone	298	natural maple	Tree removal	29
ceramic	301	tumbled marble Listello	300	plastic, open-front	Trenchers, rental	39
high boy	195	tumbled slate	300	wood	Trenching	41
marble	300	tumbled stone	300	Toilet supply line	hand	40
patio door	216	vinyl composition	289-290	Toilet tank bolt kit	Trim	
Thru-the-wall utility fan	380	vinyl floor	288-289	Toilet tissue paper	aluminum siding	114
Thrutone	139	wall	303	holder	bamboo flooring	280
Thru-wall furnace, gas	404	wall, ceramic	303	door	194
Tie straps	513	wood flooring	282	Toilet To Go Kit	fiber cement siding	112
Ties, collar	75	Tile accessory set,		Toilets	hardwood flooring	281
Tile		porcelain	305	cadet	heart pine flooring	281
accessories, ceramic	304	Tile adhesive		Cadet	painting labor	471, 479
accessories, toilet		ceramic	293	Champion	window	355
tissue holder	304	resilient	290	Comfort Height	wood flooring	279
accessories,		rubber	290	compact	Trim & rough-in Roman	
toothbrush holder	305	stone	306	Gabrielle	tub	354
accessories, towel bar	305	thin-set	306	Hamilton	Trim enamel, latex satin	492
acoustic, demolition	34	vinyl	290	hook-up kit for low-boy	Trim pack wood paneling	252
anti-fracture membrane	305	Tile adhesive caulk,		one-piece	Trim paint	492
anti-fracture membrane		ceramic	307	pressure assist	eggshell	492
kit	307	ceramic	307	San Raphael	flat	494
backerboard	295	Tile backer	245	urinals	Trimmers	75
bullnose, ceramic	301-302	Tile backer tape	249	wall-mount	Trimming, trench bottom	40
carpet	308	Tile backerboard	295	Williamsburg	Trine	436
ceiling	254	Tile (vinyl) cutter	291	Tongue and groove	Triple-track storm	
ceiling, acoustical	253	Tile flooring, cork	275	siding, cedar	doors	204-205
ceiling, tin design	254	Tile forms	355	Tools	Troffer fluorescent	
ceiling, wood fiber	254	Tile kit, bathtub	355	ceramic tile	fixtures	258
ceramic caulk	307	Tile Perfect	307	drywall	parabolic	258
					U-lamp	258

- Trowel
drywall250
outside corner250
Trowel finishing, concrete .49
Troweling machine, rental .39
Trowels
margin notch291
notched291
pointing291
Tru-Glaze 4508 epoxy
gloss coating496
Trusses
fink76
gable76
roof76
T-square, drywall250
T-straps513
T-top roof exhaust vent .145
Tub
laundry336
utility laundry, kit336
Tub & shower faucet
single control360
single-handle360
single-knob360
Tub door
bypass355
sliding356
Tub faucet360-362
lever handle361
single-knob360
Tub, bath, removal352
Tub, laundry
hose337
overflow tube337
Tubular skylights172
Tuf-Tex spray texture246
Tumbled tile
marble listello300
slate300
stone300
Tumbler & toothbrush
holder305
Tung oil491
Turbine vents, roof91, 146
Turned spindle deck rail .456
Twinfast249
Two-gang box, Super
Blue, non-metallic422
Two-handle lavatory
faucet372
Type X gypsum board243
Tyvec suit538
Tyvek house wrap88
- U**
U.S. Ceramic
Tile299, 301-303
UF compression connector,
non-metallic419
UF-B sheathed cable419
U-lamp troffer fluorescent
fixture258
Ultra Silent bath fan379
Ultra Touch87
Ultra white elastomeric
roof coating137
Ultra-Hide
alkyd gloss enamel493
interior latex eggshell492
interior latex paint492
interior paint492
- Ultrasonic cleaning530
Undercoater interior
enamel491
Undercounter refrigerator .316
Underground cable, UF-B
sheathed419
Underground feeder
compression connector,
non-metallic419
Underlay, roof88
Underlayment140, 283
cement-based285
fast-setting patch285
foam283-284
laminated flooring283-284
liquid285
roof134
tile295
tile backerboard295
Underlayment & floor
patch286
Underwater tile repair
mortar307
Unfaced fiberglass batt
insulation84
Universal hub bolt-on
A Type438
Urethane, roof, spray
foam140
Urethane sheathing86
Urinal flush valve, Sloan
Royal363
Urinals, Dover364
USG245, 254
USG Interiors257, 295
Utilatub laundry tub336
Utility access door248
Utility bowl sink337
Utility cabinets
birch317
finished320
maple321
oak319, 321
red oak318
Utility fan
thru-the-wall380
vertical discharge379
Utility laundry tub kit336
Utility sink337
- V**
V siding, pine108
Vacuum, HEPA540
Valance, cabinets316, 319
Valley flashing
aluminum141
roll143
Valspar488, 491
ValueTest exhaust fan378
ValueTest vertical
discharge bath fan379
ValuSeries pointing
trowel291
Valve lines374
Valves
angle364
flush, Sloan Royal363
flush, urinal363
toilet, remove &
replace352
wall stop364
Vance Industries334
Vanguard hardwood
flooring280
Vanity
Arkansas375
Charleston374
Danville375
Kingston374
maple375
Monterey375
oak374-375
solid surface sink top377
Springfield374
Virginia375
with drawer375
with marble top377-378
Vanity cabinet378
mirrored with marble
top378
Vanity mirror382
Vanity top
granite377
Neptune shell marble376
Newport cultured
marble376
oval bowl cultured
marble376-377
rectangular cultured
marble376
shell bowl cultured
marble376, 377
Vanity top & bowl,
cultured marble377
Vapor barrier40, 81, 283
blanket insulation82
paper87
perm rating82
vapor-resistant coating82
Vapor retarder92
Varathane
exterior classic clear489
exterior clear finish489
interior classic clear489
oil-based floor finish489
Varnish, marine488
Velux172-173
Veneer base board245
Veneer plaster246
Vent
plumbing389
soffit89
Vent channel, rafter bay88
Vent kit, bath382
Vent, roof
dormer144
ridge144-145
T-top exhaust145
turbine146
waterproofing130
Vented range hood343
Ventilation
attic83
crawl space82
roof83
Ventilator, bath382
Ventilator retrofit, heat
recovery406
Ventilators, power92
Venting skylights173
Ventlite doors
fiberglass exterior201
steel exterior199
Vents
attic91
cedar90
continuous89
dormer90
eave90
foundation88
gable89-90
louvered90
redwood90
ridge90
roof turbine91
screen89
soffit89
under eave89
VentSure ridge vent144
Vermiculite insulation87
Vertical discharge bath
fan379
ValueTest379
Vertical discharge utility
fan379
Vibrators, rental39
Victorian base molding,
hardwood259
Victorian lavatory faucet .373
Viewer, door214
Villeta faucet370
Vinyl
bay windows158
circular windows159
door bottom196
double-hung
replacement windows .157
fascia108
garden windows158
hopper windows159
jalousie windows159
patch285
screen doors203
siding107
siding removal106
siding repair105
single-hung windows158
soffit108
Vinyl composition
tile289-290
Vinyl drywall outside
corner bead248
Vinyl floor tile288-289
Vinyl floor tile,
slip-retardant289
Vinyl flooring
removal278
roll286-287
sheet286-287
transition reducer strip .292
Vinyl flooring tools,
roller, extendable291
Vinyl sheet flooring287
Vinyl siding
mounting block96
trim pieces96
Vinyl tile
adhesive290
cutter291
Vinyl tileboard molding . .270
Vinyl wall base
dryback292
self-stick293
Vinyl-clad
wood awning windows .160
wood casement
windows160
wood windows159

W	Wall surround kit		dessicants	518	metal roof	135
Waferboard	bathtub	355	electric system	521	paint, elastomeric	494
Wainscot, tile	tub	355	floor cover	520	paper	88
Wainscot paneling	Wall texture,		floors	520	roof vent	130
Walkway	Sand-Texture	493	gas & oil appliances	521	roof, remove & replace	130
demolition	Wall tile, ceramic	301, 303	hygrometer	518	roof, repair	129
forms	Wallboard		insulation	519	sealer	495
Walkways, concrete	demolition	34, 316	paneling	520	wood protector	490
Wall	L-trim	248	plaster	519	Watertight conduit hub	430
bathtub	mold resistant	243	stucco	519	Watts Radiant	305
braces	painting	483-484	wallboard	519	Wave bath light fixture	441
fireblocks	primer	246	wallcovering	520	Wax	
opening, breakthrough	sander	250	wood	519	bowling alley	491
plates	texture spray	244	Water damage, dryout,		paste	491
straightening	Wallboard stilts	250	structural drying		Wax toilet bowl gasket	364
tub	Wallcovering, designer		air movers	522	Weatherhead	432
Wall & floor tile, ceramic	panel	252	ceilings	522	PVC	422
Wall & ceiling panel,	Wall-mount lantern,		hardwood flooring	523	Weatherproof blank	
FRP	curved glass	443	negative air scrubbers	523	cover, non-metallic	428
Wall & ceiling repair	Wall-mounted lavatory,		walls	522	Weatherproof conduit	
Wall base	removal	367	Water dispenser	336	box	427
molding	Walls		Water extraction	529-531	Weatherproof electrical	
rubber	adding	241	carpet	531	box, 2 gang	427
self-stick	concrete	47	hard surface	531	Weatherproof lampholder	
strip, vinyl	demolition	30	Water hammer	393	& cover	428
thermoplastic	painting	480-481, 483-485	arrester	407	Weatherproofing	88
vinyl	partition, adding	270	Water heaters	394	Weather-resistant wood	
Wall bracing	removal	239	100-gallon commercial	405	coating	488
Wall cabinets	setting with adhesive	294	Ariston	407	Weatherstripping	
end panel	setting with mortar	294	bracing	512	aluminum, adjustable	196
finished	staining	485	connection	512	foam	196
oak	tile	294	electric	406-407	garage door	223
square	Warming system		electric, tankless	407	magnetic	196
washer dryer	ceramic tile floor	305	FVIR	405	vinyl, remove & replace	196
Wall cavity dryer	thermostat	305	gas	405	window seal sets	172
Wall control switch	Wash down, manhours	467	gas fired	405	Weco	307
Wall demolition	Washer, kitchen sink		gas, tankless	407	Welded handy box	424
Wall enamel, latex satin	basket strainer	336	high altitude	405	Welded square box	425
Wall exhaust fan,	Washer-dryer wall		oil fired	405	Welded wire mesh	45
chain-operated	cabinets	319	point-of-use	407	Western red cedar siding	108
Wall finish, demolition,	Washing		PowerStream	407	Westinghouse Lighting	441
wet	masonry	115	power-vent	405	Westminster Ceramics	300
Wall forms, concrete	pressure	468	propane	405	Wet location conduit	
Wall framing	Washing, paint prep,		propane fired	405	box cover	428
Wall furnace, gas	manhours	467	tall boy	405	Wet location receptacle	
Wall insulation	Waste disposal	29	Water pipe, remove &		cover, GFCI	428
Wall kit	Watco	488	replace	408	Wet patch roof cement	135
bathtub	Water		Water pump	540	rubber	135
tile	blasting	115	Water resistant gypsum		Wet-Stick fibered roof	
tub	extraction	529	board	243	coating	137
Wall lantern	Water Claw	531	Water Seal waterproofer	490	Wet-Stick roof cement	135
Wall light, opal glass	Water closet		Water shield	88	Wheel glass cutters	171
Wall louvers	Water closet		Water supply, low water		Wheel loader, rental	28, 39
Wall materials	flange, cast iron	364	pressure	393	Wheelbarrow	540
ceiling tile	toilet	362-363	Water surge shock		Whirlpool bath	
drywall	Water damage		absorber	407	Cadet Elite	353
gypsum wallboard	cleanup	524	Water table	38	Devonshire	354
lath & plaster	contaminated flood-		Water-based primer	493	Elite EZ-Install heater	354
wood paneling	water	516	Water-based wood stain	488	Portrait	354
Wall oven	dryout	515	Waterblasting		Renaissance	353
Wall paint	restorative drying	515	manhours	468	Williamsburg Elite	353
eggshell	Water damage & mold		masonry	115	Whirlpool tub apron	354
latex	remediation	515	Waterborne sanding		White cement	114
Wall plate	insurance coverage	515	sealer	489	White Diamond bowling	
coaxial cable	OSHA	516	Waterfall kitchen faucet	333	alley wax	491
decorator phone	personal protective		Waterproofer, concrete		White oak strip flooring	281
single gang Decora	gear	516	& masonry	495	White wash pickling stain	488
single gang plastic	Water damage, dryout		WaterSeal	490	Whole house fans	91
Wall registers, install	air movers	518	Waterproofing		Williamsburg	
Wall stop	basement	520	masonry walls	130	lavatory faucet	372
	concrete block	520	material	135	pedestal lavatory bowl	366
	dehumidifiers	518	membrane	305	Roman tub filler	354

- Wilsonart counters322
 Wind clips140
 Window
 demolition, wet534
 drip cap141
 framing69
 screen168
 straighten opening514
 Window bolt, double-hung166
 Window glass, remove & replace170
 Window grille systems169
 Window guards167
 Window locks
 flip lock171
 key, sliding171
 thumbscrew bar171
 Window mullions166
 Window openings
 closure, masonry wall156
 closure, wood frame156
 cut new156
 Window operators
 awning166
 jalousie166
 Window painting, labor486-487
 Window roof covers, bay164
 Window roofs164-165
 Window screens160
 patch168
 spline168
 Window shutters167
 Window sill165
 ceramic301
 Window trim, bath wall355
 Windows
 adding or moving153
 aluminum148
 aluminum single hung160-161
 aluminum sliding161-162
 aluminum, horizontal161
 awning160
 awning, aluminum162
 bay158
 bay, angle164
 building codes148
 casement160
 casement, bow164
 casement, bay158
 caulk157
 caulk removal157
 circular, vinyl159
 counterweighted152
 cut new opening156
 double-hung157, 163
 egress window172
 energy-efficiency standards148
 escape wells172
 fixed aluminum162
 fixed octagonal163
 garden158
 glass setting labor170
 glazing putty replacement150
 grille sets, tilt sash169
 heat loss & gain147
 jalousie159, 163
 louvered, aluminum163
 Low-E glass147
 measure & cut glass170
 modern147
 octagonal, wood163
 picture162
 removal35, 156
 replacement155, 157-158
 sash repair151, 156
 sash springs166
 sill, ceramic301
 size, reducing156
 storm149, 165
 trim removal156
 vinyl bay158
 vinyl double hung157
 vinyl garden158
 vinyl hopper159
 vinyl jalousie159
 vinyl single hung158
 vinyl, custom157
 vinyl, replacement157
 vinyl-clad awning160
 vinyl-clad casement160
 vinyl-clad double-hung159-160
 vinyl-clad wood159
 weatherstripping172
 wood147
 wood, repair149
 wood, replacement156
 Wire
 bell433
 screen458
 speaker433
 thermostat cable433
 type THHN copper432
 UF cable419
 Wire brush50
 Wire mesh, welded45
 Wireless door bell436
 Wiring residences
 adding outlets & switches414
 aluminum wiring411
 ground wire413
 knob & tube wiring411
 low voltage wiring414
 non-metallic sheathed cable (Romex)412
 smoke detectors416
 Wonderboard tile backerboard295
 Wood
 shakes137
 shingles137
 siding removal106
 Wood bleach kit487
 Wood coating, weather-resistant488
 Wood conditioner491
 Wood deck
 patch built-up roofing132
 staining475
 Wood doors
 entry193
 screen203
 screen, installation202
 screen, remove & replace202
 Wood filler
 acrylic281
 Wood finish487
 penetrating487
 Wood flooring281
 adhesive282
 hardwood272
 installation tools281
 laminated274
 plank280
 softwood272
 strip272
 strips279
 tile282
 touch-up278
 trim279
 Wood paneling trim pack252
 Wood preservative463, 490-491
 copper491
 Termin-8490
X - Y - Z
 Zinsser490
 Zip-Mount417
 ZPW clear wood preservative491