


\$88.25



2016 NATIONAL PLUMBING & HVAC ESTIMATOR

By James A. Thomson

Includes inside the back cover:



Inside the back cover of this book you'll find a software download certificate. To access the download, follow the instructions printed there. The download includes the National Estimator, an easy to-use estimating program with all the cost estimates in this book. The software will run on PCs using Windows XP, Vista, 7, 8, or 10 operating systems.

Quarterly price updates on the Web are free and automatic all during 2016. You'll be prompted when it's time to collect the next update. A connection to the Web is required.

Download all of Craftsman's most popular costbooks for one low price with the Craftsman Site License. <http://CraftsmanSiteLicense.com>



- Turn your estimate into a bid.
- Turn your bid into a contract.
- ConstructionContractWriter.com



Craftsman Book Company

6058 Corte del Cedro, Carlsbad, CA 92011

Acknowledgments

The sample "Standard Form Subcontract" and "Subcontract Change Order" forms used in the final section of this book are reprinted with the permission of the publisher, the Associated General Contractors of America (National Office), 1957 E Street NW, Washington, District of Columbia 20006.

Looking for other construction reference manuals?

Craftsman has the books to fill your needs. **Call toll-free 1-800-829-8123** or write to Craftsman Book Company, 6058 Corte del Cedro, Carlsbad, CA 92011 for a **FREE CATALOG** of over 100 books, including how-to manuals, annual cost books, and estimating software.
Visit our Web site: <http://www.craftsman-book.com>

Cover design by: *Jennifer Johnson*
Photos: *iStock by Getty Images™*

© 2015 Craftsman Book Company
ISBN 978-1-57218-320-9
Published September 2015 for the year 2016.

Contents

How to Use This Book	5	Fire Protection Equipment	174
Plumbing Equipment		Fire Protection Sprinkler Pipe and Fittings (Roll Grooved).....	176
Domestic Hot Water Heaters	19	Fire Protection Branch Pipe & Fittings.....	180
Water Softeners	22	Fire Protection Sprinkler Pipe and Fittings (CPVC)	183
Kitchen Equipment.....	25	HVAC Equipment	
Kitchen Equipment Connections.....	26	Commercial Boilers	185
Plumbing Fixtures	27	Commercial Boiler Connections.....	190
Plumbing Fixture Rough-In	31	Commercial Boiler Components and Accessories	192
Piping Systems		Centrifugal Pumps and Pump Connections.....	206
Copper Pipe, Type K with Brazed Joints	33	Heat Exchangers and Connections	207
Copper Pipe, Type K with Soft-Soldered Joints ...	43	Fan Coil Units and Connections	208
Copper Pipe, Type L with Brazed Joints	53	Reheat Coils and Connections	209
Copper Pipe, Type L with Soft-Soldered Joints....	62	Unit Heaters and Connections.....	210
Copper Pipe, Type M with Brazed Joints	71	Chillers and Chiller Connections.....	211
Copper Pipe, Type M with Soft-Soldered Joints... 80		Condensing Units and Cooling Towers	212
Copper Pipe, Type K & L with Roll Grooved Joints	89	Cooling Towers and Cooling Tower Connections	213
PVC, Schedule 40, with Solvent-Weld Joints	91	Steel Piping Systems	
PVC, Schedule 80, with Solvent-Weld Joints.....	101	Carbon Steel, Schedule 40 with 150# Fittings & Butt-Welded Joints.....	214
Polyethylene-Aluminum Pipe with Crimped Joints.....	111	Carbon Steel, Schedule 40 with 150# M.I. Fittings & Threaded Joints.....	223
Polyethylene-Aluminum Pipe with Compression Joints	116	Carbon Steel, Schedule 5 with Pressfit Fittings.....	234
Plumbing and Piping Specialties	119	Carbon Steel, Schedule 80 with 300# Fittings & Butt-Welded Joints.....	237
Cast Iron, DWV, Service Weight, No-Hub with Coupled Joints.....	135	Carbon Steel, Schedule 80 with 300# M.I. Fittings & Threaded Joints	247
Cast Iron, DWV, Service Weight, Hub & Spigot with Gasketed Joints	141	Carbon Steel, Schedule 160 with 3,000-6,000# Fittings	255
Copper, DWV, with Soft-Soldered Joints.....	146	Carbon Steel, Schedule 40 with Roll-Grooved Joints.....	266
ABS, DWV with Solvent-Weld Joints	150	Carbon Steel, Schedule 10 with Roll-Grooved Joints.....	273
PVC, DWV with Solvent-Weld Joints.....	154	Carbon Steel, Schedule 40 with Cut-Grooved Joints	280
PVC, DWV with Gasketed Bell and Spigot Joints.....	159	Residential HVAC Assemblies	286
Polypropylene, Schedule 40, with Heat-Fused Joints.....	164	Air Handling Unit Accessories	290
Floor, Area, Roof and Planter Drains	168		
Cleanouts	169		
Fire Protection			
Fire Protection Sprinklers.....	170		

Heat Recovery Ventilators - Commercial.....	291	Fiberglass Pipe Insulation.....	397
Heat Recovery Ventilators - Residential.....	292	Calcium Silicate Pipe Insulation with	
Water Coil Piping	294	Aluminum Jacket.....	399
Air Handling Unit Coil Connections	297	Closed Cell Elastomeric Pipe Insulation	400
Gas-Fired Furnaces.....	299	Thermal Duct Insulation	401
Energy Recovery Systems, Enthalpy.....	301	Balancing of HVAC Systems	402
Unit Heaters	302	Temperature Controls.....	405
Infrared Heaters.....	304		
Heat Pump Systems.....	305	Ductile Iron Pipe Systems	
Water Pump Systems	313	Ductile Iron, Class 153, Cement-Lined with	
Geothermal/Domestic Water Wells.....	316	Mechanical Joints.....	407
Biomass-Fired Boilers	319	Ductile Iron, Class 153, Double Cement-Lined	
Fans and Blowers	324	with Mechanical Joints.....	409
Ventilators & Residential Exhaust Fans	326	Ductile Iron, Class 110, Cement-Lined with	
Apparatus Housing	331	Mechanical Joints.....	411
Air Devices, Registers & Grilles	333	Cast Iron, Class 150 with Mechanical Joints ...	412
Air Devices, Diffusers & Grilles	334	Asbestos-Cement, Class 2400 or 3000 with	
Terminal Units (VAV)	337	Mechanical Joints	413
Ducting Systems		Fiberglass Tanks	415
Ductwork Specialties.....	339	Plastic Tanks	416
Galvanized Steel Ductwork.....	344	Trenching	418
Installed Ductwork Per Pound	346	Equipment Rental.....	420
Galvanized Steel Spiral Ductwork	348	Close-Out Items.....	421
Galvanized Steel Round Spiral Fittings.....	349	HVAC & Plumbing Demolition	422
Galvanized Steel Rectangular Ductwork	351	Budget Estimating.....	435
Galvanized Steel Rectangular			
90 Degree Elbows.....	353	Forms and Letters	
Galvanized Steel Spiral Duct.....	356	Change Estimates.....	438
Galvanized Steel Spiral Duct Fittings	358	Subcontract Forms.....	447
Galvanized Steel Spiral Tees	360	Purchase Orders	451
Galvanized Steel Spiral Crosses	366	Construction Schedules	453
Galvanized Steel Rectangular Ductwork	369	Letter of Intent.....	456
Galvanized Steel Rectangular Elbows.....	381	Submittal Data.....	458
Galvanized Steel Drops and Tees.....	391	Billing Breakdown Worksheet	461
Galvanized Steel Round Ductwork.....	394		
Fiberglass Ductwork.....	395	Index	463

How to Use This Book

This 2016 National Plumbing & HVAC Estimator is a guide to estimating labor and material costs for plumbing, heating, ventilating and air conditioning systems in residential, commercial and industrial buildings.



Inside the back cover of this book you'll find a software download certificate. To access the download, follow the instructions printed there. The download includes an easy to-use estimating program with all the cost estimates in this book. The software will run on PCs using Windows XP, Vista, 7, 8, or 10 operating systems.

When the National Estimator program has been installed, click Help on the menu bar to see a list of topics that will get you up and running. Or go online to www.costbook.com and click Support tab to view interactive tutorials for National Estimator.

Costs in This Manual will apply within a few percent on a wide variety of projects. Using the information given on the pages that follow will explain how to use these costs and suggest procedures to follow when compiling estimates. Reading the remainder of this section will help you produce more reliable estimates for plumbing and HVAC work.



Manhour Estimates in This Book will be accurate for some jobs and inaccurate for others. No manhour estimate fits all jobs because every construction project is unique. Expect installation times to

vary widely from job to job, from crew to crew, and even for the same crew from day to day.

There's no way to eliminate all errors when making manhour estimates. But you can minimize the risk of a major error by:

1. Understanding what's included in the manhour estimates in this book, and
2. Adjusting the manhour estimates in this book for unusual job conditions.

The Craft@Hrs Column. Manhour estimates in this book are listed in the column headed *Craft@Hrs*. For example, on page 19 you'll see an estimate for installing a 6 gallon hot water heater. In the *Craft@Hrs* column opposite 6 gallon you'll see:

P1 @ .500

To the left of the @ symbol you see an abbreviation for the recommended work crew.

Page 7 shows the wage rates and craft codes used in this book.

To the right of the @ symbol you see a number. The number is the estimated manhours (not crew hours) required to install each unit of material listed. In the case of a 6 gallon hot water heater, P1 @ .500 means that .500 manhours are required to install 1 hot water heater.



Costs in the Labor \$ Column are based on manhour estimates in the *Craft@Hrs* column. Multiply the manhour estimate by the assumed hourly labor cost to find the installation cost in the *Labor \$* column. For example, .500 manhours times \$36.03 (the average wage for crew P1) is \$18.015, or \$18.00 rounded.

Quarterly price updates on the Web are free and automatic all during 2016. You'll be prompted by Craftsman Software Update when it's time to collect the next update. A connection to the Web is required.

Manhour Estimates include all productive labor normally associated with installing the materials described. These estimates assume normal conditions: experienced craftsmen working on reasonably well planned and managed new construction with fair to good productivity. Labor estimates also assume that materials are standard grade, appropriate tools are on hand, work done by other crafts is adequate, layout and installation are relatively uncomplicated, and working conditions don't slow progress.

All manhour estimates include tasks such as:

- Unloading and storing construction materials, tools and equipment on site.
- Working no more than two floors above or below ground level.
- Working no more than 10 feet above an uncluttered floor.
- Normal time lost due to work breaks.
- Moving tools and equipment from a storage area or truck not more than 200 feet from the work area.
- Returning tools and equipment to the storage area or truck at the end of the day.
- Planning and discussing the work to be performed.
- Normal handling, measuring, cutting and fitting.
- Regular cleanup of construction debris.
- Infrequent correction or repairs required because of faulty installation.

National Plumbing & HVAC Estimator

If the work you're estimating won't be done under these conditions, you need to apply a correction factor to adjust the manhour estimates in this book to fit your job.

Applying Correction Factors. Analyze your job carefully to determine whether a labor correction factor is needed. Failure to consider job conditions is probably the most common reason for inaccurate estimates.

Use one or more of the recommended correction factors in Table 1 to adjust for unusual job conditions. To make the adjustment, multiply the manhour estimate by the appropriate conversion factor. On some jobs, several correction factors may be needed. A correction factor less than 1.00 means that favorable working conditions will reduce the manhours required.



Supervision Expense to the installing contractor is not included in the labor cost. The cost of supervision and non-productive labor varies widely from job to job. Calculate the cost of supervision and non-productive labor and add this to the estimate.

Hourly Labor Costs also vary from job to job. This book assumes an average manhour labor cost of \$42.40 for plumbers and \$41.16 for sheet metal workers. If these hourly labor costs are not accurate for your jobs, adjust the labor costs up or down by an appropriate percentage. Instructions on the next page explain how to make these adjustments. If you're using the National Estimator disk, it's easy to set your own wage rates.

Hourly labor costs in this book include the basic wage, fringe benefits, the employer's contribution to welfare, pension, vacation and apprentice funds, and all tax and insurance charges based on wages. Table 2 at the top of the next page shows how hourly labor costs in this book were calculated. It's important that you understand what's included in the figures in each of the six columns in Table 2. Here's an explanation:

Column 1, the base wage per hour, is the craftsman's hourly wage. These figures are representative of what many contractors are paying plumbers, sheet metal workers and helpers in 2016.

Column 2, taxable fringe benefits, includes vacation pay, sick leave and other taxable benefits. These fringe benefits average about 5.46% of the base wage for many plumbing and HVAC contractors. This benefit is in addition to the base wage.

Condition	Correction Factor
Work in large open areas, no partitions	.85
Prefabrication under ideal conditions, bench work	.90
Large quantities of repetitive work	.90
Very capable tradesmen	.95
Work 300' from storage area	1.03
Work 400' from storage area	1.05
Work 500' from storage area	1.07
Work on 3rd through 5th floors	1.05
Work on 6th through 9th floors	1.10
Work on 10th through 13th floors	1.15
Work on 14th through 17th floors	1.20
Work on 18th through 21st floors	1.25
Work over 21 floors	1.35
Work in cramped shafts	1.30
Work in commercial kitchens	1.10
Work above a sloped floor	1.25
Work in attic space	1.50
Work in crawl space	1.20
Work in a congested equipment room	1.20
Work 15' above floor level	1.10
Work 20' above floor level	1.20
Work 25' above floor level	1.30
Work 30' above floor level	1.40
Work 35' to 40' above floor level	1.50

Table 1 Recommended Correction Factors



Column 3, insurance and employer-paid taxes in percent, shows the insurance and tax rate for the craft workers. The cost of insurance in this column includes workers' compensation and contractor's casualty and liability coverage. Insurance rates vary widely from state to state and depend on a contractor's loss experience. Note that taxes and insurance increase the hourly labor cost by approximately 30%. There is no legal way to avoid these costs.

Column 4, insurance and employer taxes in dollars, shows the hourly cost of taxes and insurance. Insurance and taxes are paid on the costs in both columns 1 and 2.

Column 5, non-taxable fringe benefits, includes employer paid non-taxable benefits such as medical coverage and tax-deferred pension and profit sharing plans. These fringe benefits average 4.82% of the base wage for many plumbing and HVAC contractors.

How to Use This Book

Column Number	1	2	3	4	5	6
		Taxable fringe benefits (at 5.46% of base wage)	Insurance and employer taxes (%)	Insurance and employer taxes (\$)	Non-taxable fringe benefits (at 4.82% of base wage)	Total hourly cost used in this book
Craft	Base wage per hour					
Laborer	20.47	1.12	32.73%	7.07	0.99	29.65
Plumber	31.21	1.70	24.27%	7.99	1.50	42.40
Sheet Metal Worker	29.89	1.63	26.01%	8.20	1.44	41.16
Operating Engineer	30.45	1.66	25.22%	8.10	1.47	41.68
Sprinkler Fitter	30.66	1.67	25.08%	8.11	1.48	41.92
Electrician	30.20	1.65	19.84%	6.32	1.46	39.63
Cement Mason	25.74	1.41	23.15%	6.29	1.24	34.68

Craft Code	Crew Composition	Average Hourly Cost per Manhour
ER	4 building plumbers, 2 building laborers, 1 operating engineer	38.65
SN	4 building sheet metal workers, 2 building laborers, 1 operating engineer	37.95
P1	1 building plumber and 1 building laborer	36.03
ST	1 sprinkler fitter	41.92
SK	4 sprinkler fitters, 2 building laborers, 1 operating engineer	38.38
SL	1 sprinkler fitter and 1 laborer	35.79
S2	1 building sheet metal worker, 1 building laborer	35.41
BE	1 electrician	39.63
CF	1 cement mason	34.68
SW	1 sheet metal worker	41.16

Table 2 Labor Costs Used in This Book

The employer pays no taxes or insurance on these benefits.

Column 6, the total hourly cost in dollars, is the sum of columns 1, 2, 4, and 5. The labor costs in Column 6 were used to compute costs in the Labor \$ column of this book.

Adjusting Costs in the Labor \$ Column. The hourly labor costs used in this book may apply within a few percent on many of your jobs. But wage rates may be much higher or lower in some areas. If the hourly costs shown in Column 6 of Table 2 are not accurate for your work, adjust labor costs to fit your jobs.

For example, suppose your hourly labor costs are as follows:

Plumber	\$19.00
Laborer	\$16.00
Total hourly crew cost	\$35.00

Your average cost per manhour would be \$17.50 (\$35.00 per crew hour divided by 2 because this is a crew of two).

A labor cost of \$17.50 is about 49% of the \$36.03 labor cost used for crew P1. Multiply costs in the Labor \$ column by .49 to find your estimated cost.

For example, notice on page 19 that the labor cost for installing a 6 gallon hot water heater is \$17.80 each. If installed by your plumbing crew working at an average cost of \$17.50 per manhour, your estimated cost would be 49% of \$17.80 or \$8.72 per heater.

Adjusting the labor costs in this book will make your estimates much more accurate. Making adjustments to labor costs is both quick and easy if you use the National Estimator program.

Equipment Cost will vary according to need and application. It typically is \$110 per hour for a 10-ton hydraulic truck-mounted crane.

Material Costs in this manual are intended to reflect what medium- to low-volume contractors will be paying in 2016 after applying normal discounts. These costs include charges for delivery to within 25 to 30 miles of the supplier.

Overhead and Profit for the installing contractor are not included in the costs in this manual unless specifically identified in the text. Markup can vary widely with local economic conditions, competition and the installing contractor's operating expenses. Add the markup that's appropriate for your company, the job and the competitive environment.

National Plumbing & HVAC Estimator

How Accurate Are These Figures? As accurate as possible considering that the editors don't know your material suppliers, haven't seen the plans or specifications, don't know what building code applies or where the job is, had to project material costs at least six months into the future, and had no record of how much work the crew that will be assigned to the job can handle.

You wouldn't bid a job under those conditions. And I don't claim that all plumbing and HVAC work is done at these prices.

Estimating Is an Art, not a science. There is no one price that applies on all jobs. On many jobs the range between high and low bid will be 10% or more. There's room for legitimate disagreement on what the correct costs are, even when complete plans and specifications are available, the date and site are established, and labor and material costs are identical for all bidders.

No estimate fits all jobs. Good estimates are custom made for a particular project and a single contractor through judgment, analysis and experience. This book is not intended as a substitute for judgment, analysis and sound estimating practice. It's an aid in developing an informed opinion of cost, not an answer book.

Additional Costs to Consider

Here's a checklist of additional costs to consider before submitting any bid.

1. Sales taxes
2. Mobilization costs
3. Payment and performance bond costs
4. Permits and fees
5. Storage container rental costs
6. Utility costs
7. Tool costs
8. Callback costs during warranty period
9. Demobilization costs

Exclusions and Clarifications

Neither the job specifications nor the contract may identify exactly what work should be included in the plumbing and HVAC bid. Obviously, you have to identify what work is included in the job.

The most efficient way to define the scope of the work is to prepare a list of tasks not normally performed by your company and attach that list to each bid submitted. Here's a good list of work that should be excluded from your bid.

Your Bid Should Exclude

Final cleaning of plumbing fixtures
Backings for plumbing fixtures
Toilet room accessories
Electrical work, including motor starters
Electrical wiring and conduit over 100 volts
Temporary utilities
Painting, priming and surface preparation
Structural cutting, patching or repairing
Fire protection and landscape sprinklers
Equipment supports
Surveying and layout of control lines
Removal or stockpiling of excess soil
Concrete work, including forming and rebar
Setting of equipment furnished by others
Equipment, unless shown, and personnel hoisting
Wall and floor blockouts
Pitch pockets
The costs of performance or payment bonds
Site utilities
Asbestos removal or disposal
Contaminated soil removal or disposal
Major increases in copper material prices
Fire dampers not shown on the plans

Your Bid Should Include

Trash sweep-up only. Others haul it away
Site utilities from building to property line only
Piping to 5 feet outside the building only
Plumbing & HVAC permits for your work only

Beware of Price Changes

There's no way to be sure what prices will be in three to six months. All labor, equipment, material and subcontract prices in a bid should be based on costs anticipated when the project is expected to be built, not when the estimate is compiled. That

presents a problem. Except for the installation of underground utilities, most plumbing and HVAC work is done six months to a year after the bid is submitted. When possible, get price protection in writing from your suppliers and subcontractors. If your suppliers and subs won't guarantee prices, include an escalation allowance in your bid to cover anticipated price increases.

Material Pricing Conditions

All equipment and material prices quoted by your vendors will be conditional. They usually don't include sales tax and are subject to specific payment and shipping terms. Every estimator should understand the meaning of common shipping terms. They define who pays the freight and who has responsibility for processing freight-damage claims. Here's a summary of important conditions you should understand.

F.O.B. Factory (Free On Board at the Factory): Title passes to the buyer when the goods are delivered by the seller to the freight carrier. The buyer pays the freight and is responsible for freight-damage claims.

F.O.B. Factory F.F.A. (Free On Board at the Factory, Full Freight Allowed): The title passes to the buyer when the goods are delivered by the seller to the freight carrier. The seller pays the freight charges, but the buyer is responsible for freight-damage claims.

F.O.B. (city of destination) (Free On Board to your city): The title passes to the buyer when the goods are delivered by the seller to the freight terminal in the city, or nearest city, of destination. The seller pays the freight and is responsible for freight-damage claims to the terminal. The buyer pays the freight charge and is responsible for freight-damage claims from the terminal to the final destination.

F.O.B. Job Site (Free On Board at job site, or contractor's shop): The title passes to the buyer when the goods are delivered to the job site (or shop). The seller pays the freight and is responsible for freight-damage claims.

F.A.S. Port [of a specific city] (Free Alongside Ship at the nearest port): The title passes to the buyer when goods are delivered to the ship dock or port terminal. The seller pays the freight and is responsible for freight-damage claims to the ship dock or port terminal only. The buyer pays the freight and is responsible for freight-damage claims from the ship dock or port terminal to the designated delivery point.

Obviously, it's to your advantage to instruct all vendors to quote costs F.O.B. the job site or your shop.

Reducing Costs

Most construction specifications allow the use of alternative equipment and materials. It's the estimator's responsibility to select the most cost-effective products. Research and compare your costs before making any decisions. Avoid selecting any material or equipment simply because that's what you've always done.

Don't recommend plastic products such as ABS, PVC, or polypropylene pipe or corrugated flexible ducts until you've checked local code requirements. Most building codes prohibit use of these materials inside public buildings such as schools, care centers and hospitals.

It's wise to select 100% factory-packaged equipment. Beware of equipment labeled "Some assembly required." Field labor costs for mounting loose coils, motors and similar equipment are very high.

Value Engineering

Let's suppose you've submitted a combined plumbing and HVAC bid for \$233,000. Your cutthroat competitor put in a bid at \$4,000 less, \$229,000. Obviously there's no way you're going to get the job. Right?

Not so fast! Maybe value engineering can help you win that contract — while fattening your profit margin.

Suppose the proposal you submitted had two parts. Part I is the bid for \$233,000, based entirely on job plans and specs, just the way they were written. But appended to your proposal is Part II, a list of suggestions for saving money without sacrificing any of the capacity or quality designed into the system. Here's an example of what might be in Part II:

1. Deduct for providing pipe hanger spacings per UPC in lieu of specified spacings: \$1,750.00
2. Deduct for reducing heating hot water pipe sizes by using 40 degrees F Delta T in lieu of specified 20 degrees F Delta T: \$4,600.00
3. Deduct for providing pressure/temperature taps at air handling units, pumps and chillers in lieu of specified thermometers and pressure gauges: \$875.00

National Plumbing & HVAC Estimator

4. Deduct for eliminating water treatment in closed piping systems: \$1,800.00
5. Deduct for piping chilled and heating hot water pumps in parallel in lieu of providing 100% standby pumps: \$2,900.00

Total deductions: \$11,925.00

Adopting these suggestions would make you low bidder by nearly \$8,000. A saving like that will be tempting to most owners, especially if the owner understands that your suggestions result in a system that is every bit as good and maybe better than the system as originally designed.

You're not offering to undercut the competition. Far from it. You're using knowledge and experience to create better value for the owner. That's called value engineering and it's likely to win the respect of nearly all cost-conscious owners.

Notice that reducing costs is only part of what value engineering is all about. You don't cut costs at the expense of system quality, integrity, capacity or performance.

Don't waste your time, and your client's, by offering to substitute cheaper or lower-quality fixtures or equipment. Any cutthroat contractor with a price list can do that. Recommend the use of inferior materials and you'll be associated with the inferior goods you promote. Some owners consider even the suggestion to be insulting.

The recommendations you make (like most of those in the example) will require design changes. You can expect to be examined (or even challenged) on these points. Be ready to explain and defend each of your suggestions. Convince the client (or the design engineer) that your ideas are based on sound engineering principles and you're well on the way to winning the owner's confidence and the contract.

Now, let's go back to the list and see how we might justify the five value engineering recommendations.

1. **Pipe Hanger Spacing.** The pipe hanger spacings recommended in the Uniform Plumbing Code (UPC) are calculated by experienced, professional structural engineers. The safety factors used in these calculations are very conservative. They've been widely used for many years and have proved to be more than adequate. There's no need for more hangers than the UPC requires.

2. **Changing HHW Delta T.** In hydronic heating systems, heat measured in Btus is pumped to terminal units. The proposed change of the Delta T, from 20 degrees F to 40 degrees F, has no effect whatsoever on how many Btus the system delivers. You're not changing anything but the volume of water being pumped. At lower volume levels, the size of the pump, the pipe and the pipe insulation can all be reduced. Not one of these changes will affect the system's ability to transmit heat. Furthermore, operating costs will also drop, since less pump horsepower will be needed to run the smaller pump.

3. **Thermometers/Pressure Gauges.** Thermometers and pressure gauges installed on or near vibrating machinery have a very short life expectancy. Gauges quickly lose accuracy under harsh conditions. Readings will become less and less reliable. That's potentially dangerous. You can avoid this problem by using insertion-type pressure/temperature taps instead. Store these sensitive gauges in a desk drawer or a tool crib when not in use. Safely stored, they're protected from damage. They'll give accurate readings longer and won't need to be replaced as often. And they're simple to use. Just insert a gauge in one of the conveniently located taps. Make the reading, then remove the gauge and put it away.

4. **Water Treatment.** ITT Bell & Gossett has done studies on corrosion in closed hydronic systems that have a make-up water rate of no more than 5% per year. These studies show that corrosion virtually stops when entrained air is either removed or depleted. No water treatment is needed in this closed system.

5. **100% Standby Pumps.** Two pumps piped and operated in parallel are more economical. Even if one pump fails, the other pump can maintain delivery at 75 to 80% of the designed flow rate. That's usually adequate for emergency operation.

These cost-saving ideas are small, but could tip the balance in your favor. I hope they demonstrate the potential that value engineering has when bidding jobs. Any time you're compiling an estimate, keep an eye out for ways to save money or reduce the owner's cost. Jot a note to yourself about each potential saving you identify. Before submitting the bid, make a list of your alternate suggestions. Maybe best of all, markup on your value engineering suggestions can be higher than your normal markup. If value engineering can cut costs by \$10,000, maybe as much as \$4,000 of that should end up in your pocket!

Value Engineering: Surplus Materials

Value engineering doesn't begin and end with job plans and specs. Value engineering means getting the most value at the least cost, no matter whether it's value to the owner or value to the contractor. Smart mechanical contractors learn to build extra value into their jobs by controlling shrinkage of materials. Nearly every significant plumbing and HVAC job ends with at least some surplus material on hand. Material left over when the job is done tends to be discarded as waste or hauled off the job in the back of a truck that doesn't have your company name on the door. And why not? It's surplus — not needed. The owner didn't need it. So now it's up for grabs.

Not quite. Let's consider who actually owns that surplus material. When your company has been paid, every piece of material your crew installed belongs to the building owner. But what about those fittings, hangers and valves delivered to the job site but never actually used? Almost certainly, those materials were included in your bid. So aren't they the property of the owner? Not in my opinion. The owner contracted for a mechanical system and (presumably) has one. Unless it's a cost-plus job or a labor-only job, the owner didn't buy materials delivered to the job site. The owner bought a mechanical system and has one — completely separate and apart from any surplus materials. In my mind, the property owner has no more claim to left-over materials than the same owner would have claim to labor hours not expended or equipment not used on the same job.

Unless there's some provision in your contract to the contrary, surplus material belongs to the installing contractor. But your right to that material and the chance of actually getting it back to your shop are two very different propositions. I see recovery of surplus material as a training issue. As a matter of company policy, make it clear to your crews that surplus material belongs to your company. The supervisor on every job should be accountable for recovery of excess material. Every significant job will have at least some surplus. Accounting for that surplus should be part of your routine close-out procedure. Fortunately, it's not difficult. I'll explain.

Control of surplus materials begins with a good checklist, or form. I recommend the Materials, Equipment and Tool form, "MET" for short. A blank MET form appears following this section. Your MET should show both what's delivered to the job site (material, equipment and tools) and surplus "drops" returned to your shop at project close-out. A MET

ensures that the estimator, the shop inventory manager and your field supervisor are on the same page. Your MET establishes accountability. Nothing falls through the cracks. Job input equals job output plus returns. Everything delivered to the job and not expended should be returned to your shop.

Here's how it works:

1. Based on the estimate that won you the job, the items needed are purchased for the job and staged for delivery to the job site.
2. As materials, equipment and tools are delivered to the job site, your supervisor completes the first three columns of the MET form: Description, Quantity and Date.
3. As work is completed, the same supervisor completes the four columns under Returned to Inventory: Quantity Returned, Date, Status Code and Value. The status code will be either "RS" (Returned and Salvaged) or "RN" (Returned New).
4. Back at your shop, both RS and RN materials should be restored to inventory.
5. If your company has an inventory manager, have that manager assign the return value to each item returned. If you're using QuickBooks Pro, the "Adjust Inventory" feature can handle this task quite easily. Add two new categories under "Inventory Stock on Hand by Vendor." The first new category is Returned Salvage. The second is Returned New. Be sure the value of RS materials includes the cost of any reconditioning done to restore salvaged materials (such as pumps and boilers) to serviceable condition.
6. Comparing MET deployed to the job site with MET returned to inventory yields MET actually used on the job. That's a very important number to every plumbing and HVAC estimator. Be sure actual usage gets entered on the Project Summary form.
7. When the take-off on your next estimate is complete, compare that materials list with a summary of RS and RN materials on hand from prior jobs.
8. Evaluate which returned materials can be redeployed on the new job.
9. It's a management decision to either (1) charge the new job for the cost of RS and RN materials already on hand, or (2) consider materials on hand as "free" and a competitive advantage in winning the new bid. Either way, RN and RS materials are an asset to your company.

National Plumbing & HVAC Estimator

Plumbing and HVAC materials are expensive. Every mechanical contractor has an interest in MET tracking. Everyone in your company should be aware of the need for good materials management. Used correctly, the MET form in this book can help engineer more value into your jobs.

Maximizing the Value of Old Estimates

There should be two profits in every job. The first is money in the bank — a return on time and expenses. The second is what you learn from the job — primarily by comparing the estimate you made with what turns out to be your actual cost. On some jobs, the value of lessons learned may outweigh net revenue.

Every plumbing and HVAC contractor has marginal jobs. That's normal. What *shouldn't* be normal is repeating mistakes. The best way to avoid trouble in your future is to keep track of your past. Keeping old estimates available for reference can help prevent errors on new estimates.

As your file of completed estimates grows, organization becomes more important. You need an easy way to find similar projects with the same components and comparable scope of work. If your estimating file is in QuickBooks Pro, searching by keyword may be enough. Otherwise, I recommend creating a short summary for each completed job, and an index that references all summaries available for comparison. You'll find a blank Project Summary form at the end of this section. To make reference easier, create an index by type of job and equipment used. You may choose to use an alphabetical index based on client name or project ID.

How to complete the Project Summary form is obvious. The many ways to use this form may not be so obvious, so here are a few pointers.

1. Use your index of Project Summary forms to find completed jobs most similar to the job you're bidding. Believe it or not, Project Summary forms with the widest margin of error will be most useful. Ask yourself: Who worked on those projects? Who was the field superintendent? Who were the vendors? Did the errors result from poor estimating or the poor performance of vendors, supervisors or crews? The most common estimating errors occur when (a) inspecting the job site, (b) examining the plans or (c) reading the specifications. What did you miss and why? Look for pitfalls to avoid in the job now being estimated. Identify the biggest two or three mistakes made when bidding that job. Make a notation about each on the Project Summary form.
2. Now look at your bid for the current job. Which mistakes made on a prior job might you expect on this job? Concentrate on the big three oversights to avoid: Inspecting the job site; examining the plans; and reading the specifications.
3. Unless there's a major error in take-off, your estimate of material costs should be within about 5 percent of the actual costs of materials. However, it's common for labor cost estimates to vary 20 percent or more from actual labor costs. This is precisely where data from old jobs comes in handy. If your Project Summary files show that some project types are consistent money-losers, either shift your company's focus to another class of work, factor more contingency into your bids, or find some way to wring inefficiencies out of the labor component. Poor staging, delivery and retrieval procedures drag down labor productivity on any job.
4. Use your file of Project Summary forms to spot any common thread that runs through either money-making jobs or money-losing jobs. For example, if the names of certain subcontractors or vendors are prominent on low-margin jobs, maybe there's a relationship between your profit margin and choice of subs and suppliers. Even the best and most reliable vendors can become complacent if not challenged occasionally.
5. Project Summary forms should note changes and extras identified after the contract was signed — both for which your company was paid and changes done without additional compensation. Projects with changes and extras that exceed about 4 percent of the contract price deserve special scrutiny. Jobs with changes beyond about 4 percent aren't good for business, at least in my opinion. Nearly all changes have a negative impact on your job schedule and require a disproportionate investment of management resources. Too many changes can antagonize the owner and design staff, even if they were responsible for the altered plans. You may know of a mechanical contractor with a reputation for capitalizing on change orders. But I've rarely seen a job plagued with changes that turned into a money-maker for anyone — except the attorneys. Your file of Project Summary forms will show job types that carry change order risk. Before finalizing and submitting any bid, consider whether the job will get mired in disputes over changes and extras. If similar jobs have ended on the courthouse steps, factor that risk into your estimate.

Utility of a Project Summary forms file is limited only by your ingenuity. The important point is to keep and organize the source of your second profit available on every job. What you learn can be more valuable than what you earn.

The Estimating Procedure

Every plumbing and HVAC estimator works under deadline pressure. You'll seldom have the luxury of spending as much time as you would like on an estimate. Estimators who aren't organized waste valuable time and tend to make careless errors. Try to be well-organized and consistent in your approach to estimating. For most projects, I recommend that you follow the procedures listed below and in the order listed:

1. Get a second set of project drawings and specifications for use by your suppliers and subcontractors. Remember that your subs and suppliers need access to the plans and specs and time to prepare their quotes.
2. Study the plans and specs carefully. Highlight important items. Make a list of specific tasks that require labor unit correction factors. The estimate is never complete until you're totally familiar with the project and the applicable construction codes.
3. Get the general contractor or owner to identify the proposed construction schedule and subcontractor lay-down (storage) area. Work schedule and site conditions always affect your costs.
4. Contact all potential suppliers and subcontractors as early as possible. Set a time when each can come to your office to make their take-offs from the spare set of contract documents.

When this important preliminary work is done, or in progress, it's time to begin your detailed take-off.

Guidelines for Good Estimating

You can compile estimates on a legal pad, a printed estimating form or on a computer. Regardless of the method, these guidelines will apply:

List Each Cost Separately on your take-off sheet. Don't combine system estimates, even if the materials are the same type. A combined system estimate may have to be completely redone if materials for one system are changed at a later date. Use the Estimate Detail Sheet on page 16 if you don't already have a good material take-off form.

Use Engineer's Identification Numbers when listing equipment. The word pump without any other description is ambiguous when there are several pumps included in the project.

Don't Forget Labor Adjustment factors if your labor costs are significantly higher or lower than the costs used in this book. See instructions on page 7 for adjusting labor costs.

Use Colored Pencils or highlighters to mark the items you've taken off and listed. Use a different color for each piping or ducting system.

Log Telephone Quotes and other important phone conversations on a telephone quote form. See the sample on page 18.

Project Estimated Costs for labor, material and equipment to the time when the work is expected to be done, not when the job is being estimated.

The only good estimate is a complete estimate. You've probably heard this saying, "He who makes the most mistakes is likely to be low bidder, and live to regret it."

Preparing the Proposal

It's both common courtesy and good business practice to deliver an unpriced copy of your bid or proposal letter to the general contractor three or four days before the bid deadline date. This gives the contractor time to study your proposal and obtain alternate pricing for items you may have excluded. To avoid misunderstandings, make sure your proposals include, as a minimum, the following elements:

1. The complete name and address of the proposed project.
2. Specification title and issue date.
3. A complete listing of drawings and their issue or revision date.
4. A complete list of addenda and their dates of issue.
5. A list of specification section numbers covered by your proposal.
6. A list of exclusions, clarifications and assumptions.

Your final bid can be phoned in or sent by fax, but it should reach the general contractor or owner no more than five or ten minutes before the bid deadline. Prices submitted too early may have to be revised because of last-minute price changes by subcontractors or suppliers.

MET Worksheet

Material, Equipment and Tool Delivery and Surplus Return Record

Project ID _____

Job Location _____

Supervisor _____

Start Date _____

[illegible]

PROJECT SUMMARY

Project ID _____ Job Location _____

Short description _____

Supervisor _____

Index ID _____ Start Date _____

Estimator _____ Client _____

Major vendors _____ Subcontractors _____

Sources of cost deviation _____

Related Projects by ID Number _____

Thumbnail Summary	Labor	Material	Equipment	Subcontract	Deployed RN/RS	Total
Actual cost						
Estimate Over/(Under)						
Full Summary						
Bid amount						
Estimated cost						
Projected profit						
Cost overrun						
Bid profit						
Change orders						
Cost of changes						
Total profit						
Total profit with RN/RS						
Redeployment						

Data carried forward from Take-Off Quantity Survey Sheet(s)

Company/Department

Project

Address

Job description

CSI Division/Account

Estimator

Checked by

Notes:

Date

Date

Estimate #

Estimate due

Item Description	Quantity	Unit	Crew @ MH/Unit	Manhours Ext.	Materials		Labor		Equipment		Subcontract		Total \$
					Unit \$	Ext. \$	Unit \$	Ext. \$	Unit \$	Ext. \$	Unit \$	Ext. \$	

Carry totals forward to Estimate Summary Sheet

Estimate # _____ of _____

Estimate Detail Sheet _____

Quotation Sheet

Job: _____

Supplier: _____

Salesperson: _____ **Phone No:** _____

Per Plans/Specs: _____ **Freight:** _____ **Terms:** _____

[illegible]


By: _____

Domestic Hot Water Heaters

Description	Craft@Hrs	Unit	Material \$	Labor \$	Equipment \$	Total \$
-------------	-----------	------	-------------	----------	--------------	----------

Electric domestic hot water heater (residential). Set in place only (floor models). Make additional allowances for pipe and electrical connections. (See below)

6 gallon						
1.5 KW/110V	P1@.500	Ea	396.00	18.00	—	414.00
10 gallon						
1.5 KW/110V	P1@.500	Ea	442.00	18.00	—	460.00
15 gallon						
1.5 KW/110V	P1@.750	Ea	466.00	27.00	—	493.00
20 gallon						
1.5 KW/110V	P1@.750	Ea	481.00	27.00	—	508.00
30 gallon						
1.5 KW/110V	P1@1.00	Ea	429.00	36.00	—	465.00
40 gallon						
1.5 KW/110V	P1@1.20	Ea	449.00	43.20	—	492.20
50 gallon						
3 KW/110V	P1@1.30	Ea	484.00	46.80	—	530.80
12 gallon						
3 KW/220V	P1@.500	Ea	390.00	18.00	—	408.00
20 gallon						
3 KW/220V	P1@.750	Ea	427.00	27.00	—	454.00
30 gallon						
3 KW/220V	P1@1.00	Ea	466.00	36.00	—	502.00
40 gallon						
3 KW/220V	P1@1.20	Ea	507.00	43.20	—	550.20
50 gallon						
3 KW/220V	P1@1.30	Ea	542.00	46.80	—	588.80




Electric domestic hot water heater (commercial), 208/240 volt. Set in place only. Make additional allowances for pipe and electrical connections. (See below)

96 gallon, 12 kw	P1@1.50	Ea	2,160.00	54.00	—	2,214.00
96 gallon, 18 kw	P1@1.50	Ea	2,930.00	54.00	—	2,984.00
96 gallon, 36 kw	P1@1.50	Ea	3,040.00	54.00	—	3,094.00
120 gallon, 18 kw	P1@2.00	Ea	3,110.00	72.10	—	3,182.10
120 gallon, 36 kw	P1@2.00	Ea	3,210.00	72.10	—	3,282.10
120 gallon, 54 kw	P1@2.00	Ea	3,800.00	72.10	—	3,872.10
120 gallon, 63 kw	P1@2.00	Ea	4,100.00	72.10	—	4,172.10

Gas-fired domestic hot water heater (residential). Set in place only, Make additional allowances for pipe and combustion venting connections. (See below)

30 gallon	P1@1.00	Ea	465.00	36.00	—	501.00
40 gallon	P1@1.00	Ea	752.00	36.00	—	788.00
50 gallon	P1@1.50	Ea	854.00	54.00	—	908.00



Domestic Hot Water Heaters

Description	Craft@Hrs	Unit	Material \$	Labor \$	Equipment \$	Total \$
-------------	-----------	------	-------------	----------	--------------	----------

Gas-fired domestic hot water heater (commercial), standard efficiency. Set in place only, Make additional allowances for pipe and combustion venting connections. (See below)

50 gal./ 95 gph	P1@2.00	Ea	2,190.00	72.10	—	2,262.10
67 gal./106 gph	P1@2.00	Ea	2,590.00	72.10	—	2,662.10
76 gal./175 gph	P1@2.00	Ea	3,470.00	72.10	—	3,542.10
91 gal./291 gph	P1@2.00	Ea	4,180.00	72.10	—	4,252.10

Gas-fired domestic hot water heater (commercial), energy miser. Set in place only, Make additional allowances for pipe and combustion venting connections. (See below)



50 gal./ 95 gph	P1@2.00	Ea	5,150.00	72.10	—	5,222.10
67 gal./106 gph	P1@2.00	Ea	5,390.00	72.10	—	5,462.10
76 gal./175 gph	P1@2.00	Ea	6,680.00	72.10	—	6,752.10
91 gal./291 gph	P1@2.00	Ea	7,940.00	72.10	—	8,012.10

Tankless natural gas water heaters. Ambient pressure. DOE and UL rated. For residential, multi-dwelling and light commercial potable water applications. Add the cost of piping, tempering valve, circulating pump, controls, and electrical connection, post-installation inspection by both the fire marshal and the mechanical inspector to validate federal, state and local energy tax credits or energy tax credit offsets. For larger arrays (laundries, institutional facilities, food processing plants), develop an estimate based on the required capacity and multiply these costs by the number of heaters required. Rated in Btus and gallons per minute capacity. (1 Mbh = 1,000 Btus)

19.5-140 Mbh, .75-5.8 Gpm	P1@16.0	Ea	1,790.00	576.00	—	2,366.00
11-199 Mbh, .5-7 Gpm	P1@20.0	Ea	2,110.00	721.00	—	2,831.00
25-235 Mbh .75-9.6 Gpm	P1@20.0	Ea	2,110.00	721.00	—	2,831.00

Tankless electric point-of-use water heaters. Ambient pressure, DOE and UL rated. For residential, multi-dwelling and light commercial potable water applications. Cost does not include piping, tempering valve, circulating pump, controls, storage tank, electrical connection. Add the cost of post-installation inspection by the mechanical inspector to validate federal, state and local energy tax credits or energy tax credit offsets. In rated gallons per minute capacity.

5.5 Kw/40 Amp, .75-2 Gpm	P1@4.00	Ea	445.00	144.00	—	589.00
9.5 Kw/50 Amp .75-2.5 Gpm	P1@4.25	Ea	528.00	153.00	—	681.00
19 Kw/100 Amp 1-3.5 Gpm	P1@4.50	Ea	877.00	162.00	—	1,039.00
28 Kw/120 Amp 1.5-5 Gpm	P1@4.75	Ea	1,600.00	171.00	—	1,771.00



Domestic Hot Water Heater Connections

Description	Craft@Hrs	Unit	Material \$	Labor \$	Equipment \$	Total \$
-------------	-----------	------	-------------	----------	--------------	----------

Domestic hot water heater connection assembly. Includes supply, return, recirculation and relief piping and fittings (copper), relief and isolation valves. Make additional allowances for gas and venting connections where applicable.

¾" residential	P1@1.75	Ea	324.00	63.10	—	387.10
¾" commercial	P1@2.25	Ea	435.00	81.10	—	516.10
1" commercial	P1@2.75	Ea	763.00	99.10	—	862.10
1¼" commercial	P1@3.50	Ea	934.00	126.00	—	1,060.00
1½" commercial	P1@3.75	Ea	972.00	135.00	—	1,107.00
2" commercial	P1@4.50	Ea	1,040.00	162.00	—	1,202.00
2½" commercial	P1@5.75	Ea	2,160.00	207.00	—	2,367.00
3" commercial	P1@6.50	Ea	3,310.00	234.00	—	3,544.00

Domestic water heater combustion vent connection. Make additional allowances for piping distances greater than 25'.

2" B-vent	P1@.090	LF	6.18	3.24	—	9.42
3" B-vent	P1@.100	LF	7.64	3.60	—	11.24
4" B-vent	P1@.110	LF	10.10	3.96	—	14.06
6" B-vent	P1@.130	LF	11.50	4.68	—	16.18
Tankless heater vent kit	P1@2.50	Ea	434.00	90.10	—	524.10
Power vent kit	P1@2.00	Ea	1,110.00	72.10	—	1,182.10

Water Softeners and Controllers

Description	Craft@Hrs	Unit	Material \$	Labor \$	Equipment \$	Total \$
-------------	-----------	------	-------------	----------	--------------	----------

Water softener, time clock controller. Including brine tank, brine well and pick-up tube. Labor includes setting in place, connecting the unit to an existing domestic water distribution system, start up and testing.

20,000 grain water softener, TCC	P1@4.50	Ea	557.00	162.00	—	719.00
30,000 grain water softener, TCC	P1@4.50	Ea	594.00	162.00	—	756.00
45,000 grain water softener, TCC	P1@4.50	Ea	660.00	162.00	—	822.00
50,000 grain water softener, TCC	P1@4.75	Ea	745.00	171.00	—	916.00
60,000 grain water softener, TCC	P1@4.75	Ea	880.00	171.00	—	1,051.00
75,000 grain water softener, TCC	P1@5.00	Ea	944.00	180.00	—	1,124.00
90,000 grain water softener, TCC	P1@5.50	Ea	1,280.00	198.00	—	1,478.00
120,000 grain water softener, TCC	P1@5.75	Ea	1,370.00	207.00	—	1,577.00

Water softener, mechanically-metered controller. Including brine tank, brine well and pick up tube. Labor includes setting in place, connecting the unit to an existing domestic water distribution system, start up and testing.

20,000 grain water softener, MMC	P1@4.50	Ea	723.00	162.00	—	885.00
30,000 grain water softener, MMC	P1@4.50	Ea	755.00	162.00	—	917.00
45,000 grain water softener, MMC	P1@4.50	Ea	822.00	162.00	—	984.00
50,000 grain water softener, MMC	P1@4.75	Ea	905.00	171.00	—	1,076.00
60,000 grain water softener, MMC	P1@4.75	Ea	1,060.00	171.00	—	1,231.00
75,000 grain water softener, MMC	P1@5.00	Ea	1,130.00	180.00	—	1,310.00
90,000 grain water softener, MMC	P1@5.50	Ea	1,450.00	198.00	—	1,648.00
120,000 grain water softener, MMC	P1@5.75	Ea	1,550.00	207.00	—	1,757.00

Water Softeners and Controllers

Description	Craft@Hrs	Unit	Material \$	Labor \$	Equipment \$	Total \$
-------------	-----------	------	-------------	----------	--------------	----------

Water softener, electronically-metered controller. Including brine tank, brine well and pick up tube. Labor includes setting in place, connecting the unit to an existing domestic water distribution system, start up and testing.

20,000 grain water softener, EMC	P1@4.50	Ea	767.00	162.00	—	929.00
30,000 grain water softener, EMC	P1@4.50	Ea	789.00	162.00	—	951.00
45,000 grain water softener, EMC	P1@4.50	Ea	866.00	162.00	—	1,028.00
50,000 grain water softener, EMC	P1@4.75	Ea	949.00	171.00	—	1,120.00
60,000 grain water softener, EMC	P1@4.75	Ea	1,110.00	171.00	—	1,281.00
75,000 grain water softener, EMC	P1@5.00	Ea	1,170.00	180.00	—	1,350.00
90,000 grain water softener, EMC	P1@5.50	Ea	1,490.00	198.00	—	1,688.00
120,000 grain water softener, EMC	P1@5.75	Ea	1,590.00	207.00	—	1,797.00

Water softener accessories

By-pass valve	P1@.400	Ea	73.90	14.40	—	88.30
Manifold adapter kit	P1@.200	Ea	19.90	7.21	—	27.11
Turbulator	P1@.400	Ea	36.50	14.40	—	50.90

Iron filter, electronically-metered controller. Manganese green sand filter. Labor includes setting in place, connecting the unit to an existing domestic water distribution system, start-up and testing.

42,000 iron filter (1.5 cf media), 5 gpm	P1@4.00	Ea	725.00	144.00	—	869.00
65,000 iron filter (2.0 cf media), 6 gpm	P1@4.50	Ea	858.00	162.00	—	1,020.00
84,000 iron filter (2.5 cf media), 8 gpm	P1@4.75	Ea	916.00	171.00	—	1,087.00
Replacement green sand media	P1@1.20	CF	42.00	43.20	—	85.20

Iron filter accessories

By-pass valve	P1@.400	Ea	73.90	14.40	—	88.30
Air vent	P1@.200	Ea	58.60	7.21	—	65.81
Air controller	P1@.400	Ea	66.20	14.40	—	80.60

Water Softener Accessories

Description	Craft@Hrs	Unit	Material \$	Labor \$	Equipment \$	Total \$
-------------	-----------	------	-------------	----------	--------------	----------

Combination iron filter/water softener. Zeolite resins soften water and remove iron and manganese. Controller automatically controls PH level. Labor includes setting in place, connecting the unit to an existing domestic water distribution system, start-up and testing.

40,000 iron filter, 1.3 cf media	P1@4.00	Ea	1,400.00	144.00	—	1,544.00
60,000 iron filter, 1.7 cf media	P1@4.50	Ea	1,520.00	162.00	—	1,682.00
80,000 iron filter, 2.5 cf media	P1@4.75	Ea	2,200.00	171.00	—	2,371.00

Hot water softener, time clock controller. Brass valve construction. Designed for 150 F. maximum operating temperature. Includes brine tank, brine well and pick-up tube. Labor includes setting in place, connecting the unit to an existing domestic water distribution system, start-up and testing.

20,000 grain hot water softener	P1@4.50	Ea	1,760.00	162.00	—	1,922.00
30,000 grain hot water softener	P1@4.50	Ea	1,870.00	162.00	—	2,032.00
40,000 grain hot water softener	P1@4.50	Ea	1,950.00	162.00	—	2,112.00
60,000 grain hot water softener	P1@4.75	Ea	2,310.00	171.00	—	2,481.00

Pressure tank, fiberglass wound. Labor includes setting in place, connecting the tank to a domestic water distribution system and testing.

Fiberglass pressure tank, 20 gallon	P1@2.00	Ea	234.00	72.10	—	306.10
Fiberglass pressure tank, 30 gallon	P1@2.00	Ea	263.00	72.10	—	335.10
Fiberglass pressure tank, 80 gallon	P1@2.75	Ea	427.00	99.10	—	526.10
Fiberglass pressure tank, 120 gallon	P1@3.50	Ea	563.00	126.00	—	689.00
Brass tank tee assembly, ¾"	P1@3.50	Ea	33.20	126.00	—	159.20
Brass tank tee assembly, 1"	P1@3.50	Ea	62.00	126.00	—	188.00
Brass tank tee assembly, 1¼"	P1@3.50	Ea	106.00	126.00	—	232.00

Description	Craft@Hrs	Unit	Material \$	Labor \$	Equipment \$	Total \$
-------------	-----------	------	-------------	----------	--------------	----------

Ultra-violet water disinfection unit. Stainless steel reactor, audible and visible alarm, lamp end-of-life indicator and 7-day override. Gpm rating at 30,000 mj/m2 output. Labor includes setting in place, connecting to the water system and testing.

UV system, 1 gpm, ¼" in/out	P1@3.00	Ea	221.00	108.00	—	329.00
UV system, 6 gpm, ½" in/out	P1@3.00	Ea	429.00	108.00	—	537.00
UV system, 8 gpm, ¾" in/out	P1@4.00	Ea	497.00	144.00	—	641.00
UV system, 12 gpm, ¾" in/out	P1@4.00	Ea	636.00	144.00	—	780.00
UV replacement lamp, 20W, 1 gpm	P1@.750	Ea	49.40	27.00	—	76.40
UV replacement lamp, 32W, 6 gpm	P1@.750	Ea	56.00	27.00	—	83.00
UV replacement lamp, 39W, 8-12 gpm	P1@.750	Ea	71.70	27.00	—	98.70
UV replacement ballast, 420 Mv/110V	P1@1.00	Ea	217.00	36.00	—	253.00

Kitchen equipment booster heater


1,000 watt	P1@4.00	Ea	549.00	144.00	—	693.00
------------	---------	----	--------	--------	---	--------

Dishwasher


Built-in	P1@5.00	Ea	813.00	180.00	—	993.00
----------	---------	----	--------	--------	---	--------

Garbage disposal


½ HP	P1@2.00	Ea	172.00	72.10	—	244.10
¾ HP	P1@2.00	Ea	287.00	72.10	—	359.10

**Grease and oil interceptor**

4 GPM	P1@4.00	Ea	332.00	144.00	—	476.00
10 GPM	P1@5.00	Ea	541.00	180.00	—	721.00
15 GPM	P1@7.00	Ea	807.00	252.00	—	1,059.00
20 GPM	P1@8.00	Ea	977.00	288.00	—	1,265.00

**Hair and lint interceptor**

1½"	P1@.650	Ea	208.00	23.40	—	231.40
2"	P1@.750	Ea	297.00	27.00	—	324.00

**All bronze ¾" to 1½" in-line NPT pump**

1/12 HP	P1@1.50	Ea	515.00	54.00	—	569.00
1/6 HP	P1@1.50	Ea	769.00	54.00	—	823.00
1/4 HP	P1@1.50	Ea	901.00	54.00	—	955.00

Kitchen Equipment Connections

Description	Craft@Hrs	Unit	Material \$	Labor \$	Equipment \$	Total \$
-------------	-----------	------	-------------	----------	--------------	----------

Kitchen appliance gas trim

1/2"	P1@1.15	Ea	39.30	41.40	—	80.70
3/4"	P1@1.30	Ea	71.80	46.80	—	118.60
1"	P1@1.60	Ea	83.20	57.60	—	140.80
1 1/4"	P1@2.10	Ea	137.00	75.70	—	212.70
1 1/2"	P1@2.50	Ea	174.00	90.10	—	264.10
2"	P1@3.00	Ea	232.00	108.00	—	340.00

Hot and cold water supply

1/2"	P1@1.10	Ea	38.60	39.60	—	78.20
3/4"	P1@1.55	Ea	54.60	55.80	—	110.40
1"	P1@1.90	Ea	74.40	68.50	—	142.90
1 1/4"	P1@2.50	Ea	105.00	90.10	—	195.10
1 1/2"	P1@3.00	Ea	131.00	108.00	—	239.00

Continuous waste

2-part	P1@.250	Ea	55.50	9.01	—	64.51
3-part	P1@.350	Ea	93.30	12.60	—	105.90
4-part	P1@.450	Ea	121.00	16.20	—	137.20

Indirect waste

1/2"	P1@1.05	Ea	12.00	37.80	—	49.80
3/4"	P1@1.50	Ea	20.30	54.00	—	74.30
1"	P1@1.90	Ea	32.60	68.50	—	101.10
1 1/4"	P1@2.15	Ea	48.30	77.50	—	125.80
1 1/2"	P1@2.60	Ea	63.60	93.70	—	157.30
2"	P1@3.00	Ea	97.20	108.00	—	205.20

Kitchen fixture waste tailpiece

1 1/2"	P1@.100	Ea	12.10	3.60	—	15.70
--------	---------	----	-------	------	---	-------

Kitchen fixture trap with solder bushing

1 1/2"	P1@.250	Ea	40.60	9.01	—	49.61
2"	P1@.300	Ea	56.50	10.80	—	67.30

Description	Craft@Hrs	Unit	Material \$	Labor \$	Equipment \$	Total \$
-------------	-----------	------	-------------	----------	--------------	----------

Water closet, floor-mounted, flush tank, white vitreous china, lined tank. Complete with trim. Make additional allowances for rough-in. Based on American Standard Cadet series. ADA means American Disabilities Act compliant. (Wheelchair accessible)

Round bowl	P1@2.10	Ea	249.00	75.70	—	324.70
Elongated bowl	P1@2.10	Ea	302.00	75.70	—	377.70
ADA, 18" high	P1@2.10	Ea	411.00	75.70	—	486.70



Water closet, floor-mounted, flush valve, white vitreous china.

Complete with trim. Make additional allowances for rough-in. Based on American Standard. ADA means American Disabilities Act compliant. (Wheelchair accessible)


Elongated bowl	P1@2.60	Ea	390.00	93.70	—	483.70
Elongated bowl, ADA 18" high	P1@2.60	Ea	464.00	93.70	—	557.70
Elongated bowl with a bedpan cleanser	P1@4.10	Ea	676.00	148.00	—	824.00
Elongated bowl, ADA 18" high with a bedpan cleanser	P1@4.10	Ea	732.00	148.00	—	880.00

Water closet, wall-hung, flush valve, white vitreous china. Complete with fixture carrier and all trim. Make additional allowances for rough-in. Based on American Standard AFWall series.

Elongated bowl	P1@3.55	Ea	621.00	128.00	—	749.00
Elongated bowl with electronic flush valve	P1@3.80	Ea	1,110.00	137.00	—	1,247.00
Elongated bowl with bedpan cleanser	P1@5.05	Ea	898.00	182.00	—	1,080.00
Electronic flush valve, add	P1@.600	Ea	489.00	21.60	—	510.60

Urinal, wall-hung, flush valve, white vitreous china. Complete with trim. Make additional allowances for rough-in.

Siphon-jet type	P1@3.15	Ea	621.00	113.00	—	734.00
Wash-out type	P1@3.10	Ea	507.00	112.00	—	619.00
Wash-down type	P1@3.00	Ea	358.00	108.00	—	466.00
Urinal carrier, add	P1@.600	Ea	114.00	21.60	—	135.40
Electronic flush valve, add	P1@.600	Ea	403.00	21.60	—	424.60



Urinal, stall-type, flush valve, white vitreous china. Complete with trim. Make additional allowances for rough-in.

Stall urinal	P1@5.00	Ea	1,210.00	180.00	—	1,390.00
--------------	---------	----	----------	--------	---	----------

Plumbing Fixtures

Description	Craft@Hrs	Unit	Material \$	Labor \$	Equipment \$	Total \$
-------------	-----------	------	-------------	----------	--------------	----------

Lavatory, wall-hung, white vitreous china. Complete with trim and fixture carrier. Make additional allowances for rough-in. ADA means American Disabilities Act compliant. (Wheelchair accessible)



Wall-hung lav	P1@2.70	Ea	519.00	97.30	—	616.30
Wall-hung, ADA	P1@2.70	Ea	755.00	97.30	—	852.30
Fixture carrier	P1@.500	Ea	107.00	18.00	—	125.00

Countertop lavatory, white. Complete with trim. Make additional allowances for rough-in.



Vitreous china	P1@2.00	Ea	384.00	72.10	—	456.10
Enameled steel	P1@2.00	Ea	324.00	72.10	—	396.10
Acrylic	P1@2.00	Ea	236.00	72.10	—	308.10

Bathtub, white, 60" x 32". Complete with trim, including shower head. Make additional allowances for rough-in.




Enameled steel	P1@2.50	Ea	540.00	90.10	—	630.10
Cast iron	P1@3.50	Ea	782.00	126.00	—	908.00
Fiberglass	P1@2.50	Ea	499.00	90.10	—	589.10
Acrylic	P1@2.50	Ea	534.00	90.10	—	624.10

Tub and shower combination, fiberglass, white. Complete with trim. Make additional allowances for rough-in.

One-piece	P1@4.50	Ea	1,110.00	162.00	—	1,272.00
Two-piece (reno)	P1@5.50	Ea	1,420.00	198.00	—	1,618.00
Four-piece (reno)	P1@6.25	Ea	1,510.00	225.00	—	1,735.00

Shower stall, white, 36" x 36". Complete with trim. Make additional allowances for rough-in.



Fiberglass one-piece	P1@3.50	Ea	691.00	126.00	—	817.00
Fiberglass three-piece	P1@4.25	Ea	890.00	153.00	—	1,043.00
Acrylic one-piece	P1@3.50	Ea	1,040.00	126.00	—	1,166.00
Acrylic three-piece	P1@4.25	Ea	1,350.00	153.00	—	1,503.00

Shower basin, 36" x 36". Complete with trim (faucet, shower head and strainer). Make additional allowances for rough-in.

Fiberglass	P1@2.50	Ea	470.00	90.10	—	560.10
Acrylic	P1@2.50	Ea	507.00	90.10	—	597.10
Molded stone	P1@2.65	Ea	489.00	95.50	—	584.50

Description **Craft@Hrs** **Unit** **Material \$** **Labor \$** **Equipment \$** **Total \$**

Kitchen sink, double compartment. Complete with trim. Make additional allowances for rough-in.

Stainless steel	P1@2.15	Ea	382.00	77.50	—	459.50
Cast iron	P1@2.50	Ea	499.00	90.10	—	589.10
Acrylic	P1@2.15	Ea	453.00	77.50	—	530.50



Kitchen sink, single compartment. Complete with trim. Make additional allowances for rough-in.

Stainless steel	P1@2.00	Ea	323.00	72.10	—	395.10
Cast iron	P1@2.10	Ea	372.00	75.70	—	447.70
Acrylic	P1@2.00	Ea	336.00	72.10	—	408.10

Bar sink. Complete with trim. Make additional allowances for rough-in.

Stainless steel	P1@2.00	Ea	289.00	72.10	—	361.10
Acrylic	P1@2.00	Ea	194.00	72.10	—	266.10



Exam room sink. Complete with trim. Make additional allowances for rough-in.

Stainless steel	P1@2.10	Ea	419.00	75.70	—	494.70
Acrylic	P1@2.10	Ea	358.00	75.70	—	433.70

Laboratory sink. Complete with trim. Make additional allowances for rough-in.


Stainless steel	P1@2.25	Ea	480.00	81.10	—	561.10
Acrylic	P1@2.25	Ea	419.00	81.10	—	500.10

Laundry sink, double compartment. Complete with trim. Make additional allowances for rough-in.

Cast iron	P1@3.50	Ea	561.00	126.00	—	687.00
Acrylic	P1@2.25	Ea	246.00	81.10	—	327.10

Laundry sink, single compartment. Complete with trim. Make additional allowances for rough-in.

Cast iron	P1@2.75	Ea	486.00	99.10	—	585.10
Acrylic	P1@2.00	Ea	171.00	72.10	—	243.10



Mop sink, floor-mounted, 36" x 24". Complete with trim. Make additional allowances for rough-in.

Molded stone	P1@2.65	Ea	684.00	95.50	—	779.50
Terrazzo	P1@2.65	Ea	754.00	95.50	—	849.50
Acrylic	P1@2.35	Ea	527.00	84.70	—	611.70


Plumbing Fixtures



Description	Craft@Hrs	Unit	Material \$	Labor \$	Equipment \$	Total \$
-------------	-----------	------	-------------	----------	--------------	----------


Slop sink, enameled cast iron with P-trap, standard. Complete with trim. Make additional allowances for rough-in.

Slop sink with P-trap, std.	P1@3.50	Ea	1,120.00	126.00	—	1,246.00
-----------------------------	---------	----	----------	--------	---	----------




Floor sink, recessed, enameled steel, white. Add 40% to material prices for acid-resisting finish. Complete with strainer. Make additional allowances for rough-in.

9" x 9"	P1@1.00	Ea	96.30	36.00	—	132.30
12" x 12"	P1@1.00	Ea	112.00	36.00	—	148.00
15" x 15"	P1@1.15	Ea	76.20	41.40	—	117.60
18" x 18"	P1@1.25	Ea	99.50	45.00	—	144.50
24" x 24"	P1@1.50	Ea	135.00	54.00	—	189.00



Drinking fountain, refrigerated, stainless steel. Complete with trim. Make additional allowances for rough-in. ADA means American Disabilities Act compliant. (Wheelchair accessible)

Free-standing	P1@2.00	Ea	1,210.00	72.10	—	1,282.10
Semi-recessed	P1@2.50	Ea	1,600.00	90.10	—	1,690.10
Fully-recessed	P1@2.50	Ea	2,770.00	90.10	—	2,860.10
Wall-hung	P1@2.00	Ea	1,130.00	72.10	—	1,202.10
Wall-hung, ADA	P1@2.50	Ea	2,770.00	90.10	—	2,860.10



Drinking fountain, non-refrigerated. Complete with trim. Make additional allowances for rough-in. ADA means American Disabilities Act compliant. (Wheelchair accessible) S.S. means stainless steel.

Recessed, china	P1@2.50	Ea	930.00	90.10	—	1,020.10
Wall-hung, china	P1@2.00	Ea	530.00	72.10	—	602.10
Recessed, S.S.	P1@2.50	Ea	1,060.00	90.10	—	1,150.10
Wall-hung, S.S.	P1@2.00	Ea	564.00	72.10	—	636.10
ADA, S.S.	P1@2.50	Ea	971.00	90.10	—	1,061.10

Plumbing Fixtures Rough-in

Description	Craft@Hrs	Unit	Material \$	Labor \$	Equipment \$	Total \$
-------------	-----------	------	-------------	----------	--------------	----------

Commercial plumbing fixture rough-in. Includes type L copper supply pipe and DWV copper (to 2½") or cast iron (MJ) DWV (over 2½") drain and vent piping. Make additional allowances for plumbing fixtures and trim. Use these costs for preliminary estimates.

Water closet, wall-hung, flush valve, with carrier	P1@2.25	Ea	935.00	81.10	—	1,016.10
Water closet, wall-hung, flush valve, no carrier	P1@1.95	Ea	340.00	70.30	—	410.30
Water closet, floor-mounted, flush valve	P1@2.75	Ea	756.00	99.10	—	855.10
Water closet, floor-mounted, tank type	P1@2.25	Ea	580.00	81.10	—	661.10
Bidet	P1@2.00	Ea	404.00	72.10	—	476.10
Urinal, wall-hung, flush valve, with carrier	P1@3.10	Ea	1,020.00	112.00	—	1,132.00
Urinal, wall-hung, flush valve, without carrier	P1@2.35	Ea	580.00	84.70	—	664.70
Lavatory, wall-hung, with carrier	P1@2.40	Ea	839.00	86.50	—	925.50
Lavatory	P1@1.90	Ea	404.00	68.50	—	472.50
Sink	P1@1.90	Ea	435.00	68.50	—	503.50
Bath tub	P1@2.35	Ea	622.00	84.70	—	706.70
Shower	P1@2.60	Ea	729.00	93.70	—	822.70
Mop sink	P1@2.40	Ea	516.00	86.50	—	602.50
Slop sink	P1@2.60	Ea	370.00	93.70	—	463.70
Laundry tub	P1@1.95	Ea	438.00	70.30	—	508.30
Wash fountain	P1@2.10	Ea	474.00	75.70	—	549.70
Lab sink, glass drainage	P1@3.80	Ea	1,870.00	137.00	—	2,007.00
Lab sink, acid resistant plastic drainage	P1@2.65	Ea	296.00	95.50	—	391.50
Drinking fountain	P1@2.20	Ea	321.00	79.30	—	400.30
Emergency eyewash and shower	P1@1.75	Ea	122.00	63.10	—	185.10
Washing machine	P1@2.25	Ea	471.00	81.10	—	552.10

Plumbing Fixtures Rough-in

Description	Craft@Hrs	Unit	Material \$	Labor \$	Equipment \$	Total \$
-------------	-----------	------	-------------	----------	--------------	----------

Commercial plumbing fixture group rough-in. Includes Type L copper supply pipe and DWV copper (to 2½") or cast iron (MJ) DWV (over 2½") drain and vent piping. Make additional allowances for plumbing fixtures and trim. Use these costs for preliminary estimates.

3-piece washroom group	P1@5.50	Ea	1,150.00	198.00	—	1,348.00
3-piece washroom group back to back	P1@9.75	Ea	2,110.00	351.00	—	2,461.00
Kitchen sink, back to back	P1@2.15	Ea	618.00	77.50	—	695.50
Battery of water closets, floor-mounted, tank type, per water closet	P1@1.75	Ea	481.00	63.10	—	544.10
Battery of water closets, floor-mounted, flush valve, per water closet	P1@2.20	Ea	628.00	79.30	—	707.30
Battery of water closets, wall-hung, flush valve, with carrier, per water closet	P1@1.80	Ea	827.00	64.90	—	891.90
Battery of water closets, wall-hung, flush valve, without carrier, per water closet	P1@1.50	Ea	242.00	54.00	—	296.00
Battery of urinals, wall-hung, flush valve with carrier, per urinal	P1@2.45	Ea	994.00	88.30	—	1,082.30
Battery of urinals, wall-hung, flush valve without carrier, per urinal	P1@1.90	Ea	513.00	68.50	—	581.50
Battery of lavatory basins, wall-hung, with carrier, per lavatory	P1@2.00	Ea	773.00	72.10	—	845.10
Battery of lavatory basins, without carrier, per lavatory	P1@1.50	Ea	349.00	54.00	—	403.00

Residential plumbing fixture rough-in. Includes polyethylene (PE) supply pipe and ABS DWV drain and vent piping. Make additional allowances for plumbing fixtures and trim. Use these costs for preliminary estimates.

Water closet, floor-mounted, tank type	P1@2.00	Ea	133.00	72.10	—	205.10
Bidet	P1@1.85	Ea	100.00	66.70	—	166.70
Lavatory	P1@1.75	Ea	100.00	63.10	—	163.10
Counter sink	P1@1.75	Ea	110.00	63.10	—	173.10
Bathtub	P1@2.10	Ea	100.00	75.70	—	175.70
Shower	P1@2.45	Ea	146.00	88.30	—	234.30
Laundry tub	P1@1.75	Ea	91.30	63.10	—	154.40
Washing machine	P1@2.00	Ea	113.00	72.10	—	185.10

Index

A

- ABS, DWV pipe150
 1/8 bend150
 1/4 bend150
 adapters152
 bushings152
 cleanouts152
 closet bend150
 closet flanges150
 combinations151
 couplings153
 hanger assemblies153
 P-traps151
 reducers153
 riser clamps153
 solvent-weld joints152-153
 tees151
 wyes151-152
 ABS, DWV, test cap152
 A/C systems286
 Access doors, steel121
 Accessories
 iron filter23
 water softener23
 Acid DWV systems164
 Actuator, damper404
 Adapters
 copper, DWV, soldered148
 CPVC sprinkler pipe184
 F.I.P., ABS152
 PE-AL pipe113
 PEX-AL pipe113
 polypropylene pipe166
 PVC, DWV156
 PVC, Schedule 4094
 PVC, Schedule 80104
 PVC sewer, bell & spigot163
 Schedule 5 steel, pressfit236
 Schedule 10 steel, roll-grooved275
 Schedule 40 steel, cut-grooved281
 Schedule 40 steel, roll-grooved268
 Type K copper, brazed37
 Type K copper, soldered47-48
 Type L copper, brazed56
 Type L copper, soldered65
 Type M copper, brazed74
 Type M copper, soldered83
 Additional costs8
 Adjusting costs7
 Air admittance valve328
 Air balance software338
 Air balancing
 air handling units402
 centrifugal fans403
 diffusers402
 fan coil units403
 fume hoods403
 grilles403
 terminal boxes402
 Air compressor406
 rental420
 Air conditioning
 budget estimates435
 residential286
 Air conditioning condensate systems
 PVC, Schedule 4091
 PVC, Schedule 80101
 Type K copper, brazed33
 Type K copper, soldered43
 Type L copper, brazed53
 Type L copper, soldered62
 Type M copper, brazed71
 Type M copper, soldered80
 Air conditioning units288
 Air cooled condenser
 condensing unit212
 Air grilles, return333
 Air handling equipment
 air conditioner288
 exhaust fans326
 housings331
 ventilators326
 Air handling units289
 accessories290
 air balancing402
 coil connection297-298
 removal424
 Air mixing box, removal423
 Air separators, Rolaitrol type201
 Air vents121
 Alarm valves171
 Apartments, HVAC estimates437
 Area drains168
 installation costs435
 Arresters, water hammer133
 As-built drawings421
 Assemblies
 air conditioning286
 forced air heating287
 Auditoriums, HVAC estimates437
- ## B
- Backfill costs, trenching418
 Backflow preventers
 double check120
 reduced pressure119
 Backhoes, rental420
 Balancing valves PEX-AL pipe .114, 118
 Ball valves
 PEX-AL pipe114, 118
 pipe and plumbing specialty .126-127
 PVC, Schedule 4097
 PVC, Schedule 80107
 PVC, Solid body, EDPM97, 107
 PVC, Solid body, threaded97, 107
 PVC, Tru-union, threaded97, 107
 PVC, Union type, Solvent
 weld98, 107
 Schedule 40 steel, threaded230
 Schedule 80 steel, threaded252
 Type K copper, brazed40
 Type K copper, soldered50
 Type L copper, brazed59
 Type L copper, soldered68
 Type M copper, brazed77
 Type M copper, soldered86
 Banks, HVAC estimates437
 Bar sinks29
 estimating435
 Barber shops, HVAC estimates437
 Base wage6
 Baseboard fins204
 Bathroom
 fans328-329
 fixtures28
 heaters328
 Bathroom sink, disconnect433
 Bathtubs28
 disconnect433
 estimating435
 Beauty shops, HVAC estimates437
 Bell & spigot pipe, PVC159
 Benders, hydraulic, rental420
 Bends
 ABS, DWV pipe150
 cast iron, no-hub136-138
 class 110 DI, cement lined411
 class 150 cast iron412
 class 153 DI, cement lined407
 class 153 DI, double cement
 lined409
 class 2400 or 3000 asbestos
 cement413
 copper, DWV, soldered147
 polypropylene pipe164
 PVC, DWV159-160
 PVC sewer, bell & spigot160
 Bevel machines, rental420
 Billing breakdown worksheet . .461-462
 Biomass fired
 boilers319-320
 central airspace heater321

Black steel pipe	177	Booster heaters	25	Schedule 40 steel, cut-grooved ..	282
assemblies	176	Bore holes, geothermal	317	Schedule 40 steel, roll-grooved ..	269
Blowers, centrifugal	324	Bowling alleys, HVAC estimates ..	437	Schedule 40 steel, threaded	226
Boiler		Branch pipe and fittings, sprinkler	182	Schedule 40 steel, welded	217
blowdown	203	Brazed joint pipe		Schedule 80 steel, threaded	250
burners	195	Type K copper	33	Schedule 80 steel, welded	241
stack	203	Type L copper	53	Schedule 160 steel, welded	261
trim	204	Type M copper	71	Type K copper, brazed	38
Boiler connections	190	Bucket steam trap	126	Type K copper, soldered	48
boiler pumps	205	Budget estimating	435	Type L copper, brazed	57
Boilers		Buildings, HVAC estimates	437	Type L copper, soldered	66
biomass fired	319-320	Burners, dual fuel	195	Type M copper, brazed	75
pulse type	322	Bushings		Type M copper, soldered	84
removal	425	ABS	152	Carbon steel fittings	214-265
steam heating	189	PVC, DWV	156	Carbon steel pipe	
Boilers, commercial		PVC, Schedule 40	94	Schedule 40	180
accessories	204	PVC, Schedule 80	104	Schedule 80	238
adjusting	198	Type K copper, brazed	38	Cast iron class 150	412
cast iron	185	Type K copper, soldered	48	Cast iron DWV pipe, hub & spigot	141
chemical feed pump	202	Type L copper, brazed	57	1/16 bend	142
combustion controls	197-198	Type L copper, soldered	66	1/8 bend	141
combustion train	192	Type M copper, brazed	75	1/4 bend	141
components	204	Type M copper, soldered	84	bends	142
deaerator/condenser	201	Butterfly valves		closet flanges	142
electrical service	196	pipe and plumbing specialty	127	combinations	143
feedwater pumps	197	PVC, Schedule 40	96	gaskets	145
firebox	187	PVC, Schedule 80	106	hanger assemblies	145
firetube	186-187	Schedule 10 steel, roll-grooved ..	277	P-traps	142
fuel train piping	193-194	Schedule 40 steel, cut-grooved ..	283	reducers	144
packaged, feedwater systems ..	202	Schedule 40 steel, roll-grooved ..	270	riser clamps	145
pumping unit	201	Schedule 40 steel, threaded	230	sanitary tees	142
refractory	197	Schedule 40 steel, welded ..	219-220	tees	142
stacks	203	Schedule 80 steel, threaded ..	251-252	wyes	143-144
water softening systems	198	Schedule 80 steel, welded	243	Cast iron DWV pipe, mechanical	
watertube	188	Type K copper, brazed	39	joint	135
Boilers, gas fired		Type K copper, soldered	50	Cast iron DWV pipe, no-hub	135
cast iron	189	Type K & L copper, roll grooved ..	90	1/8 bend	135-136
steel	188	Type L copper, brazed	58	1/4 bend	136
Bolt and gasket sets		Type L copper, soldered	67	caps	139
pipe and plumbing specialty	122	Type M copper, brazed	76	closet bends	136
polypropylene pipe	167	Type M copper, soldered	85	closet flanges	136
PVC, Schedule 40	99			combinations	138
PVC, Schedule 80	109			couplings	139
Schedule 10 steel, roll-grooved ..	279			crosses	139
Schedule 40 steel, cut-grooved ..	284			hanger assemblies	140
Schedule 40 steel, roll-grooved ..	271			horizontal assembly	135
Schedule 40 steel, threaded	232			P-traps	136
Schedule 40 steel, welded	222			reducers	139
Schedule 80 steel, threaded	253			riser clamps	140
Schedule 80 steel, welded	245			tees	138-139
Schedule 160 steel, full face	264			wyes	136-138
Schedule 160 steel, ring face	264			Cast iron sprinkler pipe fittings	
Type K copper, brazed	41			cap	181
Type K copper, soldered	52			couplings	181
Type L copper, brazed	60			cross	181
Type L copper, soldered	69			ells	180
Type M copper, brazed	78			plugs	181
Type M copper, soldered	87			reducers	180
Boom lifts, rental	420			reducing tee	180
		C			
		Calcium silicate pipe insulation ..	399		
		California Code, 2010	199		
		Can washers, installation costs ..	435		
		Caps			
		cast iron, no-hub	139		
		cast iron, threaded	181		
		CPVC sprinkler pipe	184		
		PE-AL pipe	114, 117		
		PEX-AL pipe	114, 117		
		PVC sewer, bell & spigot	163		
		PVC, Schedule 40	95		
		PVC, Schedule 80	105		
		roll grooved, Victaulic	178		
		Schedule 10 steel, roll-grooved ..	276		

Ceiling diffusers	334-335	Close-out items	421	Computer rooms, HVAC estimates .	437
Central air space heater, biomass fired	321	Closet bends, ABS, DWV pipe . . .	150	Condenser units	205
Central dehumidification	300	Closet flanges		Condenser water systems	
Centrifugal blowers	324	ABS, DWV pipe	150	Schedule 40 steel, cut-grooved . .	280
Centrifugal fans, air balancing . .	403	cast iron, hub & spigot	142	Schedule 40 steel, roll-grooved . .	266
Centrifugal pumps, HVAC	206	cast iron, no-hub	136	Condensing units, air cooled	212
Centrifugal water-cooled chiller . .	211	copper, DWV, soldered	147	Condominiums, HVAC estimates . .	437
Ceramic heater	304	PVC, DWV	155-156	Configurable controller	338
Chain hoists, rental	420	Clothes dryers, exhaust	327	Connections	
Change estimates	438-448	Cocktail lounges, HVAC estimates .	437	air handling unit, HVAC	297-298
change order log	443	Coil connection, air handling		continuous waste	26
example	439	unit	297-298	fire department	174
summary	442, 446	Coil, duct mounted, removal	429	flexible duct	343
take-off	440, 444	Coils, reheat, HVAC	209	hot and cold water supply	26
worksheet	441, 445	Cold water connections	26	indirect waste	26
Check valves	171	Collars, galvanized steel	343	kitchen equipment	26
Chemical feed pump, boiler	202	Combinations		Siamese	174
Chemical feed system	202	ABS	151	water heaters	21
Chemical systems		cast iron, hub & spigot	143	Connectors, pipe	123
polypropylene, DWV	164	cast iron, no-hub	138	flexible	124
PVC, Schedule 40	91	copper, DWV, soldered	147	Construction schedule	453-455
PVC, Schedule 80	101	polypropylene pipe	165	Contents	3
Chilled water systems		Combustion controls, boiler	197-198	Continuous waste connections	26
Schedule 10 steel, roll-grooved . .	273	Combustion monitoring	205	Control modules, pollution	199
Schedule 40 steel, cut-grooved . .	280	Combustion train, boiler	192	Control valves	
Schedule 40 steel, roll-grooved . .	266	Come-alongs, rental	420	2 way	405-406
Schedule 40 steel, threaded	223	Commercial boilers	186-189	3 way	405-406
Schedule 80 steel, threaded	247	combustion trains	192	electric	405
Type K copper, brazed	33	components and accessories . . .	204	pipe and plumbing specialty	132-133
Type K copper, soldered	43	connections	190	pneumatic	406
Type L copper, brazed	53	Commercial fans and blowers . . .	324	PVC, Schedule 40	99
Type L copper, soldered	62	Commercial fixture rough-ins	31	PVC, Schedule 80	109
Type M copper, brazed	71	group	32	Schedule 10 steel, roll-grooved . .	278
Type M copper, soldered	80	Commercial water heaters	19, 20	Schedule 40 steel, cut-grooved . .	284
Chillers		Compaction, trenching	418	Schedule 40 steel, roll-grooved . .	271
centrifugal	211	Compactors, rental	420	Schedule 40 steel, threaded	231
drinking fountain	30	Companion flanges		Schedule 40 steel, welded	221
reciprocating	211	150 pound, threaded	122	Schedule 80 steel, threaded	253
removal	426	300 pound, threaded	122	Schedule 80 steel, welded	244-245
water cooled, connection	211	PVC	122	Schedule 160 steel, flanged	263-264
Chlorinated polyvinyl chloride pipe .	183	PVC, Schedule 40	99	Schedule 160 steel, threaded . . .	263
Churches, HVAC estimates	437	PVC, Schedule 80	109	Type K copper, brazed	41
Circuit balance valves	127	Schedule 40 steel, threaded	232	Type K copper, soldered	51
Circulating pumps		Type K copper, brazed	41	Type L copper, brazed	60
all bronze	120	Type K copper, soldered	51	Type L copper, soldered	69
iron body	121	Type L copper, brazed	60	Type M copper, brazed	78
Clarifications	8	Type L copper, soldered	69	Type M copper, soldered	87
Classrooms, HVAC estimates	437	Type M copper, brazed	78	Controllers	338
Cleanouts		Type M copper, soldered	87	Controls	
ABS	152	welding type	121	boiler	203
ABS/PVC	169	Composite pipe	111	HVAC	404
copper, DWV, soldered	147	compression fittings	116	Cooling systems, residential	286
end-of-line	169	compression joint fittings	117	Cooling towers	
floor	169	compression joints	116	connection assembly	213
installation costs	435	crimped joint	111	demolition	427
PVC, DWV	157	crimped joint fittings	111-112	forced draft	213
wall	169	Compressed air systems		galvanized steel	212
Closed loop heat pump	306	Type K copper, brazed	33	induced draft	212
		Type L copper, brazed	53	removal	427

Cooling units, variable volume	337	reducers	90	bushings	84
Copper fittings, roll grooved	89	roll grooved	89	caps	84
Copper pipe	89	tees	89	companion flanges	87
Copper pipe, DWV, soldered	146	valves	90	couplings	84
1/8 bend	146	Copper pipe, Type L brazed	53-54	ells	81-82
1/4 bend	147	adapters	56	hanger assemblies	88
adapters	148	bolt and gasket sets	60	maximum working pressure	80
assembly with riser	146	bushings	57	pressure gauges	87
cleanouts	147	caps	57	reducers	83
closet flanges	147	companion flanges	60	riser clamps	88
combinations	147	couplings	57	strainers	86
couplings	148	ells	54-55	tees	82
crosses	147	hanger assemblies	61	thermometers with wells	87
hanger assemblies	149	pressure gauges	60	unions	84
horizontal assemblies	146	reducers	56	valves	85-87
P-traps	147	riser clamps	61	Copper piping, removal	430
reducers	148	strainers	59	Correction factors	6
riser clamps	149	tees	55	Countertop sinks/lavatories	28
tees	147	thermometers with wells	60	Couplings	
test caps	148	unions	57	ABS	153
test tees	148	valves	58-60	cast iron, no-hub	139
wyes	147	Copper pipe, Type L soldered	62-63	cast iron, threaded	181
Copper pipe, Type K brazed	33-34	adapters	65	copper, DWV, soldered	148
adapters	37	bolt and gasket sets	69	CPVC sprinkler pipe	183
bolt and gasket sets	41	bushings	66	galvanized steel spiral duct	359
bushings	38	caps	66	PE-AL pipe	112-113, 117
caps	38	companion flanges	69	PEX-AL pipe	113, 117
companion flanges	41	couplings	66	polypropylene pipe	166
couplings	38	ells	63-64	PVC, DWV	156
ells	34-35	hanger assemblies	70	PVC, Schedule 40	95
hanger assemblies	42	maximum working pressure	62	PVC, Schedule 80	105
pressure gauges	41	pressure gauges	69	PVC sewer, bell & spigot	160
reducers	37	reducers	65	roll grooved, Victaulic	179
riser clamp	42	riser clamps	70	Schedule 5 steel, pressfit	235-236
strainers	40	strainers	68	Schedule 10 steel, roll-grooved	276
tees	35-36	tees	64	Schedule 40 steel, cut-grooved	282
thermometers with wells	41	thermometers with wells	69	Schedule 40 steel, roll-grooved	269
unions	38	unions	66	Schedule 40 steel, threaded	226
valves	39-41	valves	67-69	Schedule 80 steel, threaded	251
Copper pipe, Type K soldered	43-44	Copper pipe, Type M brazed	71-72	Type K copper, brazed	38
adapters	47-48	adapters	74	Type K copper, soldered	49
bolt and gasket sets	52	bolt and gasket sets	78	Type K & L copper, roll grooved	90
bushings	48	bushings	75	Type L copper, brazed	57
caps	48	caps	75	Type L copper, soldered	66
companion flanges	51	companion flanges	78	Type M copper, brazed	75
couplings	49	couplings	75	Type M copper, soldered	84
ells	44-45	ells	72	CPVC sprinkler pipe	183
hanger assemblies	52	hanger assemblies	79	adapters	184
pressure gauges	52	maximum working pressure	71	cap	184
reducers	47	pressure gauges	78	coupling	183
riser clamps	52	reducers	74	elbows	183
strainers	51	riser clamps	79	fittings	184
tees	45-46	strainers	77	flange	184
thermometers with wells	52	tees	73	head adapter	184
unions	48	thermometers with wells	78	reducing tees	183
valves	49-51	unions	75	tees	183
Copper pipe, Type K & L	89-90	valves	76-78	Craft codes	7
coupling	90	Copper pipe, Type M soldered	80-81	Craft@hrs	5
ells	89	adapters	83	Cranes, rental	420
flange adapter	90	bolt and gasket sets	87	Crew composition	7

[illegible]

Fan coils	327	Fittings, pipe		Forced air heating, residential	287
Fan controls	327	copper, DWV, soldered	146	Forced-draft cooling tower	213
Fans		expansion tank	123	Forklifts, rental	420
attic	326	M.I., 150 pound	224	Forms and letters	438
bathroom	326-328	malleable iron, Schedule 40	...266	Fringe benefits	6
ceiling exhaust	326-327	polypropylene	164	Front-end loaders, rental	420
ceiling mounted	326	PVC, DWV	154	Fuel train piping	193-194
centrifugal air foil	324	PVC sewer, bell & spigot	159	Fume hoods, air balancing	403
centrifugal utility	324	PVC, Schedule 40	92	Furnace removal	425
commercial	326	PVC, Schedule 80	101-102	Furnaces, residential	299
exhaust	326, 328-329	Schedule 10 steel, roll-grooved	..274	high efficiency	299
exhaust, roof	325	Schedule 40 steel, cut-grooved	..280	wall	300
humidistat	327	Schedule 40 steel, roll-grooved	..267	with A/C	299
kitchen	327	Schedule 40 steel, threaded	...224	Fusible plug dampers	341
roof	326	Schedule 40 steel, welded	215		
room ventilation	326	Schedule 80 steel, threaded	...248		
speed controller	327	Type K copper, brazed	42		
thru-wall	326	Type L copper, brazed	54		
timer	327	Type L copper, soldered	63		
tube-axial	325	Type M copper, brazed	72		
vane-axial	324	Type M copper, soldered	81		
ventilation	326-327	Fixtures			
wall exhaust	326	bathroom	28		
wall mounted	326	disconnect	433		
washroom	326-327	estimating costs	435		
Feedwater pumps, boiler	197	removal	432		
feedwater systems	205	Flange adapter, Type K & L			
Fiberglass		copper, roll grooved	90		
blanket	401	Flanges			
ductwork	396	CPVC sprinkler pipe	184		
pipe insulation	397-398	polypropylene pipe	167		
pressure tank	23	roll grooved, Victaulic	179		
rigid board	401	Schedule 10 steel, roll-grooved	..276		
tank	24, 415	Schedule 40 steel, cut-grooved	..282		
Filter, iron	24	Schedule 40 steel, roll-grooved	..269		
Fire dampers	340	Schedule 40 steel, threaded	...232		
Fire department connection	174	Schedule 40 steel, welded	218		
Fire extinguisher	175	Schedule 80 steel, threaded	...253		
Fire extinguishing systems	322	Schedule 80 steel, welded	242		
Fire hydrant	175	Schedule 160 steel, slip on	...262		
Fire protection		Schedule 160 steel, weld neck	..262		
CPVC sprinkler pipe	183	Flanges, companion			
fire hose cabinets	173	150 pound, threaded	122		
plastic sprinkler pipe	183	150 pound, welding type	121		
pumps	174	300 pound, threaded	122		
Siamese connections	174	PVC	122		
sprinkler fittings	177-181	Flashing			
sprinkler heads	172	pipe	167		
sprinkler pipe	176-177	roof	123, 153, 158		
steel pipe nipples	182	Flat panel water heater	323		
switches	172	Flexible connections, ductwork	...343		
valves	171	Flexible fiberglass duct	396		
Fire pumps	174	Flexible pipe connectors	124		
Firebox boilers	187	Floor drains	168		
Fire-rated doors	121	estimating	435		
Firetube boilers	186-187	Floor sinks	30, 168		
Fittings		estimating	435		
ductwork	359	Flues, water heater	21		
roll grooved	89	Foot valve	314		

Schedule 40 steel, threaded .229-230	Schedule 40 steel, welded222	High rise offices, HVAC estimates . .437
Schedule 40 steel, welded219	Schedule 80 steel, threaded254	Holding tank415-416
Schedule 80 steel, threaded251	Schedule 80 steel, welded246	Hood, duct kit327
Schedule 80 steel, welded242	Schedule 160 steel265	Hooks, pipe125
Schedule 160 steel, flanged .262-263	Type K copper, brazed42	Hose bibbs133
Type K copper, brazed39	Type K copper, soldered52	Hot and cold water connections . . .26
Type K copper, soldered49	Type L copper, brazed61	Hot water boilers
Type L copper, brazed58	Type L copper, soldered70	biomass fired319-320
Type L copper, soldered67	Type M copper, brazed79	connections, HVAC190
Type M copper, brazed76	Type M copper, soldered88	gas fired185-187
Type M copper, soldered85	Hangers, pipe124	gas fired, cast iron189
Geothermal	PE-AL115, 118	gas fired, steel188
bore holes317	PEX-AL115, 118	high pressure188
heat pump306-308	steel band124	oil fired187
wells316	Hard water softener22, 23, 24	Hot water reheat coils209
Globe valves	Head adapter, CPVC184	Hot water softener24
pipe and plumbing specialty .130-131	Headers, PEX-AL pipe114	Hot water systems
PVC, Schedule 4096	Heads, sprinkler172	piping214
PVC, Schedule 80106	Heat/cool thermostat405	Schedule 40 steel, cut-grooved . .280
Schedule 10 steel, roll-grooved . .277	Heat exchangers	Schedule 40 steel, roll-grooved . .266
Schedule 40 steel, cut-grooved . .283	demolition429	Type K copper, brazed33
Schedule 40 steel, roll-grooved . .270	HVAC207	Type K copper, soldered43
Schedule 40 steel, threaded . . .230	removal429	Type L copper, brazed53
Schedule 40 steel, welded219	Heat pumps307-311	Type L copper, soldered62
Schedule 80 steel, threaded . . .251	accessories312	Type M copper, brazed71
Schedule 80 steel, welded . .242-243	air to air309	Type M copper, soldered80
Schedule 160 steel, flanged . . .263	demolition428	Hot water tank
Type K copper, brazed39	geothermal306	disconnect433
Type K copper, soldered49	removal428	removal432
Type L copper, brazed58	split system309	Hourly labor costs6
Type L copper, soldered67	supplemental electric heating	How to use this book5
Type M copper, brazed76	coil312	HRV (heat recovery
Type M copper, soldered85	thermostats312	ventilators)291-292
Grease and oil interceptors25	Heat reclaimer204	Hub & spigot C.I. pipe, DWV141
Green sand filter23	Heat recovery203, 205, 301	Humidistat control327
Greywater tank417	Heat recovery systems	HVAC
Grilles	continuous blowdown202	boiler connections190
air balancing403	stack waste199	controls404
removal423	Heat recovery ventilators292	demolition422
return air333	Heat transfer equipment210	HVAC balancing
Ground source heat pump306	Heat-A-Lamp®329	air403
	Heaters	wet404
H	bathroom328	HVAC equipment
Hair and lint interceptors25	biomass fired321	air conditioning units288
Hanger assemblies	ceramic304	air handling equipment331
ABS153	commercial304	air handling units289-290
cast iron, hub & spigot145	gas fired304	boilers185-189
cast iron, no-hub140	infrared304	centrifugal blowers324
copper, DWV, soldered149	infrared bulb328	connections, air handling
polypropylene pipe167	infrared tube304	unit297-298
PVC, DWV157	residential furnaces299	fan coil units208
PVC, Schedule 40100	resistance329	heat exchangers207
PVC, Schedule 80110	unit303	heat transfer equipment210
Schedule 10 steel, roll-grooved . .279	Heat-fused joint pipe,	pumps206
Schedule 40 steel, cut-grooved . .285	polypropylene164	reheat coils209
Schedule 40 steel, roll-grooved . .272	Heating systems287	unit heaters210
Schedule 40 steel, threaded . . .232	estimating435	variable-air volume units337
	residential287	HVAC systems
	Help5	Type K copper, brazed33

Type K copper, soldered	.43
Type L copper, brazed	.53
Type L copper, soldered	.62
Type M copper, brazed	.71
Type M copper, soldered	.80
Hydrant, fire	.175
Hydraulic benders, rental	.420

I	
Indicator post	.175
Indirect waste connections	.26
Indirect water heater	.203
Induced-draft cooling tower	.212
Infrared	
bulb heater	.328
heater	.304
tube heater	.304
Injector	.314
Installation costs, ductwork	.396
Instructing, operating personnel	.421
Instructions for this book	.5
Insulation, pipe	
calcium silicate	.399
elastomeric	.400
fiberglass	.397, 398
Insulation removal	.434
Insurance	.6
Interceptors	.25
Iron filter	.23, 24
accessories	.23
Iron removal	.23
Irrigation systems	
PVC, Schedule 40	.91
PVC, Schedule 80	.101

J	
Jet pump	.313

K	
Kitchen equipment	.25
connections	.26
Kitchen fixtures	
tailpiece connections	.26
trap connections	.26
Kitchen sinks	.29
disconnect	.433

L	
Labor costs	.6
Laboratories, HVAC estimates	.437
Laboratory DWV pipe systems	.164

Laundry sinks	.29
disconnect	.433
Lavatories	.28
estimating	.435
Lead flashing	.123, 153, 158
LEED certification	.185-186, 187-189, .286, 305, 308, 312, 319-320, 322
Letter of intent	.456-457
Libraries, HVAC estimates	.437
Line voltage thermostat	.405
Lined ductwork, installed	.346-347
Low voltage thermostat	.405

M	
Makeup air units	.336
Malleable iron fittings	
150 pound	.214
300 pound	.237
Schedule 10 steel pipe	.274
Schedule 40 steel, roll-grooved	.266
Manganese filters	
green sand	.23
iron	.23
Manhours	.5
Manifolds, PEX-AL pipe	.114
Manufacturing plants, HVAC	
estimates	.437
Markers, pipe and duct	.421
Markets, HVAC estimates	.437
Material costs	.7
Material pricing conditions	.9
Materials, Equipment, and	
Tool form	.10
Maximum working pressures	
Type K copper, brazed	.33
Type K copper, soldered	.43
Type L copper, brazed	.53
Type L copper, soldered	.62
Type M copper, brazed	.71
Type M copper, soldered	.80
Mechanical joint coupling	.139
Mechanical tee, roll grooved,	
Victaulic	.179
Medical buildings, HVAC estimates	.437
MET	.10
worksheet	.14
Miscellaneous tools	
PE-AL pipe	.115, 118
PEX-AL pipe	.115, 118
MJ coupling	.139
Molded stone	
mop sinks	.29
shower basins	.28
Monthly rental, equipment	.420
Mop sink, disconnect	.433
Motels, HVAC estimates	.437
Museums, HVAC estimates	.437

N	
Nail clips	
PE-AL pipe	.115, 118
PEX-AL pipe	.115, 118
Nameplates, equipment	.421
Nipples	
Schedule 40 steel, threaded	.227-229
steel pipe, fire protection	.182
Non-taxable fringe benefits	.6
NPT pump, in-line	.25, 120-121
Nursing homes, HVAC estimates	.437

O	
Office buildings, HVAC estimates	.437
Office trailers, rental	.420
Oil fuel train piping	.205
Old estimates	.12
Open loop heat pump	.307-308
O-rings	
PE-AL pipe	.115, 118
PEX-AL pipe	.115, 118
Overflow drains	.168
estimating	.435
Overhead and profit	.7

P	
Packaged boiler feedwater	
systems	.202
PE-AL pipe	.111-116
adapters	.113
brass fittings	.111
caps	.114, 117
compression brass fittings	.116
couplings	.112-113, 117
crimp rings	.115, 118
crimped brass fittings	.111
ells	.111-112, 116-117
hangers	.115, 118
miscellaneous tools	.115, 118
nail clips	.115, 118
O-rings	.115, 118
tees	.112, 117
valves	.114, 118
PEX-AL pipe	.111-116
adapters	.113
brass fittings	.111
caps	.114, 117
compression brass fittings	.116
couplings	.112-113, 117
crimp rings	.115, 118
crimped brass fittings	.111
ells	.111-112, 116-117
hangers	.115, 118
manifolds	.114
miscellaneous tools	.115, 118

nail clips	115, 118	sump pit	417	Pressure gauges	
O-rings	115, 118	tank	416	dial-type	125
tees	112, 117	Plug dampers, fusible	341	PVC, Schedule 40	100
valves	114, 118	Plugs		PVC, Schedule 80	109
Pipe		cast iron, threaded	181	Schedule 10 steel, roll-grooved	279
connector	123-124	polypropylene pipe	166	Schedule 40 steel, cut-grooved	285
flashing	123, 153, 158, 167	PVC, Schedule 40	95	Schedule 40 steel, roll-grooved	271
hangers	124	PVC, Schedule 80	105	Schedule 40 steel, threaded	232
hooks	125	Schedule 40 steel, threaded	226	Schedule 40 steel, welded	222
markers	421	Schedule 80 steel, threaded	250	Schedule 80 steel, threaded	254
sleeves	125, 153, 158, 167	Plumbing		Schedule 80 steel, welded	245
sleeves, cut-grooved	285	budget estimates	435	Type K copper, brazed	41
Pipe insulation		equipment	26	Type K copper, soldered	52
calcium silicate	399	fixture costs	435	Type L copper, brazed	60
elastomeric	400	fixture rough-in	31-32	Type L copper, soldered	69
fiberglass	397-398, 415	fixtures	32	Type M copper, brazed	78
removal	434	specialties	134	Type M copper, soldered	87
Pipe machines, rental	420	Plumbing fixture		Pressure pump	174
Pipe sizes		disconnect	433	Pressure reducing valves	133
Type K copper, brazed	33	removal	432	Pressure switches	172, 314
Type K copper, soldered	43	Pollution control modules	199	Pressure tank	23-24, 314
Type L copper, brazed	53	Pollution control stack retrofit	319, 321	Pressure/temperature taps	
Type L copper, soldered	62	Polyethylene sewage pit	417	Schedule 10 steel, roll-grooved	279
Type M copper, brazed	71	Polyethylene sump pit	417	Schedule 40 steel, cut-grooved	285
Type M copper, soldered	80	Polyethylene-aluminum pipe	111-116	Schedule 40 steel, roll-grooved	272
Piping		Polypropylene DWV pipe	164	Schedule 40 steel, threaded	232
air handling unit coil	297-298	adapters	166	Schedule 40 steel, welded	222
cast iron	141	bends	164	Schedule 80 steel, threaded	254
class 110 DI, cement lined	411	bolt and gasket sets	167	Schedule 80 steel, welded	245
class 150 cast iron	412	combinations	165	Schedule 160 steel	264
class 153 DI, cement lined	407	couplings	166	Price updates	5
class 153 DI, double cement		fittings	164	Pricing, HVAC systems	435
lined	409	flanges	167	Process systems	
class 2400 or 3000 asbestos		hanger assemblies	167	PVC, Schedule 40	91-92
cement	413	heat-fused joint pipe	164	PVC, Schedule 80	101-102
copper	146	plugs	166	Project summary	12
CPVC sprinkler	183	P-traps	164	Project summary worksheet	15
polypropylene	164	reducers	167	Proposal, preparing	13
PVC	154	riser clamps	167	P-traps	
PVC, DWV	154	tees	165	ABS	151
Schedule 10 steel,		wyes	165-166	cast iron, hub & spigot	142
roll-grooved	273-274	Polyvinyl chloride pipe		cast iron, no-hub	136
Schedule 40 steel, cut-grooved	280	Schedule 40	91	copper, DWV, soldered	147
Schedule 40 steel, roll-grooved	266	Schedule 80	101	polypropylene pipe	164
Schedule 40 steel, threaded	223	Potable water storage tank	416	PVC, DWV	156
Schedule 40 steel, welded	214	Potable water systems		Pulse type boilers	322
Schedule 80 steel, threaded	248	PVC, Schedule 40	91	Pumping unit for boilers	201
Schedule 80 steel, welded	237-238	PVC, Schedule 80	101	Pumps	
Piping, removal	430	Type K copper, brazed	33	boiler	205
Piping specialties	134	Type K copper, soldered	43	centrifugal	206
Piping systems		Type L copper, brazed	53	heat	306-308
chilled water	214	Type L copper, soldered	62	in-line	25
hot water	214	Type M copper, brazed	71	in-line circulating	120-121
recirculating water	246	Type M copper, soldered	80	removal	431
Planter drains	168	Pressfit		submersible	313
Plastic		fittings	234	sump, installation costs	435
sewage pit	417	Type O o-rings	234	well water	313
sprinkler pipe	183	Pressure controller	338	Purchase order	451-452
		Pressure fiberglass tank	24		

<

Residential furnaces	299-300	Schedule, construction	453-455	flanges	269
Residential water heaters	19-20	Schedule 5 carbon steel pipe,		hanger assemblies	272
Resistance heater	329	pressfit	234	horizontal assembly	266
Retail shops, HVAC estimates	437	adapters	236	pressure gauges	271
Retrofit pollution control stack	319-321	couplings	235-236	pressure/temperature taps	272
Return air grilles	333	ells	234-235	reducers	268
Return registers	334	reducing ells	235	reducing tees	268
Riser clamps		reducing tees	236	riser clamps	272
ABS	153	tees	236	strainers	271
cast iron, hub & spigot	145	Schedule 10 carbon steel pipe,		tees	267
cast iron, no-hub	140	roll-grooved	273	thermometers with wells	271
copper, DWV, soldered	149	adapters	275	valves	269-271
pipe and plumbing specialty	125	bolt and gasket sets	279	vertical assembly	266
polypropylene pipe	167	caps	276	Schedule 40 carbon steel pipe,	
PVC, DWV	157	couplings	276	threaded	224
PVC, Schedule 40	100	ells	274	bolt and gasket sets	232
PVC, Schedule 80	110	flanges	276	caps	226
Schedule 10 steel, roll-grooved	279	hanger assemblies	279	companion flanges	232
Schedule 40 steel, cut-grooved	285	horizontal assembly	273	control valves	231-232
Schedule 40 steel, roll-grooved	272	pressure gauges	279	couplings	226
Schedule 40 steel, threaded	233	pressure/temperature taps	279	crosses	225
Schedule 40 steel, welded	222	reducers	275	ells	224
Schedule 80 steel, threaded	254	reducing tees	275	fire protection	180
Schedule 80 steel, welded	246	riser clamps	279	hanger assemblies	232
Schedule 160 steel	265	strainers	278	horizontal assembly	223
Type K copper, brazed	42	tees	274	nipples	227-229
Type K copper, soldered	52	thermometers with wells	279	plugs	226
Type L copper, brazed	61	valves	276-278	pressure gauges	232
Type L copper, soldered	70	vertical assembly	273	pressure/temperature taps	232
Type M copper, brazed	79	Schedule 40		reducers	225
Type M copper, soldered	88	threadolet	134	reducing tees	225
Rolairtrol type air separators	201	weldolet	134	riser clamps	233
Roll-grooved fittings	179	Schedule 40 carbon steel pipe	215	strainers	231
Roll-grooved joint, Schedule 40		Schedule 40 carbon steel pipe,		tees	224
carbon steel	266	cut grooved	280	thermometers with wells	232
Roof		adapters	281	unions	226
drains	168	bolt and gasket sets	284	valves	227, 229-231
exhaust fan	325	caps	282	vertical assembly	223
fans	326	couplings	282	Schedule 40 carbon steel pipe,	
flashing	123, 153, 158	ells	280	welded	214
Roof exhauster	326	flanges	282	bolt and gasket sets	222
Roof top unit, removal	424	hanger assemblies	285	caps	217-218
Rough-ins		pipe sleeves	285	companion flanges	218
commercial fixture	31	pressure gauges	285	ells	215
commercial group	32	pressure/temperature taps	285	pressure gauges	222
residential	32	reducers	282	pressure/hanger assemblies	222
Round galvanized steel ductwork	394	reducing tees	281	pressure/temperature tap	222
Roustabouts, rental	420	riser clamps	285	reducers	217
Run and branch, tees, galvanized		strainers	284	riser clamp	222
steel	365	tees	281	strainers	220-221
		thermometers with wells	285	tees	216
		valves	283-284	thermometers with wells	222
S		Schedule 40 carbon steel pipe,		threadolets	218
Saddle tee, roll grooved, Victaulic	179	roll-grooved	266-267	valves	219-221
Safety, trenching	418	adapters	268	vertical assembly	214
Sandstone, trenching	418	bolt and gasket sets	271	weldolets	218
Sanitary tees		caps	269	Schedule 40 polypropylene pipe	164
cast iron DWV pipe	142	couplings	269	Schedule 40 PVC pipe	91-92
polypropylene pipe	165	ells	267		

Schedule 80	flanges	.262	kitchen	.29
PVC pipe	hanger assemblies	.265	laboratory	.29
threadolet	horizontal assembly	.255	laundry	.29
weldolet	pressure gauges	.264	medical	.29
Schedule 80 carbon steel pipe,	pressure/temperature taps	.264	molded stone	.29
threaded	reducers	.260-261	mop	.29
bolt and gasket sets	riser clamps	.265	removal	.432
caps	tees	.259	slop	.30
couplings	thermometers with wells	.264	stainless steel	.29
crosses	threadolets	.262	Skip loaders, rental	.420
ells	unions	.260	Sleeves	
flanges	valves	.262-264	galvanized steel pipe	.153, 158
hanger assemblies	weldolets	.261	polypropylene pipe	.167
horizontal assembly	Schedule 80 PVC pipe	.102	Slop sink, disconnect	.433
plugs	Scissor-lifts, rental	.420	Slope, trench	.418
pressure gauges	Scotch marine firetube boilers	.186-187	Softener, water	.22
pressure/temperature taps	Self-sticking markers	.421	Software	.338
reducers	Sensor		Solar water heater	.323
reducing tees	CO2	.405	Solder, soft	.33, 43
riser clamps	HVAC controls	.404	Soldered joint fittings	
strainers	Septic tank	.415	Type K copper	.43
tees	Service sinks	.29	Type L copper	.62
thermometers with wells	estimating	.435	Soldered joint pipe	.43, 80
unions	Sewage lift tank	.417	copper, DMV	.146
valves	Sewage tank	.415	Type K copper	.43
vertical assembly	Sewer pipe, PVC bell & spigot	.159	Type L copper	.62
Schedule 80 carbon steel pipe,	Shale, trenching	.418	Type M copper	.80
welded	Shallow well water pump	.313	Solenoid valves	.204
bolt and gasket sets	Sheet metal	.346-347	Solvent-weld joint pipe	
caps	Shoring, trench	.418	PVC, DWV	.154
ells	Shower stall		PVC, Schedule 40	.91
flanges	disconnect	.433	PVC, Schedule 80	.101
hanger assemblies	removal	.432	Specialties, piping and plumbing	.134
horizontal assembly	Showers	.28	Speed controller, fan	.327
pressure gauges	estimating	.435	Spin-ins, plain	.343
pressure/temperature tap	Siamese connection	.174	Spiral crosses, galvanized	
reducers	Silent check valves		steel	.366-368
riser clamps	pipe and plumbing specialty	.129	Spiral duct, galvanized	
strainers	PVC, Schedule 40	.98	steel	.356-357, 366-368
tees	PVC, Schedule 80	.108	Spiral tees, galvanized steel	.363, 365
thermometers with wells	Schedule 10 steel, roll-grooved	.278	Sprinkler fittings	.177-181
threadolets	Schedule 40 steel, cut-grooved	.284	Sprinkler heads	.172
unions	Schedule 40 steel, roll-grooved	.270	Sprinkler systems	
valves	Schedule 40 steel, threaded	.231	black steel pipe	.176-177
vertical assembly	Schedule 40 steel, welded	.220	branch pipe and fittings	.182
weldolets	Schedule 80 steel, threaded	.252	heads	.172
Schedule 160 carbon steel pipe,	Schedule 80 steel, welded	.244	per head costs	.170
plain end	Type K copper, brazed	.40	square foot costs	.170
Schedule 160 carbon steel pipe,	Type K copper, soldered	.50	switches	.172
threaded	Type L copper, brazed	.59	valves	.171
ells	Type L copper, soldered	.68	Square-foot costs, HVAC	.435
horizontal assembly	Type M copper, brazed	.77	Stack waste, heat recovery	.199
tees	Type M copper, soldered	.86	Stainless steel	
unions	Sinks	.28-30	doors	.121
vertical assembly	acrylic	.29	sinks	.29
Schedule 160 carbon steel pipe,	bar	.29	Standard form subcontract	.448
welded	cast iron	.29	Steam boiler connections, HVAC	.190
bolt and gasket sets	countertop	.28	Steam boilers	
caps	disconnect	.433	biomass fired	.320
ells	exam room	.29	connections	.190
			gas fired	.185

Steam heating boilers	189	reducing tees	281	pressure gauges	222
Steam systems, piping	238	riser clamps	285	pressure/temperature tap	222
Steam traps	125, 204	strainers	284	reducers	217
Steel collars	343	tees	281	riser clamp	222
Steel doors	121	thermometers with wells	285	strainers	220-221
Steel ductwork,		valves	283-284	tees	216
galvanized	356-357, 359	Steel pipe, Schedule 40		thermometers	222
fittings	358	roll-grooved	266	threadolets	218
Steel pipe		adapters	268	unions	218
black	176-177	bolt and gasket sets	271	valves	219-221
cooling systems	234	caps	269	weldolets	218
heating systems	234	couplings	269	Steel pipe, Schedule 80	
nipples, threaded	182, 229	ells	267	threaded	247-248
pressfit system	234	flanges	269	ball valves	252
process applications	234	hanger assemblies	272	bolt and gasket sets	253
Steel pipe fittings, Schedule 40		pressure gauges	271	butterfly valves	251-252
steel, roll-grooved	266	pressure/temperature taps	272	caps	250
Steel pipe nipples, threaded	227-229	reducers	268	control valves	253
Steel pipe, Schedule 5 pressfit	234	reducing tees	268	couplings	251
adapters	236	riser clamps	272	crosses	250
couplings	235-236	strainers	271	ells	248
ells	234-235	tees	267	flanges	253
reducing ells	235	thermometers with wells	271	gate valves	251
reducing tees	236	valves	269-271	globe valves	251
tees	236	Steel pipe, Schedule 40		hanger assemblies	254
Steel pipe, Schedule 10		threaded	224	plugs	250
roll-grooved	273-274	ball valves	230	pressure gauges	254
adapters	275	bolt and gasket sets	232	pressure/temperature taps	254
bolt and gasket sets	279	butterfly valves	230	reducers	249
caps	276	caps	226	reducing tees	249
control valves	278	companion flanges	232	riser clamps	254
couplings	276	control valves	231	silent check valves	252
ells	274	couplings	226	strainers	252-253
flanges	276	crosses	225	swing check valves	252
hanger assemblies	279	ells	224	tees	249
horizontal assembly	273	hanger assemblies	232	thermometers with wells	254
pressure gauges	279	horizontal assembly	223	unions	250
pressure/temperature taps	279	nipples	227-229	valves	253
reducers	275	plugs	226	Steel pipe, Schedule 80	
reducing tees	275	pressure gauges	232	welded	237-238
riser clamps	279	pressure/temperature taps	232	bolt and gasket sets	245
strainers	278	reducers	225	butterfly valves	243
tees	274	riser clamps	233	caps	241
thermometers with wells	279	silent check valves	231	control valves	244-245
valves	276-278	strainers	231	ells	238
vertical assembly	273	swing check valves	231	flanges	242
Steel pipe, Schedule 40		tees	224-225	gate valves	242
cut-grooved	280	thermometers with wells	232	globe valves	242-243
adapters	281	unions	226	hanger assemblies	246
bolt and gasket sets	284	valves	229-230, 232	pressure gauges	245
caps	282	vertical assembly	223	pressure/temperature tap	245
couplings	282	Steel pipe, Schedule 40		reducers	240-241
ells	280	welded	214-215	riser clamps	246
flanges	282	bolt and gasket sets	222	silent check valves	244
hanger assemblies	285	caps	217	strainers	244
pipe sleeves	285	control valves	221	swing check valves	243
pressure gauges	285	ells	215	tees	239-240
pressure/temperature taps	285	flanges	218	thermometers with wells	245
reducers	282	hanger assemblies	222	threadolets	242

unions	241	Sump pit	417	shallow burial	415-416
valves	245	Sump pumps, installation costs ..	435	sump	417
weldolets	241	Supermarkets, HVAC estimates ..	437	swimming pool	291
Steel pipe, Schedule 160	256	Supervision expense	6	water	416
bolt and gasket sets	264	Supervision valves		Taxable fringe benefits	6
ells	258	flanged	170	Taxes	6
hanger assemblies	265	grooved	171	Tees	
pressure gauges	264	Supply registers	333	ABS	151-152
pressure/temperature taps	264	Supports, wall bracket	124	cast iron, hub & spigot	142
riser clamps	265	Surplus materials	10	cast iron, no-hub	138-139
thermometers with wells	264	Swimming pool heat recovery		cast iron, threaded	180
Steel pipe, Schedule 160		ventilators	291	class 110 DI, cement lined	411
plain end	256	Swing check valves		class 150 cast iron	412
Steel pipe, Schedule 160		pipe and plumbing specialty ..	127-128	class 153 DI, cement lined	407
threaded	256-260	PVC, Schedule 40	98	class 153 DI, double cement	
ells	257-258	PVC, Schedule 80	108	lined	410
horizontal assembly	255	Schedule 10 steel, roll-grooved ..	277	class 2400 or 3000 asbestos	
tees	259	Schedule 40 steel, cut-grooved ..	283	cement	414
unions	260	Schedule 40 steel, roll-grooved ..	270	copper, DWV, soldered	147
vertical assembly	256	Schedule 40 steel, threaded	231	CPVC sprinkler pipe	183
Steel pipe, Schedule 160 welded ..	256	Schedule 40 steel, welded	220	PE-AL pipe	112, 117
caps	261	Schedule 80 steel, threaded	252	PEX-AL pipe	112, 117
ells	257-258	Schedule 80 steel, welded	243	polypropylene pipe	165
flanges	262	Schedule 160 steel, flanged	263	PVC, DWV	155
horizontal assembly	255	Type K copper, brazed	40	PVC, Schedule 40	93
reducers	260-261	Type K copper, soldered	50	PVC, Schedule 80	103
tees	259	Type L copper, brazed	59	PVC sewer, bell & spigot	162
threadolets	262	Type L copper, soldered	68	roll grooved, Victaulic	178-179
unions	260	Type M copper, brazed	77	Schedule 5 steel, pressfit	236
valves	262-264	Type M copper, soldered	86	Schedule 10 steel, roll-grooved ..	274
vertical assembly	256	Switches, sprinkler system	172	Schedule 40 steel, cut-grooved ..	281
weldolets	261			Schedule 40 steel, roll-grooved ..	267
Steel piping, removal	430			Schedule 40 steel, threaded	224
Storage vans, rental	420			Schedule 40 steel, welded	216
Stores, HVAC estimates	437			Schedule 80 steel, threaded	249
Strainers				Schedule 80 steel, welded	239-240
pipe and plumbing specialty ..	131-132			Schedule 160 steel, threaded	259
PVC, Schedule 40	98-99			Schedule 160 steel, welded	259
PVC, Schedule 80	108			spiral, galvanized steel	360-365
Schedule 10 steel, roll-grooved ..	278			Type K copper, brazed	35-36
Schedule 40 steel, cut-grooved ..	284			Type K copper, soldered	45-46
Schedule 40 steel, roll-grooved ..	271			Type K & L copper, roll grooved ..	89
Schedule 40 steel, threaded	231			Type L copper, brazed	55
Schedule 40 steel, welded	220-221			Type L copper, soldered	64
Schedule 80 steel,				Type M copper, brazed	73
threaded	252-253			Type M copper, soldered	82
Schedule 80 steel, welded	244			with run and branch, galvanized	
Type K copper, brazed	40			steel	365
Type K copper, soldered	51			Terminal box controller	338
Type L copper, brazed	59			Terminal boxes, air balancing	402
Type L copper, soldered	68			Test caps	
Type M copper, brazed	77			ABS DWV	152
Type M copper, soldered	86			copper, DWV, soldered	148
Subcontract				Test plugs, PVC sewer, bell	
change order	450			& spigot	163
forms	447			Test tees, copper, DWV, soldered ..	148
Submersible pump	313			Theaters, HVAC estimates	437
Submittal data	458-459			Thermometers with wells	
Submittal index	460			pipe and plumbing specialty	126
Suction diffusers	120			PVC, Schedule 40	100

PVC, Schedule 80	109	thermometers with wells	41	strainers	68
Schedule 10 steel, roll-grooved	279	unions	38	tees	64
Schedule 40 steel, cut-grooved	285	valves	39-41	thermometers with wells	69
Schedule 40 steel, roll-grooved	271	Type K copper pipe, soldered	43-44	unions	66
Schedule 40 steel, threaded	232	adapters	47-48	valves	67-69
Schedule 40 steel, welded	222	bolt and gasket sets	52	Type M copper pipe, brazed	71-72
Schedule 80 steel, threaded	254	bushings	48	adapters	74
Schedule 80 steel, welded	245	caps	48	bolt and gasket sets	78
Schedule 160 steel	264	companion flanges	51	bushings	75
Type K copper, brazed	41	couplings	49	caps	75
Type K copper, soldered	52	ells	44-45	couplings	75
Type L copper, brazed	60	hanger assemblies	52	ells	72
Type L copper, soldered	69	pressure gauges	52	hanger assemblies	79
Type M copper, brazed	78	pressure/temperature taps	52	pressure gauges	78
Type M copper, soldered	87	reducers	47	pressure/temperature taps	78
Thermostats, heat pump	312	riser clamps	52	reducers	74
Threadolets		strainers	51	riser clamps	79
pipe and plumbing specialty	134	tees	45-46	strainers	77
Schedule 40 steel, welded	218	thermometers with wells	52	tees	73
Schedule 80 steel, welded	242	unions	48	thermometers with wells	78
Schedule 160 steel, welded	262	valves	49-51	unions	75
Tier IV	199	Type K & L copper pipe,		valves	76-78
Timer, fan	327	roll grooved		Type M copper pipe, soldered	80-81
Tin solder	33, 43, 62, 80	coupling	90	adapters	83
Toilet		ells	89	bolt and gasket sets	87
disconnect	433	flange adapter	90	bushings	84
removal	432	reducers	90	caps	84
Tools	115, 118	tees	89	companion flanges	87
Trailers, office, rental	420	valves	90	couplings	84
Transceiver	338	Type L copper pipe, brazed	53-54	ells	81-82
Trap primers, installation costs	435	adapters	56	hanger assemblies	88
Traps with bushing connections	26	bolt and gasket sets	60	pressure gauges	87
Traps, steam	125	bushings	57	pressure/temperature taps	87
Treatment tank	417	cap	57	reducers	83
Triple duty valves	120	companion flanges	60	riser clamps	88
Trucks, rental	420	couplings	57	strainers	86
Tub		ells	54	tees	82
disconnect	433	hanger assemblies	61	thermometers with wells	87
removal	432	pressure gauges	60	unions	84
Tub and shower combinations	28	pressure/temperature taps	61	valves	85-87
Tube-axial fan	325	reducers	56		
Turning vanes	342	riser clamps	61		
Tutorial	5	strainers	59		
Type I and II PVC		tees	55		
pipe	91-92, 101-102	thermometers with wells	60		
Type K copper pipe, brazed	33-34	unions	57		
adapters	37	valves	58-60		
bolt and gasket sets	41	Type L copper pipe, soldered	62-63		
bushings	38	adapters	65		
caps	38	bolt and gasket sets	69		
companion flanges	41	bushings	66		
couplings	38	caps	66		
ells	34	companion flanges	69		
hanger assemblies	42	couplings	66		
pressure gauges	41	ells	63-64		
pressure/temperature taps	42	hanger assemblies	70		
reducers	37	pressure gauges	69		
riser clamps	42	pressure/temperature taps	69		
strainers	40	reducers	65		
tees	35-36	riser clamps	70		

U

U-bolts, galvanized	124
Ultra-violet	
disinfection	25
water treatment	25
Underground piping, PVC	159
Unions	
dielectric	122
PVC, Schedule 40	95
PVC, Schedule 80	105
Schedule 40 steel, threaded	226
Schedule 40 steel, welded	218
Schedule 80 steel, threaded	250
Schedule 80 steel, welded	241
Schedule 160 steel, threaded	260
Schedule 160 steel, welded	260
Type K copper, brazed	38

Type K copper, soldered	48	Schedule 80 steel, threaded	253	Water hammer arresters	133
Type L copper, brazed	57	Schedule 80 steel, welded	245	Water heaters	
Type L copper, soldered	66	Schedule 160 steel, flanged	263	commercial	19-20
Type M copper, brazed	75	solenoid	204	connections	21
Type M copper, soldered	84	solvent weld	97, 107	estimating	435
Unit heaters	210, 303	sprinkler system	171	residential	19-20
connections	210	supervision, flanged	170	solar	323
demolition	428	supervision, grooved	171	tankless	20
gas fired	210	tags	421	tankless indirect	203
hot water	301	triple duty	120	Water meters	
HVAC connections	210	Type K copper, brazed	40	by-pass and connection	
removal	428	Type K copper, soldered	50	assembly	119
steam	302	Type L copper, brazed	60	compound type	119
Upblast ventilation	330	Type L copper, soldered	67-69	turbine type	119
Updates	5	Type M copper, brazed	76-78	Water motor gong	175
Urinals	27	Type M copper, soldered	85-87	Water pump	313
disconnect	433	Vane-axial fan	324	Water softener	22-24
estimating	435	Vans, storage, rental	420	accessories	23
Using this book	5	Variable-air volume		Water softening systems, boiler	198
Utility fan	324	cooling units	337	Water source heat pump	307-308
UV disinfection unit	25	reheat units	337	Water storage tank	416
		Vent systems	435	Water wells, drilling	316
V		cast iron, hub & spigot	141	Watertube boilers	188
Vacuum breakers	120, 204	cast iron, no-hub	141	Weekly rental, equipment	420
atmospheric	120	copper	146	Welding machines, rental	420
hose connection	120	PVC, DWV	154	Weldolets	
Value engineering	9	Ventilation		pipe and plumbing specialty	134
Valves		ductwork	346-347	Schedule 40 steel, welded	218
air admittance	328	exhausters	329	Schedule 80 steel, welded	241
alarm	171	fans	326-327	Schedule 160 steel, welded	261
check, flanged	171	Ventilator, heat recovery	301	Wells	
check, grooved	171	Vents, air	121	drilling	316
control	221	Verantis	199	geothermal	316
double check detector	171	Victaulic roll-grooved fittings	177-179	pipe	314
dry	171			water pump	313
fire protection	171	W - X - Y - Z		Well-to-well heat pump	307-308
PE-AL pipe	114, 118	Wall exhauster	326	Wheel, heat recovery	301
PEX-AL pipe	114, 118	Wall fan	326	Wireless transceiver	338
pipe and plumbing		Wash fountains, installation costs	435	Wyes	
specialty	126-128, 133	Waste heat controls	203	ABS	151-152
PVC, Schedule 40	96-99	Waste systems		cast iron, hub & spigot	143-144
PVC, Schedule 80	106-109	cast iron, hub & spigot	141	cast iron, no-hub	136-138
PVC, threaded	97, 107	cast iron, no-hub	141	class 150 cast iron	412
PVC, Tru-union	97, 107	copper	146	class 153 DI, cement lined	408
PVC, union type, solvent		PVC	154	class 153 DI, double cement	
weld	98, 107	PVC, DWV	154	lined	410
removal	431	Water closets	27	class 2400 or 3000 asbestos	
Schedule 40 steel,		disconnect	433	cement	414
cut-grooved	283-284	estimating	435	copper, DWV, soldered	147
Schedule 40 steel, roll-grooved	271	Water coil piping	294	polypropylene pipe	165-166
Schedule 40 steel, threaded	232	Water connections, hot and cold	26	PVC, DWV	155
Schedule 40, welded	221	Water cooled chiller connection	211	PVC sewer, bell & spigot	160-162

Practical References for Builders

Basic Plumbing with Illustrations, Revised

This completely revised edition brings this comprehensive manual fully up-to-date with all the latest plumbing codes. It is the journeyman's and apprentice's guide to installing plumbing, piping, and fixtures in residential and light commercial buildings: how to select the right materials, lay out the job and do professional-quality plumbing work, use essential tools and materials, make repairs, maintain plumbing systems, install fixtures, and add to existing systems. Includes extensive study questions at the end of each chapter, and a section with all the correct answers.

384 pages, 8 1/2 x 11, \$44.75

eBook (PDF) also available; \$22.37 at www.craftsman-book.com

Construction Contract Writer



Relying on a "one-size-fits-all" boilerplate construction contract to fit your jobs can be dangerous — almost as dangerous as a handshake agreement. *Construction Contract Writer* lets you draft a contract in minutes that precisely fits your needs and the particular job, and meets both state and federal requirements. You just answer a series of questions — like an interview — to construct a legal contract for each project you take on. Anticipate where disputes could arise and settle them in the contract before they happen. Include the warranty protection you intend, the payment schedule, and create subcontracts from the prime contract by just clicking a box. Includes a feedback button to an attorney on the Craftsman staff to help should you get stumped — *No extra charge*.

\$149.95. Download the *Construction Contract Writer* at <http://www.constructioncontractwriter.com>

CD Estimator

If your computer has *Windows*™ and a CD-ROM drive, CD Estimator puts at your fingertips over 150,000 construction costs for new construction, remodeling, renovation & insurance repair, home improvement, framing & finish carpentry, electrical, concrete & masonry, painting, earthwork and heavy equipment and plumbing & HVAC. Quarterly cost updates are available at no charge on the Internet. You'll also have the *National Estimator* program — a stand-alone estimating program for *Windows*™ that *Remodeling* magazine called a "computer wiz," and *Job Cost Wizard*, a program that lets you export your estimates to QuickBooks Pro for actual job costing. A 60-minute interactive video teaches you how to use this CD-ROM to estimate construction costs. And to top it off, to help you create professional-looking estimates, the disk includes over 40 construction estimating and bidding forms in a format that's perfect for nearly any *Windows*™ word processing or spreadsheet program. **CD Estimator is \$133.50**

Plumber's Handbook Revised

This new edition shows what will and won't pass inspection in drainage, vent, and waste piping, septic tanks, water supply, graywater recycling systems, pools and spas, fire protection, and gas piping systems. All tables, standards, and specifications are completely up-to-date with recent plumbing code changes. Covers common layouts for residential work, how to size piping, select and hang fixtures, practical recommendations, and trade tips. It's the approved reference for the plumbing contractor's exam in many states. Includes an extensive set of multiple-choice questions after each chapter, with answers and explanations in the back of the book, along with a complete sample plumber's exam.

352 pages, 8 1/2 x 11, \$41.50

Building Code Compliance for Contractors & Inspectors

Have you ever failed a construction inspection? Have you ever dealt with an inspector who has his own interpretation of the Code and forces you to comply with it? This new book explains what it takes to pass inspections under the 2009 *International Residential Code*. It includes a Code checklist — with explanations and the Code section number — for every trade, covering some of the most common reasons why inspectors reject residential work. The author uses his 30 years' experience as a building code official to provide you with little-known information on what code officials look for during inspections. **232 pages, 8 1/2 x 11, \$32.50**

eBook (PDF) also available; \$16.25 at www.craftsman-book.com

Plumber's Exam Preparation Guide

Hundreds of questions and answers to help you pass the apprentice, journeyman, or master plumber's exam. Questions are in the style of the actual exam. Gives answers for both the Standard and Uniform plumbing codes. Includes tips on studying for the exam and the best way to prepare yourself for examination day. **320 pages, 8 1/2 x 11, \$34.00**

Uniform Plumbing Code Quick-Card

This 6-page, laminated, fold-out guide provides the basic numbers, flow rates and formulas the plumber needs based on the 2012 *Uniform Plumbing Code* (UPC) and 2012 *International Plumbing Code* (IPC). Like a Cliffs Notes to the Plumbing Code. **6 pages, 8 1/2 x 11, \$7.95**

Plumbing & HVAC Manhour Estimates

Hundreds of tested and proven manhours for installing just about any plumbing and HVAC component you're likely to use in residential, commercial, and industrial work. You'll find manhours for installing piping systems, specialties, fixtures and accessories, ducting systems, and HVAC equipment. If you estimate the price of plumbing, you shouldn't be without the reliable, proven manhours in this unique book.

224 pages, 5 1/2 x 8 1/2, \$28.25

Paper Contracting: The How-To of Construction Management Contracting

Risk, and the headaches that go with it, have always been a major part of any construction project — risk of loss, negative cash flow, construction claims, regulations, excessive changes, disputes, slow pay — sometimes you'll make money, and often you won't. But many contractors today are avoiding almost all of that risk by working under a construction management contract, where they are simply a paid consultant to the owner, running the job, but leaving him the risk. This manual is the how-to of construction management contracting. You'll learn how the process works, how to get started as a CM contractor, what the job entails, how to deal with the issues that come up, when to step back, and how to get the job completed on time and on budget. Includes a link to free downloads of CM contracts legal in each state.

272 pages, 8 1/2 x 11, \$55.50

eBook (PDF) also available; \$27.25 at www.craftsman-book.com

Planning Drain, Waste & Vent Systems

How to design plumbing systems in residential, commercial, and industrial buildings. Covers designing systems that meet code requirements for homes, commercial buildings, private sewage disposal systems, and even mobile home parks. Includes relevant code sections and many illustrations to guide you through what the code requires in designing drainage, waste, and vent systems. **192 pages, 8 1/2 x 11, \$29.95**

Code Check Plumbing & Mechanical, 4th Edition

Save time, money, and potential delays for code violations. Code Check Plumbing & Mechanical is an essential reference guide, providing reliable information on up-to-date residential plumbing and mechanical codes. This handy guide, cross-referenced to the current *International Residential Code*, *Uniform Plumbing Code*, and *Uniform Mechanical Code*, provides answers to hundreds of commonly-asked plumbing questions. This spiral-bound book, in easy-to-use flip chart format, and with durable laminated pages, easily withstands abuse on the jobsite. It's specifically designed for quick on-site reference, and summarizes national code specifications. It includes 116 drawings and 45 tables to answer questions on the plumbing code in force anywhere in the U.S. **49 pages, 8 1/2 x 11, \$24.95**

Construction Forms for Contractors

This practical guide contains 78 practical forms, letters and checklists, guaranteed to help you streamline your office, organize your jobsites, gather and organize records and documents, keep a handle on your subs, reduce estimating errors, administer change orders and lien issues, monitor crew productivity, track your equipment use, and more. Includes accounting forms, change order forms, forms for customers, estimating forms, field work forms, HR forms, lien forms, office forms, bids and proposals, subcontracts, and more. All are also on the CD-ROM included, in Excel spreadsheets, as formatted Rich Text that you can fill out on your computer, and as PDFs. **360 pages, 8 1/2 x 11, \$48.50**

eBook (PDF) also available; \$24.75 at www.craftsman-book.com

National Construction Estimator

Current building costs for residential, commercial, and industrial construction. Estimated prices for every common building material. Provides manhours, recommended crew, and gives the labor cost for installation. Includes a free download of an electronic version of the book with *National Estimator*, a stand-alone *Windows*™ estimating program. An interactive multimedia video that shows how to use the software to compile construction cost estimates is free at www.costbook.com.

672 pages, 8 1/2 x 11, \$87.50. Revised annually

eBook (PDF) also available; \$43.75 at www.craftsman-book.com

Estimating Home Building Costs, Revised

Estimate every phase of residential construction from site costs to the profit margin you include in your bid. Shows how to keep track of man hours and make accurate labor cost estimates for site clearing and excavation, footings, foundations, framing and sheathing finishes, electrical, plumbing, and more. Provides and explains sample cost estimate worksheets with complete instructions for each job phase. This practical guide to estimating home construction costs has been updated with digital Excel estimating forms and worksheets that ensure accurate and complete estimates for your residential projects. Enter your project information on the worksheets and Excel automatically totals each material and labor cost from every stage of construction to a final cost estimate worksheet. Load the enclosed CD-ROM into your computer and create your own estimate as you follow along with the step-by-step techniques in this book.

336 pages, 8 1/2 x 11, \$38.00

eBook (PDF) also available; \$19.00 at www.craftsman-book.com

Insurance Restoration Contracting: Startup to Success

Insurance restoration — the repair of buildings damaged by water, fire, smoke, storms, vandalism and other disasters — is an exciting field of construction that provides lucrative work that's immune to economic downturns. And, with insurance companies funding the repairs, your payment is virtually guaranteed. But this type of work requires special knowledge and equipment, and that's what you'll learn about in this book. It covers fire repairs and smoke damage, water losses and specialized drying methods, mold remediation, content restoration, even damage to mobile and manufactured homes. You'll also find information on equipment needs, training classes, estimating books and software, and how restoration leads to lucrative remodeling jobs. It covers all you need to know to start and succeed as the restoration contractor that both homeowners and insurance companies call on first for the best jobs.

640 pages, 8 1/2 x 11, \$69.00

eBook (PDF) also available; \$34.50 at www.craftsman-book.com



Craftsman Book Company
6058 Corte del Cedro
Carlsbad, CA 92011

Call me,
1-800-829-8123
Fax (760) 438-0398

Name _____

e-mail address (for order tracking and special offers) _____

Company _____

Address _____

City/State/Zip _____ ☐ This is a residence

Total enclosed _____ (In California add 7.5% tax)

*Free Media Mail shipping, within the US,
when your check covers your order in full.*

Contractor's Guide to QuickBooks 2015

QuickBooks 2015 has many new features that simplify a building contractor's bookkeeping work. You'll wonder how you managed without them. To help you make the most of these new features, or to make getting set up with *QuickBooks* almost painless, this user-friendly manual walks you through *QuickBooks*' detailed setup procedure and explains step-by-step how to create a first-rate accounting system. You'll learn in days, rather than weeks, how to use *QuickBooks* to get your contracting business organized, with simple, fast accounting procedures. But setting up *QuickBooks* from scratch can be time-consuming. On the free download included with purchase of the book you'll find a *QuickBooks* file preconfigured for a construction company. Open it, enter your company's data, add info on your suppliers, subs and customers, and you're up and running. The setup's done for you. **288 pages, 8 1/2 x 11, \$68.50**

See checklist for other available editions.

eBook (PDF) also available; \$34.25 at www.craftsman-book.com

eBooks also available for 2006, 2007, 2008, 2009, 2010 and 2012.

Home Building Mistakes & Fixes

This is an encyclopedia of practical fixes for real-world home building and repair problems. There's never an end to "surprises" when you're in the business of building and fixing homes, yet there's little published on how to deal with construction that went wrong - where out-of-square or non-standard or jerry-rigged turns what should be a simple job into a nightmare. This manual describes jaw-dropping building mistakes that actually occurred, from disastrous misunderstandings over property lines, through basement floors leveled with an out-of-level instrument, to a house collapse when a siding crew removed the old siding. You'll learn the pitfalls the painless way, and real-world working solutions for the problems every contractor finds in a home building or repair jobsite. Includes dozens of those "surprises" and the author's step-by-step, clearly illustrated tips, tricks and workarounds for dealing with them.

384 pages, 8 1/2 x 11, \$52.50

eBook (PDF) also available; \$26.25 at www.craftsman-book.com

In A Hurry?

We accept phone orders charged to your

☐ Visa, ☐ MasterCard, ☐ Discover or ☐ American Express

Card# _____

Exp. date _____ Initials _____

Tax Deductible: Treasury regulations make these references tax deductible when used in your work. Save the canceled check or charge card statement as your receipt.

Order online: www.craftsman-book.com

Free on the Internet! Download any of Craftsman's estimating databases for a 30-day free trial! www.craftsman-book.com/downloads

**Download free construction contracts legal for your state at:
www.construction-contract.net**

10-Day Money Back Guarantee

- ☐ 44.75 Basic Plumbing with Illustrations, Revised
- ☐ 32.50 Building Code Compliance for Contractors & Inspectors
- ☐ 133.50 CD Estimator
- ☐ 24.95 Code Check Plumbing & Mechanical, 4th Edition
- ☐ 48.50 Construction Forms for Contractors
- ☐ 68.50 Contractor's Guide to *QuickBooks* 2015
- ☐ 57.00 Contractor's Guide to *QuickBooks Pro* 2010
- ☐ 56.50 Contractor's Guide to *QuickBooks Pro* 2009
- ☐ 54.75 Contractor's Guide to *QuickBooks Pro* 2008
- ☐ 53.00 Contractor's Guide to *QuickBooks Pro* 2007
- ☐ 49.75 Contractor's Guide to *QuickBooks Pro* 2005
- ☐ 48.50 Contractor's Guide to *QuickBooks Pro* 2004

Prices subject to change without notice

- ☐ 38.00 Estimating Home Building Costs, Revised
- ☐ 52.50 Home Building Mistakes & Fixes
- ☐ 69.00 Insurance Restoration Contracting: Startup to Success
- ☐ 87.50 National Construction Estimator w/FREE *Natl Estimator* Download
- ☐ 55.50 Paper Contracting: The How-To of Constr Management Contracting
- ☐ 29.95 Planning Drain, Waste & Vent Systems
- ☐ 34.00 Plumber's Exam Preparation Guide
- ☐ 41.50 Plumber's Handbook Revised
- ☐ 28.25 Plumbing & HVAC Manhour Estimates
- ☐ 7.95 Uniform Plumbing Code Quick-Card
- ☐ 88.25 National Plumbing & HVAC Estimator w/FREE *Natl Estimator* Download
- ☐ FREE Full Color Catalog