




2021 NATIONAL HOME IMPROVEMENT ESTIMATOR

Edited by Ray F. Hicks

Includes inside the back cover:



Inside the back cover of this book you'll find a software download certificate. To access the download, follow the instructions printed there. The download includes the National Estimator, an easy to-use estimating program with all the cost estimates in this book. The software will run on PCs using Windows XP, Vista, 7, 8, or 10 operating systems.

Quarterly price updates on the Web are free and automatic all during 2021. You'll be prompted when it's time to collect the next update. A connection to the Web is required.

Download all of Craftsman's most popular costbooks for one low price with the Craftsman Site License. <http://CraftsmanSiteLicense.com>



- Turn your estimate into a bid.
- Turn your bid into a contract.
- ConstructionContractWriter.com



Craftsman Book Company

6058 Corte del Cedro, Carlsbad, CA 92011

Acknowledgments

Portions of chapters 8, 9 and 15 first appeared in the book *Renovating & Restyling Older Homes* by Lawrence Dworin. Mr. Dworin served as a resource in the development of this manuscript and contributed many valuable insights from his years of experience in the industry. An order form for *Renovating & Restyling Older Homes*, and his other construction reference *Profits in Buying & Renovating Homes* appears on the final pages of this manual.

Looking for other construction reference manuals?

Craftsman has the books to fill your needs. **Call toll-free 1-800-829-8123**
or visit our Web site: <http://www.craftsman-book.com>

Cover design by: *Jennifer Johnson*
Photos: *iStock by Getty Images™*
Graphics by: *Devona Quindoy and Christal Stimpson*
Production Manager: *Christine Pray*
Layout by: *Christine Pray*
Software production: *Emma Campbell*

© 2020 Craftsman Book Company
ISBN 978-1-57218-365-0
Published September 2020 for the year 2021.


Contents

1 Pricing Home Improvement Jobs	5	7 Roofing and Flashing.....	117
This book works two ways	8	Flashing leaks	118
Craft codes and crews.....	15	Roof repairs.....	121
Area modification factors	18	Roofing material.....	122
2 Demolition	27	<i>Cost estimates</i>	
Before you begin	27	Roof repairs	129
<i>Cost estimates</i>		Composition shingles.....	130
Equipment rental	28	Built-up roofing.....	131
Sitework demolition.....	29	Roof patching	134
Building demolition	30	Wood shingle roofing.....	137
Wood framing demolition	33	Slate and tile roofing	139
3 Foundations and Slabs	37	Roof flashing.....	141
Pre-construction checklist.....	38	Gutters and downspouts.....	146
<i>Cost estimates</i>		8 Windows	147
Equipment rental	39	Window repair	149
Concrete flatwork.....	40	Sash repair	151
Concrete finishing.....	49	Counterweighted windows	152
4 Rough Carpentry.....	53	Adding or moving a window	153
Floor beams	53	<i>Cost estimates</i>	
Wood floor repairs.....	56	Window repairs.....	156
Wall framing	57	Vinyl windows	157
Roof repairs.....	58	Aluminum windows.....	161
<i>Cost estimates</i>		Wood windows	163
Framing repairs.....	62	Storm windows.....	166
Framing room additions.....	64	Window accessories.....	166
Subflooring.....	66	Window glazing.....	170
Wall and ceiling changes	70	Skylights	173
Roof framing changes	75	9 Doors	175
5 Insulation and Moisture Control	79	Door repair and replacement	175
Ceiling insulation	79	Adding or moving a door.....	182
Wall and floor insulation.....	80	Hanging a slab door	184
Attic and roof ventilation	83	Door terms	188
<i>Cost estimates</i>		<i>Cost estimates</i>	
Fiberglass insulation	84	Exterior doors	191
Panel insulation	85	Prehung doors.....	197
Vapor barrier.....	87	Screen and storm doors	202
Vents and louvers.....	88	Interior doors	206
Roof ventilators.....	91	Patio doors.....	214
6 Siding and Trim.....	93	Closet doors	218
Vinyl siding installation	96	Garage doors	223
Wood siding installation	97	10 Walls and Ceilings	227
Estimating procedure for siding	104	Drywall installation	228
Masonry fireplaces	104	Wood paneling.....	235
<i>Cost estimates</i>		Removing partitions.....	239
Siding and soffit repairs.....	105	<i>Cost estimates</i>	
Vinyl siding	107	Drywall	242
Wood board siding.....	108	Textured finishes for drywall	244
Texture 1-11 plywood siding.....	111	Drywall bead and tools.....	247
Fiber cement siding	112	Wall paneling	251
Aluminum siding and soffit.....	113	Suspended ceilings	255
Stucco and masonry siding	114	Moldings.....	259
		Partition walls	270

11 Floors and Tile	271	16 Porches and Decks	445
Wood flooring installation	272	Adding a porch.....	446
Ceramic tile installation.....	276	Elevated decks	448
<i>Cost estimates</i>		<i>Cost estimates</i>	
Wood strip and plank flooring	278	Deck lumber.....	452
Laminate plank flooring	283	Alternative deck materials.....	454
Vinyl flooring.....	286	Porch and deck stairs.....	457
Ceramic tile.....	293	Pool replastering.....	459
Natural stone and slate flooring	298	Spa replastering.....	460
Ceramic field wall tile	301	17 Painting and Finishing.....	461
Carpet.....	308	Paint application techniques	464
12 Kitchens.....	309	<i>Cost estimates</i>	
Kitchen cabinet standards.....	312	Labor estimates for painting.....	466
<i>Cost estimates</i>		Stains and finishes	487
Kitchen demolition.....	315	Wood preservatives.....	490
Cabinets and countertops	317	Interior paints.....	492
Cabinet knobs, pulls and hinges	324	Exterior paints.....	494
Sinks and faucets.....	328	18 Earthquake Damage	497
Appliances	339	Types of damage	497
13 Bathrooms	345	What FEMA recommends.....	499
Bathroom additions.....	345	When making alterations	504
<i>Cost estimates</i>		When adding a room	505
Tubs, enclosures and shower stalls	352	Checking for earthquake damage.....	505
Tub and shower faucets	360	Repair of foundations and floor slabs.....	506
Toilets	362	Framing repairs	508
Lavatory sinks.....	367	Cracks in plaster and stucco	509
Vanity cabinets and countertops.....	374	Fireplaces and chimneys.....	510
Bath exhaust fans.....	378	Mechanical, electrical, and plumbing systems.....	511
Medicine cabinets.....	382	<i>Cost estimates</i>	
Bathroom accessories.....	385	Foundation anchors and brackets.....	512
14 Plumbing and HVAC	391	Cripple wall bracing	512
Heating types and considerations	391	Hold-down anchors.....	512
Framing for plumbing and HVAC.....	394	Bracing a water heater	512
<i>Cost estimates</i>		Framing straps and braces	512
Furnace replacement.....	396	Concrete repairs	513
Chimney flue components	399	Straighten a frame wall.....	514
Water heaters	405	Straighten a window opening	514
DWV pipe replacement.....	407	Plaster and stucco repair.....	514
15 Electrical.....	409	19 Water Damage and	
Wiring residences	411	Mold Remediation	515
Adding outlets and switches.....	414	Building Dryout.....	515
<i>Cost estimates</i>		Mold Remediation.....	525
Non-metallic cable.....	417	<i>Cost estimates</i>	
PVC conduit and fittings.....	420	Water extraction	529, 531
EMT conduit and fittings.....	422	Pre-drying	529
Flex conduit and fittings	426	Remove appliances	530
Rigid and IMC conduit and fittings	429	HVAC system cleaning	530
Switches and receptacles.....	434	Carpet removal	531
Distribution panels	436	Drywall repairs	532
Lighting.....	440	Demolition.....	532-534
Smart home electrical mgmt. system.....	444	Cleanup after water extraction	534
		Mold inspection and remediation protocol.....	535
		Containment structure.....	536
		Remove mold by abrading.....	537
		Encapsulation	537
		Personal protection equipment	538
		Air movers, dryers and drying systems.....	539
		Other dryout and mold equipment.....	540
		Index.....	541

Pricing Home Improvement Jobs

1



Estimating home improvement costs requires specialized skills. You can't price home improvement work the same way you'd price new construction. The proportion of labor expense is greater. There's far more risk because there are far more variables and unknowns. An example will make this clear.

Hanging doors in new construction is a 1-2-3 affair. You know ahead of time exactly what's required. You built the wall, installed the frame and know each door will fit right the first time. There won't be any surprises. An experienced estimator can forecast the cost of hanging a door in a new home with a high degree of certainty.

Now let's look at the same task on a home improvement project. First, remember that you may be hanging only one door. There's no chance to improve the production rate on second or later doors. Installing this door is probably different from the last door you installed on a similar project and will be different from your next door installation.

Work starts with removing the old door. That's probably not too hard — once you break through six coats of accumulated paint on the hinges. Let's assume you work carefully and don't damage the casing or trim. The next step is to install a blind Dutchman where the original hinges were attached. If the frame's badly chewed up from years of neglect and abuse, you'll have to remove and replace the entire frame. Don't forget that the building has settled over the years. The frame has probably twisted out of plumb. More time will be needed to shim and level the frame.

Finally the door is installed and swings smoothly. But the job still isn't finished. You have to paint the door to match and will certainly have to haul away the old door and the debris.

Every home improvement cost estimate comes with dozens of chances to make an expensive mistake. Surprises are inevitable and nearly all surprises will add to the cost, not reduce the cost. Estimating new construction is a snap by comparison.

All home improvement has similar problems:

- ❖ No chance for economies of scale (mass production),
- ❖ Difficulty in removing just enough of the old,
- ❖ Work doesn't follow the normal (from the ground, up) sequence of construction,
- ❖ Difficulty adding new materials to deteriorated or nonstandard existing materials,
- ❖ The need to match designs, colors and textures,
- ❖ Covering up for another contractor's mistakes,
- ❖ Struggling to get access to the place where the work is to be done,
- ❖ Protecting adjacent surfaces and pathway to the work area,
- ❖ Initial uncertainty about how much work is needed.

If you're an experienced home improvement contractor, you understand this already. Whether experienced or not, you know full well that accurate pricing is crucial to survival in the home improvement business. Unfortunately, most home improvement specialists have far less experience in pricing their work than in getting the work done. No wonder so many home improvement companies sink into obscurity.

But it doesn't have to be that way.

The chapters that follow explain how to price each type of home improvement work. Emphasis will be on avoiding risk — pricing pitfalls that can turn any home improvement contract into a financial nightmare.

No Price Fits All Jobs

There's no single way to arrive at the correct price for home improvement work. Neither is there a single correct price for most home improvement projects. But there are both good and bad ways to estimate prices and there are good and bad prices for any proposed job. Your task as a home improvement estimator is to produce consistently good estimates on most jobs. If you're already doing that, congratulations. You don't need this book. Return it where you bought it and get a refund. But if you're not, information in the following chapters will make or save you many times what you paid for the book.

It's accepted wisdom among home improvement specialists that salespeople need authority to quote prices when closing a sale. When trying to wrap up a deal, there's no substitute for having current cost information at your fingertips. That's especially true on larger jobs where you've prepared detailed plans and a written estimate. The owner will have questions and suggestions that change the job specs. If you want to close the sale then and there, you'd better know how much to add or subtract for each change the owner wants.

Most home improvement companies authorize salespeople to quote prices from an approved list in a price book. That simplifies the salesperson's job, eliminates most major errors, and saves the owner of the company from approving every item in every estimate. In our opinion, quoting from a price book is the only way to build sales volume in the home improvement business. That means every home improvement contractor needs a good price book.

Of course, the best price book for your company would be based on your actual cost experience — work done by your crews on your jobs with materials from your dealers and installed by your subcontractors. Since every contractor uses different crews, subcontractors and suppliers, every price book should be different. And, of course, prices in the company price book should be revised regularly to reflect current labor and material costs.

Having admitted that there's no substitute for developing your own price book, we'll suggest that you not bother. Most home improvement contractors don't have the time or patience to maintain current installed prices for thousands of repair and

remodeling items. Even if you did, spending hundreds of hours a year keeping a price book current would be a waste of time. Prices for home improvement work are usually negotiated on site. There's little value in keeping a book of exact costs if you have to cut a special deal to close each sale.

Instead, we suggest that you let this manual serve as your company price book. Using the prices in this book (and included software download) will eliminate most of the common estimating mistakes. If your labor costs are higher or if your crews aren't as skilled as most tradesmen, you may have to increase the selling prices listed here to make a reasonable profit. And, of course, sometimes you're going to have a job with costs that exceed what any reasonable estimate could have predicted. This manual isn't a substitute for the exercise of good judgment. That's always your job.

Cost Plus Markup Equals Selling Price

The figures in this manual show both costs to the contractor and a recommended selling price. The difference between your cost and your selling price is your markup. Markup varies widely, far more than either material cost or labor cost. You're the final authority on markup. You decide what markup fits best — based on market conditions, your client, and the profit you feel is reasonable. Once you decide on the "right" markup, it's easy to plug that percentage into the bid, assuming you use National Estimator.

Every construction contractor needs to distinguish between "markup" and "profit." Markup is what you add to estimated labor and material costs (usually called "hard costs") to find the selling price. Profit is what you have left when all bills have been paid. The two are very different. Profit is just the frosting on the cake.

Markup is also different from "margin." Figure 1-1 shows percentages of markup for various levels of hard costs. For example, if your markup on a \$20,000 job is 50 percent, the selling price will be \$30,000. The margin on that job is 33 percent, \$10,000 divided by the selling price of \$30,000. (Note the bottom row in Figure 1-1.) Margin is what's left after hard costs are recovered, and includes profit.

Markup vs. Margin				
Hard Cost	Price at 50% Markup	Price at 70% Markup	Price at 100% Markup	Price at 150% Markup
\$50	\$75	\$85	\$100	\$125
\$100	\$150	\$170	\$200	\$250
\$200	\$300	\$340	\$400	\$500
\$300	\$450	\$510	\$600	\$750
\$400	\$600	\$680	\$800	\$1,000
\$500	\$750	\$850	\$1,000	\$1,250
\$1,000	\$1,500	\$1,700	\$2,000	\$2,500
\$2,000	\$3,000	\$3,400	\$4,000	\$5,000
\$3,000	\$4,500	\$5,100	\$6,000	\$7,500
\$4,000	\$6,000	\$6,800	\$8,000	\$10,000
\$5,000	\$7,500	\$8,500	\$10,000	\$12,500
\$6,000	\$9,000	\$10,200	\$12,000	\$15,000
\$7,000	\$10,500	\$11,900	\$14,000	\$17,500
\$8,000	\$12,000	\$13,600	\$16,000	\$20,000
\$9,000	\$13,500	\$15,300	\$18,000	\$22,500
\$10,000	\$15,000	\$17,000	\$20,000	\$25,000
\$11,000	\$16,500	\$18,700	\$22,000	\$27,500
\$12,000	\$18,000	\$20,600	\$24,000	\$30,000
\$13,000	\$19,500	\$22,100	\$26,000	\$32,500
\$14,000	\$21,000	\$23,800	\$28,000	\$35,000
\$15,000	\$22,500	\$25,500	\$30,000	\$37,500
\$16,000	\$24,000	\$27,200	\$32,000	\$40,000
\$17,000	\$25,500	\$28,900	\$34,000	\$42,500
\$18,000	\$27,000	\$30,600	\$36,000	\$45,000
\$19,000	\$28,500	\$32,300	\$38,000	\$47,500
\$20,000	\$30,000	\$34,000	\$40,000	\$50,000
\$30,000	\$45,000	\$51,000	\$60,000	\$75,000
\$40,000	\$60,000	\$68,000	\$80,000	\$100,000
\$50,000	\$75,000	\$85,000	\$100,000	\$125,000
Hard Cost	33% Margin	41% Margin	50% Margin	60% Margin

Figure 1-1

Markup (based on cost) vs. Margin (based on selling price)

Many successful home improvement contractors find they can stay in business if hard costs are 59 percent of selling price. Hard costs include material expense, subcontract costs and labor (including taxes and insurance). The other 41 percent of selling price (“margin”) compensates the sales staff, covers overhead, supervision and contingency, and should yield a modest profit. From Figure 1-1, you can see that markup on hard costs has to be 70 percent to yield a margin of 41 percent.

To put this formula to work in your home improvement company, add 70 percent to your hard costs to find the selling price. Of course, some jobs need more markup and others can get by on less. A smaller job with more risk done for a demanding client may require greater markup. A larger job done mostly by subcontractors can usually carry a smaller markup.

Home improvement contractors have all the overhead of any business: office rent, telephone, owner’s salary, office salaries, legal and accounting expense, insurance, auto and truck expense, and more. But unlike other contractors, home improvement specialists routinely deal with high risk from both the unknown and the unknowable — at least until work actually begins. Since most of what you didn’t or couldn’t anticipate will inflate your costs, you’re assuming significant risk. That’s why markups for home improvement work have to be higher than for new construction.

Naturally, competition dictates markup. If you’re not getting enough work at 70 percent markup, maybe 70 percent is too much for your area. But remember that you shouldn’t have to bid remodeling work on a level playing field. New construction usually goes to the lowest responsible bidder. A creative salesman who follows the recommendations in this book has an advantage over lowball bidders who rely on price alone to sell their services.

If you have trouble using *National Estimator*, we’ll be glad to help, and we don’t charge you for it.

Free telephone assistance is available from 8 a.m. until 5 p.m. Pacific time Monday through Friday (except holidays). Call 760-438-7828, Ext. 2.

This Book Works Two Ways

Inside the back cover of this book you’ll find a software download certificate. To access the download, follow the instructions printed there. The download includes the *National Estimator*, an easy-to-use estimating program with all the cost estimates in this book.

The software will run on PCs using Windows XP, Vista, 7, 8, or 10 operating systems.



When the *National Estimator* program has been installed, click Help on the menu bar to see a list of topics that will get you up and running. Or, go online to www.craftsman-book.com and click on Support, then Tutorials, to view an interactive tutorial for *National Estimator*.

Estimates That Work Two Ways

This manual is designed for use by both the owner of a home improvement business and by company sales staff. Prices shown in this manual include both hard costs (labor and material) and a recommended selling price (usually based on 70 percent markup). Sales staff will use the selling price.

Figure 1-2 shows the last page of an estimate for the Stillwel room addition, including 70 percent markup. The company estimator created this estimate from a job survey prepared by a sales representative. Figure 1-2 is for company use and was created in the National Estimator program.

Qty	Craft@Hours	Unit	Material	Labor	Equipment	Total
Roll & brush 1 coat of water base undercoat on interior flush doors						
Medium .3 MH/Door, 11.5 Doors/Gal						
3.00	2P@.9000	Ea	5.07	21.36	0.00	26.43
Roll & brush 1st finish coat of water base enamel on interior flush doors						
Medium .25 MH/Door, 12.5 Doors/Gal						
3.00	2P@.7500	Ea	5.39	17.80	0.00	23.18
Roll & brush 1 coat water base undercoat on vanity cabinet						
Medium 93 SF/MH, 250 SF/Gal						
0.90	2P@.9720	CSF	6.99	23.06	0.00	30.05
Roll & brush 1st finish coat of water base enamel on vanity cabinet						
Medium 103 SF/MH, 288 SF/Gal						
0.90	2P@.8740	CSF	7.02	20.70	0.00	27.72
Roll 1st coat of water base stain on rough sawn or resawn wood siding						
Medium 225 SF/MH, 213 SF/Gal						
17.00	2P@7.548	CSF	157.08	178.50	0.00	335.58
Roll 2nd coat of water base stain on rough sawn or resawn wood siding						
Medium 275 SF/MH, 273 SF/Gal						
17.00	2P@6.188	CSF	122.63	146.73	0.00	269.36
**Subtotal: Painting						
	40.7		1,014.54	973.46	0.00	1,988.00
Total Manhours, Material, Labor, and Equipment:						
	456.0		18,641.82	11,675.42	540.29	30,857.53
Total Only (Subcontract) Costs:						
						4,028.33
Subtotal:						34,885.85
70.00% Markup:						24,420.10
Estimate Total:						59,305.95

Figure 1-2

Estimate with a 70 percent markup shown

Figure 1-3 shows the last page of a proposal for the same job. This is what the customer sees. It was created by the Job Cost Wizard program. Both National Estimator and Job Cost Wizard are included in the free download that comes with this book. Notice that the total is nearly the same in both documents, \$59,305.95. Figure 1-2, the estimate, shows 70 percent markup on hard costs. Figure 1-3, the proposal, doesn't show the markup at all. Instead, markup has been distributed proportionately throughout each cost item in the job. Job Cost Wizard does this distribution at the click of a button.

Craftsman Construction		Proposal	
6058 Corte del Cedro Box 6500 Fairfield, GA 30456 856-3806		Date	Estimate #
		8/3/21	494
		Customer	Job
		Bill Stillwel	Room Addition
Description	Qty	Rate	Amount
Roll & brush 1st finish coat of water base enamel on vanity cabinet. Medium 103 SF/MH, 288 SF/Gal			
Material, per CSF	0.90	13.26	11.94
Labor, per CSF	0.90	39.09	35.18
Roll 1st coat of water base stain on rough sawn or resawn wood siding. Medium 225 SF/MH, 213 SF/Gal			
Material, per CSF	17	15.71	267.04
Labor, per CSF	17	17.85	303.45
Roll 2nd coat of water base stain on rough sawn or resawn wood siding. Medium 275 SF/MH, 273 SF/Gal			
Material, per CSF	17	12.26	208.47
Labor, per CSF	17	14.67	249.44
*Painting subtotal			3,379.60
*Project Subtotal			59,305.96
*Project Total			59,305.96

Figure 1-3

Proposal for the same job not showing the markup

Once an estimate is finished in the National Estimator program and saved to computer disk, press **(Ctrl)** on your keyboard and tap the letter **(J)** to convert the estimate into a proposal in Job Cost Wizard. You can't make changes in the Job Cost Wizard screen. But it's easy to toggle back to National Estimator program (press **(Alt)** and tap the **(Tab)** key), make a change, and then press **(Ctrl)-(J)** once again.

Job Cost Wizard offers dozens of choices on what you show and don't show in written proposals. Your bids can be long (full description for everything in the estimate) or short (only a summary of each category). You can show or hide labor and material cost detail. You can show or hide markup and profit.

Once work begins, you'll want to monitor job expenses to be sure actual costs remain consistent with estimated costs. If you use QuickBooks to pay bills and figure payroll, let QuickBooks do the comparisons for you. Job Cost Wizard exports the proposal to QuickBooks, where you can prepare progress invoices and track expenses against estimates.

The National Estimator program lets you change anything in the costbook or even add your own estimated costs. Make the *National Home Improvement Estimator* your collection point for all estimating and pricing information. Anything you add to the costbook shows up in red and can be migrated to later editions of this manual when available. The *National Home Improvement Estimator* starts out as your most useful estimating reference. What you add to the costbook will make it even more valuable.

Job Survey (Scope of Work)

Of course, neither a good price book nor a computer estimating program will solve all of your estimating problems. Computers seldom make mistakes in addition or multiplication. But nothing prevents you from making expensive estimating mistakes on your own. By far the most common estimating mistake will be omitting something essential to the job.

Get in the habit of completing an exhaustive job survey before beginning any estimate for home improvement work. Some of your estimates on a job may be too high. Other estimates on a job may be too low. With any luck, your over-estimates will roughly balance with your under-estimates, leaving the job total about where it should be. But the estimated price for anything omitted from a job survey is always zero. That's a 100 percent miss. It's hard to balance a complete miss with anything. A few of those can create a financial disaster.

Material Costs in This Book

Material costs for each item are listed in the column headed Material. These are neither retail nor wholesale prices. They are estimates of what most contractors who buy in moderate volume will pay suppliers as of mid-2021. Discounts may be available for purchases in larger volumes.

Add Delivery Expense to the material cost for other than local delivery of reasonably large quantities. Cost of delivery varies with the distance from source of supply, method of transportation, and quantity to be delivered. But most material dealers absorb the delivery cost on local delivery (5 to 15 miles) of larger quantities to good customers. Add the expense of job site delivery when it's a significant part of the material cost.

Add Sales Tax when sales tax will be charged to the contractor buying the materials. In some states, contractors have to collect sales tax based on the contract price. No matter what your state (or county) requires, National Estimator can handle the task. Click **Edit** on the National Estimator menu bar. Then click **Sales Tax**.

Waste and Coverage Loss is included in the installed material cost. The cost of many materials per unit after installation is greater than the purchase price for the same unit because of waste, shrinkage or coverage loss during installation. For example, about 120 square feet of nominal 1" x 4" square edge boards will be needed to cover 100 square feet of floor or wall. There's no coverage loss with plywood sheathing, but waste due to cutting and fitting will average about 6 percent.

Costs in the Material column of this book assume normal waste and coverage loss. Small and irregular jobs may require a greater waste allowance. Materials priced without installation (with no labor cost) don't include an allowance for waste and coverage except as noted.

Labor Costs for installing the material or doing the work described are listed in the column headed Labor. The labor cost per unit is the labor cost per hour multiplied by the manhours per unit shown after the @ sign in the Craft@Hrs column. Labor cost includes the basic wage, the employer's contribution to welfare, pension, vacation and apprentice funds, and all tax and insurance charges based on wages.

Supervision Expense to the general contractor isn't included in the labor cost. The cost of supervision and non-productive labor varies widely from job to job. Calculate the cost of supervision and non-productive labor and add this to the estimate.

Payroll Taxes and Insurance are included in the labor cost. See the following section for more on the "contractor's burden."

Manhours per Unit and the Craft performing the work are listed in the Craft@Hrs column. To find the units of work done per worker in an 8-hour day, divide 8 by the manhours per unit. To find the units done by a crew in an 8-hour day, multiply the units per worker per 8-hour day by the number of crew members.

Manhours include all productive labor normally associated with installing the materials described.

This will usually include tasks such as:

- ❖ Unloading and storing construction materials, tools and equipment on site.
- ❖ Moving tools and equipment from a storage area or truck on site at the beginning of the day.
- ❖ Returning tools and equipment to a storage area or truck on site at the end of the day.
- ❖ Normal time lost for work breaks.
- ❖ Planning and discussing the work to be performed.
- ❖ Normal handling, measuring, cutting and fitting.
- ❖ Keeping a record of the time spent and work done.
- ❖ Regular cleanup of construction debris.
- ❖ Infrequent correction or repairs required because of faulty installation.

Adjust the Labor Cost to the job you're figuring when your actual hourly labor cost is known or can be estimated. The labor costs listed in Figure 1-5 will apply within a few percent on many jobs. But labor costs may be much higher or much lower on the job you're estimating.

If the hourly wage rates listed in Figure 1-5 aren't accurate, divide your known or estimated cost per hour by the listed cost per hour. The result is your adjustment for any figure in the Labor column for that craft.

Adjust for Unusual Labor Productivity. Costs in the Labor column are for normal conditions: experienced craftsmen working on reasonably well-planned and managed home improvement projects with fair to good productivity. Labor estimates assume that materials are standard grade, appropriate tools are on hand, work done by other crafts is adequate, layout and installation are relatively uncomplicated, and working conditions don't slow progress.

Working conditions at the jobsite have a major effect on labor cost. Estimating experience and careful analysis can help you predict the effect of most changes in working conditions. Obviously, no single adjustment will apply on all jobs. But the adjustments that follow should help you produce more accurate labor estimates. More than one condition may apply on a job.

Jobsite conditions affect labor costs

- ❖ Add 10% to 15% when working temperatures are below 40 degrees or above 95 degrees.
- ❖ Add 30% to 35% when temperatures are below 20 degrees. Materials and tools are hard to handle. Bulky clothing restricts freedom of movement.
- ❖ Add 15% to 25% for work on a ladder or a scaffold, in a 36" crawl space, in a congested area, or remote from the material storage point.
- ❖ Add 50% for work in an 18" to 36" crawl space. Allow extra time for cleaning out the area before work begins.
- ❖ Add 200% if portions of the crawl space are less than 18". Allow extra time for passing tools and materials. Few contractors bid on work like this.
- ❖ Deduct 10% when the work is in an open area with excellent access and good light.
- ❖ Add 1% for each 10 feet that materials must be lifted above ground level.
- ❖ Add 5% to 50% for tradesmen with below-average skills. Deduct 5% to 25% for highly-motivated, highly-skilled tradesmen.
- ❖ Deduct 10% to 20% when an identical task is repeated many times for several days at the same site.
- ❖ Add 20% to 50% on small jobs where fitting and matching of materials is required, adjacent surfaces have to be protected and the job site is occupied during construction.
- ❖ Add 25% to 50% for work done following a major flood, fire, earthquake, hurricane or tornado while skilled tradesmen are not readily available. Material costs may also be higher after a major disaster.
- ❖ Add 10% to 35% for demanding specs, rigid inspections, unreliable suppliers, a difficult owner or an inexperienced architect.

Use an Area Modification Factor from pages 18 through 26 if your material, hourly labor or equipment costs are unknown and can't be estimated. Here's how: Use the labor and material costs in this manual without modification. Then add or deduct the percentages shown for labor, material and equipment.

Equipment Costs for small tools and expendable supplies (such as saws and tape) are usually considered overhead expense and are covered by your markup. Equipment costs for larger equipment (such as a compressor or backhoe) should be

based on the rental rate for the period needed. Equipment rental costs are included in sections where heavy equipment may be needed.

Labor and Material Costs Change. These costs were compiled in the fall of 2020 and projected to mid-2021 by adding a small percentage. This projection will be accurate for some materials and inaccurate for others. No one can predict material price changes accurately.

How Accurate Are These Figures? They're as accurate as possible considering that the estimators who wrote this book don't know your subcontractors or material suppliers, haven't seen the plans or specifications, don't know what building code applies or where the job is, had to project material costs at least six months into the future, and had no record of how much work the crew that will be assigned to the job can handle.

You wouldn't bid a job under those conditions. And we don't claim that all construction is done at these prices.

Estimating Is an Art, not a science. On many jobs the range between high and low bid will be 20 percent or more. There's room for legitimate disagreement on what the correct costs are, even when complete plans and specifications are available, the date and site are established, and labor and material costs are identical for all bidders.

No cost fits all jobs. Good estimates are custom-made for a particular project and a single contractor through judgment, analysis and experience.

This book isn't a substitute for judgment, analysis and sound estimating practice. It's an *aid* in developing an *informed opinion* of cost. If you're using this book as your sole cost authority for contract bids, you're reading more into these pages than the editors intend.

Use These Figures to compile preliminary estimates, when a "snap" bid is needed to close the deal, and when no actual costs are available. This book will reduce the chance of error or omission on bid estimates, speed "ball park" estimates, and be a good guide when there's no time to get a quote.

Where Do We Get These Figures? From the same sources all professional estimators use: material suppliers, material price services, analysis of plans, specifications, estimates and completed project costs, and both published and unpublished cost studies compiled by both private and government agencies. In addition, we conduct nationwide mail and phone surveys and have the use of several major national estimating databases.

We'll Answer Your Questions about any part of this book and explain how to apply these costs. Free telephone assistance is available from 8 a.m. until 5 p.m. Pacific time Monday through Friday except holidays. Phone 760-438-7828, Ext. 2. We don't accept collect calls and can't estimate the job for you. But if you need clarification on something in this manual, we can help.

Labor Costs and Crews

Throughout this manual you'll see a column headed *Craft@Hrs.* Letters and numbers in this column show our estimates of:

- ❖ Who will do the work (the craft code)
- ❖ An @ symbol which means at
- ❖ How long the work will take (manhours).

For example, in Chapter 4, page 70, you'll find estimates for installing BC plywood wall sheathing by the square foot. The *Craft@Hrs* column opposite 1/2" plywood wall sheathing shows:

B1@.016

That means we estimate the installation rate for crew B1 at 0.016 manhours per square foot. That's the same as 16 manhours per 1,000 square feet.

Figure 1-4 is a table that defines each of the craft codes used in this book. Notice that crew B1 is composed of two craftsmen: one laborer and one carpenter. To install 1,000 square feet of 1/2" BC wall sheathing at 0.016 manhours per square foot, that crew would need 16 manhours (one 8-hour day for a crew of two).

Notice also in the table that the cost per manhour for crew B1 is listed as \$33.85. That's the average for a laborer (listed at \$30.31 per hour) and a carpenter (listed at \$37.38 per hour): \$30.31 plus \$37.38 is \$67.69. Divide by 2 to get \$33.85, the average cost per manhour for crew B1.

In the table, the cost per manhour is the sum of hourly costs of all crew members divided by the number of crew members. That's the average cost per manhour.

Costs in the Labor column in this book are the product of the installation time (in manhours) multiplied by the cost per manhour. For example, in Chapter 4, the labor cost listed for 1/2" BC wall sheathing is \$0.54 per square foot. That's the installation time (0.016 manhours per square foot) multiplied by \$33.85, the average cost per manhour for crew B1.

Figure 1-5 shows hourly labor costs components — base wage, typical fringe benefits, payroll taxes, insurance and the total hourly cost.

The labor costs shown in Column 6 were used to compute the manhour costs for crews and the figures in the Labor column.

Craft Codes		
Craft Code	Cost Per Manhour	Crew Composition
B1	\$33.85	1 laborer, 1 carpenter
B2	\$35.02	1 laborer, 2 carpenters
B3	\$32.67	2 laborers, 1 carpenter
B4	\$37.45	1 laborer, 1 operating engineer, 1 reinforcing iron worker
B5	\$37.06	1 laborer, 1 carpenter, 1 cement mason, 1 operating engineer, 1 reinforcing iron worker
B6	\$32.93	1 laborer, 1 cement mason
B7	\$30.72	1 laborer, 1 truck driver
B8	\$36.51	1 laborer, 1 operating engineer
B9	\$33.06	1 bricklayer, 1 bricklayer's helper
BB	\$37.97	1 bricklayer
BC	\$37.38	1 carpenter
BE	\$40.63	1 electrician
BF	\$34.28	1 floor layer
BG	\$36.13	1 glazier
BH	\$28.15	1 bricklayer's helper
BL	\$30.31	1 laborer
BR	\$35.97	1 lather
BS	\$33.27	1 marblesetter
CF	\$35.55	1 cement mason
CT	\$35.35	1 mosaic & terrazzo worker
D1	\$36.51	1 drywall installer, 1 drywall taper
DI	\$36.47	1 drywall installer
DT	\$36.60	1 drywall taper
HC	\$29.39	1 plasterer helper
OE	\$42.71	1 operating engineer
P1	\$36.89	1 laborer, 1 plumber
PM	\$43.47	1 plumber
PP	\$34.27	1 painter, 1 laborer
PR	\$37.46	1 plasterer
PT	\$38.22	1 painter
R1	\$35.99	1 roofer, 1 laborer
RI	\$39.33	1 reinforcing iron worker
RR	\$41.66	1 roofer
SW	\$42.16	1 sheet metal worker
T1	\$32.99	1 tile layer, 1 laborer
TL	\$35.66	1 tile layer
TR	\$31.13	1 truck driver

Figure 1-4

Craft codes used in this manual

Hourly Labor Cost						
	1	2	3	4	5	6
Craft	Base wage per hour	Taxable fringe benefits (5.56% of base wage)	Insurance and employer taxes (%)	Insurance and employer taxes (\$)	Non-Taxable fringe benefits (4.91% of base wage)	Total hourly cost used in this book
Bricklayer	\$27.76	\$1.54	24.94%	\$7.31	\$1.36	\$37.97
Bricklayer's Helper	20.58	1.14	24.94	5.42	1.01	28.15
Building Laborer	21.00	1.17	32.07	7.11	1.03	30.31
Carpenter	26.11	1.45	30.97	8.54	1.28	37.38
Cement Mason	26.40	1.47	22.89	6.38	1.30	35.55
Drywall Installer	27.02	1.50	23.22	6.62	1.33	36.47
Drywall Taper	27.11	1.51	23.22	6.65	1.33	36.60
Electrician	30.97	1.72	19.65	6.42	1.52	40.63
Floor Layer	25.34	1.41	23.52	6.29	1.24	34.28
Glazier	26.34	1.46	25.34	7.04	1.29	36.13
Lather	27.11	1.51	21.05	6.02	1.33	35.97
Marble Setter	25.06	1.39	21.13	5.59	1.23	33.27
Millwright	26.56	1.48	21.02	5.89	1.30	35.23
Mosaic & Terrazzo Worker	26.62	1.48	21.13	5.94	1.31	35.35
Operating Engineer	31.25	1.74	24.83	8.19	1.53	42.71
Painter	28.02	1.56	24.55	7.26	1.38	38.22
Plasterer	26.74	1.49	28.05	7.92	1.31	37.46
Plasterer Helper	20.98	1.17	28.05	6.21	1.03	29.39
Plumber	32.01	1.78	24.00	8.11	1.57	43.47
Reinforcing Ironworker	28.06	1.56	28.12	8.33	1.38	39.33
Roofer	26.73	1.49	43.00	12.13	1.31	41.66
Sheet Metal Worker	30.66	1.70	25.62	8.29	1.51	42.16
Sprinkler Fitter	31.46	1.75	24.70	8.22	1.55	42.98
Tile Layer	26.86	1.49	21.13	5.99	1.32	35.66
Truck Driver	22.60	1.26	25.81	6.16	1.11	31.13

Figure 1-5*Components of hourly labor costs*

It's important that you understand what's included in the figures in each of the six columns in the table. Here's an explanation:

Column 1, the base wage per hour, is the craftsman's hourly wage. These figures are representative of what many contractors will be paying craftsmen working on home improvement jobs in 2021.

Column 2, taxable fringe benefits, includes vacation pay, sick leave and other taxable benefits. These fringe benefits average 5.56 percent of the base wage for many construction contractors. This benefit is in addition to the base wage.

Column 3, insurance and employer taxes in percent, shows the insurance and tax rate for construction trades. The cost of insurance in this column includes workers' compensation and contractor's casualty and liability coverage. Insurance rates vary widely from state to state and depend on a contractor's loss experience. Note that

taxes and insurance increase the hourly labor cost by 30 to 35 percent for most trades. There is no legal way to avoid these costs.

Column 4, insurance and employer taxes in dollars, shows the hourly cost of taxes and insurance for each construction trade. Insurance and taxes are paid on the costs in both columns 1 and 2.

Column 5, non-taxable fringe benefits, includes employer paid non-taxable benefits such as medical coverage and tax-deferred pension and profit sharing plans. These fringe benefits average 4.91 percent of the base wage for many construction contractors. The employer pays no taxes or insurance on these benefits.

Column 6, the total hourly cost in dollars, is the sum of columns 1, 2, 4 and 5.

These hourly labor costs will apply within a few percent on many jobs. But wage rates may be much higher or lower in the area where you do business. We recommend using your actual labor cost rather than national averages. That's easy with the National Estimator program. When copying and pasting any cost to your estimate, adjust the assumed hourly labor cost to your actual cost. You need do this only once for each trade. And you can make this adjustment at any time. Any change you make is applied to that trade throughout the estimate.

Abbreviations			
4WD	four-wheel drive	EPA	Environmental Protection Agency
ABS	acrylonitrile butadiene styrene	F	Fahrenheit
AC	alternating current	GFCI	ground fault circuit interrupter
ACQ	Alkaline Copper Quat	GRS	galvanized rigid steel
ADA	Americans with Disabilities Act	H	height
ANSI	American Nat. Standards Institute	HOM	higher order mode
APP	atactic polypropylene	HP	horsepower
ASTM	Amer. Society for Testing Materials	HVAC	heating, ventilating & air cond.
AWG	American Wire Gauge	ID	inside diameter
BF	board foot	IMC	intermediate metal conduit
Btr	better	KD	kiln dried
Btu(s)	British thermal unit(s)	KO	knockout
C	Celsius/Centigrade	kW	kilowatt(s)
CF	cubic foot	L	length
CFM	cubic feet per minute	Lb(s)	pound(s)
CLF	100 linear feet	LF	linear foot
CPM	cycles per minute	LS	lump sum
CSF	100 square feet	MBF	1,000 board feet
CY	cubic yard	MDF	medium density fiberboard
d	penny	mm	millimeter(s)
D	depth	Mo	month
DWV	drain, waste & vent	MPH	miles per hour
Ea	each	MSF	1,000 square feet
EMT	electric metallic tube	NEC	National Electrical Code
NEMA	National Electrical Manufacturer's Assoc.	OC	spacing from center to center
OD	outside diameter	OSB	oriented strand board
OSHA	Occupational Safety & Health Admin.	oz.	ounce(s)
PSI	pounds per square inch	PVC	polyvinyl chloride
R	thermal resistance	S4S	surfaced 4 sides
SBS	styrene butadiene styrene	SF	square foot
SFCA	(per) square foot of contact area	Sq	100 square feet
Std	standard	SY	square yard
T	thick	T&G	tongue & groove edge
UL	Underwriter's Laboratory	USDA	United States Dept. of Agriculture
UV	ultraviolet	W	width
X	by or times		

Figure 1-6

Abbreviations used in this manual

Area Modification Factors

Construction costs are higher in some areas than in other areas. Add or deduct the percentages shown on the following pages to adapt the costs in this book to your jobsite. Adjust your cost estimate by the appropriate percentages in this table to find the estimated cost for the site selected. Where 0% is shown, it means no modification is required.

Modification factors are listed by state and province. Areas within each state are listed by the first three digits of the postal zip code. For convenience, one representative city is identified in each three-digit zip or range of zips. Percentages are based on the average of all data points in the table. Factors listed for each state and province are the average of all data in that state or province. Figures for the zips are the average of all information in that area. And figures in the Total column are the weighted average of factors for Labor, Material and Equipment.

The National Estimator program will apply an area modification factor for any five-digit zip you select. Click Utilities. Click Options. Then select the Area Modification Factors tab.

These percentages are composites of many costs and will not necessarily be accurate when estimating the cost of any particular part of a building. But when used to modify costs for an entire structure, they should improve the accuracy of your estimates.

Area Modification Factors

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Alabama Average		-1	-7	0	-4%
Anniston	362	0	-13	-1	-6%
Auburn	368	-1	-8	0	-4%
Bellamy	369	-2	13	-1	5%
Birmingham	350-352	-3	8	-1	2%
Dothan	363	-1	-13	0	-7%
Evergreen	364	-2	-20	-1	-10%
Gadsden	359	-4	-15	-1	-9%
Huntsville	358	1	-3	0	-1%
Jasper	355	-2	-16	-1	-8%
Mobile	365-366	-1	-3	0	-2%
Montgomery	360-361	-1	-3	0	-2%
Scottsboro	357	0	-8	0	-4%
Selma	367	-1	-10	0	-5%
Sheffield	356	-1	1	0	0%
Tuscaloosa	354	1	-9	0	-4%
Alaska Average		14	33	4	23%
Anchorage	995	16	38	5	26%
Fairbanks	997	16	40	5	27%
Juneau	998	18	20	6	19%
Ketchikan	999	3	36	1	18%
King Salmon	996	16	32	5	23%

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Arizona Average		1	-9	0	-4%
Chambers	865	1	-19	0	-8%
Douglas	855	0	-18	0	-8%
Flagstaff	860	2	-17	1	-7%
Kingman	864	1	-11	0	-5%
Mesa	852	1	5	0	3%
Phoenix	850	1	6	0	3%
Prescott	863	3	-16	1	-6%
Show Low	859	2	-18	1	-7%
Tucson	856-857	0	-10	0	-5%
Yuma	853	0	5	0	2%
Arkansas Average		-2	-13	0	-7%
Batesville	725	0	-20	0	-9%
Camden	717	-4	1	-1	-2%
Fayetteville	727	0	-8	0	-4%
Fort Smith	729	-1	-14	0	-7%
Harrison	726	-1	-25	0	-12%
Hope	718	-3	-15	-1	-8%
Hot Springs	719	-2	-25	-1	-13%
Jonesboro	724	-1	-18	0	-9%
Little Rock	720-722	-1	-6	0	-3%
Pine Bluff	716	-4	-19	-1	-11%

Area Modification Factors

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Russellville	728	0	-9	0	-4%
West Memphis	723	-3	-1	-1	-2%
California Average		2	16	1	9%
Alhambra	917-918	3	15	1	8%
Bakersfield	932-933	1	4	0	2%
El Centro	922	1	-1	0	0%
Eureka	955	1	13	0	7%
Fresno	936-938	0	-5	0	-2%
Herlong	961	2	17	1	9%
Inglewood	902-905	3	16	1	9%
Irvine	926-927	3	24	1	13%
Lompoc	934	3	2	1	3%
Long Beach	907-908	3	17	1	9%
Los Angeles	900-901	3	13	1	8%
Marysville	959	1	18	0	9%
Modesto	953	1	2	0	1%
Mojave	935	0	11	0	5%
Novato	949	3	36	1	18%
Oakland	945-947	3	48	1	24%
Orange	928	3	22	1	12%
Oxnard	930	3	1	1	2%
Pasadena	910-912	4	16	1	9%
Rancho Cordova	956-957	2	6	1	4%
Redding	960	1	-8	0	-3%
Richmond	948	2	35	1	17%
Riverside	925	1	7	0	4%
Sacramento	958	1	6	0	3%
Salinas	939	3	-1	1	1%
San Bernardino	923-924	0	4	0	2%
San Diego	919-921	3	13	1	8%
San Francisco	941	3	55	1	27%
San Jose	950-951	3	33	1	17%
San Mateo	943-944	4	40	1	21%
Santa Barbara	931	3	11	1	7%
Santa Rosa	954	3	32	1	16%
Stockton	952	2	7	1	4%
Sunnyvale	940	3	39	1	20%
Van Nuys	913-916	3	14	1	8%
Whittier	906	3	14	1	8%
Colorado Average		2	1	1	1%
Aurora	800-801	3	11	1	7%
Boulder	803-804	3	5	1	4%
Colorado Springs	808-809	2	-3	1	0%
Denver	802	3	13	1	8%
Durango	813	1	-3	0	-1%
Fort Morgan	807	2	-6	1	-2%
Glenwood Springs	816	2	6	1	4%
Grand Junction	814-815	1	-1	0	0%
Greeley	806	3	8	1	5%
Longmont	805	3	1	1	2%
Pagosa Springs	811	0	-9	0	-4%
Pueblo	810	-1	2	0	0%
Salida	812	2	-15	1	-6%

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Connecticut Average		1	16	0	8%
Bridgeport	066	0	13	0	6%
Bristol	060	1	24	0	12%
Fairfield	064	2	17	1	9%
Hartford	061	0	23	0	11%
New Haven	065	-1	15	0	7%
Norwich	063	0	7	0	3%
Stamford	068-069	4	21	1	12%
Waterbury	067	1	12	0	6%
West Hartford	062	1	9	0	5%
Delaware Average		1	3	0	2%
Dover	199	1	-9	0	-4%
Newark	197	2	10	1	6%
Wilmington	198	0	9	0	4%
District of Columbia					
Washington	200-205	2	23	1	12%
Florida Average		0	-10	0	-5%
Altamonte Springs	327	-1	-6	0	-3%
Bradenton	342	0	-12	0	-6%
Brooksville	346	0	-16	0	-7%
Daytona Beach	321	-2	-18	-1	-9%
Fort Lauderdale	333	3	1	1	2%
Fort Myers	339	0	-12	0	-6%
Fort Pierce	349	-2	-20	-1	-10%
Gainesville	326	-1	-18	0	-9%
Jacksonville	322	-1	-3	0	-2%
Lakeland	338	-3	-13	-1	-8%
Melbourne	329	-2	-15	-1	-8%
Miami	330-332	2	-1	1	1%
Naples	341	3	-8	1	-2%
Ocala	344	-3	-23	-1	-12%
Orlando	328	0	2	0	1%
Panama City	324	-2	-21	-1	-11%
Pensacola	325	-1	-17	0	-8%
Saint Augustine	320	-1	-4	0	-2%
Saint Cloud	347	0	-5	0	-2%
St Petersburg	337	0	-12	0	-6%
Tallahassee	323	0	-13	0	-6%
Tampa	335-336	-1	-1	0	-1%
West Palm Beach	334	1	-5	0	-2%
Georgia Average		-1	-7	0	-4%
Albany	317	-2	-10	-1	-6%
Athens	306	0	-11	0	-5%
Atlanta	303	3	23	1	12%
Augusta	308-309	-2	-2	-1	-2%
Buford	305	0	-5	0	-2%
Calhoun	307	-1	-19	0	-9%
Columbus	318-319	-1	-6	0	-3%
Dublin/Fort Valley	310	-3	-13	-1	-8%
Hinesville	313	-2	-11	-1	-6%
Kings Bay	315	-2	-19	-1	-10%

Area Modification Factors

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Macon	312	-2	-7	-1	-4%
Marietta	300-302	1	8	0	4%
Savannah	314	-1	-7	0	-4%
Statesboro	304	-2	-21	-1	-11%
Valdosta	316	-1	-1	0	-1%
Hawaii Average		17	25	6	20%
Aliamanu	968	17	29	6	22%
Ewa	967	17	23	6	20%
Halawa Heights	967	17	23	6	20%
Hilo	967	17	23	6	20%
Honolulu	968	17	29	6	22%
Kailua	968	17	29	6	22%
Lualualei	967	17	23	6	20%
Mililani Town	967	17	23	6	20%
Pearl City	967	17	23	6	20%
Wahiawa	967	17	23	6	20%
Waianae	967	17	23	6	20%
Wailuku (Maui)	967	17	23	6	20%
Idaho Average		0	-19	0	-9%
Boise	837	1	-12	0	-5%
Coeur d'Alene	838	0	-21	0	-10%
Idaho Falls	834	-1	-19	0	-9%
Lewiston	835	0	-24	0	-11%
Meridian	836	0	-19	0	-9%
Pocatello	832	-1	-20	0	-10%
Sun Valley	833	0	-18	0	-8%
Illinois Average		-1	9	0	4%
Arlington Heights	600	1	29	0	14%
Aurora	605	2	28	1	14%
Belleville	622	-2	2	-1	0%
Bloomington	617	1	-4	0	-1%
Carbondale	629	-3	-6	-1	-4%
Carol Stream	601	2	28	1	14%
Centralia	628	-3	-3	-1	-3%
Champaign	618	-1	-3	0	-2%
Chicago	606-608	2	31	1	15%
Decatur	623	-2	-13	-1	-7%
Galesburg	614	-2	-6	-1	-4%
Granite City	620	-3	11	-1	3%
Green River	612	-1	12	0	5%
Joliet	604	0	29	0	13%
Kankakee	609	-2	-4	-1	-3%
Lawrenceville	624	-4	-9	-1	-6%
Oak Park	603	3	35	1	18%
Peoria	615-616	-1	15	0	6%
Peru	613	0	4	0	2%
Quincy	602	3	31	1	16%
Rockford	610-611	-2	8	-1	3%
Springfield	625-627	-2	2	-1	0%
Urbana	619	-3	-6	-1	-4%

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Indiana Average		-2	-3	-1	-3%
Aurora	470	-1	-9	0	-5%
Bloomington	474	1	-6	0	-2%
Columbus	472	0	-9	0	-4%
Elkhart	465	-2	-7	-1	-4%
Evansville	476-477	-2	12	-1	4%
Fort Wayne	467-468	-3	1	-1	-1%
Gary	463-464	-4	23	-1	8%
Indianapolis	460-462	-1	10	0	4%
Jasper	475	-2	-14	-1	-8%
Jeffersonville	471	0	-11	0	-5%
Kokomo	469	-2	-15	-1	-8%
Lafayette	479	-2	-9	-1	-5%
Muncie	473	-4	-13	-1	-8%
South Bend	466	-4	0	-1	-2%
Terre Haute	478	-4	-2	-1	-3%
Iowa Average		-2	-4	-1	-3%
Burlington	526	0	2	0	1%
Carroll	514	-3	-20	-1	-11%
Cedar Falls	506	-1	-7	0	-4%
Cedar Rapids	522-524	0	5	0	2%
Cherokee	510	-2	4	-1	1%
Council Bluffs	515	-2	1	-1	-1%
Creston	508	-3	6	-1	1%
Davenport	527-528	-1	3	0	1%
Decorah	521	-2	-14	-1	-8%
Des Moines	500-503	-2	13	-1	5%
Dubuque	520	-2	-7	-1	-4%
Fort Dodge	505	-2	-5	-1	-3%
Mason City	504	0	-6	0	-3%
Ottumwa	525	0	-13	0	-6%
Sheldon	512	0	-15	0	-7%
Shenandoah	516	-3	-26	-1	-14%
Sioux City	511	-2	14	-1	5%
Spencer	513	-1	-14	0	-7%
Waterloo	507	-4	-1	-1	-3%
Kansas Average		-2	2	-1	0%
Colby	677	-1	-17	0	-8%
Concordia	669	-1	-25	0	-12%
Dodge City	678	-2	-7	-1	-4%
Emporia	668	-3	20	-1	8%
Fort Scott	667	-2	-11	-1	-6%
Hays	676	-2	-26	-1	-13%
Hutchinson	675	-3	-9	-1	-6%
Independence	673	-3	67	-1	29%
Kansas City	660-662	0	10	0	5%
Liberal	679	-2	33	-1	14%
Salina	674	-3	-11	-1	-7%
Topeka	664-666	-3	2	-1	-1%
Wichita	670-672	-2	-6	-1	-4%

Area Modification Factors

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Kentucky Average		-1	-8	0	-4%
Ashland	411-412	-4	-5	-1	-4%
Bowling Green	421	0	-11	0	-5%
Campton	413-414	-1	-23	0	-11%
Covington	410	-1	5	0	2%
Elizabethtown	427	-1	-20	0	-10%
Frankfort	406	1	13	0	7%
Hazard	417-418	-2	-19	-1	-10%
Hopkinsville	422	-2	-9	-1	-5%
Lexington	403-405	1	1	0	1%
London	407-409	-1	-13	0	-7%
Louisville	400-402	-1	5	0	2%
Owensboro	423	-2	-6	-1	-4%
Paducah	420	-2	2	-1	0%
Pikeville	415-416	-3	-14	-1	-8%
Somerset	425-426	0	-23	0	-11%
White Plains	424	-3	-6	-1	-4%

Louisiana Average		-1	7	-1	2%
Alexandria	713-714	-3	13	-1	4%
Baton Rouge	707-708	0	21	0	10%
Houma	703	-2	11	-1	4%
Lafayette	705	0	18	0	8%
Lake Charles	706	-2	30	-1	13%
Mandeville	704	-1	-5	0	-3%
Minden	710	-2	-8	-1	-5%
Monroe	712	-2	-14	-1	-8%
New Orleans	700-701	0	5	0	2%
Shreveport	711	-2	-6	-1	-4%

Maine Average		0	-10	0	-5%
Auburn	042	-1	-7	0	-4%
Augusta	043	-1	-9	0	-5%
Bangor	044	-1	-11	0	-6%
Bath	045	1	-15	0	-6%
Brunswick	039-040	1	-3	0	-1%
Camden	048	-1	-21	0	-10%
Cutler	046	-1	-15	0	-7%
Dexter	049	-1	-8	0	-4%
Northern Area	047	-2	-16	-1	-8%
Portland	041	2	2	1	2%

Maryland Average		1	3	0	2%
Annapolis	214	4	13	1	8%
Baltimore	210-212	-1	16	0	7%
Bethesda	208-209	3	24	1	13%
Church Hill	216	2	-10	1	-4%
Cumberland	215	-4	-12	-1	-8%
Elkton	219	2	-14	1	-5%
Frederick	217	1	13	0	7%
Laurel	206-207	2	15	1	8%
Salisbury	218	1	-14	0	-6%

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Massachusetts Average		2	23	1	12%
Ayer	015-016	1	11	0	6%
Bedford	017	3	30	1	15%
Boston	021-022	3	77	1	37%
Brockton	023-024	3	41	1	20%
Cape Cod	026	2	6	1	4%
Chicopee	010	1	14	0	7%
Dedham	019	2	36	1	18%
Fitchburg	014	2	21	1	11%
Hingham	020	3	37	1	19%
Lawrence	018	2	28	1	14%
Nantucket	025	3	16	1	9%
New Bedford	027	1	12	0	6%
Northfield	013	2	3	1	2%
Pittsfield	012	1	0	0	1%
Springfield	011	-1	18	0	8%

Michigan Average		-2	3	-1	1%
Battle Creek	490-491	-3	1	-1	-1%
Detroit	481-482	0	15	0	7%
Flint	484-485	-3	-5	-1	-4%
Grand Rapids	493-495	-2	4	-1	1%
Grayling	497	1	-17	0	-7%
Jackson	492	-3	1	-1	-1%
Lansing	488-489	-1	1	0	0%
Marquette	498-499	-1	7	0	3%
Pontiac	483	-3	29	-1	12%
Royal Oak	480	-2	18	-1	7%
Saginaw	486-487	-2	-9	-1	-5%
Traverse City	496	-1	-4	0	-2%

Minnesota Average		0	-1	0	-1%
Bemidji	566	-1	-11	0	-6%
Brainerd	564	0	-6	0	-3%
Duluth	556-558	-2	7	-1	2%
Fergus Falls	565	-1	-20	0	-10%
Magnolia	561	0	-18	0	-8%
Mankato	560	0	-8	0	-4%
Minneapolis	553-555	1	28	0	13%
Rochester	559	0	-3	0	-1%
St Cloud	563	-1	6	0	2%
St Paul	550-551	1	26	0	12%
Thief River Falls	567	0	-5	0	-2%
Willmar	562	-1	-11	0	-6%

Mississippi Average		-2	-11	-1	-6%
Clarksdale	386	-3	-16	-1	-9%
Columbus	397	-1	1	0	0%
Greenville	387	-4	-26	-1	-14%
Greenwood	389	-3	-18	-1	-10%
Gulfport	395	-2	-11	-1	-6%
Jackson	390-392	-3	-2	-1	-3%
Laurel	394	-3	-11	-1	-7%

Area Modification Factors

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
McComb	396	-2	-22	-1	-11%
Meridian	393	-2	8	-1	3%
Tupelo	388	-1	-13	0	-7%
Missouri Average		-1	-5	0	-3%
Cape Girardeau	637	-2	-8	-1	-5%
Caruthersville	638	-1	-15	0	-7%
Chillicothe	646	-2	-7	-1	-4%
Columbia	652	1	-9	0	-4%
East Lynne	647	-1	10	0	4%
Farmington	636	-3	-15	-1	-8%
Hannibal	634	0	-4	0	-2%
Independence	640	-1	13	0	5%
Jefferson City	650-651	1	-11	0	-5%
Joplin	648	-2	-10	-1	-6%
Kansas City	641	-2	15	-1	6%
Kirksville	635	0	-33	0	-15%
Knob Noster	653	0	7	0	3%
Lebanon	654-655	-2	-23	-1	-12%
Poplar Bluff	639	-1	-21	0	-10%
Saint Charles	633	1	2	0	1%
Saint Joseph	644-645	-3	2	-1	-1%
Springfield	656-658	-2	-15	-1	-8%
St Louis	630-631	-2	20	-1	8%
Montana Average		0	-7	0	-3%
Billings	590-591	0	-4	0	-2%
Butte	597	1	-7	0	-3%
Fairview	592	-1	27	0	12%
Great Falls	594	-1	-11	0	-6%
Havre	595	-1	-19	0	-9%
Helena	596	0	-4	0	-2%
Kalispell	599	1	-15	0	-6%
Miles City	593	-1	-15	0	-7%
Missoula	598	1	-14	0	-6%
Nebraska Average		-1	-17	0	-8%
Alliance	693	-1	-21	0	-10%
Columbus	686	-1	-15	0	-7%
Grand Island	688	0	-18	0	-8%
Hastings	689	0	-20	0	-9%
Lincoln	683-685	0	-9	0	-4%
McCook	690	1	-21	0	-9%
Norfolk	687	-3	-19	-1	-10%
North Platte	691	0	-14	0	-6%
Omaha	680-681	-1	1	0	0%
Valentine	692	-2	-31	-1	-15%
Nevada Average		2	0	1	1%
Carson City	897	2	-12	1	-4%
Elko	898	1	19	0	9%
Ely	893	2	-8	1	-3%
Fallon	894	2	-2	1	0%
Las Vegas	889-891	2	5	1	3%
Reno	895	2	-4	1	-1%

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
New Hampshire Average		1	-4	0	-1%
Charlestown	036	1	-11	0	-5%
Concord	034	1	-7	0	-3%
Dover	038	1	1	0	1%
Lebanon	037	2	-8	1	-3%
Littleton	035	-1	-12	0	-6%
Manchester	032-033	0	4	0	2%
New Boston	030-031	1	5	0	3%
New Jersey Average		1	20	0	9%
Atlantic City	080-084	-2	12	-1	4%
Brick	087	2	2	1	2%
Dover	078	1	19	0	9%
Edison	088-089	1	28	0	13%
Hackensack	076	3	18	1	10%
Monmouth	077	3	22	1	12%
Newark	071-073	1	23	0	11%
Passaic	070	2	23	1	12%
Paterson	074-075	2	13	1	7%
Princeton	085	-2	23	-1	10%
Summit	079	3	32	1	16%
Trenton	086	-3	19	-1	7%
New Mexico Average		0	-17	0	-8%
Alamogordo	883	-1	-22	0	-11%
Albuquerque	870-871	2	-8	1	-3%
Clovis	881	-2	-22	-1	-11%
Farmington	874	2	-4	1	-1%
Fort Sumner	882	-3	0	-1	-2%
Gallup	873	1	-17	0	-7%
Holman	877	2	-24	1	-10%
Las Cruces	880	-1	-17	0	-8%
Santa Fe	875	3	-20	1	-8%
Socorro	878	1	-32	0	-14%
Truth or Consequences	879	-2	-15	-1	-8%
Tucumcari	884	-1	-17	0	-8%
New York Average		0	13	0	6%
Albany	120-123	-1	16	0	7%
Amityville	117	2	18	1	9%
Batavia	140	-3	5	-1	1%
Binghamton	137-139	-3	0	-1	-2%
Bronx	104	2	19	1	10%
Brooklyn	112	3	12	1	7%
Buffalo	142	-4	7	-1	1%
Elmira	149	-4	-1	-1	-3%
Flushing	113	3	30	1	15%
Garden City	115	3	29	1	15%
Hicksville	118	3	27	1	14%
Ithaca	148	-4	-6	-1	-5%
Jamaica	114	3	27	1	14%
Jamestown	147	-4	-11	-1	-7%
Kingston	124	0	-8	0	-4%
Long Island	111	3	62	1	30%

Area Modification Factors

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Montauk	119	1	15	0	7%
New York (Manhattan)	100-102	3	64	1	31%
New York City	100-102	3	64	1	31%
Newcomb	128	-1	2	0	0%
Niagara Falls	143	-4	-8	-1	-6%
Plattsburgh	129	1	-3	0	-1%
Poughkeepsie	125-126	1	2	0	1%
Queens	110	4	33	1	17%
Rochester	144-146	-3	8	-1	2%
Rockaway	116	3	18	1	10%
Rome	133-134	-3	-6	-1	-4%
Staten Island	103	3	15	1	8%
Stewart	127	-1	-9	0	-5%
Syracuse	130-132	-3	7	-1	2%
Tonawanda	141	-4	2	-1	-1%
Utica	135	-4	-8	-1	-6%
Watertown	136	-2	0	-1	-1%
West Point	109	1	11	0	6%
White Plains	105-108	3	27	1	14%

North Carolina Average					
Asheville	287-289	1	-16	0	-7%
Charlotte	280-282	1	15	0	7%
Durham	277	2	-3	1	0%
Elizabeth City	279	1	-18	0	-8%
Fayetteville	283	-1	-12	0	-6%
Goldsboro	275	1	-2	0	0%
Greensboro	274	1	-7	0	-3%
Hickory	286	-1	-17	0	-8%
Kinston	285	-1	-19	0	-9%
Raleigh	276	3	2	1	3%
Rocky Mount	278	-1	-14	0	-7%
Wilmington	284	1	-14	0	-6%
Winston-Salem	270-273	0	-10	0	-5%

North Dakota Average					
Bismarck	585	0	6	0	3%
Dickinson	586	-1	34	0	15%
Fargo	580-581	0	1	0	0%
Grand Forks	582	0	-3	0	-1%
Jamestown	584	-1	-7	0	-4%
Minot	587	-1	21	0	9%
Nekoma	583	-1	-20	0	-10%
Williston	588	-1	47	0	21%

Ohio Average					
Akron	442-443	-2	4	-1	1%
Canton	446-447	-2	-3	-1	-2%
Chillicothe	456	-2	-3	-1	-2%
Cincinnati	450-452	-1	7	0	3%
Cleveland	440-441	-3	11	-1	3%
Columbus	432	0	11	0	5%
Dayton	453-455	-3	6	-1	1%

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Lima	458	-3	-8	-1	-5%
Marietta	457	-2	-8	-1	-5%
Marion	433	-3	-9	-1	-6%
Newark	430-431	-1	8	0	3%
Sandusky	448-449	-1	-5	0	-3%
Steubenville	439	-3	6	-1	1%
Toledo	434-436	-1	16	0	7%
Warren	444	-4	-6	-1	-5%
Youngstown	445	-5	-1	-2	-3%
Zanesville	437-438	-2	0	-1	-1%

Oklahoma Average					
Adams	739	-2	-20	-1	-10%
Ardmore	734	-3	1	-1	-1%
Clinton	736	-3	-2	-1	-3%
Durant	747	-4	-20	-1	-11%
Enid	737	-4	-4	-1	-4%
Lawton	735	-3	-15	-1	-8%
McAlester	745	-4	-10	-1	-7%
Muskogee	744	-2	-16	-1	-8%
Norman	730	-2	-6	-1	-4%
Oklahoma City	731	-2	-4	-1	-3%
Ponca City	746	-3	1	-1	-1%
Poteau	749	-2	-13	-1	-7%
Pryor	743	-2	-11	-1	-6%
Shawnee	748	-4	-13	-1	-8%
Tulsa	740-741	-1	1	0	0%
Woodward	738	-4	15	-1	5%

Oregon Average					
Adrian	979	-1	-24	0	-12%
Bend	977	1	-11	0	-5%
Eugene	974	2	-9	1	-3%
Grants Pass	975	2	-13	1	-5%
Klamath Falls	976	2	-19	1	-8%
Pendleton	978	0	-7	0	-3%
Portland	970-972	2	19	1	10%
Salem	973	2	-7	1	-2%

Pennsylvania Average					
Allentown	181	-2	8	-1	3%
Altoona	166	-3	-14	-1	-8%
Beaver Springs	178	-3	-8	-1	-5%
Bethlehem	180	-1	10	0	4%
Bradford	167	-4	-13	-1	-8%
Butler	160	-4	1	-1	-2%
Chambersburg	172	-1	-13	0	-7%
Clearfield	168	2	-8	1	-3%
DuBois	158	-2	-19	-1	-10%
East Stroudsburg	183	0	-11	0	-5%
Erie	164-165	-3	-10	-1	-6%
Genesee	169	-4	-5	-1	-4%
Greensburg	156	-4	-5	-1	-4%
Harrisburg	170-171	-2	8	-1	3%

Area Modification Factors

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Hazleton	182	-3	-3	-1	-3%
Johnstown	159	-4	-16	-1	-9%
Kittanning	162	-4	-9	-1	-6%
Lancaster	175-176	-2	1	-1	-1%
Meadville	163	-4	-16	-1	-9%
Montrose	188	-3	-6	-1	-4%
New Castle	161	-4	-1	-1	-3%
Philadelphia	190-191	-3	27	-1	11%
Pittsburgh	152	-4	17	-1	6%
Pottsville	179	-4	-12	-1	-8%
Punxsutawney	157	-4	-1	-1	-3%
Reading	195-196	-4	9	-1	2%
Scranton	184-185	-2	4	-1	1%
Somerset	155	-4	-16	-1	-9%
Southeastern	193	0	18	0	8%
Uniontown	154	-4	-9	-1	-6%
Valley Forge	194	-3	27	-1	11%
Warminster	189	-1	24	0	11%
Warrendale	150-151	-4	16	-1	5%
Washington	153	-4	23	-1	8%
Wilkes Barre	186-187	-3	2	-1	-1%
Williamsport	177	-3	-1	-1	-2%
York	173-174	-3	2	-1	-1%
Rhode Island Average		1	10	0	5%
Bristol	028	1	9	0	5%
Coventry	028	1	9	0	5%
Cranston	029	1	12	0	6%
Davisville	028	1	9	0	5%
Narragansett	028	1	9	0	5%
Newport	028	1	9	0	5%
Providence	029	1	12	0	6%
Warwick	028	1	9	0	5%
South Carolina Average		-1	-2	0	-1%
Aiken	298	0	9	0	4%
Beaufort	299	-1	-4	0	-2%
Charleston	294	-1	0	0	-1%
Columbia	290-292	0	-4	0	-2%
Greenville	296	0	17	0	8%
Myrtle Beach	295	0	-17	0	-8%
Rock Hill	297	-1	-11	0	-6%
Spartanburg	293	-2	-6	-1	-4%
South Dakota Average		-1	-12	0	-6%
Aberdeen	574	-1	-15	0	-7%
Mitchell	573	-1	-11	0	-6%
Mobridge	576	-2	-18	-1	-9%
Pierre	575	-2	-20	-1	-10%
Rapid City	577	-2	-14	-1	-8%

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Sioux Falls	570-571	0	-2	0	-1%
Watertown	572	-1	-7	0	-4%
Tennessee Average		0	-5	0	-2%
Chattanooga	374	-1	5	0	2%
Clarksville	370	1	2	0	1%
Cleveland	373	-1	-1	0	-1%
Columbia	384	-1	-14	0	-7%
Cookeville	385	0	-18	0	-8%
Jackson	383	-1	-3	0	-2%
Kingsport	376	0	-11	0	-5%
Knoxville	377-379	-1	-3	0	-2%
McKenzie	382	-1	-16	0	-8%
Memphis	380-381	-1	3	0	1%
Nashville	371-372	1	4	0	2%
Texas Average		-2	12	-1	5%
Abilene	795-796	-4	0	-1	-2%
Amarillo	790-791	-2	-2	-1	-2%
Arlington	760	-1	4	0	1%
Austin	786-787	1	24	0	12%
Bay City	774	-1	86	0	39%
Beaumont	776-777	-3	43	-1	18%
Brownwood	768	-3	-14	-1	-8%
Bryan	778	0	18	0	8%
Childress	792	-3	-28	-1	-14%
Corpus Christi	783-784	-2	41	-1	18%
Dallas	751-753	-1	15	0	6%
Del Rio	788	-3	4	-1	0%
El Paso	798-799	-3	-12	-1	-7%
Fort Worth	761-762	-1	5	0	2%
Galveston	775	-3	55	-1	24%
Giddings	789	0	13	0	6%
Greenville	754	-3	9	-1	3%
Houston	770-772	-1	58	0	26%
Huntsville	773	-2	59	-1	26%
Longview	756	-2	4	-1	1%
Lubbock	793-794	-3	-11	-1	-7%
Lufkin	759	-3	20	-1	8%
McAllen	785	-3	-9	-1	-6%
Midland	797	-3	25	-1	10%
Palestine	758	-2	7	-1	2%
Plano	750	0	15	0	7%
San Angelo	769	-3	-9	-1	-6%
San Antonio	780-782	-2	19	-1	8%
Texarkana	755	-3	-15	-1	-8%
Tyler	757	-1	-15	0	-7%
Victoria	779	-2	29	-1	12%
Waco	765-767	-3	-2	-1	-3%
Wichita Falls	763	-3	-16	-1	-9%
Woodson	764	-3	-3	-1	-3%

Area Modification Factors

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Utah Average		1	-9	1	-3%
Clearfield	840	2	-3	1	0%
Green River	845	1	-7	0	-3%
Ogden	843-844	0	-19	0	-9%
Provo	846-847	2	-16	1	-6%
Salt Lake City	841	2	-1	1	1%
Vermont Average		1	-11	0	-5%
Albany	058	1	-16	0	-7%
Battleboro	053	1	-9	0	-4%
Beecher Falls	059	1	-19	0	-8%
Bennington	052	-1	-12	0	-6%
Burlington	054	3	5	1	4%
Montpelier	056	2	-10	1	-4%
Rutland	057	-1	-13	0	-7%
Springfield	051	-1	-11	0	-6%
White River Junction	050	1	-12	0	-5%
Virginia Average		0	-8	0	-4%
Abingdon	242	-2	-18	-1	-9%
Alexandria	220-223	3	18	1	10%
Charlottesville	229	1	-15	0	-6%
Chesapeake	233	0	-8	0	-4%
Culpeper	227	1	-12	0	-5%
Farmville	239	-2	-24	-1	-12%
Fredericksburg	224-225	1	-11	0	-5%
Galax	243	-2	-20	-1	-10%
Harrisonburg	228	1	-14	0	-6%
Lynchburg	245	-2	-17	-1	-9%
Norfolk	235-237	0	-4	0	-2%
Petersburg	238	-2	-5	-1	-3%
Radford	241	-1	-18	0	-9%
Reston	201	3	12	1	7%
Richmond	232	-1	5	0	2%
Roanoke	240	-1	-18	0	-9%
Staunton	244	0	-15	0	-7%
Tazewell	246	-3	-10	-1	-6%
Virginia Beach	234	0	-6	0	-3%
Williamsburg	230-231	0	-6	0	-3%
Winchester	226	0	9	0	4%
Washington Average		1	-2	1	0%
Clarkston	994	0	-18	0	-8%
Everett	982	2	2	1	2%
Olympia	985	2	-6	1	-2%
Pasco	993	0	2	0	1%
Seattle	980-981	3	21	1	11%
Spokane	990-992	0	-7	0	-3%
Tacoma	983-984	2	3	1	2%
Vancouver	986	2	4	1	3%

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Wenatchee	988	1	-14	0	-6%
Yakima	989	0	-10	0	-5%
West Virginia Average		-2	-8	-1	-5%
Beckley	258-259	1	-11	0	-5%
Bluefield	247-248	-1	2	0	0%
Charleston	250-253	1	8	0	4%
Clarksburg	263-264	-3	-11	-1	-7%
Fairmont	266	0	-24	0	-11%
Huntington	255-257	-1	-7	0	-4%
Lewisburg	249	-2	-29	-1	-14%
Martinsburg	254	-1	-10	0	-5%
Morgantown	265	-3	-6	-1	-4%
New Martinsville	262	-2	-18	-1	-9%
Parkersburg	261	-3	5	-1	1%
Romney	267	-4	-10	-1	-7%
Sugar Grove	268	-3	-14	-1	-8%
Wheeling	260	-3	14	-1	5%
Wisconsin Average		-1	1	0	0%
Amery	540	0	-3	0	-1%
Beloit	535	0	10	0	5%
Clam Lake	545	-1	-17	0	-8%
Eau Claire	547	-1	-4	0	-2%
Green Bay	541-543	0	6	0	3%
La Crosse	546	-2	3	-1	0%
Ladysmith	548	-2	-1	-1	-2%
Madison	537	2	14	1	8%
Milwaukee	530-534	0	12	0	6%
Oshkosh	549	-1	9	0	4%
Portage	539	0	0	0	0%
Prairie du Chien	538	-2	-12	-1	-7%
Wausau	544	-1	-6	0	-3%
Wyoming Average		0	-1	0	-1%
Casper	826	-1	4	0	1%
Cheyenne/Laramie	820	1	-6	0	-2%
Gillette	827	-1	7	0	3%
Powell	824	0	-7	0	-3%
Rawlins	823	0	17	0	8%
Riverton	825	-1	-12	0	-6%
Rock Springs	829-831	0	2	0	1%
Sheridan	828	1	-8	0	-3%
Wheatland	822	0	-7	0	-3%
UNITED STATES TERRITORIES					
Guam		53	-21	-5	18%
Puerto Rico		2	-47	-5	-21%
VIRGIN ISLANDS (U.S.)					
St. Croix		18	-15	-4	2%
St. John		52	-15	-4	20%
St. Thomas		23	-15	-4	5%

Canadian Area Modification Factors


To find the cost in Canada in Canadian dollars, increase the costs in this book by the appropriate percentage listed below. These figures convert costs to Canadian dollars based on \$1.00 Canadian to \$0.76 U.S.

Location	Mat.	Lab.	Equip.	Total Wtd. Avg.
Alberta Average	26	-1	7	13%
Calgary	26	1	7	14%
Edmonton	25	2	7	14%
Fort McMurray	28	-7	7	12%
British Columbia Average	26	-15	7	7%
Fraser Valley	26	-16	7	6%
Okanagan	27	-18	7	6%
Vancouver	26	-11	7	9%
Manitoba Average	20	-22	5	0%
North Manitoba	20	-22	5	0%
Selkirk	20	-22	5	0%
South Manitoba	20	-22	5	0%
Winnipeg	20	-22	5	0%
New Brunswick	16	-47	3	-13%
Moncton	16	-47	3	-13%

Location	Mat.	Lab.	Equip.	Total Wtd. Avg.
Newfoundland/Labrador	19	-29	4	-3%
Nova Scotia Average	17	-36	4	-8%
Amherst	16	-36	3	-8%
Nova Scotia	17	-35	4	-7%
Sydney	17	-37	4	-8%
Ontario Average	22	-11	5	7%
London	22	-10	5	7%
Thunder Bay	24	-14	6	6%
Toronto	21	-9	5	7%
Quebec Average	19	-24	4	-1%
Montreal	19	-24	4	-1%
Quebec City	19	-24	4	-1%
Saskatchewan Average	23	-18	5	4%
La Ronge	24	-21	6	3%
Prince Albert	22	-20	5	2%
Saskatoon	22	-14	5	5%

Demolition

2



Nearly all home improvement projects require some breaking out and removing of existing materials and disposal of debris. Most will require protection of adjacent surfaces, taking safety precautions (such as setting up barricades), closing off doorways or windows, and normal cleanup. The demolition figures in this chapter include these tasks and will apply on most home improvement jobs that don't involve unusual conditions or complications. Costs will be higher when access to the work is limited, when your crew doesn't have complete control of the construction site, or when debris must be moved longer distances or around obstacles. All figures assume that debris is piled on site or in a bin. Add the cost of hauling to the nearest disposal site and tippage charges, if required. No salvage value is assumed except as noted.

Many of the following chapters include estimated costs to remove the old and replace with new materials of a similar description. For example, you'll find costs for removing shingles and replacing shingles in the roofing chapter. That's appropriate because they're part of the same task and usually performed by the same contractor. The estimates in this chapter are for demolition only and don't consider the cost of replacing what has been removed.

Of all construction tasks, demolition is probably the most difficult to estimate with any certainty. You're never sure what's in a wall to be demolished until the job begins. That's why it's best to exclude from your demolition bid what isn't in your estimate. Use the checklist to the right to help identify potential problems before they develop.

Demolition Checklist

- Can you anticipate any problem getting a demolition permit for this job?
- Is there a noise ordinance which will limit hours of operation or selection of equipment?
- Can the debris box be located close to the work?
- Can a trencher get to the job site?
- Is the site accessible to wheeled equipment?
- Will the debris have to be hand-carried to the roll-off box or gondola?
- Is there a direct route from the demolition site to the debris box?
- Will you need to re-route any plumbing, electrical, phone or gas lines?
- Will you need to remove and replace lawn sprinklers?
- Will you need to cut back or remove any bushes or trees?
- Will you have to remove and re-install a fence or gate?
- Does a septic tank or drain field extend into the site of construction?
- Can (must) materials generated from your project be recycled or salvaged?

	Day	Week	Month
Equipment Rental for Demolition.			
Air compressors, wheel-mounted			
16 CFM, shop type, electric	79.00	184.00	549.00
30 CFM, shop type, electric	84.00	252.00	756.00
80 CFM, shop type, electric	98.00	299.00	893.00
100 CFM, gasoline unit	131.00	391.00	1,100.00
125 CFM, gasoline unit	162.00	488.00	1,460.00
Paving breakers (no bits included) hand-held, pneumatic			
To 40 lb	51.00	163.00	359.00
41 - 55 lb	81.00	288.00	612.00
56 - 70 lb	68.00	234.00	463.00
71 - 90 lb	117.00	276.00	593.00
Paving breakers jackhammer bits			
Moil points, 15" to 18"	6.00	14.00	30.00
Chisels, 3"	7.00	17.00	44.00
Clay spades, 5-1/2"	10.00	23.00	62.00
Asphalt cutters, 5"	8.00	24.00	51.00
Pneumatic chippers, medium weight, 10 lb	35.00	102.00	284.00
Air hose rental, 50 LF section			
5/8" air hose	9.00	18.00	45.00
3/4" air hose	11.00	24.00	57.00
1" air hose	14.00	33.00	69.00
1-1/2" air hose	22.00	66.00	169.00
Dump truck rental rate plus mileage			
3 CY	426.00	1,120.00	2,160.00
5 CY	450.00	1,180.00	3,400.00
Hammer rental			
Electric brute breaker	65.00	260.00	814.00
Gas breaker	89.00	358.00	972.00
Demolition hammer, electric	58.00	323.00	650.00
Roto hammer, 7/8", electric	64.00	256.00	690.00
Roto hammer, 1-1/2", electric	62.00	248.00	600.00
Stump grinder, 9 HP	155.00	620.00	1,660.00
Brush chipper, trailer-mounted 40 HP	292.00	856.00	2,130.00
Chain saw, 18", gasoline	70.00	274.00	791.00
Chop saw, 14", electric	41.00	164.00	478.00
Backhoe/loader, wheel-mounted, diesel or gasoline			
1/2 CY bucket capacity, 55 HP	259.00	796.00	1,840.00
1 CY bucket capacity, 65 HP	240.00	740.00	2,230.00
1-1/4 CY bucket capacity, 75 HP	234.00	787.00	2,180.00
1-1/2 CY bucket capacity, 100 HP	417.00	1,150.00	2,940.00
Wheel loader, front-end load and dump, diesel			
3/4 CY bucket, 4WD, articulated	201.00	685.00	2,070.00
1 CY bucket, 4WD, articulated	354.00	1,030.00	2,890.00
2 CY bucket, 4WD, articulated	555.00	1,630.00	4,320.00

	Craft@Hrs	Unit	Material	Labor	Total	Sell
Sitework Demolition						
Debris disposal and removal. Tipping charges for solid waste disposal at the dump vary from \$30 to \$120 per ton. For planning purposes, estimate waste disposal at \$75 per ton, plus the hauling cost. Call the dump or trash disposal company for actual charges. Typical costs are shown below.						
Dumpster, 3 CY trash bin, emptied weekly	—	Mo	—	—	330.00	—
Dumpster, 40 CY solid waste bin (lumber, drywall, roofing)						
Hauling cost, per load	—	Ea	—	—	230.00	—
Add to per load charge, per ton	—	Ton	—	—	55.00	—
Low-boy, 14 CY solid waste container (asphalt, dirt, masonry, concrete)						
Hauling cost, per load (7 CY maximum load)	—	Ea	—	—	230.00	—
Add to per load charge, per ton	—	Ton	—	—	55.00	—
Recycler fees. Recycling construction waste materials can substantially reduce disposal costs. Recycling charges vary from \$95 to \$120 per load, depending on the type of material and the size of the load. Add the cost of hauling to a recycling facility.						
Greenwaste	—	Ton	—	—	30.00	—
Asphalt, per load (7 CY)	—	Ea	—	—	100.00	—
Concrete, masonry or rock, per load (7 CY)	—	Ea	—	—	100.00	—
Dirt, per load (7 CY)	—	Ea	—	—	100.00	—
Mixed loads, per load (7 CY)	—	Ea	—	—	100.00	—
Bush and tree removal. Includes cutting into manageable pieces with power hand tools and dumping debris in a trash bin on site. Add the cost of power equipment rental, if needed.						
Shrubs and bushes, including stump removal.						
4' high, per each	BL@.750	Ea	—	22.70	22.70	38.60
Tree removal. Costs will vary widely depending on the condition, size, location and accessibility of the tree. Includes cutting into manageable pieces with power hand tools and dumping debris in a trash bin or chipper on site. Does not include stump removal or grinding. Add the cost of power equipment rental, bucket truck, and other specialized equipment if needed. Large shade tree removal may require a crew of 5 or more. Use \$2,000 as a minimum job charge for trees with a 36" diameter trunk and larger.						
8" to 12" diameter trunk	B8@2.50	Ea	—	91.30	91.30	155.00
13" to 18" diameter trunk	B8@3.50	Ea	—	128.00	128.00	218.00
19" to 24" diameter trunk	B8@5.50	Ea	—	201.00	201.00	342.00
25" to 36" diameter trunk	B8@7.00	Ea	—	256.00	256.00	435.00
Stump grinding, using a 9 HP wheel-mounted stump grinder						
6" to 10" diameter stump	B8@.800	Ea	—	29.20	29.20	49.60
11" to 14" diameter stump	B8@1.04	Ea	—	38.00	38.00	64.60
15" to 18" diameter stump	B8@1.30	Ea	—	47.50	47.50	80.80
19" to 24" diameter stump	B8@1.50	Ea	—	54.80	54.80	93.20
Fencing demolition. Remove chain link fence and cemented posts for disposal. These figures assume fencing is removed by cutting ties at posts and rails and rolling the fabric. These rolls can be heavy. A larger crew will be needed on larger jobs.						
To 6' high	BL@.100	LF	—	3.03	3.03	5.15
Remove chain link fence and cemented posts for salvage,						
To 6' high	BL@.120	LF	—	3.64	3.64	6.19
Remove board fence and cemented posts for disposal,						
To 6' high	BL@.100	LF	—	3.03	3.03	5.15

	Craft@Hrs	Unit	Material	Labor	Total	Sell
Building Demolition						
Single-story room demolition. Includes breaking out a concrete or masonry foundation using pneumatic tools, breaking materials into manageable pieces with hand tools and handling debris to a trash bin on site. Includes the cost of erecting a temporary vapor barrier to seal the wall opening in the existing structure. Add the cost of wall patching on the remaining structure. Add the cost of equipment rental.						
Demolish a wood-frame addition built on a concrete slab, including grade beams. Use these figures to estimate the cost of demolishing an attached garage.						
Per square foot of floor area demolished	BL@.100	SF	—	3.03	3.03	5.15
Demolish a wood-frame addition built on a conventional foundation, including wood deck, stairs to grade, and the concrete or concrete block foundation.						
Per square foot of floor area demolished	BL@.120	SF	—	3.64	3.64	6.19
Detached garage demolition. Includes breaking materials into manageable pieces with hand tools and handling debris to a trash bin on site. No slab or foundation demolition included. No salvage of materials assumed.						
Frame garage with wood or aluminum siding						
One-car garage, to 10' wide by 22' deep	BL@16.5	Ea	—	500.00	500.00	850.00
Two-car garage, to 20' wide by 28' deep	BL@23.0	Ea	—	697.00	697.00	1,180.00
Frame garage with stucco siding						
One-car garage to 12' wide by 22' deep	BL@23.5	Ea	—	712.00	712.00	1,210.00
One-car to 16' wide by 22' deep	BL@28.5	Ea	—	864.00	864.00	1,470.00
Two-car garage to 22' wide by 28' deep	BL@42.5	Ea	—	1,290.00	1,290.00	2,190.00
Brick or block garage						
One-car garage to 12' wide by 22' deep	BL@23.0	Ea	—	697.00	697.00	1,180.00
One-car garage to 16' wide by 22' deep	BL@28.0	Ea	—	849.00	849.00	1,440.00
Two-car garage to 20' wide by 22' deep	BL@33.0	Ea	—	1,000.00	1,000.00	1,700.00
Cutting a building. Interior finish stripped back to the structural walls. Building structure to remain. No allowance for salvage value. These costs include loading and hauling up to 6 miles but no dump fees. Costs are per square foot of floor area based on 8' ceiling height. Add the cost of equipment rental. Figures in parentheses show the approximate "loose" volume of materials after demolition.						
Residential building (125 SF per CY)	BL@.100	SF	—	3.03	3.03	5.15
Building Component Demolition. Itemized costs for demolition of building components when building is being remodeled, repaired or rehabilitated and not completely demolished. Costs include protecting adjacent areas and normal clean-up. Costs are to break out the items listed and pile debris on site or in a bin.						
Brick wall demolition. Cost per square foot removed measured on one face. Removed using a pneumatic breaker. Add the cost of equipment rental. Figures in parentheses show the volume before and after demolition and weight of the materials after demolition.						
4" thick walls (60 SF per CY and 36 lbs. per SF)	BL@.061	SF	—	1.85	1.85	3.15
8" thick walls (30 SF per CY and 72 lbs. per SF)	BL@.110	SF	—	3.33	3.33	5.66

	Craft@Hrs	Unit	Material	Labor	Total	Sell
Brick sidewalk demolition. Cost per square foot removed. Add the cost of Bobcat rental. Larger jobs will require a crew of 2 or more. Figures in parentheses show the volume before and after demolition and weight of materials after demolition.						
2-1/2" thick brick on sand base, no mortar bed, removed using hand tools (100 SF per CY and 28 lbs. per SF)	BL@.010	SF	—	.30	.30	.51
Brick pavers up to 4-1/2" thick with mortar bed, removed using a pneumatic breaker (55 SF per CY and 50 lbs. per SF)	BL@.050	SF	—	1.52	1.52	2.58

Concrete masonry wall demolition. Cost per square foot of wall removed measured on one side. Removed using a pneumatic breaker. Add the cost of equipment rental. Figures in parentheses show the volume before and after demolition and weight of materials after demolition.

4" thick walls (60 SF per CY and 19 lbs. per SF)	BL@.066	SF	—	2.00	2.00	3.40
6" thick walls (40 SF per CY and 28 lbs. per SF)	BL@.075	SF	—	2.27	2.27	3.86
8" thick walls (30 SF per CY and 34 lbs. per SF)	BL@.098	SF	—	2.97	2.97	5.05
12" thick walls (20 SF per CY and 46 lbs. per SF)	BL@.140	SF	—	4.24	4.24	7.21
Reinforced or grouted walls add	—	%	—	—	50.0	—

Concrete foundation demolition (footings). Steel reinforced, removed using a pneumatic breaker. Add the cost of equipment rental. Figures in parentheses show the volume before and after demolition.

Cost per CY (.75 CY per CY)	BL@3.96	CY	—	120.00	120.00	204.00
Cost per LF with width and depth as shown						
6" W x 12" D (35 LF per CY)	BL@.075	LF	—	2.27	2.27	3.86
8" W x 12" D (30 LF per CY)	BL@.098	LF	—	2.97	2.97	5.05
8" W x 16" D (20 LF per CY)	BL@.133	LF	—	4.03	4.03	6.85
8" W x 18" D (18 LF per CY)	BL@.147	LF	—	4.46	4.46	7.58
10" W x 12" D (21 LF per CY)	BL@.121	LF	—	3.67	3.67	6.24
10" W x 16" D (16 LF per CY)	BL@.165	LF	—	5.00	5.00	8.50
10" W x 18" D (14 LF per CY)	BL@.185	LF	—	5.61	5.61	9.54
12" W x 12" D (20 LF per CY)	BL@.147	LF	—	4.46	4.46	7.58
12" W x 16" D (13 LF per CY)	BL@.196	LF	—	5.94	5.94	10.10
12" W x 20" D (11 LF per CY)	BL@.245	LF	—	7.43	7.43	12.60
12" W x 24" D (9 LF per CY)	BL@.294	LF	—	8.91	8.91	15.10

Concrete sidewalk demolition. To 4" thick, cost per SF removed. Figures in parentheses show the volume before and after demolition.

Non-reinforced, removed by hand with sledge (60 SF per CY)	BL@.050	SF	—	1.52	1.52	2.58
Reinforced with wire mesh. Mesh cut into manageable pieces, then removed using pneumatic breaker. Add the cost of equipment rental.						
(55 SF per CY)	BL@.060	SF	—	1.82	1.82	3.09

	Craft@Hrs	Unit	Material	Labor	Total	Sell
Porch and deck demolition. Includes breaking materials into manageable pieces with hand tools and handling debris to a trash bin on site.						
Demolish an enclosed wood-frame porch. Includes breaking out the concrete or masonry pier foundation. Per square foot of floor.						
One story	BL@.250	SF	—	7.58	7.58	12.90
Two story	BL@.225	SF	—	6.82	6.82	11.60
Three story	BL@.196	SF	—	5.94	5.94	10.10
Demolish a screened porch built on a concrete slab. Includes demolition of one concrete or wood frame step to grade. Per square foot of floor area.						
Porch and one step (no slab demolition)	BL@.100	SF	—	3.03	3.03	5.15
Demolish a wood deck with railing or kneewall. Includes demolition of the wood deck and up to 7 steps to grade.						
Deck to 150 SF	BL@18.5	Ea	—	561.00	561.00	954.00
Add per SF for deck over 150 SF	BL@.100	SF	—	3.03	3.03	5.15

Concrete slab demolition. Break up and remove concrete slab using a compressor and pneumatic hammer. Includes loosening concrete with a pick and handling debris to a trash bin on site. Costs for demolition of reinforced concrete slab include burning off rebars with an acetylene torch. Add the rental cost of a compressor, pneumatic hammer and a torch, as required. Figures in parentheses show the volume before and after demolition.

4" non-reinforced concrete (60 SF per CY)	BL@.057	SF	—	1.73	1.73	2.94
4" reinforced concrete (60 SF per CY)	BL@.071	SF	—	2.15	2.15	3.66
6" non-reinforced concrete (45 SF per CY)	BL@.083	SF	—	2.52	2.52	4.28
6" reinforced concrete (45 SF per CY)	BL@.103	SF	—	3.12	3.12	5.30
8" non-reinforced concrete (30 SF per CY)	BL@.109	SF	—	3.30	3.30	5.61
8" reinforced concrete (30 SF per CY)	BL@.122	SF	—	3.70	3.70	6.29

Asphalt pavement demolition. Asphaltic concrete (bituminous) 3" thick, removed using a pneumatic spade. Add the cost of equipment rental and dump fees. Figures in parentheses show the volume before and after demolition and weight of debris.

Break up and shovel on to a truck (4 SY per CY and 660 lbs. per SY)	BL@.140	SY	—	4.24	4.24	7.21
--	---------	----	---	------	------	------

Concrete wall demolition. Steel reinforced, removed using a compressor and pneumatic breaker. Add the cost of equipment rental. Figures in parentheses show the volume before and after demolition.

Cost per CY (1.33 CY per CY)	BL@4.76	CY	—	144.00	144.00	245.00
Cost per SF with thickness as shown						
3" wall thickness (80 SF per CY)	BL@.045	SF	—	1.36	1.36	2.31
4" wall thickness (55 SF per CY)	BL@.058	SF	—	1.76	1.76	2.99
5" wall thickness (45 SF per CY)	BL@.075	SF	—	2.27	2.27	3.86
6" wall thickness (40 SF per CY)	BL@.090	SF	—	2.73	2.73	4.64
8" wall thickness (30 SF per CY)	BL@.120	SF	—	3.64	3.64	6.19
10" wall thickness (25 SF per CY)	BL@.147	SF	—	4.46	4.46	7.58
12" wall thickness (20 SF per CY)	BL@.176	SF	—	5.33	5.33	9.06

	Craft@Hrs	Unit	Material	Labor	Total	Sell
Wood Framing Demolition. Typical costs for demolition of wood frame structural components using hand tools. Normal center-to-center spacing (12" thru 24" OC) is assumed. Includes breaking materials into manageable pieces with hand tools and handling debris to a trash bin on site. Costs include removal of Romex cable as necessary, protecting adjacent areas, and normal clean-up. Costs do not include temporary shoring to support structural elements above or adjacent to the work area. (Add for demolition of flooring, roofing, sheathing, etc.) Figures in parentheses give the approximate "loose" volume and weight of the materials after being demolished.						
Ceiling joist demolition. Per in-place SF of ceiling area removed.						
2" x 4" (720 SF per CY and 1.18 lbs. per SF)	BL@.009	SF	—	.27	.27	.46
2" x 6" (410 SF per CY and 1.76 lbs. per SF)	BL@.013	SF	—	.39	.39	.66
2" x 8" (290 SF per CY and 2.34 lbs. per SF)	BL@.018	SF	—	.55	.55	.94
2" x 10" (220 SF per CY and 2.94 lbs. per SF)	BL@.023	SF	—	.70	.70	1.19
2" x 12" (190 SF per CY and 3.52 lbs. per SF)	BL@.027	SF	—	.82	.82	1.39
Floor joist demolition. Per in-place SF of floor area removed.						
2" x 6" (290 SF per CY and 2.04 lbs. per SF)	BL@.016	SF	—	.48	.48	.82
2" x 8" (190 SF per CY and 2.72 lbs. per SF)	BL@.021	SF	—	.64	.64	1.09
2" x 10" (160 SF per CY and 3.42 lbs. per SF)	BL@.026	SF	—	.79	.79	1.34
2" x 12" (120 SF per CY and 4.10 lbs. per SF)	BL@.031	SF	—	.94	.94	1.60
Rafter demolition. Per in-place SF of actual roof area removed.						
2" x 4" (610 SF per CY and 1.42 lbs. per SF)	BL@.011	SF	—	.33	.33	.56
2" x 6" (360 SF per CY and 2.04 lbs. per SF)	BL@.016	SF	—	.48	.48	.82
2" x 8" (270 SF per CY and 2.68 lbs. per SF)	BL@.020	SF	—	.61	.61	1.04
2" x 10" (210 SF per CY and 3.36 lbs. per SF)	BL@.026	SF	—	.79	.79	1.34
2" x 12" (180 SF per CY and 3.94 lbs. per SF)	BL@.030	SF	—	.91	.91	1.55
Stud wall demolition. Interior or exterior, includes allowance for plates and blocking, per in-place SF of wall area removed, measured on one face.						
2" x 3" (430 SF per CY and 1.92 lbs. per SF)	BL@.013	SF	—	.39	.39	.66
2" x 4" (310 SF per CY and 2.58 lbs. per SF)	BL@.017	SF	—	.52	.52	.88
2" x 6" (190 SF per CY and 3.74 lbs. per SF)	BL@.025	SF	—	.76	.76	1.29
Stud wall demolition, salvage condition. Remove wall cover (nailed hardboard or fiberboard) from partition wall and salvage the stud framing. Per linear foot of stud wall.						
2" x 4" x 8", 16" on center	BL@.156	LF	—	4.73	4.73	8.04
Roof cover demolition. Includes breaking materials into manageable pieces with hand tools and handling debris to a trash bin on site. Cost per Sq or "square". (1 square = 100 square feet.) Figures in parentheses show the approximate "loose" volume and weight of materials after being demolished.						
Built-up, 5 ply (2.5 Sq per CY and 250 lbs per Sq)	BL@1.50	Sq	—	45.50	45.50	77.40
Shingles, asphalt, single layer (2.5 Sq per CY and 240 lbs per Sq)	BL@1.33	Sq	—	40.30	40.30	68.50
Shingles, asphalt, double layer (1.2 Sq per CY and 480 lbs per Sq)	BL@2.00	Sq	—	60.60	60.60	103.00
Shingles, slate. Weight ranges from 600 lbs. to 1,200 lbs. per Sq (1 Sq per CY and 900 lbs per Sq)	BL@1.79	Sq	—	54.30	54.30	92.30

	Craft@Hrs	Unit	Material	Labor	Total	Sell
Shingles, wood (1.7 Sq per CY and 400 lbs per Sq)	BL@2.02	Sq	—	61.20	61.20	104.00
Clay or concrete tile (.70 Sq per CY)	BL@1.65	Sq	—	50.00	50.00	85.00
Remove gravel stop or flashing	BL@.070	LF	—	2.12	2.12	3.60

Interior and exterior finish demolition. Includes breaking materials into manageable pieces with hand tools and handling debris to a trash bin on site. Figures in parentheses show the approximate "loose" volume and weight of the materials after being demolished. Demolition for disposal. No salvage of materials included.

Plywood sheathing, up to 1" thick, cost per in-place SF

(200 SF per CY and 2 lbs. per SF)	BL@.017	SF	—	.52	.52	.88
Wood board sheathing (250 SF per CY and 2 lbs. per SF)	BL@.030	SF	—	.91	.91	1.55
Metal siding, using hand tools (200 SF per CY and 2 lbs. per SF)	BL@.027	SF	—	.82	.82	1.39
Stucco on walls or soffits, cost per in-place SF, removed using hand tools (150 SF per CY and 8 lbs. per SF)	BL@.036	SF	—	1.09	1.09	1.85
Wallboard 1/2" thick, cost per in-place SF, removed using hand tools. Add 50% to labor costs for 1" wallboard.						
Gypsum, walls or ceilings (250 SF per CY and 2.3 lbs. per SF)	BL@.010	SF	—	.30	.30	.51
Including strip furring	BL@.015	SF	—	.45	.45	.77
Plywood or insulation board (200 SF per CY and 2 lbs. per SF)	BL@.018	SF	—	.55	.55	.94
Insulation, fiberglass batts or rolls, cost per square foot removed (500 SF per CY and .3 lb per SF)	BL@.003	SF	—	.09	.09	.15
Plaster on walls, cost per square foot removed by hand (150 SF per CY and 8 lbs. per SF)	BL@.015	SF	—	.45	.45	.77
Remove baseboard molding						
Single member base, no salvage	BL@.022	LF	—	.67	.67	1.14
Base and base shoe, no salvage	BL@.038	LF	—	1.15	1.15	1.96
Remove and salvage single member base	BL@.025	LF	—	.76	.76	1.29
Remove and salvage base and base shoe	BL@.044	LF	—	1.33	1.33	2.26

Ceiling demolition. Knock down with hand tools at heights to 9' and handle debris to a trash bin on site. Building structure to remain. No allowance for salvage value. Costs shown are per square foot of ceiling. Figures in parentheses show the approximate "loose" volume after demolition.

Plaster ceiling (typically 175 to 200 SF per CY)

Including lath and furring	BL@.025	SF	—	.76	.76	1.29
Including suspended grid	BL@.020	SF	—	.61	.61	1.04
Acoustic tile ceiling (typically 200 to 250 SF per CY)						
Including suspended grid	BL@.010	SF	—	.30	.30	.51
Including grid in salvage condition	BL@.019	SF	—	.58	.58	.99
Tile glued or stapled to ceiling	BL@.015	SF	—	.45	.45	.77
Tile on strip furring, including furring	BL@.025	SF	—	.76	.76	1.29
Drywall ceiling (typically 250 to 300 SF per CY)						
Nailed or attached with screws to joists	BL@.010	SF	—	.30	.30	.51

	Craft@Hrs	Unit	Material	Labor	Total	Sell
Floor cover demolition. Includes breaking materials into manageable pieces with hand tools and handling debris to a trash bin on site. Cost per square yard of floor removed. (1 square yard = 9 square feet.) Figures in parentheses show the approximate "loose" volume and weight of the materials after demolition.						
Ceramic tile (25 SY per CY and 34 lbs. per SY)	BL@.263	SY	—	7.97	7.97	13.50
Hardwood, nailed (25 SY per CY and 18 lbs. per SY)	BL@.290	SY	—	8.79	8.79	14.90
Hardwood, glued (25 SY per CY and 18 lbs. per SY)	BL@.503	SY	—	15.20	15.20	25.80
Linoleum, sheet (30 SY per CY and 3 lbs. per SY)	BL@.056	SY	—	1.70	1.70	2.89
Resilient tile (30 SY per CY and 3 lbs. per SY)	BL@.300	SY	—	9.09	9.09	15.50
Terrazzo (25 SY per CY and 34 lbs. per SY)	BL@.286	SY	—	8.67	8.67	14.70
Carpet on tack strip (40 SY per CY and 5 lbs. per SY)	BL@.028	SY	—	.85	.85	1.45
Glue-down carpet with rubber backing (35 SY per CY and 1.7 lbs. per SY)	BL@.160	SY	—	4.85	4.85	8.25
Add for each LF of room perimeter	BL@.008	LF	—	.24	.24	.41
Carpet pad (35 SY per CY and 1.7 lbs. per SY)	BL@.014	SY	—	.42	.42	.71
Removal of interior items. Includes breaking materials into manageable pieces with hand tools and handling debris to a trash bin on site. Items removed in salvageable condition do not include an allowance for salvage value. Figures in parentheses give the approximate "loose" volume of the materials after demolition. Removed in non-salvageable condition (demolished) except as noted.						
Windows, typical cost to remove window, frame and hardware, cost per SF of window						
Metal (36 SF per CY)	BL@.058	SF	—	1.76	1.76	2.99
Wood (36 SF per CY)	BL@.063	SF	—	1.91	1.91	3.25
Wood stairs, cost per in-place SF or LF						
Risers (25 SF per CY)	BL@.116	SF	—	3.52	3.52	5.98
Landings (50 SF per CY)	BL@.021	SF	—	.64	.64	1.09
Handrails (100 LF per CY)	BL@.044	LF	—	1.33	1.33	2.26
Posts (200 LF per CY)	BL@.075	LF	—	2.27	2.27	3.86
Hollow metal door and frame in a masonry wall. (2 doors per CY)						
Single door to 4' x 7'	BL@1.00	Ea	—	30.30	30.30	51.50
Two doors, per opening to 8' x 7'	BL@1.50	Ea	—	45.50	45.50	77.40
Wood door and frame in a wood frame wall (2 doors per CY)						
Single door to 4' x 7'	BL@.500	Ea	—	15.20	15.20	25.80
Two doors, per opening to 8' x 7'	BL@.750	Ea	—	22.70	22.70	38.60
Metal door and frame in masonry wall, salvage condition						
Hollow metal door to 4' x 7'	BL@2.00	Ea	—	60.60	60.60	103.00
Wood door to 4' x 7'	BL@1.00	Ea	—	30.30	30.30	51.50

Online Preview

Index

- A**
- Abbreviations..... 17
 - ABS pipe 408
 - Absorber, shock water surge..... 407
 - ABTCO 251
 - AC cable..... 419
 - AC quiet rocker switch Decora..... 434
 - AC quiet toggle switch..... 434
 - Access door..... 248
 - Access doors foundation..... 88
 - Accessories, ridge vents ... 90
 - Acid cleaning masonry..... 115
 - wash 50, 115
 - Acid wash, manhours..... 466
 - Acknowledgments 2
 - Acoustic ceiling texture labor 469
 - Acoustic roll-on..... 493
 - Acoustic tile demolition 34, 315
 - Acoustical ceiling demolition 254
 - panel..... 255-257
 - patch..... 245
 - suspended..... 256
 - texture touch-up kit..... 244
 - tile adhesive 254
 - Acrylic latex paint 492
 - mirrored sheet 171
 - mortar admix 307
 - paint..... 40
 - roof coating..... 137
 - sheet..... 171
 - skylights..... 173
 - stain 487
 - suspended lighting panel..... 258
 - tape 291
 - wood filler 281
 - Actuating devices, garage doors 225
 - Adapter, box 421
 - Additive feather edge 286
 - resilient flooring 285
 - Additives coloring..... 47
 - concrete..... 47
 - perlite paint texturing 493
 - Adhesive acoustical ceiling tile 254
 - bond 133
 - cold process 133
 - cove base 290
 - field..... 134
 - flooring..... 282
 - marble & granite..... 306
 - modified bitumen 133
 - nozzle 291
 - primer 282
 - resilient tile 290
 - sheet flooring..... 290
 - spray..... 249
 - tile 293-294
 - vinyl tile..... 290
 - white silicone 171
 - wood flooring 282
 - Adhesive caulk, ceramic tile 307
 - Adhesive remover 282
 - flooring..... 285
 - Admix, acrylic mortar..... 307
 - Admixtures coloring..... 47
 - concrete..... 47
 - Aggregate base..... 40, 46
 - roofing 132
 - Aggregate sealer..... 495
 - Air compressor, rental 28
 - Air conditioner 397
 - Air gap 334
 - cover..... 334
 - Air hose, rental 28
 - Air mover 539
 - Air scrubber 539
 - Alkyd gloss enamel 493
 - All-season storm doors 204-205
 - All-season storm doors, triple-track..... 204
 - Alpine ceiling panel 257
 - Aluminum door bottom 196
 - drip edge 141
 - fascia 114
 - foil 88
 - patio cover..... 459
 - patio doors..... 215
 - roll flashing 141
 - roof coating..... 137
 - screen rolls..... 168
 - siding 113
 - siding removal..... 106
 - siding repair..... 105
 - soffit..... 114
 - storm windows..... 165
 - thermal door sill..... 195
 - windows, fixed 162
 - Aluminum conduit threaded 431
 - Aluminum siding painting..... 482
 - Aluminum wiring..... 411
 - Amber shellac..... 490
 - American Flexible Conduit..... 419
 - American Marazzi..... 296-298
 - American Marazzi..... 303
 - American Molding..... 262
 - American Shower & Bath 337, 357-358
 - American Standard..... 330, 333-334, 338, 353-354, 360-363, 366-372, 385-386
 - Anchor clip..... 458
 - Anchor, foundation 512
 - Anchor, hold-down 512
 - Andersen 214, 216
 - Angle flashing..... 142
 - Angle bay windows..... 164
 - Angle valve 364
 - Ann Arbor birch paneling ... 252
 - Anti-fracture membrane kit..... 307
 - membrane water-proofing 305
 - tile membrane..... 305
 - Antimicrobial..... 536
 - Anti-siphon toilet fill valve... 364
 - Appliance receptacle..... 435
 - Appliance removal..... 530
 - Appliances connect..... 417
 - disconnect 417
 - kitchen, removal 315
 - new connection 417
 - remove & replace cable... 417
 - Apron roof 143
 - whirlpool tub 354
 - Aqua Mix 307
 - Aqua-Tough tile underlayment..... 295
 - Arch, bullnose drywall 247
 - Architectural laminate shingles 130
 - Area modification factors... 18
 - Area modification factors, Canadian 26
 - Area walls, sheet metal... 389
 - Ariston 407
 - Arlington Industries..... 422
 - Armstrong..... 255-257, 285-291, 293
 - Asceri Hi-Arc lavatory faucet..... 373
 - Ashland sink 329
 - Asphalt base..... 51
 - fiberglass shingles..... 130
 - paving 51
 - paving, demolition 32, 51
 - recycling 29
 - Asphalt roofing 132
 - built-up..... 132
 - emulsion 133
 - fabric..... 131
 - saturated cotton roof patch..... 136
 - SEBS..... 135
 - Asphalt shingles fiberglass..... 131
 - repair 130
 - Astragal, T-..... 194
 - Attachments, skid steer equipment..... 39
 - Attic conversions 57
 - Attic fans belt drive..... 91
 - Attic ventilation 83
 - Attic vents..... 91
 - Avenite counters..... 322
 - Awning, remove & replace..... 106
 - Awning windows aluminum..... 162
 - operators 166
 - vinyl-clad wood..... 160
- B**
- Bacharach kitchen faucet..... 331
 - Backer, tile..... 245
 - Backer tape, tile..... 249
 - Backerboard ceramic tile 295
 - RhinoBoard 295
 - tile 295
 - Wonderboard..... 295
 - Backfill, concrete excavation 40
 - Backhoe, rental 28
 - Backing, carpentry..... 73
 - Backplate, knob..... 326
 - Backsplash 322
 - Baffle, sound 340
 - Baffle light kit..... 440
 - Bahama pedestal lavatory, bowl 366
 - Balance, sash..... 166
 - Ballista range hood..... 343
 - Baluster 455
 - deck rail..... 456
 - Balustrade deck..... 456
 - Bamboo flooring trim..... 280
 - hardwood flooring..... 280
 - plank flooring..... 280
 - Banner 329
 - Bar doors..... 209
 - Bar faucet 338
 - single handle 338
 - two-handle 338-339
 - Bar kit, QO load center ground 440
 - Bar light fixture 441
 - Bar sink composite 338
 - Manchester composite... 338
 - polycast 338
 - single bowl..... 337
 - stainless steel..... 338
 - Bar, towel 305, 385-386, 388
 - Barn & fence paint..... 496
 - Barrier, foil 88
 - Base adhesive 290
 - asphalt..... 51
 - ceramic tile 295
 - lavatory 367
 - rubber wall 292
 - self-stick wall 293
 - shower, one-piece 358
 - slab 49
 - vinyl wall 292-293
 - Base cabinets..... 318
 - end panel..... 317
 - finished 320-321
 - oak..... 320
 - unfinished birch 317
 - unfinished oak 318
 - Base cap molding, primed finger joint..... 260
 - Base corner molding 259
 - MDF primed..... 261
 - Base molding..... 263
 - colonial 263
 - combination 264
 - MDF colonial 261
 - paperwrap colonial 263
 - paperwrap ranch base ... 264
 - polystyrene colonial..... 264
 - primed finger joint..... 260
 - shoe..... 264
 - Victorian hardwood..... 259
 - Base plate cover, toilet.... 364
 - Base sheet, fiberglass.... 133
 - Base shoe molding, primed finger joint..... 260
 - Base, wall thermoplastic 292

Baseboard	Farmington	367	Bead, corner, spray	Board siding
demolition	Laurel	368	adhesive	cedar
painting labor	Lucerne	369	249	pine
Baseboard heater,	Memoirs	369	Beaded baseboard	repair
electric	Miami	369	molding	105
404	Minette	369	Beaded Cape Cod plank...	Board, cement
Baseboard molding	Murro	369	252	245
beaded	oval	368	Beaded paneling	Bobcats
259	Ovalyn	368	251	39
MDF	Radiant	368	Beadex paper faced	Boiler, hydronic heating
261	Renaissance	367	metal	system
Basement doors	round	368	247	398
226	Seychelle	367-368	Beams	Boiler breeching
Basement HVAC	steel	368	ceiling	401-403
restoration	under counter mount	368	collar	Bolt
92	wall hung	369	75	bolt kit
Basement post removal....	369	368	grade	512
63	367-368	368	needle	toilet tank
Basement storm	368	368	Bed molding	364
windows	368	263	Bedding mortar,	Bolt-on A type
165	368	263	CustomFloat	universal hub
Basin strainer, remove &	368	306	Behr	438
replace	369	487, 490, 492-495	Bell wire	Bolts, double-hung
352	Bathroom vanity top	376	433	window
Basket strainer	Bathrooms	additions	Bemis Mfg	166
garbage disposal	additions	345	365-366	Bond adhesive
335	conversions	346	Berm	permanent
junior	exterior additions	348	530	133
kitchen sink	floor plans	349	Bestview Ltd	Bonding mortar
335-336	in basements	347	298	305-306
Basket strainer washer	in garages	348	Bevel siding	flexible
kitchen sink	naming conventions	345	cedar	306
336	space minimums	350	108	Bonding primer
Basswood molding	Bathtub	353	108	concrete
259	enameled steel	352	108	493
Bath accessories	Princeton	353	108	Bookcase, painting labor...
385-388	recessed	353	108	468
black finish	removal	352	108	Boone International
388	353	352	108	293
brass	353	353	108	Bosch
386, 388	353	355	108	407
brass & chrome	353	355	108	Boston polish
386, 388	353	355	108	491
ceramic & chrome	353	355	108	Bottle jacks
387	353	355	108	62
ceramic tile	353	355	108	Bow window roof
294	353	355	108	164-165
chrome	353	355	108	Bowl, lavatory
386-388	353	355	108	366
chrome & brass	353	355	108	Bowl sink, utility
386	353	355	108	337
chrome & porcelain	353	355	108	Bowling alley wax
386	353	355	108	491
economy	353	355	108	Box
386	353	355	108	428
nickel	353	355	108	2 gang weatherproof
388	353	355	108	electrical
Bath accessory set,	353	355	108	427
porcelain	353	355	108	drawn 2-device switch...
305	353	355	108	425
Bath cabinet	353	355	108	drawn handy
framed	353	355	108	424
382	353	355	108	drawn octagon
stainless steel	353	355	108	425
382	353	355	108	multi gang switch
storage	353	355	108	425
383	353	355	108	non-metallic old work
swing door	353	355	108	switch
383	353	355	108	422
top lighted	353	355	108	non-metallic round
383	353	355	108	conduit
Bath ceiling blower	353	355	108	428
378	353	355	108	rectangular weather-
Bath fan	353	355	108	proof
378-380	353	355	108	427
ceiling	353	355	108	Super Blue non-
381	353	355	108	metallic three gang....
ceiling & wall	353	355	108	422
378	353	355	108	Super Blue non-
ceiling or wall	353	355	108	metallic two gang
379	353	355	108	422
chain-operated	353	355	108	welded square
380	353	355	108	425
Designer Series	353	355	108	Box adapter
381	353	355	108	421
exhaust	353	355	108	Box cover
380	353	355	108	426
exhaust with heater	353	355	108	blank handy
381	353	355	108	424
exhaust with light	353	355	108	finished
380	353	355	108	425
Heat-A-Lamp	353	355	108	square surface
381	353	355	108	425
QuietTest	353	355	108	Box for ceiling fan
380	353	355	108	425
solitaire	353	355	108	pancake
381	353	355	108	425
timer switch	353	355	108	Box room contents
382	353	355	108	529
Ultra Silent	353	355	108	Boxes, cardboard
379	353	355	108	538
vertical discharge	353	355	108	Brace plate installation
379	353	355	108	92
with heater, infrared	353	355	108	Braces, wall
381	353	355	108	513
with light	353	355	108	Bracing
380-381	353	355	108	carpentry
Bath heater	353	355	108	67
exhaust fan	353	355	108	cripple wall
381	353	355	108	512
Heat-A-Lamp	353	355	108	temporary
381	353	355	108	67
infrared bulb	353	355	108	Bracket
381	353	355	108	foundation
Bath light bar	353	355	108	512
441	353	355	108	non-metallic low
Bath Unlimited	353	355	108	voltage mounting
387-388	353	355	108	422
Bath vent kit	353	355	108	Bracket, hanger, lavatory ...
382	353	355	108	369
Bathrobe hook ...	353	355	108	Brass storm doors
385-386, 388	353	355	108	205
Bathroom accessories	353	355	108	Brass Craft
ceramic tile soap dish...	353	355	108	334, 362, 364
304	353	355	108	
towel bar, ceramic	353	355	108	
305	353	355	108	
Bathroom sink	353	355	108	
367-369	353	355	108	
cadet	353	355	108	
368	353	355	108	
drop-in	353	355	108	
367-368	353	355	108	

- Breaker
arc fault, HomeLine 437
GFCI 437
ground fault interrupter
 plug-on circuit 440
HomeLine 437
main circuit 438
QO miniature circuit 439
tandem circuit 439
- Breaker box, ground
bar kit 440
- Breaker, paving, rental 28
- Brick
cleaning 115
demolition 30
painting 477-478
pointing 115
repointing 115
- Brick masonry
painting labor 476
- Brick molding 195
- Brick molding set
primed finger joint 260
- Brick paver tile 300
- Bridging, carpentry 65
- Broan Manufacturing 344,
378-382
- Brookfield cast iron
kitchen sink 330
- Brookstone birch
paneling 252
- Broom finish, concrete 49
- Brown coat plaster 114
- Bruce 278, 282
- Brush
painting labor 468
wire 50
- Brush chipper, rental 28
- Brushes
crow's foot 250
drywall texture 250
- Bubble wrap 538
- Buggies, rental 39
- Building dryout,
interior work
appliances 516
basement 517
ceiling 516
flooring 516
furniture 516
heavy items 517
lamps 516
mud and debris 517
outlets 516
securing valuables 516
vents and registers 517
wall switches 516
walls 516
- Building paper 87, 134
- Building wire
type THHN 432
- Built-up girders, carpentry 62
- Built-up roofing 132, 134
Cold-Ap cement 133
demolition 33
insulation 131-132
patch 131
tear-off 129
torch and mop system 134
- Bulb heater & fan,
Heat-A-Lamp 381
- Bulkhead light fixture
outdoor 443
- Bull float, rental 39
- Bullnose
ceramic tile 301
corner bead 247
corner tile 302
drywall arch 247
outside corner 247
plastic corner 247
- Bulls Eye shellac 490
- Bumper, garage door 224
- Buried cable 419
- Burn off paint labor 466
- Bush removal 29
- Bushing
insulated metallic
 grounding 430
non-metallic reducer 420
rigid or IMC reducing 430
thermoplastic
 insulating 430
- Butcher's 491
- BX cable, flexible
armored 419
- Bypass door 218
- accessories 219
bathtub 355
beveled mirror 218
closet 218
hardware 222
mirrored 218-219
shower 356
- C**
- Cabinet demolition, wet 534
- Cabinet door 316
- Cabinet drawer front 316
- Cabinet hinge
overlay 327
self-closing 328
semi-concealed 328
- Cabinet knobs 324-326
- Cabinet trim 320
- Cabinets
base 317-318, 320-321
bath 382-383
bathroom vanity 374-375
corner 383
door trim 316
end panel 316-318
filler strip 318-319
finished 320
frameless 383
kitchen, unfinished
 birch 317
 medicine 382-384
 oak 320-321
 painting labor 469
 pantry 319-321
 removal 315
 trim 320
 trim, finished 322
 utility 317-321
 vanity 378
 wall 317-321
- Cable
AC 419
appliance connection 417
appliance re-connect 417
appliance, remove &
 replace 417
BX 419
coaxial 433
data communication 433
fish through stud wall 417
flexible armored BX 419
thermostat 433
Type NM-B Romex
 sheathed 417-418
Type UF-B sheathed 419
underground 419
- Cable coupling, EMT to
non-metallic sheathed 424
- Cable snake flat wire
fish tape 417
- Cadet Series bar faucet 338
- Cafe doors 209
- Calcium chloride 47
- Cambay vinyl sheet
flooring 287
- Cambria countertop 323
- Can, ceiling light 440
- Canopy, remove &
replace 106
- Cant strips 137
roofing 86
- Cap 146
ceramic surface 302
chimney 146
PVC service entrance 422
service entrance 432
- Cap molding, colonial 264
- Cap sheet, roofing 133
- Cap, post 456-457
- Cape Cod plank 252
- Carbon monoxide alarm,
battery powered 436
- Carborundum rub 50
- Cardboard boxes 538
- Carflex liquid-tight
flexible conduit 427
- Carlson 420-422, 427-428
- Carol Cable 433
- Carpentry
backing and nailers 73
beams and girders 62
bridging or blocking 65
ceiling beams 68
ceiling joists 73
door openings 69
dormer studs 76
fascia board 76
fireblocks 68
floor joists 64-65
floor repairs 62
furring 72
plates 67
posts 63
rafters 75
roof sheathing 77
roof trusses 76
room additions 64
sheathing 70
sill plates 64
studs 66
subflooring 66
wall assemblies 70
wall framing 66
window openings 69
- Carpet 308
cleaning 532
demolition 35
removal 278
removal 531
roller, extendable 291
- transition strip 292
water extraction 531
- Cartridge, disposal 340
- Casement windows 164
lock handle 166
operator handle 166
vinyl-clad wood 160
- Casing 263
aluminum siding 114
colonial 260
colonial door 195
door 191, 206
economy 265
paperwrap colonial 264
paperwrap ranch 265
polystyrene 266
polystyrene colonial 264
polystyrene fluted 265
polystyrene ranch 265
prefinished colonial 264
prefinished fluted
 ranch 260, 265
- Casing, MDF 261
- Caspian sheet vinyl
flooring 286
- Cast iron
pipe, remove &
 replace 408
radiator, remove &
 replace 398
water closet flange 364
- Cast iron kitchen
sink 329-330
- Cast molding 262
chair rail 262
- Cast-in-place concrete 47
- Cat doors 216
- Catalina Lighting 443
- Caulk
ceramic tile 307
ceramic tile adhesive 307
removal 157
roof 136
window exterior 157
- Caulking, manhours 466
- Cedar
panels, sidewall
 shingle 113
 roofing 137
 shingles 138
 siding 108-109
- Cedar louvered vents 90
- Cedarmill 112
- Ceiling
beams 68
demolition 242
demolition, wet 533
joists 73
painting 470
painting manhours 469-470
repair 244
staining manhours 470
texture manhours 469
tile adhesive 254
touch-up kit 244
- Ceiling and wall pane
FRP 253
- Ceiling fan
bath 378
bath heater & fan 381
gazebo 444
QuietTest 380
San Marino 444

Ceiling fan box.....	425	Cement, roofing		Chimneys.....	399-403	Clip, anchor	458
non-metallic.....	422	cold process	133	A vent	402-403	Clips & screws.....	329
pancake.....	425	flashing	135	all fuels	402-403	Clips, drywall repair.....	249
Ceiling fixture.....	440	Kool Patch.....	135	aluminum.....	399-400	Closers, door	217
drum	441	lap roof	133	B vent	401	Closet, painting labor.....	470
fluorescent.....	441	rubber wet patch	135	base tee.....	400-402	Closet doors	210
flush mount.....	441	Wet Stick	135	C vent.....	399-400	bi-fold.....	219-220
glass globe.....	442	Center, HomeLine		cap.....	146	bypass.....	218
incandescent flush		indoor main lug load.....	437	double wall	401-402	mirrored bypass.....	218-219
mount	442	Central air conditioning....	397	double wall		Closet pole molding.....	263
mushroom flush		Central air filtration		insulated.....	402-403	Closure strips, horizontal... 141	
mount	442	retrofit, HEPA	398	elbow	400-403	CMU, painting.....	477
remove & replace	441	Central humidifier	397	flue.....	399-403	CO/ALR duplex	
Sunburst flush mount ...	442	Ceramic		flue rain cap.....	399	receptacle.....	435
swirl dome light.....	442	floor & wall.....	297	gas or propane.....	399-402	Coal furnace.....	404
Ceiling insulation		Ceramic tile		L vent.....	401-402	Coated glass fabric.....	136
batt and roll blanket.....	79	accessories	304	liner.....	399	yellow resin.....	136
Kraft-faced.....	79	accessory set	305	liner (flue) aluminum....	399	Coating	
loose-fill	79	adhesive	293	liner rain cap.....	399	elastomeric roof.....	137
R-value	79	adhesive caulk.....	307	masonry, repair	104	fibered roof	137
Ceiling latex paint.....	492	backer.....	295	rain cap.....	400-403	floor, epoxy.....	495
Ceiling lighting panel		backerboard	295	repairing earthquake		foundation and roof	129
acrylic	258	bullnose	301	damage	510	roof	137
styrene.....	258	bullnose corner.....	302	roof flashing.....	400-403	roof and foundation	129
Ceiling panel.....	256	caulk	307	single wall.....	399-400	weather-resistant.....	488
acoustical	256	demolition	35, 315	stack	401-402	wood.....	488
classic fine-textured.....	256	floor.....	295-298	storm collar.....	400-403	Coating kit	
fiberglass.....	257	floor warming system ...	305	supports & brackets	403	seam.....	291
Firecode Fifth Avenue ...	257	glazed.....	303	termination		corrosion.....	92
fissured.....	257	installation	293	assembly	400-403	Coatings	
fissured fire guard	256	mosaic accent	304	Chlorinated rubber paint... 496		concrete.....	495
Grenoble.....	256	mosaic octagon	304	C-hook, garage door	224	epoxy gloss	496
gypsum lay-in	257	Natura.....	296	Chop saw, rental	28	epoxy primer.....	496
mineral fiber.....	257	removal.....	278	Chrome light fixture	441	specialty	496
plain white	256	Saltillo	299	Circuit breaker		Coaxial cable.....	433
Prestige	256	sink rail	302	arc fault, HomeLine	437	wall plate	433
random textured	255	soap dish	304	GFCI.....	437	Coaxial F-connector	
Sahara	256	surface cap	302	ground fault interrupter		for RG6.....	433
suspended.....	255-257	surface cap corner	302	plug-on	440	Cobra Rigid ridge vent ... 145	
textured	257	threshold.....	301	HomeLine	437	Cofair Products.....	135
Ceiling repair	245	toilet tissue holder	304	main.....	438	Coffer dam.....	92
Ceiling texture	246	tool.....	291	main, all-in-one.....	438	Coil, kickplate	459
patch.....	245	toothbrush & tumbler		QO miniature	439	Cold process adhesive,	
popcorn patch.....	245	holder	305	tandem	439	modified bitumen	133
spray.....	244-245	wall	301, 303	Circular windows half		Cold process cement.....	133
touch-up kit.....	244	window sill	301	circle, vinyl.....	159	Collar beams, carpentry ... 75	
Ceiling tile	254	Ceramic tile definitions ... 276		Civic Square	290	Collar ties	75
acoustical	253	Ceramic tile flooring.....	276	Clamp		Colonial base molding.... 263	
tin design	254	tips on.....	277	ground rod.....	432	MDF.....	261
wood fiber.....	254	Chain link fence		Snap Strap PVC		paperwrap	263
Ceiling tile grid system		demolition	29	conduit.....	420	polystyrene	264
zero-clearance tile grid... 255		Chain saw, rental.....	28	wood floor.....	281	Colonial cap	
Ceiling tile, wet	533	Chain-operated wall		Clamp connector,		paperwrap molding.....	264
Ceiling wire hanging kit ... 255		exhaust fan.....	380	two-piece	419	Colonial casing	
Ceiling, suspended		Chair rail		Classic faucet handle	370	finger jointed.....	260
cross tee.....	255	cast polyurethane	262	Clay roofing tile.....	139	paperwrap	264
installation	254	Clearwood PS	266	Cleaning		polystyrene	264
main beam.....	255	MDF.....	261	after water extraction.... 534		prefinished.....	264
wall molding.....	255	paperwrap	266	antimicrobial	536	Colonial crown	
CeilingMAX.....	255	polymer.....	263	brick.....	115	paperwrap molding.....	268
Ceilings, suspended.....	237	polystyrene	266	carpet	532	Colonial door casing.....	195
Cellar doors, steel	194	prefinished.....	266	HVAC.....	530	Colonial outside corner	
Cement		primed finger joint.....	260	masonry.....	115	molding.....	267
board	245	Chalk line, self chalking... 291		pressure wash	468	Colonial stop molding	269
coloring.....	47	Chandelier	442	stone.....	115	Colonial storm doors,	
joint compound.....	245	Channel vent, rafter bay.... 88		terra cotta	115	triple-track.....	205
mixer, rental.....	39	Chesapeake floor tile.....	289	Ultrasonic.....	530	Colonnade kitchen	
siding.....	113	Chime kit, door	436	Clear cedar siding	108	faucet.....	332
soffit, fiber.....	112			Clear wood		Colorant, grout.....	307
tile.....	139			preservative.....	491	Coloring agents	
underlayment.....	285			protector	490	concrete.....	47, 49
white	114			Clearshield.....	488	Column, porch	455

- Combination base
 molding.....264
- Combination coupling.....424
- Combination service
 entrance device.....438
- Combination service
 entrance load center437
- Commercial Electric440
- Communication cable,
 category 5E433
- Composite kitchen sink ...338
- bar338
- Beaumont.....331
- double bowl.....330
- Forsyth.....330
- Greenwich.....330
- single bowl.....330
- 60/40 bowl.....331
- Composition tile,
 vinyl289-290
- Compound
 glazing.....170
- latex glazing.....170
- Compression conduit
 coupling, rigid or IMC430
- Compression connector
 EMT.....423
- EMT-to-box offset.....424
- non-metallic UF.....419
- Compression faucet
 repair.....352
- Compression inlet
 dishwasher connector ...341
- Compressor, rental.....28
- Concrete
 additives47
- architectural.....47
- bonding primer493
- coatings.....495
- coloring.....47
- curb.....44
- delivery charges.....46
- driveways.....46
- embossed finish.....50
- enamel.....495
- epoxy floor coating.....495
- expansion joints.....46
- exposed aggregate.....49
- finishing.....50
- flatwork.....40
- floor painting
 labor.....474-475
- footings, demolition.....31
- form stripping.....43
- forms.....42, 48
- foundations.....48
- grade beams.....48
- granite aggregate.....46
- grinding.....513
- grout mix.....46
- grouting.....50
- high early strength.....47
- joints.....46
- keyway.....48
- lightweight.....46
- mix.....46
- patching.....50
- planing.....513
- plasticized.....47
- protective coating.....495
- pump mix.....46
- pumping.....39
- ready-mix.....46
- recycling.....29
- reinforcing steel.....44
- repair.....513
- retaining walls.....47
- sawing.....50
- sealer.....495
- shingles.....140
- sidewalk.....49
- slab demolition.....32
- slabs.....49
- specialty finishes.....50
- stain.....495
- stamped finish.....50
- tile.....139
- tile roofing.....140
- topping.....50
- walks.....49
- wall demolition.....32
- wall form.....43
- walls.....47
- waterproof.....495
- waterproofing sealer.....495
- Concrete & masonry
 waterproof.....495
- Concrete block
 demolition.....31
- painting.....476-478
- Concrete conveyor, rental...39
- Concrete deck patch
 built-up roofing.....131
- Concrete pier
 replacement.....63
- Concrete saws, rental.....39
- Conditioner, wood.....491
- Conduit
 Carflex liquid-tight.....427
- EMT.....422, 426
- EMT, removal.....422
- ENT.....427
- flex appliance
 connection.....417
- flexible aluminum.....426
- flexible steel.....426
- galvanized IMC.....429
- GRS.....429
- IMC.....429
- installation, rigid.....429
- removal, rigid.....429
- Schedule 40 PVC.....420
- Schedule 80 PVC.....420
- Conduit body.....421
- PVC Type T.....421
- threaded aluminum.....431
- Conduit box
 adapter.....421
- cover, steel.....424, 426
- installation.....424
- non-metallic round.....428
- steel.....425
- three-gang non-
 metallic.....422
- two-gang non-
 metallic.....422
- Conduit bushing, rigid.....430
- Conduit clamp, Snap
 Strap PVC.....420
- Conduit connector
 90-degree.....426
- flex.....427
- Conduit coupling
 rigid.....429-430
- Conduit elbow
 45-degree rigid steel429
- rigid or IMC steel.....429
- Conduit fitting
 Carflex.....427
- non-metallic.....421
- Conduit hub, watertight...430
- Conduit installation
 confined area.....429
- Conduit locknut.....430
- Conduit nipple.....431
- Conduit sill plate
 service entrance.....432
- Conduit strap.....431
- Connector
 90-degree flexible.....426
- dishwasher.....340-341
- EMT compression.....423
- EMT offset screw.....423
- EMT set screw.....423
- EMT-to-box offset
 compression.....424
- flex screw-in.....426
- flex squeeze.....427
- non-metallic UF
 compression.....419
- two-piece clamp.....419
- Containment
 dust.....536
- mold.....536
- Contents.....3
- Continuous vents.....89
- Contractors Wardrobe.....359
- Contractors, state license
 dryout.....515
- mold remediation.....515
- Control switch, fan.....382
- Convection heating,
 baseboard.....398
- Cooktop
 electric.....342
- electric ceramic glass...342
- gas.....342
- Cooling system, patio.....458
- Copper
 formed flashing.....141
- roll flashing.....141
- window roofs.....164
- Copper pipe
 DWV.....408
- water.....408
- Copper step flashing.....141
- Copper wire, type
 THHN.....432
- Copper wood
 preservative.....491
- Cord, disposal
 accessory kit.....340
- Corian countertops.....322
- Cork
 roll.....293
- tile flooring.....275
- tile, natural.....293
- Corner
 MDF primed base.....261
- plastic bullnose.....247
- Corner and cove molding
 inside.....266-267
- paperwrap.....266
- prefinished.....267
- Corner bead
 bullnose.....247
- drywall.....247
- flex.....248
- inside.....247
- outside.....248
- spray adhesive.....249
- Corner block
 polyurethane.....262
- Corner cabinet,
 frameless.....383
- Corner entry shower kit...358
- Corner molding
 inside.....267
- paperwrap outside.....267
- polystyrene inside.....267
- polystyrene outside.....267
- prefinished inside.....267
- prefinished outside.....267
- Corner shelf, ceramic.....304
- Corner tape, flexible
 metal.....249
- Corner trowel.....250
- Cornices, painting.....480
- Corrosion coatings.....92
- Corrugated
 fiberglass.....140
- metal roofing.....138
- metal siding.....113
- CorStone.....330, 331
- Cost plus markup
 equals selling price.....7
- Cotton insulation.....87
- Cotton roof patch
 asphalt saturated.....136
- Counter edge, oak.....268
- Counterflashing.....144
- Countertops.....322
- Corian.....322
- granite.....323
- laminated plastic.....323-324
- marble vanity.....376
- miter bolt kit.....324
- plastic laminate.....323
- setting with adhesive....294
- setting with mortar.....294
- solid surface.....322
- stone, engineered.....323
- tile.....295
- Coupling, combination.....424
- EMT to non-metallic
 sheathed cable.....424
- non-metallic standard...421
- rigid conduit.....429
- rigid or IMC
 compression conduit430
- Cove and corner
 molding
 inside.....266-267
- paperwrap.....266
- Cove base
 adhesive.....290
- adhesive nozzle.....291
- Cove molding.....268
- spring.....268
- Cover
 faucet hole.....335
- patio, aluminum.....459
- Covers
 2 gang blank.....428
- blank handy box.....424
- dual weatherproof
 lampholder.....428

- entrance 194
 entry..... 193, 198-200
 entry, decorative fan..... 200
 entry, decorative
 half lite..... 200
 exterior..... 192-193, 197-198
 exterior fan lite..... 197
 exterior flush..... 197
 exterior prehung 197-199
 exterior prehung,
 with mini-blind 198
 exterior, installation 191
 fiberglass 200-201
 fir..... 193
 fire..... 192
 fire-rated 197
 flush 219
 flush closet 219
 flush closet, lauan 219
 folding, accordion 217
 foundation access 88
 French 193
 French, interior 208
 garage 223-224
 garage, extension
 spring..... 225
 garage, jamb hinge 224
 handle sets 202
 hanging slab doors..... 184
 hardboard 192, 209
 hardware 221
 hardware, exit..... 226
 hemlock 197
 installation 191, 197
 206, 209
 interior..... 207-208, 211-212
 interior cafe 209
 interior slab..... 206
 interior, birch..... 206
 interior, colonial 211
 interior, colonist 211
 interior, fir 208
 interior, French 212-213
 interior, full louver,
 pine 212
 interior, hardboard..... 207
 interior, hardboard,
 colonist 207
 interior, lauan..... 206-207
 interior, oak..... 206, 208, 212
 interior, pine 208
 interior, pine louver..... 212
 interior, prehung 209-210
 interior, prehung,
 knotty alder..... 212
 interior, solid core..... 207
 lauan..... 210
 lever latchset 213
 lockset repair 201
 metal, reversible 194
 mirrored 221
 mirrored, frameless 221
 mobile home..... 222
 molded face..... 207-208
 oak..... 210
 pantry 212
 patio..... 214
 patio grille 216
 patio handle 216
 patio lock 216
 patio roller..... 216
 patio threshold..... 216
 patio, aluminum 215
 patio, double 215
 patio, fiberglass 215
 patio, gliding 214
 patio, hinged 214
 patio, sliding 214
 patio, sliding,
 aluminum..... 215
 patio, steel..... 215
 patio, swinging..... 214-215
 patio, vinyl 215
 pet 216
 pet, cat..... 216
 pocket..... 222
 prehung 186, 197
 red oak..... 192
 removal..... 35, 197
 repair 175, 191
 replacement..... 175
 replacement
 procedure 185
 screen..... 203
 screen, installation..... 202
 screen, metal..... 203
 screen, pine 203
 screen, replace..... 203, 216
 screen, steel 203
 screen, vinyl 203
 screen, wood 203
 security 205
 security, Paradise-
 style..... 205
 security, with screen,
 heavy-duty..... 205
 setting trim 184
 shower..... 356, 359-360
 sidelites 198
 slab 192-193
 solid core 192, 197
 steel 198
 steel exterior..... 199
 steel, 6-panel..... 198
 steel, entry..... 198
 steel, exterior..... 199
 steel, prehung..... 198
 steel, prehung, with
 mini-blind..... 198
 stile & rail..... 208
 storm..... 204-205
 storm, all-season 204
 storm, aluminum..... 204
 storm, aluminum
 and wood..... 204
 storm, removal..... 204
 storm, self-storing..... 204
 storm, triple-track..... 204
 storm, woodcore..... 205
 terms..... 188
 weatherstripping 196
 Doors, entry..... 175
 antiquing..... 176
 reassembling 179
 rebuilding..... 178
 refinishing 176
 repairing holes..... 177
 Doors, exterior
 framing and replacing..... 179
 Doors, interior..... 181
 Dormer
 studs..... 75-76
 vents..... 90, 144
 Double bowl kitchen
 sink 329
 cast iron..... 329
 stainless steel..... 328
 Double cylinder door
 handle..... 202
 Double doors 211-212
 Double oven, wall..... 342
 Double-hung windows
 insulated 159
 replacement..... 157
 screens..... 160
 vinyl-clad..... 159
 wood 163
 Double-track storm
 windows..... 165
 Downlight ceiling fixture... 440
 Downspouts
 acid wash 466
 galvanized steel..... 146
 painting labor..... 476
 remove and replace 106
 residential 146
 Drain connector
 garbage disposal to
 dishwasher 341
 Drain stopper..... 336
 flat sink 336
 Drain, waste and vent
 lines, plumbing for..... 393
 Drainboards, countertops... 295
 Drawer front
 cabinet..... 316
 Drawn box
 2-device switch..... 425
 handy..... 424
 octagon..... 425
 Drip cap 141
 door bottom seal 196
 molding, wood 114
 Drip edge..... 142
 aluminum..... 141
 Driveway forms..... 43, 49
 Driveways, concrete 49
 Drop ceiling
 panel..... 255-257
 soffit..... 316
 Drop-in lavatory sink..... 367
 Drum mushroom
 ceiling fixture 441
 Dry ice blasting..... 537
 Dry rot remediation..... 92
 Dry tile grout
 non-sanded 307
 Dryback vinyl wall base... 292
 Dryer, wall cavity 539
 Dry-out..... 529
 Drywall
 arch, bullnose..... 247
 ceiling, demolition..... 315
 ceilings 232
 corner bead 247
 corner tape 249
 demolition..... 34, 242, 316
 demolition, wet 532
 dustless sanding
 system..... 251
 finish 244
 fire code type X 243
 fire-resistant..... 243
 flexible 244
 greenboard 244
 hand sander 250
 hanging..... 228
 installation 242, 244
 J-bead 248
 joint compound..... 245-246
 joint tape..... 246
 J-trim..... 248
 L-trim 248
 mildew resistant..... 243
 moisture resistant..... 243
 moisture-resistant..... 243
 mold resistant..... 243
 nails 249
 outside corner trowel..... 250
 painting..... 483-484
 panel lift 250
 patch..... 242
 primer 246
 repair 242
 repair clips..... 249
 repair kit..... 248
 repair patch 248
 repair sheet 244
 repairing 234
 sander kit..... 250
 sanding respirator..... 250
 sanding sponge 250
 screws 249
 sound deadening..... 243
 spray texture..... 244
 tape 246
 tape, white, fiberglass ... 246
 taping and finishing 230
 texture 244
 texture spray..... 244
 textured finishes 232
 topping compound..... 246
 vinyl outside corner
 bead 248
 Drywall tools
 electronic stud sensor ... 249
 hammer 250
 sander 251
 screw gun, battery-
 powered 249
 screwdriver 249
 screwdriver bit 250
 screws, collated..... 249
 stilts 250
 texture brush 250
 trowel..... 250
 trowel, corner..... 250
 T-square 250
 Dual sensing smoke
 alarm..... 436
 Dual weatherproof
 lampholder & cover 428
 Dual-ionization
 smoke detector..... 436
 Duct
 heating, removal..... 396
 runs, installation 397
 Duct tape 538
 Dumont kitchen sink..... 329
 Dump fees 29
 Dump trucks
 rental 28
 Dumpster 538
 rental 29
 trash..... 29

Duplex receptacle	mechanical systems..... 511	Electrical management	Entertainment sink..... 338
CO/ALR..... 435	plaster..... 509	system, Smart home 444	Entrance cap, PVC..... 422
commercial grade..... 435	plumbing systems..... 511	Electrical non-metallic	Entry doors..... 193, 198-200
handy box cover..... 424	stucco..... 509	tubing conduit..... 427	deco fan lite..... 193
straight blade..... 434	Earthquake damage,	Electrical systems	fiberglass..... 200-201
waterproof cover..... 428	checking for	licensing and code	oak..... 194
Durabase..... 358	before making repairs... 506	compliance..... 410	Epoxy crack repair..... 513
Durastall..... 358	jobsite walk..... 506	National Electrical	Epoxy floor coating..... 495
Duratemp panel siding 111	structural engineer..... 506	Code (NEC)..... 410	Epoxy gloss coating..... 496
Durock backerboard..... 295	Earthquake damage,	power shortfall..... 409	Epoxy mortar..... 306
Durock cement board..... 245	cosmetic..... 497	repairing earthquake	Epoxy primer..... 496
Dust control..... 536	Earthquake damage,	damage..... 511	Equipment costs..... 13
Dustless drywall	increased risk	service upgrade..... 410	Equipment rental
sanding system..... 251	when adding a room..... 504	Eliane ceramic tile..... 297	demolition..... 28
DWV pipe remove &	when making	Eljer..... 329	foundations and slabs 39
replace..... 408	alterations..... 504	Eljer Plumbingware..... 367	Escape window..... 172
	when removing wall	Elkay Mfg..... 328, 338	Estimating home
	bracing..... 505	Embossed basswood	improvement costs
E	Earthquake damage,	molding..... 259	hanging doors..... 5
E.L. Mustee..... 336, 358	structural..... 497	Embossed concrete..... 50	price book..... 6
Earthquake anchor..... 512	Easysills..... 165	Embossed decorative	problems..... 5
Earthquake damage	Eave closure..... 140	molding..... 259	Estwing..... 250
(IBC) seismic safety	Eave vents..... 90	Embossed polystyrene	Eternit..... 139
standards..... 497	Decomesh..... 89	casing..... 265	Excavation..... 41
(IPMC) seismic safety	Eaves painting..... 480	Embossed polystyrene	backfilling..... 40
standards..... 497	Edeck..... 452	molding	fine grading..... 40
(IRC) seismic safety	Edge	base..... 263	footings..... 40
standards..... 497	counter..... 268	chair rail..... 266	rock..... 40
structural	drip..... 141-142	crown..... 268	spreading..... 41
improvements..... 498	flashing, roof..... 143	Embossed prefinished	tamping..... 41
structural	Edge forms, concrete... 40, 43	molding	topsoil..... 41
improvements, (IRC).... 498	Edge protection tile..... 303	chair rail..... 266	Excelon vinyl
structural	Edge pulls..... 222	Embossed tileboard..... 251	composition tile..... 289-290
improvements,	Edge V-plank..... 252	Embossing leveler..... 285	Exhaust fan..... 380
permits for..... 498	Efficiency cast iron	Emergency dry-out	bath..... 378-381
Earthquake damage	kitchen sink..... 329	service..... 529	bath, vertical discharge... 379
prevention	Egg & dart cast molding... 262	Emser International..... 298	ceiling..... 379
anchors, hold-down..... 500	Egg knob locksets..... 202	EMT conduit..... 422, 426	QuietTest..... 380
bracing hillside homes... 502	Eggshell wall paint, latex... 492	45-degree elbow..... 423	timer switch..... 382
bracing, cripple walls..... 500	Elastocaulk..... 136	90-degree elbow..... 423	utility, vertical discharge... 379
bracing, open front..... 501	Elastomastic..... 136	combination coupling.... 424	ValueTest with light..... 380
foundation bolting..... 499	Elastomeric roof coat..... 137	compression connector... 423	vertical discharge..... 379
masonry chimneys,	Elastomeric water-	coupling..... 424	wall..... 379
anchoring..... 503	proofing paint..... 494	offset compression	with heater..... 381
tension ties on	Elastotape..... 136	connector..... 424	with infrared heater..... 381
split-level homes..... 503	Elbow	offset screw connector... 423	Exhauster, roof..... 145
Earthquake damage	45-degree plain end..... 421	set screw connector..... 423	Exit bar..... 226
prevention, FEMA	90-degree..... 423	strap..... 424	Expansion bolt..... 512
recommendations..... 499	90-degree standard	EMT conduit, removal.... 422	Expansion joints
bracing hillside homes... 502	radius..... 421	EMT strap..... 424	concrete..... 46
cripple wall bracing..... 500	EMT 45-degree..... 423	Emulsion, asphalt..... 133	Exposed aggregate finish... 49
foundation bolting..... 499	EMT 90-degree..... 423	Enamel	Exposed aggregate
hold-down anchors..... 500	pulling..... 423	floor & porch..... 495	sealer..... 495
masonry chimneys,	rigid or IMC steel	interior & exterior..... 493	Exposed round conduit
anchoring..... 503	conduit..... 429	latex..... 492	box, non-metallic..... 428
open front bracing..... 501	rigid steel conduit..... 429	oil-based..... 496	Extendable roller..... 291
tension ties on split-level	rigid steel conduit..... 429	painting..... 483-484	Extension kit, jamb..... 216
homes..... 503	service entrance..... 432	wall & trim..... 492	Exterior & interior stain,
Earthquake damage repair	Electric baseboard	Enamel undercoater	acrylic..... 487
chimneys..... 510	heaters..... 404	interior..... 491	Exterior clear finish..... 489
concrete cracks..... 507	Electric cooktop..... 342	Encapsulate mold..... 537	Exterior door jambs..... 194
cracks in plaster	Electric metallic tube	Encapsulated fiberglass	Exterior doors..... 193
and stucco..... 509	conduit..... 422, 426	roll insulation..... 85	fir..... 192
drywall..... 510	Electric metallic tube	Enclosure, shower..... 356	flush..... 192
electrical systems..... 511	conduit removal..... 422	pivot door..... 359	prehung..... 197
epoxy injection..... 507	Electric service panel..... 439	End panel	Exterior jambs, kerfed 194
fireplaces..... 510	Electric space heaters..... 392	base cabinets..... 317	Exterior pain, satin flat.... 494
floors out of level..... 508	Electric wall oven..... 342	cabinets..... 316, 318	Exterior painting..... 466
foundations and slabs... 507	Electric water	wall cabinets..... 319	Exterior sanding,
framing..... 508	heater..... 406-407	Energy-efficient	manhours..... 467
gypsum drywall..... 510	PowerStar™..... 407	electrical upgrades..... 444	Exterior stain..... 487
	tankless..... 407	ENT conduit..... 427	Plus 10..... 487

- Exterior trim, painting 463
 Exterior wall assemblies..... 71
 Exterior window shutters... 167
 Extraction, water..... 529
 Extruded polymer
 molding..... 263
 Eyeball trim light kit 440
- F**
- F channel..... 459
 F connector for
 RG6 coaxial cable 433
 Fabback acrylic
 mirrored sheet 171
 Fabric
 asphalt roofing..... 131
 polyester stress-block... 136
 Factors
 high time painting 466
 painting difficulty 480
 Fairfax faucet,
 two-handle..... 374
 Fairfax kitchen faucet 333
 Fan lite doors..... 197, 201
 Fans..... 444
 attic exhaust 91
 bath 378-381
 bath exhaust..... 378-381
 bath exhaust & heater ... 381
 bath exhaust,
 QuieTTTest..... 380
 bath exhaust, vertical
 discharge..... 379
 bath, premium 379
 SensAire control
 switch 382
 utility exhaust, vertical
 discharge..... 379
 utility, thru-the-wall 380
 wall exhaust,
 chain-operated 380
 Fascia
 aluminum..... 114
 board 76
 staining 473
 vinyl 108
 Fashion Series 252
 Fasteners..... 458-459
 deck screws..... 459
 Fast-setting patch..... 285
 Faucet hole cover..... 335
 Faucets
 bar 338
 bar, single handle 338
 bar, two-handle..... 338-339
 bidet..... 362
 compression, repair..... 352
 kitchen 331-333
 kitchen, two-handle ... 333-334
 kitchen, two-handle,
 with spray 334
 laundry, two-handle 337
 lavatory..... 370-372
 lavatory, adjustable
 center 374
 lavatory, center set ... 371-374
 lavatory, infrared..... 371
 lavatory, two-handle 372
 pressure balanced..... 361
 Roman tub..... 354
 shower and tub..... 360
 supply 374
 tub & shower 360-362
 tub and shower..... 360
 Feather edge additive..... 286
 Federal Emergency
 Management Agency
 (FEMA)
 recommendations..... 499
 structural improvements... 498
 Fees, recycling 29
 Felt
 roofing 133
 roofing, glass fiber..... 134
 scribing 291
 Fence
 demolition 29
 staining labor 474
 Fence & barn paint..... 496
 Fence post preservative... 490
 Fernco 341
 Fiber cement
 lap siding 112
 siding 113
 siding panel 112
 soffit..... 112
 trim for siding..... 112
 Fiber-cement
 roofing 139
 Fibered aluminum
 roof coating..... 137
 Fibered roof coating 137
 Fiberglass
 base sheet..... 133
 bathtubs..... 357
 panels..... 140
 reinforcing membrane... 136
 screen rolls 168
 shower stall 358
 window trim, bath..... 355
 Fiberglass asphalt
 shingles 131
 Fiberglass ceiling
 panel 256-257
 Fiberglass entry
 doors..... 200-201
 Fiberglass insulation
 batt 84
 Kraft-faced..... 84
 roll..... 84-85
 unfaced..... 84
 Fiberglass mat roof patch... 135
 Fiberglass reinforced
 plastic panels..... 253
 Fiberon 452, 454
 Field adhesive, SBS 134
 Field tile
 setting with adhesive 294
 setting with mortar..... 294
 Fill, excavation..... 40
 Filler, crack 136
 Filler strip..... 317-319
 oak..... 321
 wood..... 138
 Film, polyethylene 87
 Finish carpentry
 countertops..... 322
 siding 107
 Finish sealer, high-gloss ... 307
 Finished box cover 425
 Finishes
 exterior clear..... 489
 flat latex..... 492
 floor, oil-based..... 489
 interior classic clear..... 489
 log home gloss..... 489
 rust-resistant..... 496
 stain gel, non-wood 488
 wood..... 487
 Finishing, concrete 49-50
 Finishing compound
 wallboard 246
 Finishing putty, Pergo..... 283
 Fink truss..... 76
 Fir doors 192-193
 Fire doors 192
 Fireblocks 68
 Firebrick..... 115
 Fireplaces
 demolition 115
 masonry, repair 104
 prefabricated 116
 repair 115
 repairing earthquake
 damage 510
 Fire-rated door frames..... 194
 Fire-rated doors 197
 Fire-resistant drywall..... 243
 Fish tape..... 413
 cable snake..... 417
 Fissured ceiling
 panel..... 256-257
 Fixed skylights..... 172-173
 Fixture removal..... 530
 Fixture gasket removal... 352
 Fixture supply lines..... 374
 Fixture valve lines..... 374
 Fixture, light
 ceiling 442
 chandelier..... 442
 chrome bath bar 441
 fluorescent ceiling..... 441
 flush mount ceiling 441
 jelly jar 443
 motion sensing 443
 mushroom flush mount... 442
 outdoor bulkhead..... 443
 outdoor wall lantern..... 443
 remove & replace 441
 wave bath 441
 Fixtures
 troffer fluorescent 258
 U-lamp troffer
 fluorescent..... 258
 Flange kit, load center.... 437
 Flashing
 aluminum roll..... 141
 aluminum siding 113
 angle 142
 copper formed 141
 counterflash 144
 galvanized 141
 gravel stop..... 142
 lead..... 143, 145
 patch..... 135
 pipe..... 143, 145
 removal..... 129
 repair 129
 roll valley 141, 143
 roof 134
 roof edge 143-144
 roof, removal 134
 roof-to-wall..... 144
 service entrance roof.... 432
 shingle..... 144
 step..... 144
 w-valley..... 144
 Flashing cement
 pro-grade 135
 Flashing leaks 118
 Flashing paper, roof 88
 Flashing, pipe, tile roof... 145
 Flat masonry & stucco
 paint..... 494
 Flat paint..... 492
 exterior, satin..... 494
 interior..... 492
 latex..... 494
 Flat sink drain stopper.... 336
 Flex conduit appliance
 connection 417
 Flex screw-in connector... 426
 FlexBond bonding
 mortar 306
 Flexible aluminum
 conduit..... 426
 Flexible armored BX
 cable..... 419
 Flexible bonding mortar... 306
 Flexible connector
 90-degree 426
 90-degree insulated..... 426
 Flexible metal corner
 tape 249
 Flexible steel conduit..... 426
 Flip locks, window 171
 Float, carpet 531
 Float finish, concrete 49
 Floating floor
 installation kit..... 280
 Flood abatement 531
 Flood Company, The..... 490
 Flooding, effects of..... 515
 Floor
 beam 62
 beam, shimming 62
 clamp 281
 decking, subflooring 66
 demolition 35
 furring 72
 joists 64-65
 repairs, framing 62
 slab, concrete..... 49
 staining 475
 Floor & porch enamel..... 495
 Floor & porch oil gloss.... 495
 Floor & wall tile, ceramic... 297
 Floor beams
 decay 53
 reinforcement with
 jack posts 55
 repair 53
 Floor coating, epoxy 495
 Floor covering
 tile, resilient 271
 wood..... 271
 Floor drying system 539
 Floor enamel 495
 Floor finish, oil-based 489
 Floor furnace, gas 404
 Floor insulation 80
 Floor jacks 54
 Floor joist
 demolition 33
 repair 54-55
 Floor molding, hardwood... 278

Floor plank choices	white oak strip 281	Foil	Framing lumber 452
for porches and decks... 450	wood 281	aluminum 88	Framing straps 512
Floor primer 285	wood laminate 283	barrier 88	Franklin Brass 386-387
Floor tile	wood plank 280	Folding doors	French doors 193, 208
ceramic 295-298	wood, installation tools... 281	locks 217	interior, double..... 212-213
granite 299	Flooring installation system	accordion 217	painting labor 471-472
marble 298	lamine floor 284	Footings..... 48	Frenchwood 214, 216
natural stone..... 299	Flooring over concrete..... 276	concrete..... 46, 48	Frieze cast molding 262
parquet 282	Flooring trim 284	continuous 48	FRP panel molding..... 253
Place n Press 289	bamboo 280	demolition 31	FRP wall and ceiling
Saltillo ceramic 299	heart pine 281	excavation 40	panel..... 253
slate 299	Flooring, resilient	keyway..... 48	Full-view storm doors 205
travertine 299	sheet vinyl 274	Forced air furnace 397	Fungicide 92
vinyl 288-289	Flooring, tile	Forced-air heating 391	Furnace
vinyl, slip-retardant 289	ceramic 276	Formica countertops..... 322	coal..... 404
wood 282	ceramic, tips on 277	Forms	counterflow, gas 397
Floor trim, wood..... 279	cork..... 275	board 43	flue 399-403
Floor warming system 305	granite 275	concrete..... 48	gas..... 398
thermostat 305	marble..... 275	curb..... 44	gas, duct..... 396
Flooring	Flooring, wood	footings..... 44	gas, floor..... 404
adhesive for rubber tile ... 290	hardwood..... 272	foundation..... 43-44	gas, thru-wall 404
adhesive for vinyl	lamine 274	keyway..... 44	gas, wall 404
sheet 290	softwood 272	plywood 43	horizontal flow, gas 397
adhesive for vinyl tile..... 290	strip..... 272	stripping..... 44	low boy, gas 396
adhesive for wood 282	Floors, sagging 54	wall 43	oil fired..... 397
adhesive remover..... 285	Floors, wood fixing	Formwork, stripping 44	remove & replace 398
bamboo plank..... 280	squeaks 56	Forsyth composite sink... 330	wood burning..... 404
carpet 308	Flue	Foundation	Furniture
ceramic tile 294	chimney 399	access doors 88	blocking 529
demolition 35, 278, 315	chimney, aluminum 399	anchor 512	moving 529
demolition, wet 533	furnace 399-403	bracket..... 512	Furniture pad 538
hardwood plank 280	Fluidmaster..... 364	crack repair..... 513	Furring
hardwood, sanding..... 281	Fluorescent ceiling	demolition 31	floor..... 72
heart pine plank..... 280	fixture 441	vent..... 88	wood 72
Hevea parquet..... 282	Fluorescent diffuser	vents 88	
installation spacer..... 283	fixture, low profile 441	Foundation and roof	
lamine floor	Fluorescent fixtures	coating, non-fibered..... 129	
underlayment 284	parabolic troffer 258	Foundation and slab	
lamine strip 284	troffer 258	pre-construction	
maple hardwood..... 279	U-lamp troffer 258	checklist..... 38	
maple strip, unfinished... 281	Flush doors..... 219	Foundation bolt..... 512	
molding, lamine 284	bi-fold closet 219	Foundation insulation 86	
molding, wood lamine... 283	birch exterior..... 192, 197	Foundations	
Northwoods hardwood... 278	birch interior... 206-207, 210	concrete..... 46-47	
oak 279	fire-rated 192	cracks (active or	
oak parquet 282	hardboard 192	dormant) 37	
oak self-stick parquet 282	hardboard exterior 197	equipment rental..... 39	
oak, solid hardwood 278	hardboard interior..... 206-209	footings..... 48	
Pergo 283	hardwood exterior... 192, 197	forms..... 43	
Pergo underlayment..... 283	lauan exterior..... 192	leaky basement walls 37	
red oak, strip 281	lauan interior... 206-207, 210	repair 37	
removal..... 278	oak entry..... 194	Frame	
repairs..... 62	oak interior..... 206, 210	painting labor..... 471	
rustic oak plank 280	painting labor..... 471-472	sink 334	
sealant, lamine 283	red oak interior 210	Frame wall, aligning 514	
setting with adhesive..... 294	steel exterior..... 198-199	Framed bypass door,	
setting with mortar 294	steel utility..... 198	bathtub 356	
sheet vinyl 286-287	Flush mount ceiling	Frameless corner	
strips, natural wood 279	fixture 441-442	cabinet..... 383	
surface preparation 284	Flush mount light fixture... 442	Frames, door 194	
teak..... 279	Flush valve	Framing	
TrafficMaster lamine... 284	urinal, Sloan Royal 363	cut window opening..... 156	
transition reducer strip... 292	Flute & reed molding 261	damage 53	
transition strip 292	Fluted casing embossed	demolition 33, 270	
trim, hardwood..... 281	polystyrene molding 265	estimating, problems	
underlayment..... 285	Fluted casing	with 53	
underlayment & patch ... 286	prefinished molding 265	interior doors 206, 209	
underlayment skimcoat... 286	Foam insulation 85	partitions, wood 66-67	
vinyl roll 286-287	Foam underlayment... 283-284	repairs..... 62	
vinyl sheet 287	Foam weatherstripping.... 196	room additions..... 64	
vinyl wall base 293	Foamular XAE 85	straightening..... 514	
water extraction 531		wall studs..... 66	

G

Gable, truss 76
Gable louver, metal 90
Gable vents 89
metal..... 90
power attic..... 92
redwood..... 90
Gabrielle Comfort
Height toilet 363
GAF 130-131, 134, 145
GAFGLAS
ply 4 glass felt 134
Torch and Mop System ... 134
Galvanized bullnose
corner bead 247
Galvanized flashing 141
Galvanized rigid steel
conduit..... 429
Galvanized roofing 138
louver..... 145
Galvanized steel rain
gutters 146
Garage demolition 30
Garage doors 223
bonded steel..... 224
bottom seal..... 223
extension springs 225
hardware 224-225
installation 223
insulated 224
jamb hinge..... 224
locks 224
low headroom kit 224
operators 225
raised panel..... 223

- replacement..... 223
 steel..... 223
 steel, non-insulated 224
 torsion spring..... 223
 trollies, installation 223
 weather seal 224
 Garage slabs 42
 Garbage disposal 339-340
 basket strainer..... 335
 connector, dishwasher
 drain 341
 cord kit..... 340
 disposer 339-340
 mounting assembly 340
 mounting gasket..... 340
 removal..... 315
 sink flange 340
 sink stopper 340
 switch, sink top 340
 Garden windows..... 158
 Gardner 135-136
 Gas breaker, rental..... 28
 Gas cooktop 342
 Gas furnace
 counterflow 397
 exterior wall duct 396
 horizontal flow 397
 interior wall duct 396
 low boy 396
 Gas water heater 405
 power vent..... 407
 tankless 407
 Gasket
 fixture, remove &
 replace 352
 mounting..... 340
 wax, toilet bowl 364
 Gates, security 205
 Gazebo ceiling fan..... 444
 GE Appliances..... 341-342
 Gel stain 488
 General requirements..... 29
 Generator 540
 Genesis kitchen faucet... 332
 Georgetown lavatory
 faucet..... 373
 Georgia-Pacific... 245, 251, 253
 GFCI circuit breaker 437
 plug-on 440
 GFCI receptacle..... 425, 435
 duplex waterproof..... 428
 hospital grade..... 435
 vertical 428
 wet location cover 428
 GFI plug-on circuit
 breaker 440
 Girders, carpentry..... 62
 Glacier Bay..... 331, 333,
 337, 360, 370-372
 Glacier Extensa
 kitchen faucet 332
 Glaslock interlocking
 shingles 130
 Glass
 jalousie 169
 measure & cut..... 170
 Glass block, mortar mix... 306
 Glass cutters 171
 Glass felt, ply 4..... 134
 Glass globe ceiling
 fixture..... 442
 Glazing bead 170
 Glazing compound 170
 Glazing points..... 170
 Glazing putty, remove
 and replace..... 170
 Glazing tool 171
 Glidden 492-495
 Gloss, polyurethane oil... 495
 Gloss & seal, tile 308
 Gloss enamel, alkyd 493
 Gloss finish, log home... 489
 Glue, Pergo laminate
 floor..... 283
 Grade beams
 concrete..... 48
 formwork..... 44
 Granite
 aggregate concrete 46
 countertop 323
 floor tile..... 299
 mortar mix 306
 setting adhesive 306
 tile, natural..... 299
 tile flooring..... 275
 vanity top 377
 Granules, roofing..... 136
 Gravel stop 142
 Gravity heating 391
 Gray Board insulation..... 85
 Grecian cast molding..... 262
 Greek key chair rail 262
 Greenboard 71
 Greenhouse panels 140
 Greenwaste, recycling..... 29
 Greenwich kitchen sink ... 330
 Grilles, door, patio 216
 Ground bar kit
 breaker box 440
 QO load center..... 440
 Ground fault interrupter
 plug-on circuit breaker... 440
 Ground rod clamp..... 432
 Grounding bushing
 insulated metallic..... 430
 Grout
 colorant..... 307
 Saltillo 307
 sanded..... 307
 sealer..... 308
 tile..... 294
 tile, non-sanded dry..... 307
 Grout mix concrete..... 46
 Grouting, concrete..... 50
 GRS conduit..... 429
 removal..... 429
 Guard, window 167
 Guardrail, demolition 29
 Gutters
 acid wash 466
 aluminum..... 146
 flashing cement 135
 galvanized steel..... 146
 painting labor..... 476
 patching material 135
 remove and replace 106
 roof caulk..... 136
 vinyl 146
 Gutting, demolition 30
 Gypboard, painting... 483, 484
 Gypsum
 demolition 34
 greenboard 71
 Type X..... 71
 Gypsum base, Imperial ... 245
 Gypsum board
 DensArmor 243
 Gypsum lay-in ceiling
 panel..... 257
 Gypsum panel lift..... 250
 Gypsum wallboard
 demolition 242
 fire code..... 243
 flexible 244
 installation 242, 244
 joint cement..... 246
 joint tape 246
 mold resistant..... 243
 primer 246
 repair 242
 spray texture..... 244
 water resistant..... 243
H
 Hammer, drywall 250
 Hampton Bay™..... 441, 443
 Hand sander 251
 drywall 250
 Handle sets 216
 double cylinder 202
 entry door..... 202
 Handrail
 painting..... 481
 patio deck 455
 Handy box
 cover, blank 424
 drawn 424
 welded 424
 Hanger bracket, lavatory... 369
 Hangers, pocket door..... 222
 Harbour Collection..... 289
 Hardboard
 lap siding 112
 panel siding 111
 Hardboard doors 192,
 207, 209
 fire-rated 197
 Hardboard siding 100
 Hardibacker 295
 Hardie 112
 Hardipanel 112
 Hardiplank 112
 Hardisoffit 112
 Hardware
 bi-fold door 221
 door, patio 216
 garage door 224-225
 pocket door..... 222
 screen door 203
 Hardwood
 flooring demolition 315
 molding, embossed 259
 molding, Victorian base... 259
 paneling 251
 Hardwood doors 192
 fire-rated 192
 prehung 197
 Hardwood flooring
 demolition 35
 maple..... 279
 molding..... 278, 280
 oak..... 278-279
 removal..... 278
 rosewood..... 279
 sanding..... 281
 strip..... 278
 TapTight 280
 trim..... 281
 Hardwood molding 259,
 278, 280
 Bruce parquet..... 282
 Harris-Tarkett... 278, 280-281
 Hartland cast iron
 kitchen sink..... 330
 HazMat protection 538
 Headers, carpentry..... 68
 Headroom kit 224
 Heart pine
 flooring trim..... 281
 plank flooring 280
 Heat recovery ventilator
 retrofit 406
 Heat-A-Lamp bulb
 heater & fan..... 381
 Heat-A-Ventlite heater.... 382
 Heaters
 baseboard, electric..... 404
 water, gas..... 405
 whirlpool bath
 EZ-Install 354
 Heating duct, removal 396
 Heating system
 component removal..... 396
 Heating systems,
 electric space heaters ... 392
 hot water, radiant
 heating 392
 Heating systems, warm air
 forced-air 391
 gravity 391
 Heating, hydronic 398
 Helmman spar
 urethane 488
 Hemlock doors 212
 Henry 133, 135-137,
 254, 285-286, 290
 HEPA central air
 filtration retrofit..... 398
 HEPA vacuum 540
 Hevea parquet flooring.... 282
 High boy threshold, oak ... 195
 High early strength
 concrete..... 47
 High time factors 466
 High-gloss enamel..... 493
 High-gloss finish sealer ... 307
 Hinges
 cabinet..... 328
 cabinet, Euro 327
 door 196
 garage door 224
 solid brass 196
 Hip and ridge shingles.... 130
 Hip shingles..... 131
 Hold-down anchor 512
 Hole cover, faucet 335
 Hollow core doors..... 207
 Hollow metal doors..... 194
 Homax 493
 HomeLine
 circuit breaker..... 437
 indoor main lug load
 center 437
 HomeStyle
 suspended ceiling..... 256

Hood	Ingenium Flushing	oak, flush	Joint repair, concrete
range	System	pine	Joint tape
range, quiet	Innovations lavatory	pine louver	drywall
range, vented	faucet	prehung	Joints, expansion
Hooks	Inside corner & cove	prehung	Joists
robe	molding	Interior flat paint	bridging
Hopper gun, ceiling	Inside corner bead	Interior latex	ceiling
finish	metal	eggshell	demolition
Hopper vinyl window	Inside corner molding	flat finish	floor
Hospital grade	polystyrene	paint, semi-gloss	TJI
receptacle GFCI	prefinished	Interior paint	J-trim, metal
Hot mix, spreading	In-Sink-Erator	Interior painting	Jubilee White Ice
Hot water dispenser	Instl-X	Interior sanding, labor	beaded paneling
Hot water heating	Installation kit	Interior trim	Junction box
systems	floating floor	baseboard	Junior basket strainer
Hotmopping, roofing	Pergo	casing	
House wrap	Installation system	molding	
Hub	laminated flooring	Interior wall assemblies	K
bolt-on A type	Insulated grounding	Interlocking shingles	Karnak
universal	bushing, metallic	Intermatic	Key locks, sliding
watertight conduit	Insulating bushing	Intermediate metal	window
Humidifier, central	high-impact	conduit	Keystone
HVAC	thermoplastic	International	Keyway form
central air conditioning	Insulation	Thermocast	Kick plates, door
cleaning	blow-in cellulose	In-wall spring wound	Kicker, garage door
component removal	board	timer	Kickplate channel
hydronic heating	board, demolition	Island sink, polycast	Kickplate coil
hydronic heating	built-up roofing,		Kidde
system	patch		KILZ
radiator, cast iron	ceiling		sealer, primer
removal of	FBX		& stainblocker
components	fiberglass	J	exterior sealer primer
restoration	fiberglass batt	J A Manufacturing	stainblocker
Hydraulic door closers	fiberglass, unfaced	334,	
Hydraulic jacks	floor	339, 361, 371, 374	Kitchen
Hydronic heating	foam	Jack roof	appliance removal
Hydro-X Vacuum	foundation	Jack posts	cabinets, removal
Hygienist, industrial	masonry	Jackhammer, rental	countertop
	natural fiber	Jalousie windows	countertop
	polystyrene	aluminum	Kitchen cabinet doors
	pouring	operators	Kitchen cabinets
	R-Gard	replacement glass	base
	rock wool	vinyl	wall
	roof, perlite	Jamb extension kit	Kitchen countertop
	SAFB	Jamb sets	miter bolt kit
	sill gasket	finger joint	Kitchen faucet
	sound control	interior	deck spray
	urethane sheathing	solid clear pine	pull-out spout
	vapor barrier	with hinges	single-handle
	vermiculite	Jams	two-handle
	wall	exterior	Kitchen sink
	Interior pressure wash	exterior door	Beaumont
	Interior & exterior stain	exterior, remove &	cast iron
	acrylic	replace	composite
	Interior acrylic latex	interior, remove &	double bowl
	paint	replace	Iveness
	Interior doors	pocket door	Newport
	birch, flush	Jameco	polycast
	cafe	James Hardie	single bowl
	fir	112, 295	stainless steel
	fire-rated	Jasco	Kitchen sink basket
	flush	490-491, 495	strainer
	half louver	J-bead	Spin-N-Lock
	hardboard	metal	washer
	hardboard, colonist	plastic	Kitchens
	hardboard, flush	J-channel	appliances
	heater closet	thermoplastic	cabinets and counters
	hemlock, prehung	vinyl	cabinets and counters,
	knotty alder	Jeffrey Court	costs
	lauan	Jelly jar fixture	cabinets and counters,
	lauan, flush	Job Cost Wizard	custom-made
	oak	9	cabinets and counters,
		Job survey (scope of	refinishing
		work)	
		11	
		Joint cement, lightweight	
		245	
		Joint compound	
		246	

- design 309
 electrical service
 checklist 315
 remodeling checklist 313
 work triangle 310
 Klean-Strip 487
 Knob and tube wiring 411
 Knobs, cabinet 324-326
 Knock down door
 frames 194
 Knockdown ceiling 245
 Knockdown drywall
 texture 244
 Knockdown stucco 493
 Knockers, door 213
 Kohler 328-330,
 332-333, 353-354, 363,
 366-369, 371, 374
 Kool Patch acrylic roof
 patching cement 135
 Kool Seal 135
 Kraft-faced fiberglass
 roll insulation 84
- L**
- Labor costs 12
 hourly 16
 jobsite conditions 13
 Labor
 high time painting 466
 Labor, manhours
 apply acoustic ceiling
 texture 469
 apply masonry block
 filler on brick masonry 476
 burn off paint 466
 caulking 466
 cutting-in 466
 masking 466
 paint, stripping 467
 painting aluminum 482
 painting baseboard 468
 painting bookcases and
 shelves 468
 painting cabinets 469
 painting closet shelf &
 pole 470
 painting concrete
 floor 474-475
 painting (CMU) 477-478
 painting decorative wood
 handrail 481
 painting door frame &
 trim 471
 painting exterior
 French door 471
 painting exterior louver
 door 471
 painting exterior panel
 (entry) door 471
 painting exterior plaster
 for stucco 480-481
 painting flush exterior
 door 471
 painting gutters &
 downspouts 476
 painting gypsum
 drywall ceiling 484
 painting gypsum drywall
 walls 483
 painting interior flush
 door 471-472
 painting interior French
 door 472
 painting interior louver
 door 472
 painting interior panel
 door 472-473
 painting molding or trim 479
 painting roof
 overhang 479-480
 painting shutters or
 blinds 481-482
 painting smooth brick
 masonry 477
 painting tongue &
 groove ceiling 469-470
 painting windows 486, 487
 painting wood deck or
 floor 475
 painting wood paneled
 walls 485
 pressure washing
 (waterblasting) 468
 repaint home exterior 466
 repaint home interior 466
 sandblasting 467
 sanding, exterior 467
 sanding, interior 466
 staining fascia 473
 staining picket fence 474
 staining rough wood
 siding 482
 staining tongue-and-groove
 ceiling 470
 staining wood deck or
 floor 475
 staining wood paneled
 walls 485
 wash down 467
 waterblasting (pressure
 washing) 468
 Lag screws
 drill tip suspension 255
 Laminate flooring
 finishing putty 283
 glue 283
 installation spacer 283
 installation system 284
 molding 284
 Pergo Presto 283
 sealant 283
 strip 284
 TrafficMaster 284
 trim 284
 underlayment 283-284
 Laminate shingles
 architectural 130
 Laminated plastic
 countertops 322-323
 Laminated plastic
 countertop 324
 Lampholder & cover
 dual weatherproof 428
 Lantern
 curved glass wall 443
 motion sensing 443
 outdoor wall 443
 Lap
 cement 133
 Lap siding
 fiber cement 112
 hardboard 112
 OSB 111
 spruce 110
 textured 111
 Lasco Bathware 356-357
 Lascoat 356
 Latch, knob
 passage 213
 Latchsets
 privacy lever 213
 privacy, egg knob 213
 Latex glazing compound 170
 Latex paint
 eggshell 492
 enamel 492-493
 exterior 494
 flat finish, interior 492
 masonry & stucco 494
 semi-gloss 493
 waterproofing 494
 Latex primer
 PVA 491
 resilient flooring 285
 Lattice molding 269
 Lauan doors 206-207, 210
 flush 192
 Laundry faucet
 two-handle 337
 wall mount 337
 Laundry tub
 double bowl 337
 overflow tube 337
 single bowl 336
 Utilatub 336
 utility kit 336
 Lavatory base 367
 Lavatory bowl 366
 Lavatory faucet
 adjustable center 374
 decorator 373
 hands free 371
 hi-arc 373
 single-handle 370-371
 single-handle, zinc 370
 two-handle 371-374
 two-handle, acrylic 371
 two-lever 371
 Lavatory hanger bracket 369
 Lavatory leg set 367
 Lavatory sink 367-369
 above counter 369
 Cadet 368
 drop-in 367-368
 Farmington 367
 Laurel 368
 Magnolia 369
 Miami 369
 Murro 369
 oval 368
 Ovalyn 368
 pedestal 366
 Radiant 368
 Reminiscence 369
 removal 367
 Renaissance 367
 round 368
 Seychelle 367-368
 Summit 368
 under counter mount 368
 wall hung 369
 wall hung, corner 369
 Lavatory trap, remove
 & replace 352
 Lay-in ceiling panel
 gypsum 257
 LB conduit body, PVC,
 Type LB 421
 LDR Industries 335
 Lead flashing 143, 145
 Leak Sentry toilet fill
 valve 364
 Leak Stopper rubberized
 roof patch 135
 Leaks roof penetrations 120
 LED lighting system
 retrofit 444
 Ledgers 73
 Leg set, pedestal
 lavatory 367
 Lenape 304-305
 Let-in bracing 67
 Let-in ribbons 73
 Leveler, embossing 285
 Lever locksets 202
 Leviton 434-435
 Lexan XL-10 171
 L-flashing 143
 Lift sash 166
 Light bar
 beveled 384
 medicine cabinet 384-385
 Light fixture
 ceiling 440
 chandelier 442
 chrome bath bar 441
 drum, mushroom 441
 jelly jar 443
 mushroom flush mount 442
 outdoor bulkhead 443
 remove & replace 441
 wave bath 441
 Light kit
 mini can 440
 mini can recessed
 eyeball 440
 recessed 440
 recessed non-IC baffle 440
 slot aperture 440
 Light-emitting diodes 444
 Lighting
 motion sensor 443
 recessed 440
 Lighting fixtures, soffit,
 kitchen 316
 Lighting panel
 acrylic 258
 styrene 258
 Lights, suspended troffer
 fixture 258
 Lightweight concrete 46
 Linoleum, sheet
 demolition 35
 Liquid underlayment 285
 Liquid-tight flexible
 conduit, Carflex 427
 Listello tumbled marble
 tile 300
 Litex 493
 Lithonia Lighting 441
 Load center
 combination ring type 437
 flange kit 437
 ground bar kit 440

HomeLine indoor main lug..... 437	Main lug load center..... 439	light bar..... 384-385	Miter bolt kit..... 324
indoor main lug..... 438	HomeLine indoor..... 437	lighted..... 383	Mobile home doors..... 222
outdoor..... 439	indoor..... 438	mirrored..... 383	Modified bitumen adhesive..... 133
Loading trucks..... 40	Mallet, rubber..... 291	octagonal..... 383	Moen..... 332, 360, 362, 370, 373-374
Locknut steel sealing conduit..... 430	Man-O-War marine spar varnish..... 488	oval..... 383	Moisturbloc polyethylene film..... 284
Locks	Maple plank flooring..... 280	single door..... 383	Moisture barrier polyethylene..... 284
deadbolt..... 202	Maple hardwood flooring, solid..... 279	sliding door..... 383	Moisture-resistant drywall..... 243
door, folding..... 217	molding..... 279	swing door..... 383	Mold
garage door..... 224	Maple strip flooring..... 281	tri-view..... 384	abrading..... 537
installation..... 201	Marble countertop..... 376	Medium density fiberboard molding..... 261	blasting..... 537
patio door..... 216	floor tile..... 298	Megatrade..... 297	containment structure..... 536
sash..... 166	Listello tumbled tile..... 300	Melard..... 367	encapsulation..... 537
sliding window..... 171	mortar mix..... 306	Membrane anti-fracture..... 305	protective equipment..... 538
window flip..... 171	mortar adhesive..... 306	fiberglass reinforcing..... 136	removal..... 537
Locksets	threshold..... 300	polyethylene tile, anti-fracture..... 305	sampling..... 535
and deadbolt..... 202	tile..... 298	tile, anti-fracture..... 305	testing..... 535
colonial knob..... 202	tile flooring..... 275	Memoirs pedestal lavatory bowl..... 366-367	Mold and mildew
egg knob..... 202	tile notch trowel..... 291	Mesh, crack repair..... 248	sanitizer..... 531
installation..... 201	Marine varnish..... 488	Metal conduit	inspection..... 535
keyed entry..... 201-202	Markup vs. margin..... 7	flexible..... 426	remediation..... 535
lever..... 202	Masco..... 361, 372-373	galvanized..... 429	by job size..... 526
Log cabin siding..... 110	Mask, safety..... 250	Metal corner bead..... 247, 249	cleaning methods..... 528
Log home gloss finish..... 489	Masonite Corp..... 253	Metal doors..... 194	industrial hygienist..... 526
Log lap siding..... 110	Masonry	bi-fold..... 220	insurance coverage..... 525
Longstrip oak flooring..... 279	chimneys, repair..... 104	rust converting..... 496	sampling and protocol..... 527
Louver	cleaning..... 115	Metal primer..... 496	Mold remediation
gable..... 90	demolition..... 30	Metal screen doors..... 203	protocol..... 535
roof..... 145	fireplace demolition..... 115	Metallic grounding	Mold Retarder..... 92
roofing..... 145	fireplaces..... 115	bushing..... 430	Molded face closet doors..... 220
Louver doors	fireplaces, repair..... 104	insulated..... 430	Molded sectional shower stall..... 357
painting..... 471-472	furring..... 72	Meter main load center..... 437	Molding
Louvered doors..... 212	insulation..... 87	Meter socket..... 437	base..... 263-264
Louvered exterior window shutters..... 167	joints..... 115	Metro sheet vinyl flooring..... 287	base cap..... 260
Louvered vents..... 90	painting labor..... 476-478	Microwave oven	base corner..... 259
Louvers	pointing..... 115	Advantium..... 342	base shoe..... 260, 264
midget..... 91	protective coating..... 495	over-the-range..... 342	bead..... 260
roof..... 91	recycling..... 29	Midget louvers..... 91	beaded baseboard..... 259
wall..... 91	repainting..... 115	Milban..... 531	brick..... 195
Low voltage wiring..... 414	veneer..... 103	Milban 1-2-3..... 536	casing..... 264-265
Low-Boy toilet kit..... 364	walls, waterproofing..... 130	Mildew resistant drywall..... 243	casing paperwrap..... 265
Low-boy, trash disposal..... 29	Masonry & concrete	Mineral fiber ceiling	casing polystyrene..... 265
Low-sound bath fan	waterproofer..... 495	panel..... 257	cast..... 262
QuietTest..... 380	Masonry & stucco paint..... 494	Mineral siding..... 93	chair rail..... 260, 262, 266
Low-voltage light kit..... 440	Masterchem..... 492, 494	asbestos cement..... 94	chair rail paperwrap..... 266
L-straps..... 512	Mastic, tile..... 294	asbestos testing..... 94	chair rail polystyrene..... 266
L-trim, drywall..... 248	Material costs..... 11	Mineral surface roll	chair rail prefinished..... 266
Lug load center	Mayfield sink..... 329	roofing..... 133	colonial crown
HomeLine indoor..... 437	Maytag..... 342	Mini can recessed light kit..... 440	paperwrap..... 268
Lumber	MDF	Miniature circuit breaker	cove..... 268
alternative building materials..... 457	casing..... 261	QO..... 439	crown..... 259
deck..... 453-454	chair rail..... 261	Minwax..... 487-489, 491	crown embossed polystyrene..... 268
pressure treated..... 452	molding, base corner..... 261	pickling stain..... 488	crown polystyrene..... 268
recycled plastic..... 457	molding, colonial base..... 261	polycrylic..... 489	crown prefinished demolition..... 34
Thompsonized..... 454	molding, crown..... 262	polyshades..... 488	embossed basswood..... 259
Luna ceiling panel..... 257	molding, plinth block..... 262	polyurethane..... 489	embossed decorative hardwood..... 259
M	molding, ultralite crown..... 262	spar urethane..... 488	extruded polymer..... 263
Magna..... 251	paneling..... 251	Miracle Sealants Co..... 307	hardwood..... 259, 280
Magnetic weatherstrip..... 196	Mechanical systems, repairing earthquake damage..... 511	Mirror bath light bar..... 441	hardwood floor..... 278
Magnolia Brick and Tile..... 300	Medicine cabinet	Mirrored doors	hardwood parquet..... 282
Mahogany doors..... 193	beveled edge..... 383-384	bi-fold..... 221	heart pine..... 281
Main circuit breaker..... 438	bi-view..... 384	bypass..... 218	inside corner..... 266-267
Main load center	etched glass..... 383	Mirrored sheet..... 171	laminated flooring..... 284
combination..... 437	framed..... 383	Mirrors	
	framed door..... 382	frosted..... 382	
	frameless..... 383-384	oval..... 382	
		vanity..... 382	
		Mission tile roofing..... 139	

- lattice 269
MDF colonial base 261
MDF ultralite crown 262
MDF, crown 262
medium density
fiberboard 261
oak, unfinished 281
outside corner 267
painting labor 479
panel 253
paperwrap 263-264
polystyrene 263-265
prefinished casing 264
primed finger joint
base 260
quarter round 261
reversible flute & reed 261
rosette block 259
round edge stop 261
spring cove 268
stool 261
stop 195, 269
stop paperwrap 269
stop polystyrene 269
stucco 196
T-astragal 194
Victorian hardwood
base 259
vinyl tileboard 270
wall base 284
wall, suspended
ceiling 255
Molding set, brick 260
Molding, crown 261
Molding, hardwood 279
rosewood 279
Monticello lavatory
faucet 373
Mop, roof 136
Mortar
acrylic admix 307
bedding 306
bonding 305-306
CustomBlend thin-set 306
epoxy 306
flexible bonding 306
porcelain 306
thin-set 306
thin-set tile 293
tile 294
tile repair 306
underwater tile repair 307
Mortar mix
glass block 306
marble & granite 306
Mosaic ceramic tile 304
Motion sensor security
light 443
heavy-duty 443
lantern 443
Moulding, hardwood 259
Mount Vernon paneling 251
Mounting assembly
disposal 340
Mounting bracket non-
metallic low voltage 422
Mounting kit, sink 334
Mud
joint cement 245
wallboard 246
Mullions, window 166
Multi gang switch box 425
Mushroom light fixture 442
- N**
Nail plate, stud 419
Nailer strip, carpentry 73
Nailers 73
Nailite siding 107
Nails
drywall 249
vinyl siding 107
National Electrical Code
(NEC) 410
National Estimator 8
Natural Images floor tile 289
Natural stone floor tile 299
Needle beams 62
Negative air scrubber 539
Neo-angle shower kit 358
Neptune 328
Neptune marble
countertop 376
New wood treatment 490
Nipple, rigid conduit 431
NM-B Romex sheathed cable
indoor & outdoor 418
NM-B Romex sheathed
indoor cable 417
Non-fibered roof and
foundation coating 129
Non-metallic
ceiling fan box 422
conduit fitting 421
low voltage device
mounting bracket 422
old work switch box 422
reducer bushing 420
sheathed cable 418
standard coupling 421
UF compression
connector 419
Non-metallic cable 417
Non-metallic sheathed
cable (Romex) 412
Northwoods hardwood
flooring 278
Notched trowels 291
NuTone 343, 378-382
Nylon carpet 308
Nylon paneling rivets 253
- O**
Oak
counter edge molding 268
hardwood flooring 278
molding, unfinished 281
parquet flooring 282
plank flooring 280
strip flooring 278, 281
Oak doors 192, 206, 210
entry 194
Oak fill strip 321
Oak threshold 195
OakCrest Products 282
Octagon box, drawn 425
Octagonal windows 163
Offset compression
connector, EMT-to-box 424
Offset screw connector,
EMT 423
Oil, Danish 488
Oil fired furnace 397
Oil gloss, polyurethane 495
- Oil, teak 491
Oil, tung 491
Oil-based enamel 496
Oil-based floor finish
Varathane 489
Oil-based primer sealer 493
Oil-fired water heater 405
Old work switch box
non-metallic 422
Olefin carpet 308
Opal glass wall light 441
Open light kit 440
Openers, garage door 225
Opening, breakthrough
wall 72
Operators, window 166
Orange peel
ceiling 245
drywall texture 244
Oriental carpet, hang dry 531
Oriented strand board
siding 111
OSB
roof sheathing 77
shear wall 512
sheathing 66, 70
siding 111
subfloor 66
Outdoor ceiling fan 444
Outdoor wall lantern 443
Outlet box
connecting appliance 417
re-connect appliance 417
Outside corner bead,
drywall 248
Outside corner
molding 263, 267
colonial 267
paperwrap 267
polystyrene 267
polystyrene colonial 267
prefinished 267
Outside corner trowel,
drywall 250
Oval light fixture
outdoor bulkhead 443
Oven
double wall 342
microwave 342
microwave, above range 342
wall 342
Overhang, painting 479-480
Overhang painting,
difficulty 480
Overhead doors, garage 223
Owens Corning 130, 144
- P**
Pad, furniture 538
Paint
acrylic latex 492
alkyd 493
barn & fence 496
ceiling 492
elastomeric 494
flat 492, 494
floor & porch 495
gloss 493
house & trim 494
interior 492
latex 494
latex ceiling 492
latex interior 492
masonry & stucco 494
polyurethane oil gloss 495
satin flat 494
semi-gloss 493
semi-gloss latex 493
swimming pool 496
texture 493
wall & trim 492-493
waterproofing 494
Paint additive, Perlite
texturing 493
Paint seal removal 156
Paint stripping
labor 467
Painting
burn off, manhours 466
high-time difficulty
factors 466
Painting and finishing
application methods 464
exterior trim 463
paint color and gloss 462
penetrating stains 463
recoating 461
surface preparation 461
wood preservatives 463
Painting labor, manhours
acid wash 466
baseboard 468
blinds 481-482
bookcases 468
brick masonry 477
burn off paint 466
cabinets 469
caulking 466
ceiling texture 469
ceilings 469-470
closet shelf and pole 470
concrete floor 474-475
CMU 477-478
cutting-in 466
door frame and trim 471
drywall ceiling 484
drywall walls 483
eaves and cornices 480
entry doors 471
exterior doors 471
French doors 471-472
gutters and downspouts 476
handrail 481
house exterior 466
house interior 466
interior doors 471-473
louver doors 471
masking 466
molding 479
paneled walls 485
plaster or stucco 480-481
pressure washing 468
roof overhang 479-480
shutters 481-482
siding 482
stripping paint 467
trim 479
windows 486-487
wood deck 475
Paling, rail 455
Pan, shower 359
Pancake box, ceiling fan 425
Panel molding, FRP 253

Panel siding.....	98	Parquet molding.....	282	Memoirs.....	366	Plank floor clamp.....	281
cedar shingle.....	113	Parquet flooring.....		Memoirs base.....	367	Plank flooring.....	
fiber cement siding.....	112	Hevea.....	282	metal leg set.....	367	bamboo.....	280
fiber-overlaid plywood.....	99	oak.....	282	removal.....	367	heart pine.....	280
hardboard.....	98, 111	oak, self-stick.....	282	Repertoire.....	366	rustic oak.....	280
MDO.....	99	tile.....	282	Seychelle.....	366	wood.....	280
OSB.....	111	Parting stop molding.....	269	Williamsburg.....	366	Plank paneling.....	252-253
particleboard.....	98	Partition walls.....		Peel & Patch water-		beaded.....	252
plywood.....	98, 111	adding.....	270	proofing.....	135	Edge-V.....	252
Panel wallcovering.....		removal.....	70	Peep sights.....	214	Plaster.....	
designer.....	252	Pass & Seymour/ Legrand.....	435	Pellets, dry ice.....	537	demolition.....	34, 242, 316
Panel, ceiling.....	253	Passage latch, knob.....	213	Penetrating stains.....	463	demolition, wet.....	533
acoustical.....	256	Paste wax.....	491	Penetrating wood finish.....		painting.....	480-481
lay-in.....	257	Patch.....		Preserva-Wood.....	487	repair.....	514
lighting.....	258	built-up roofing.....	131-132	Pergo.....	283	veneer.....	246
suspended.....	255-257	drywall.....	248	finishing putty.....	283	Plaster of Paris.....	246
Panel, distribution.....		Elastocaulk roof patch... Elastomastic roof patch... flashing.....	136 136 135	flooring.....	283	Plastering.....	
disconnect & remove.....	437	Kool Patch cement.....	135	flooring sealant.....	283	pool.....	460
Panel, electric service.....	439	PondPatch.....	136	flooring underlayment... installation.....	283 283	spa.....	460
Paneling.....		popcorn.....	245	installation kit.....	283	Plastic.....	
beaded.....	251	roof caulk.....	136	laminated glue.....	283	conduit.....	420
birch.....	252	roof cement.....	135	Presto floor molding.....	283	gutters.....	146
demolition.....	252	roofing.....	134-135	Presto laminate flooring... Pergola patio cover.....	283 459	lumber.....	457
fiberboard.....	251	roofing, cotton.....	136	Perimeter berm.....	530	siding.....	107
FRP.....	253	roofing, wood shingle... underlayment.....	137 285-286	Perimeter wall insulation... Perlite texturing paint additive.....	86 493	Plasticized concrete.....	47
hardboard.....	251	vinyl.....	285	Permanent Bond.....		Plate.....	
hardwood.....	252	Wet Patch roof cement... Wet Stick roof cement... Patching.....	135 135 135	Adhesive.....	133	service entrance.....	
hardwood plank.....	251-252	concrete.....	50	Perma-Shield.....	216	conduit sill.....	432
MDF.....	251	Patio cover, aluminum... Patio doors.....	459 214-215	Pet doors.....	216	single gang Decora wall.....	435
oak print.....	251	aluminum.....	214-215	Phone wall plate.....	433	single gang plastic wall.....	435
pine plank.....	252-253	aluminum, double.....	214	Picket fence.....		stud nail.....	419
plywood.....	251-253	fiberglass, swinging.....	215	staining labor.....	474	Plate cover, toilet base... Plate straps.....	364 513
prefinished.....	252	gliding, vinyl.....	214	Pickling stain.....		Plate, splash.....	344
rivets.....	253	grille.....	216	white wash.....	488	Plates.....	
tileboard.....	251-252	handles.....	216	Picture windows.....	162	carpentry.....	64
trim pack.....	252-253	hardware.....	216	Pier, concrete.....	63	carpentry piecework rates... Platinum lavatory faucet... Plexiglas.....	67 373 171
wainscot.....	253	hinged, vinyl-clad... installation.....	214 214	Pine.....		Plinth.....	455
Panelized shingles.....	113	jamb extension kit.....	216	door casing.....	195	Plinth block.....	259
Panels.....		locks.....	216	door casing, fluted... flooring trim.....	195 281	MDF primed.....	262
fiberglass.....	140	roller.....	216	flooring trim.....	281	Plug.....	
greenhouse.....	140	screen.....	216	plank flooring.....	280	connecting appliance... Plug-on circuit breaker, ground fault interrupter... Plumb bob.....	417 440 291
sun.....	140	screen & track.....	216	screen doors.....	203	Plumb Shop.....	336, 341
Panic bar, door.....	226	swinging, double... threshold.....	214 216	siding.....	108-110	Plumbing and HVAC.....	
Panic door hardware.....	226	vinyl.....	215	108-110.....		bathtub framing.....	395
Pantry.....		Patio roof.....	455	Pine doors.....	208	framing for improve- ments.....	394
cabinet.....	319-321	Patio screens.....		Pine jamb sets.....	209	repairs, cutting floor joists.....	394
doors.....	212	replacement.....	216	Pine planking.....	252-253	repairs, pricing.....	394
Paper.....		Pavement.....		Pine square rosette molding.....	259	repairs, utility walls... Plumbing drain, waste and vent lines.....	395 393
Aquabar.....	87	concrete.....	46, 49	Pine.....		Plumbing systems repair.....	
building.....	134	demolition.....	32	ABS.....	408	earthquake damage.....	511
Moistop.....	88	Paver tile.....	299	ABS replacement of cast iron.....	408	Plumbing vent.....	389
Pyro-Kure.....	88	brick.....	300	copper replacement of cast iron.....	408	relocate.....	389
roof flashing.....	88	Paving.....		copper replacement of galvanized.....	408	Plus 10 Exterior Stain... Ply 4 glass felt.....	487 134
roof underlay.....	88	asphalt.....	51	PVC DWV.....	408	Plywood.....	
Seekure.....	88	concrete.....	46, 49	PVC replacement of cast iron.....	408	roof sheathing.....	77
vapor barrier.....	87	demolition.....	32	Pipe flashing.....	143, 145	sheathing.....	66, 70
Paper holder.....		Paving breaker, rental... Pea gravel, concrete.....	28 46	tile roof.....	145	siding.....	111
toilet tissue.....	304	Pedestal lavatory.....		Pitch pan.....	129	siding, T 1-11.....	111
Paper-faced metal trim... Paperwrap molding.....	247	Bahama.....	366	Pitch pocket.....	129	subfloor.....	66
base.....	263	Classic base.....	367	Pits, excavation.....	40		
casing.....	264-265	leg set.....	367	Place n Press floor tile... Plain end 45-degree elbow.....	289 421		
chair rail.....	266			Planing concrete.....	513		
colonial cap.....	264						
colonial crown.....	268						
inside corner & cove... outside corner.....	266 267						
stop.....	269						
Parabolic troffer.....							
fluorescent fixture.....	258						
Parisa faucet.....	370						
Parks Corporation.....	489						

- Plywood cap molding 263
 Plywood siding 99
 pre-finished 99
 Pneumatic breaker
 rental 28
 Pocket doors
 edge pull 222
 hangers 222
 hardware 222
 jamb 222
 kit, converging 222
 Pointing trowel 291
 Pointing, masonry 115
 Points, glazing 170
 Pole sander 251
 Polish, Boston 491
 Poly bags 538
 Poly sheeting 536
 Polyblend ceramic tile
 caulk 307
 Polycarbonate sheet 171
 Polycast kitchen sink 330
 Polycrylic protective
 finish 489
 Polyester stress-block
 fabric 136
 Polyester carpet 308
 Polyethylene film 40, 87
 moisture barrier 284
 Polyethylene membrane
 Schluter Ditra 308
 Polymer molding 263
 Polyshades polyurethane
 stain 488
 Polystyrene casing ... 264-265
 reversible 266
 Polystyrene insulation ... 85, 86
 Polystyrene molding
 base 264
 base embossed 263
 chair rail 266
 crown 268
 crown embossed 268
 embossed 265
 inside corner 267
 lattice 269
 outside corner 267
 spring cove 268
 stop 269
 Polyurethane
 fast-drying 489
 oil gloss 495
 stain 488
 Polyurethane cast
 molding 262
 chair rail 262
 corner block 262
 cross head 262
 frieze 262
 rope 262
 PondPatch 136
 Pool paint 496
 Pool replastering 460
 Popcorn ceiling
 patch 245
 spray 244
 spray texture 244
 Porcelain
 bath accessory set 305
 mortar 306
 towel bar 305
 Porcelain, glazed floor
 tile 296
 Porch
 columns 455
 columns, aluminum 455
 demolition 452
 enclosure screen 458
 misting system 458
 repair 452
 roof framing 455
 screen frame 458
 support posts 455
 Porch & floor enamel 495
 Porches
 additions 446
 balustrades 448
 columns and posts 447
 elevated decks 448
 Porches and decks
 choices in floor plank 450
 inspecting for decay 445
 maintenance 451
 Portland cement, stucco 114
 Portrait whirlpool bath 354
 Post base, plinth 455
 Posts
 basement 63
 cap 456-457
 carpentry 63
 deck 452-453, 456
 jack posts 63
 porch 452, 455
 wood 455
 Pouring insulation 87
 Power attic gable vents 92
 Power distribution box 540
 Power massage shower
 head 362
 Power vent, gas water
 heater 407
 Power ventilators
 attic gable 92
 roof-mount 92
 Power washing 468
 PowerStar 407
 PowerStream 407
 Power-vent
 water heater 405
 PPE 538
 Pre-drying 529
 Prefinished molding
 casing 264-265
 chair rail 266
 crown 268
 inside corner 267
 inside corner & cove 267
 outside corner 267
 Prefinished paneling 252
 Prehung doors 209-211
 double 212
 exterior 198
 fire-rated 197, 211
 French 212-213
 hardboard 197
 heater closet 210
 installation 197
 interior 212
 oak 212
 pantry 212
 patio, steel 215
 steel 199-200
 steel, exterior, with
 mini-blind 198
 steel, half lite 198
 steel, installation 197
 Prelude 255
 Premium Plus 495
 interior flat paint 492
 primer sealer 493
 satin flat exterior paint 494
 Preserva products 487
 Preservative
 dock & fence post 490
 wood 490-491
 Preserva-Wood
 penetrating finish 487
 Pressure wash interior 530
 Pressure washer 540
 Pressure washing
 manhours 468
 Price Pfister 332-333,
 337, 360-362,
 370-371, 373
 Primed finger joint casing
 colonial 260
 ranch 260
 Primed finger joint molding
 base 260
 base cap 260
 base shoe 260
 bead 260
 brick 260
 chair rail 260
 crown 261
 flute and reed 261
 quarter round 261
 stool 261
 Primed tilt double-hung
 windows 163
 Primer
 adhesive 282
 bonding 493
 clean metal 496
 concrete 493
 epoxy 496
 flooring 285
 gypsum wallboard 246
 latex 491
 metal 496
 resilient flooring 285
 rusty metal 496
 water-based 492
 Primer sealer 494
 oil-based 493
 stainblocker 494
 Privacy latchset 213
 Pro Finisher 489
 Propane water heater 405
 Propane-fired water
 heater 405
 Protection, tile edge 303
 Protector wood 490
 ProtectoWrap 307
 Protocol, mold
 remediation 535
 Provisa range hood 343
 Pro-Wall 3 354
 P-trap remove &
 replace 352
 Pull
 brass-plated spoon-foot ... 327
 cabinet 326-327
 S swirl 327
 wire 327
 wire, solid brass 327
 Pull bar 281
 Pull plates, door 213
 Pulling elbow, 90-degree ... 423
 Pulls, edge, pocket door ... 222
 Pump, water 540
 Pump mix concrete 46
 Pumps, sewer 389
 Purity siding 113
 Purlins, carpentry 76
 Push bar, door 226
 Push plates, door 213
 Pushbutton garage door ... 224
 Putty, finishing 283
 PVA latex primer 491
 PVC faucet supply 374
 PVC conduit
 coupling 421
 elbow 421
 Schedule 40 420
 Schedule 80 420
 PVC conduit body 421
 PVC conduit clamp,
 Snap Strap 420
 PVC pipe 408
 DWV 408
 PVC service entrance
 cap 422
 Pyro-Kure paper 88
- ## Q
- QO circuit breaker
 GFI plug-on 440
 main 438
 miniature 439
 tandem 439
 QO load center ground
 bar kit 440
 QO main lug load
 center 438-439
 Quarry tile 299
 Quarrybasics 299
 Quarter round
 bamboo 280
 floor molding ... 278-280, 284
 molding 263
 primed finger joint 261
 Quick Roof 135
 QuickBooks 10
 QuietTest bath fan 380
 Quietzone 86
 Quik-Tape 248
 Qwik-Gard 440
- ## R
- RACO 424-426
 RADAR Illusion
 ceiling panel 257
 Radiant heating systems ... 392
 Radiator
 cast iron 398
 Rafter
 bay vent channel 88
 spacing 88
 Rafters
 demolition 33
 rough carpentry 75
 Ragione 296

Rail	floor molding..... 278-279	Resilient tile	bow window..... 164
deck..... 456	lamine flooring..... 284	adhesive..... 290	built-up..... 132
painting..... 481	Reducer floor	demolition..... 35	cant strips..... 86
sink..... 302	molding..... 279-280	removal..... 278	deck..... 455
Rail molding	Reducer strip	Resin siding..... 107	demolition..... 33
chair..... 266	tile..... 304	Respirator..... 538	flashing..... 88
embossed polystyrene... 266	vinyl flooring..... 292	sanding drywall..... 250	flashing, removal..... 134
embossed prefinished... 266	Reducing window	Retaining wall forms..... 47	flashing, self-adhesive... 134
paperwrap..... 266	opening size..... 156	Reversible doors..... 194	insulation..... 86
prefinished chair..... 266	Reducing bushing	Reversible flute & reed	louver..... 91, 145
Railing	non-metallic..... 420	molding	membrane..... 132
patio deck..... 455	rigid or IMC..... 430	primed finger joint..... 261	patch..... 135
Rain cap, chimney..... 400	Redwood	Reversible polystyrene	patch, shingle..... 137
Rain gutters..... 146	siding..... 109	casing..... 266	patio..... 455
aluminum..... 146	vents..... 90	R-Gard insulation..... 86	patio cover..... 459
galvanized steel..... 146	Reed & flute molding..... 261	RhinoBoard..... 295	sagging ridge board..... 59
Ranch base paperwrap	Refinishing in-ground	Ribbands..... 73	sheathing, OSB..... 70, 77
molding..... 264	spa..... 460	Ribbons, carpentry..... 73	sheathing, plywood..... 77
Ranch casing..... 195, 265	Reinforcing	Ridge and hip shingles... 130	silicone coating..... 141
Clearwood PS..... 265	bars..... 44	Ridge shingles..... 131	tile, clay..... 139
paperwrap..... 265	membrane, fiberglass... 136	Ridge vent..... 144	tile, concrete..... 140
polystyrene..... 265	slab..... 47	aluminum..... 90	trusses..... 76
primed finger joint..... 260	steel..... 44	Cobra Rigid..... 145	underlay..... 88
Ranch door casing	steel, galvanized..... 45	coil..... 90	urethane spray foam 140
primed finger joint..... 195	Remediation	rigid..... 145	Roof and foundation
Ranch stop molding..... 269	dry rot..... 92	shingle-over..... 145	coatingnon-fibered..... 129
Random textured	mold..... 535	VentSure..... 144	Roof apron..... 143
ceiling panel..... 255	Removal	Rigid conduit	Roof caulk..... 136
Range hood..... 343	appliance..... 530	coupling..... 429	Roof cement..... 135
Ballista..... 343	carpet..... 531	strap..... 431	wet patch..... 135
custom..... 344	fixture..... 530	Rigid insulation..... 85	Wet-Stick..... 135
Provisa..... 343	glazing putty..... 170	Rigid steel conduit	Roof coating
vented..... 343	skylight..... 172	elbow..... 429	acrylic..... 137
RCA..... 433	window..... 156	galvanized..... 429	aluminum..... 137
Ready-mix concrete..... 46	window glass..... 170	installation..... 429	elastomeric..... 137
Rebar..... 44	windows..... 156	removal..... 429	fibered..... 137
Rebond..... 308	Remover	Ring type meter socket ... 437	silicone..... 137
Receptacle	adhesive..... 282	Rings, towel..... 385-386, 388	Snow Roof..... 137
appliance flush mount ... 435	flooring adhesive..... 285	Rivets..... 255	Roof covers..... 164
CO/ALR duplex..... 435	Rental	paneling..... 253	Roof deck
duplex..... 435	air mover..... 539	Robe hook..... 385-386, 388	removal..... 129
duplex straight blade ... 434	dehumidifiers..... 538	Roberts..... 282	repair..... 129
GFCI..... 435	dry ice blaster..... 537	Rock, recycling..... 29	walking..... 140
GFCI, hospital grade ... 435	floor drying system..... 539	Rocker switch, Decora	Roof edge flashing... 143-144
remove..... 434	generator..... 540	AC quiet..... 434	Roof exhaust vent T-top... 145
side-wired single..... 435	gypsum panel lift..... 250	Rockwool insulation..... 87	Roof flashing
Receptacle cover	negative air scrubber... 539	Rod clamp, ground..... 432	chimney..... 400-401
GFCI, wet location..... 428	remediation equipment... 538	Roll, screen..... 168	service entrance..... 432
horizontal duplex	wall cavity dryer..... 539	Roll flashing	Roof framing..... 75
weatherproof..... 428	Repainting a home..... 466	aluminum..... 141	jacking..... 75
Recessed bathtub	Repair shingles, tin..... 144	copper..... 141	Roof jack..... 145
Princeton..... 353	Repair clips, drywall..... 249	Roll roofing..... 134	rubber..... 145
Recessed light kit..... 440	Repair kit	mineral surface..... 133	Roof loading..... 140
Recessed lighting..... 440	drywall..... 248	Roll valley flashing..... 143	Roof openings, cut
Recoating..... 461	toilet..... 364	Roller	for skylights..... 172
Rectangular weather-	Repair mesh, crack..... 248	extendable..... 291	Roof overhang
proof box..... 427	Repair patch, drywall..... 248	painting labor..... 468	painting..... 479-480
Recycler fees..... 29	Repairs, door..... 191	Roller spline tool..... 168	adding..... 61
Recycling	Repertoire pedestal	Rollers, door, patio..... 216	Roof patch
fees..... 29	lavatory bowl..... 366	Roll-on	cotton..... 136
Red cedar, western,	Replace-A-Vent..... 89	texture, acoustic..... 493	rubberized..... 135
siding..... 108	Replacement screen	texture, stucco..... 493	Roof patching cement,
Red Dot..... 427-428	doors..... 203	Rollup doors, garage..... 223	white..... 135
Red oak	Replacement windows	Roman tub	Roof repair..... 58
plank flooring..... 280	vinyl..... 157	filler..... 354	Roof sheathing..... 60
strip flooring..... 278, 281	vinyl double-hung..... 157	trim & rough-in..... 354	Roof turbine vents 91, 146
Red rosin sheathing..... 87	vinyl single-hung..... 158	Romex..... 412	Roof vent
RedGard waterproofing	Replastering	Romex sheathed cable	repair, waterproofing 130
membrane..... 305	pool..... 460	indoor..... 417-418	waterproofing..... 130
Reducer	spa..... 460	indoor & outdoor..... 418	Roof vent kit, bath..... 382
bamboo..... 280	Resilient flooring, sheet	Roof	Roof ventilation..... 83
carpet..... 284	vinyl..... 274	bay window..... 164	

- Roof waterproofing 135
 repair 129
 replace 130
- Roofing
 asphalt 132
 base sheet 133
 broom with scraper 136
 built-up 132, 134
 built-up, patch 131-132
 built-up, tear-off 129
 cement trowel 136
 clay tile 139
 concrete tile 140
 demolition 33
 felt 133
 fiber-cement slate 139
 fiberglass panels 140
 flashing, removal 134
 flashing, self-adhesive 134
 galvanized 138
 granules 136
 gravel 132
 membrane 132
 mop 136
 patch 135
 roll 133-134
 sheet metal 138
 sheets 138
 shingle remover 136
 shingle starter strip 131
 shingles, algae-resistant 130
 shingles, architectural 130
 shingles, asphalt
 fiberglass 130-131
 shingles, hip and ridge 131
 slate 139
 tar 132
 tear-off 129
 tile 140
 tile, clay 139
 tools 136
- Roofing cement, built-up 133
 Roofing fabric, asphalt 131
 Roofing louver,
 galvanized 145
 Roofing material,
 for new roof 122
 built-up 127
 modified bitumen
 (APP and SBS) 127
 shingles, asphalt-
 fiberglass (composition) 124
 shingles, wood 123
- Roofing materials, life
 expectancy 121
 Roof-mount power
 ventilator 92
- Roofs
 flashing leaks 118
 how to measure area 128
 repairs 121
 source of leaks 117
 Roof-to-wall flashing 144
 Rope cast molding 262
 Rope crown cast molding 262
 Roppe 292-293
 Rosette molding 259
 square 259
 Rosette set 195
- Rosewood
 hardwood flooring 279
 flooring trim 279
- Roto hammer rental 28
- Rough carpentry 53
 backing and nailers 73
 bracing 67
 ceiling joists 73
 ceilings and joists 73
 collar beams 75
 collar ties 75
 curbs 75
 dormer studs 75
 floor joists 64
 floor trusses 65
 furring 72
 girders 62
 joists 68
 ledger strips 73
 plates 67
 posts 63
 purlins 76
 rafters 75
 ribbons 73
 roof trusses 76
 sill plates 64
 studding 66-67
 subflooring 66
 trimmers 75
 wall openings 72
 wall studs 66
 window openings 72
- Round conduit box
 non-metallic 428
- Round edge stop
 molding 261
- Royal Mouldings 263-270
- Royelle vinyl sheet
 flooring 287
- Rub, carborundum 50
- Rubber
 mallet 291
 roof jack 145
 wall base 292
 wet patch roof cement 135
- Rubber studded tile 290
- Rubber tile adhesive 290
- Rubberized roof patch 135
- Rust resistant finish 496
- Rustic oak plank flooring 280
- Rustic siding, pine 108, 110
- Rust-Oleum 488-489, 496
- S**
- Sack finish 50
- Saddle & sill 300
- Safety respirator mask 250
- Safety Zone vinyl floor
 tile 289
- Sahara ceiling panels 256
- Saltillo
 ceramic floor tile 299
 grout mix 307
- Salvage, demolition 35
- Sampling, mold 535
- San Marino ceiling fan 444
- Sand, fill 40, 49
- Sand & Kleen 251
- Sandblasting
 manhours 467
 masonry 115
- Sanded grout 307
- Sander
 drywall 250
 gypsum wallboard 251
- Sanding hardwood floor 281
- Sanding sealer,
 waterborne 489
- Sanding sponge 250
- Sanding system
 drywall 251
 dustless 251
- Sanding, paint prep
 manhours 466-467
- Sand-Texture wall texture 493
- Sash
 balance 166
 cord repair 156
 lift 166
 locks 166
 springs, wood window 166
 window, repair 156
- Saturated cotton roof patch
 asphalt 136
- Savannah lavatory faucet 373
- Sawing concrete slab 50
- SBS field adhesive 134
- ScapeWel window 172
- Schedule 40 PVC
 conduit 420
- Schedule 80 PVC
 conduit 420
- Schluter Ditra poly-
 ethylene membrane 308
- Schluter Systems 303-304,
 308
- Scotchguard 532
- Scratch coat, plaster 114
- Screed, rental 39
- Screen
 aluminum rolls 168
 fiberglass rolls 168
 frame kit 167
 patch 168
 porch enclosure 458
 spline 168, 459
 window 168
- Screen doors
 hardware 203
 installation 202-203
 metal 203
 pine 203
 replacement 203
 security, steel 203
 steel, replacement 203
 vinyl 203
 wood 203
- Screen frame 458
- Screen vents 89
- Screen wire 458
- Screens
 patio door 216
 window 160
- Screw gun, drywall 249
- Screwdriver, drywall 249
- Screwdriver bit, drywall 250
- Screw-in connector, flex 426
- Screws
 deck 459
 drywall 249
 drywall to steel 249
 drywall to wood 249
 lag, drill tip 255
 self-tapping 141
- Screws & clips, sink
 mount 329
- Scribing felt 291
- Scrubber, negative air 539
- Seal, garage door 223
- Seal & tile gloss 308
- Sealant, laminate flooring 283
- Sealer
 concrete 495
 exposed aggregate 495
 grout 308
 high-gloss finish 307
 oil-based 493
 painting 483-484
 primer 493
 sanding 489
 sill 86
 tile 308
 tile & stone 307
 water-based 492
 waterproofing 495
- Sealer primer
 stainblocker 494
 water-base 494
- Sealer's Choice 15 Gold 307
- Sealing conduit locknut,
 steel 430
- Seal-Krete 495
- Seam coating kit 291
- Seats, toilet 365-366
- SEBS styrene-ethylene-
 butylene-styrene
 asphalt 135
- Security doors 205
 heavy-duty 205
- Security doors, Paradise-
 style 205
- Security gates, folding 205
- Security light, motion
 sensor 443
- Security storm doors 205
- Seekure paper 88
- Seismic safety standards,
 earthquakes 497
- Self-stick
 parquet flooring, oak 282
 vinyl wall base 293
 wall base 293
- Self-storing storm doors 204
- Self-tapping screws 141
- Semco 305
- Semi-gloss
 latex paint 493
 wall enamel 492
- Senco 249
- SensAire wall control
 switch 382
- Sentinel Products 285
- Sentinel sheet vinyl
 flooring 287
- Septic disposal cartridge 340
- Sequentia 253
- Service entrance
 cap 432
 cap, PVC 422
 device, combination 438
 elbow 432
 meter main load center 437
 roof flashing 432
- Service entrance conduit
 sill plate 432
- Service panel, electric 439

Set screw connector	Shingle starter strip	131	corrugated	113	Single-hung windows	158,
EMT	Shingles		demolition	34	160-161
Setting adhesive, marble	algae-resistant	130	fiber cement	112	Single-texture drywall	
& granite stone	architectural	130	fiber cement shingles	113	brush	250
Seychelle pedestal	asphalt	130	hardboard	100	Sink	
lavatory	asphalt, repair	130	hardboard lap	112	bathroom	367-369
bowl	cedar	138	hardboard panel	111	frame	334
Shake felt	demolition	33	lap	110	hardware	329
Shakertown siding	fiberglass asphalt	131	log cabin	110	lavatory	367-369
Shakes	hip and ridge	131	mineral	93-94	mounting kit	334
siding, replacement	interlocking	130	mounting block, fixture	107	removal	315
cedar	laminated	130	Nailite	107	strainer shank nut	336
Shank nut sink strainer	panelized	113	OSB	111	under counter mount	368
Shaping slopes	roofing	130	painting	482	Sink rail, ceramic	302
Shaw HardSurfaces	siding	113	panel	98	Sink trap remove &	
Shear wall	siding, replacement	105	panelized shingles	113	replace	352
Sheathed cable	slate	139	pine	108	Sink, lavatory	
indoor	tin repair	144	pine rustic	108, 110	Hydra	369
indoor & outdoor	wood	137	pine shiplap	110	Magnolia	369
Romex	wood, repair	137	plywood	99, 111	Morning	369
Type NM-B Romex	ShockWave	536	redwood	109	Reminiscence	369
Sheathing	Shoe molding, base	264	removal	106	Sinks	
board	Shower & bathtub		repair	105	bar	337-338
carpentry	units	356-357	resin	107	bowl	337
demolition	Shower & tub faucet		shingle	113	Breckenridge	331
insulated	single control	360	shingle and shake	100	Cambridge	331
plywood	single-knob	360	shingles, replacement	105	cast iron	329-330
roof	Shower base	358	southern yellow		composite	330-331, 338
T 1-11	Shower curtain rod,		pine	109-110	double bowl	328, 330
Sheathing paper	permanent	389	staining	482	double bowl composite	331
Sheet	Shower door	356	T 1-11 plywood	111	entertainment	338
acrylic	bypass	360	thermoplastic	107	kitchen	329-331
mirrored	hinged	359	touch up paint	108	kitchen, basket strainer	335
Plexiglas	pivot	359	trim	114	mounting clips	329
Sheet flooring	swinging	359	vinyl	96, 107	polycast	330
adhesive	Shower faucet	360-362	western red cedar	108	Silhouette polycast	330
removal	lever handle	361	wood	93	single bowl	328, 330
vinyl	single-knob	360	wood, diagonal	97	stainless steel	328-329
Sheet metal	Shower head		wood, horizontal	97	stainless steel kitchen	328
gutters, downspouts	power massage	362	wood, vertical	97	stainless steel single	
roofing	remove & replace	352	Siding & deck stain	487	bowl	328
Sheetrock	sunflower	362	Siding and roofing, metal	247	utility	337
ceiling panel	Shower pan	359	Siding installation,		Skid steer loaders rental	39
demolition	Shower stall	357	removing old siding	95	Skimcoat patch &	
fire code	demolition	357	Siding, estimating		underlayment	286
flexible	smooth wall	357	procedure	104	Skylight removal	172
installation	three-piece	358	Signature kitchen faucet	332	Skylights	
painting	Shower stall kit		SilentStep	283	acrylic	173
repair	neo-angle	358	Silestone countertop	323	cut roof opening	172
water resistant	round	358	Silhouette polycast		fixed	172-173
Sheets, roofing	Showers	356-357	kitchen sink	330	trimmers	75
Shelf	corner entry kit	358	Silicone roof		tubular	172
bath, with glass	fiberglass	357	coating	137, 141	venting	173
bathroom	stall	357	Silicone sealant		Slab doors	192-194, 206-207
corner	stall kit	357	window caulk	157	installation	191
glass	stall kit, add-on	362	Siliconizer crack filler	136	Slab leveling	513
painting	ShowMe	8	Sill		Slabs	
Shellac, amber	Shutters		door, thermal	195	base	49
ShellGard RTU	painting	481-482	window	165	calculating area	42
Shelves, painting labor	remove and replace	106	window, ceramic	301	concrete	46
Sherwin-Williams	window	167	Sill & saddle	300	finishes	49
Shield, ice & water	Sidelites, steel door	198	Sill plate, service		forms	43
Shim shingles	Sidewalk demolition	31	entrance conduit	432	garage	42
Shims	Sidewalks, concrete	46, 49	Sill plate gasket	86	on grade	49
flooring	Side-wired receptacle,		Sill plates	64	repair	37
stud	single	435	removal	63	Slate	
Shingle flashing	Siding	107, 112	Sill sealer	86	floor tile, natural	299
Shingle and shake siding	accessories, mounting	107	Single bowl kitchen sink		roofing	139
furring, estimating	aluminum	93, 114	stainless steel	328	tile, tumbled	300
Shingle panels	aluminum corrugated	113	Single gang wall plate	435	Sleepers, carpentry	73
Shingle siding	cedar	108	Single receptacle			
cedar	cedar T&G	109	side-wired	435		

- Slide dimmer
illuminated 436
incandescent 436
- Sliding windows 161-162
- Sloan Royal flush valve... 363
- Slopes, shaping 41
- Slot aperture light kit 440
- Smart home electrical
management system 444
- Smoke alarm, dual
sensing 436
- Smoke and CO Alarm 436
- Smoke detectors 416
basic 436
dual sensing 436
dual-ionization 436
- Snap Strap PVC conduit
clamp 420
- Soaker bathtub 353
- Soap dish 386-388
ceramic 304
porcelain 305
- Soap dispenser 335
- Soffit
painting 479-480
wood 73
- Soffit vents, louvered 89
- Soffits
aluminum 114
demolition 34
fiber cement 112
kitchen 316
pendent lighting 316
refrigerator, under
counter 316
removal 106
stucco 114
vinyl 108
- Soil compaction 41
- Solar lens 172
- Solid core doors
birch exterior 192, 197
entry 193
fir entry 193
hardboard exterior... 192, 197
hardboard interior 207
hardwood exterior... 192
lauan exterior 192
prehung exterior 197
red oak 192
red oak exterior 192
- Solid surface countertop... 322
- Solitaire bath fan 381
- Sound baffle, removable... 340
- Sound control 86
- Soundbloc foam
underlayment 283
- Southern yellow pine
siding 109-110
- Spa replastering 460
- Spacer, laminate flooring... 283
- Spacing, rafter 88
- Spanish tile roofing 139
- Spar urethane
Helmman 488
Spar varnish, marine 488
- Spatter ceiling 245
- Spatter drywall texture... 244
- Speaker wire 433
- Speed-Wall
interior latex enamel... 493
PVA latex primer 491
- Spider box, electric 540
- Spin-N-Lock sink strainer... 335
- Splash plate 344
- Spline
screen, porch 459
tool 168
window screen 168
- Split system, remove 398
- Sponge, sanding, drywall... 250
- Spray adhesive 249
- Spray painting, labor 468
- Spray texture 244-246
ceiling 244
wallboard 244
- Spreading soil 41
- Spring cove molding 268
- Spring wound timer
in-wall 436
- Springs
garage door 223
garage, extension 225
window sash 166
- Spruce lap siding 110
- Square box
surface cover 425
welded 425
- Square D 437-440
- Square rosette molding... 259
- Squeeze connector, flex... 427
- Stain
acrylic interior &
exterior 487
concrete 495
deck 487
deck & siding 487
Deck Plus 487
exterior 487
gel 488
Plus 10 487
polyurethane 488
siding 487
white wash 488
wood 488
- Stainblocker
primer sealer 494
water-based 492
- Staining labor, manhours
ceiling 470
fascia 473
paneled walls 485
picket fence 474
siding 482
wood deck 475
- Stainless steel sink... 328-329
double bowl 328
single bowl 328
- Stair nose 284
bamboo 280
molding 278-280
- Stair stringers, basement... 226
- Stairs
basement 226
deck 457-458
demolition 35
porch 457-458
stringers 458
- Stall kit, shower 357
add-on 362
corner entry 358
neo-angle 358
round 358
- Stall, shower 357
fiberglass 358
- Stamped concrete 50
- Stanadyne 334, 360
- Standard coupling
non-metallic 421
- Standard radius elbow... 421
- Starter strip 131
Starter strip, aluminum
siding 114
- Steam cleaning, masonry... 115
- Steel conduit
elbow 429
elbow, rigid or IMC 429
galvanized rigid 429
- Steel doors
entry 199-200
exterior 198-199
exterior, with mini-blind... 198
frames 194
garage 223
installation 197
screen 203
- Steel octagon box cover... 426
- Steel sealing conduit
locknut 430
- Stem wall 48
- Step flashing 141, 144
copper 141
- Sterling Plumbing 354-355, 359
- Stile & rail doors 208
- Stilts, drywall 250
- Stone
base 49
cleaning 115
countertops 323
floor tile 299
roofing 139
sealer 307
setting adhesive 306
slate 139
tile, travertine 298
tile, tumbled 300
- Stonit 139
- Stool molding primed
finger joint 261
- Stop, gravel 142
- Stop fixture supply 364
- Stop molding 195
colonial 269
paperwrap colonial 269
parting 269
polystyrene colonial... 269
polystyrene ranch 269
ranch 269
round edge 261
- Stopper, drain 336
- Stops Rust 496
- Storage, off site 538
- Storage cabinet
bath 383
etched glass 383
Store-in-Door 204
- Storm collar
chimney 400-401
- Storm doors 204-205
aluminum 205
full-view 205
removal 204
security 205
self-storing 204
- triple-track 204
woodcore 205
- Storm windows 149, 165
remove and replace 106
- StormGuard 88
- Straight blade receptacle
duplex 434
- Straightening framing 514
- Strainer
junior basket 338
sink shank nut 336
- Strainer, basin remove
& replace 352
- Strap
EMT 424
rigid conduit 431
- Straps
framing 512
hardware 513
T 513
tie 513
- Stress-block fabric
polyester 136
- Stretch wrap 538
- Stringers, deck stair... 458
- Strip, transition 292
- Strip flooring
laminate 284
maple, unfinished 281
natural wood 279
red oak 281
white oak 281
- Stripping
forms 44
soil 41
- Stripping paint labor 467
- Strips
asphalt roofing starter... 131
cant 137
shingle starter 131
- Structoglas 253
- Stucco
knockdown 493
molding, redwood 196
paint 494
painting 480-481
plastering 114
portland cement 114
removal 106
repair 103, 105, 514
soffit vents 89
texture 493
wall assembly, wood
framed 71
- Stud sensor, electronic... 249
- Stud straightening 67
- Stud wall, demolition 33
- Studding 66
- Studs
carpentry piecework
rates 66
dormer 76
straps 513
wall assemblies 66
- Stump grinder, rental 28
- Stump grinding 29
- Stylistik II floor tile 289
- Styrene suspended
lighting panel 258
- Styrene-ethylene-butylene-
styrene asphalt 135

Subfloor	fish.....	417	Tile	Tile accessory set,	
board sheathing.....	tile backer.....	249	accessories, ceramic.....	porcelain.....	305
OSB.....	Tape-on bead.....	247	accessories, toilet	Tile adhesive	
plywood.....	Tapping block.....	281	tissue holder.....	ceramic.....	293
Subflooring	TapTight		accessories,	resilient.....	290
installation.....	hardwood flooring.....	280	toothbrush holder.....	rubber.....	290
piecework rates.....	hardwood molding.....	280	accessories, towel bar... 305	stone.....	306
Sump pump.....	Tar, roofing.....	132	acoustic, demolition.....	thin-set.....	306
Sundial vinyl sheet	T-astragal.....	194	anti-fracture membrane... 305	vinyl.....	290
flooring.....	Teak flooring.....	279	anti-fracture membrane	Tile adhesive caulk,	
Sunflower shower head... 362	Teak oil.....	491	kit.....	ceramic.....	307
Supply lines.....	Tear-off, roofing.....	129	backerboard.....	backerboard.....	245
toilet.....	Temporary wall bracing.... 67		bullnose, ceramic... 301-302	Tile backer tape.....	249
Supply stop.....	Termin-8 wood		carpet.....	Tile backerboard.....	295
Surface box cover,	preservative.....	490	ceiling.....	Tile cutter, vinyl.....	291
square.....	Terrazzo, demolition.....	35	ceiling, acoustical.....	Tile flooring, cork.....	275
Surface preparation	Testing, mold.....	535	ceiling, tin design.....	Tile forms.....	355
flooring.....	Textolite counters.....	322	ceiling, wood fiber.....	Tile kit, bathtub.....	355
labor.....	Texture		ceramic caulk.....	Tile Perfect.....	307
manhours.....	paint.....	493	ceramic floor.....	Tile repair	
Surface preparation for	paint additive.....	493	ceramic floor & wall.....	mortar.....	306
painting or finishing.....	roll-on.....	493	ceramic wall.....	mortar, underwater.....	307
Surround, bathtub.....	Sand-Texture wall.....	493	ceramic, demolition.....	Tile tool, ceramic.....	291
Surround kit	stucco.....	493	clay, roofing.....	Tile tub wall.....	354
bathtub.....	Texture 1-11 plywood		concrete roof.....	Tile underlayment	
tub wall.....	siding.....	111	demolition.....	Aqua-Tough.....	295
Suspended ceiling	Texture brushes, drywall... 250		edge protection.....	Tile wall kit.....	355
demolition.....	Texture spray, gypsum		finish.....	Tile, ceiling, zero	
installation.....	board.....	244	floor.....	clearance grid system... 255	
installation kit.....	Texture touch-up kit		glazed ceramic.....	Tileboard	
light kit.....	acoustic ceiling.....	244	glazed porcelain.....	batten.....	251
lighting panel.....	Texture, drywall.....	244	gloss & seal.....	embossed.....	251
panel.....	ceiling.....	245	granite.....	Tileboard molding, vinyl... 270	
panel, acoustical.....	spray.....	244, 246	granite floor.....	Tilt double-hung windows... 163	
Suspended ceiling	Textured ceiling panels... 257		grout.....	Timberline Ultra.....	130
panel.....	Textured lap siding.....	111	grout, sanded.....	Timbertex.....	131
systems.....	Texturing paint additive		installation.....	Timer, in-wall, spring	
Suspended ceilings.....	Perlite.....	493	marble.....	wound.....	436
Sweep, door.....	The Association of Bay		marble floor.....	Timer switch.....	382
Swimming pools	Area Governments.....	500	mortar.....	Tin repair shingles.....	144
paint.....	Themes sheet vinyl		mosaic ceramic.....	Tissue holder.....	387-388
refinishing.....	flooring.....	287	natural cork.....	TJ joists.....	65
Switch	Thermal expansion tank... 406		non-sanded dry grout... 307	T-molding.....	280
AC quiet toggle.....	Thermal sill.....	195	parquet floor.....	bamboo.....	280
Decora AC quiet rocker	Thermoplastic siding.....	107	paver.....	wood floor.....	279
remove.....	Thermostat, floor		Place n Press floor.....	hardwood.....	279
sink top.....	warming system.....	305	polyethylene	Toggle switch, AC quiet... 434	
Switch & cover.....	Thermostat cable.....	433	membrane.....	Toilet base plate cover.... 364	
Switch box	THHN copper wire,		quarry.....	Toilet bowl	
drawn 2-device.....	gauge.....	432	reducer strip.....	gasket.....	364
multi gang.....	Thin-set mortar.....	306	repair, mortar.....	reset.....	352
non-metallic old work... 422	CustomBlend.....	306	resilient, demolition.....	Toilet fill valve	
Switches	Thompson's.....	490	roofing.....	anti-siphon.....	364
fan control.....	Thompsonized decking		rubber studded.....	remove & replace.....	352
timer, exhaust fan.....	lumber.....	454	Saltillo ceramic floor.....	Toilet flange, cast iron.... 364	
T	Thoro.....	495	sealer.....	Toilet paper holder... 385-386,	
T 1-11 plywood siding.....	Thoroseal protective		sealer, high-gloss.....	388
T molding.....	coating.....	495	setting with adhesive.... 294	recessed.....	386
wood floor.....	Threaded conduit body... 431		setting with mortar.....	Toilet repair kit.....	364
Tall boy water heater.....	Three gang box		slate floor.....	Toilet seat	
Tall Elite.....	Super Blue, non-		thin-set mortar.....	cushioned vinyl.....	366
Tamping, excavation.....	metallic.....	422	travertine floor.....	molded wood.....	365
Tandem circuit breaker... 439	Threshold		tumbled marble listello.. 300	natural maple.....	366
Tank, thermal expansion... 406	ceramic.....	301	tumbled slate.....	plastic open-front.....	365
Tape	high boy.....	195	tumbled stone.....	wood.....	365
acrylic.....	marble.....	300	vinyl composition.... 289-290	Toilet supply line.....	364
corner bead.....	patio door.....	216	vinyl floor.....	Toilet tank bolt kit.....	364
drywall.....	Thru-the-wall utility fan... 380		wall.....	Toilet tissue paper	
drywall joint.....	Thrutone.....	139	wall, ceramic.....	holder.....	304-305
	Thru-wall furnace, gas.... 404		wood flooring.....	Toilet To Go Kit.....	362
	Tie straps.....	513			
	Ties, collar.....	75			

- Toilets
 cadet..... 362
 Cadet..... 363
 Champion..... 363
 Comfort Height..... 363
 compact..... 362
 Gabrielle..... 363
 Hamilton..... 363
 hook-up kit for low-boy... 364
 one-piece..... 363
 pressure assist..... 363
 San Raphael..... 363
 urinals..... 364
 wall-mount..... 363
 Williamsburg..... 363
- Tongue and groove siding, cedar..... 109
- Tools
 ceramic tile..... 291
 drywall..... 249-251
 glazing..... 171
 roof repair..... 136
 spline..... 168
- Toothbrush & tumbler holder..... 305
- Toothbrush holder... 385-386, 388
 porcelain..... 305
- Top, laminated plastic..... 323-324
- Topping compound wallboard..... 246
- Topping, concrete..... 50
- Topsoil, excavation..... 41
- Torsion springs..... 223
- Touch control lavatory faucet..... 371
- Touch-up kit
 spray texture..... 244
 wood floor..... 278
- Towel bar..... 385-388
 ceramic..... 305
 porcelain..... 305
- Towel ring..... 385-388
- Track, patio door..... 216
- TrafficMaster laminate flooring..... 284
- Transit mix concrete..... 46
- Transition reducer strip vinyl flooring..... 292
- Transition strip
 carpet to tile..... 292
 oak to tile..... 292
- Trap, lavatory, remove & replace..... 352
- Trash bins..... 29
- Trash compactor removal... 315
- Trash pump..... 540
- Travertine
 floor tile..... 299
 stone tile..... 298
- Treads, concrete, finishing... 49
- Treatment, wood..... 490
- Tree removal..... 29
- Trenchers, rental..... 39
- Trenching..... 41
 hand..... 40
- Trim
 aluminum siding..... 114
 bamboo flooring..... 280
 door..... 194
 fiber cement siding..... 112
 hardwood flooring..... 281
 heart pine flooring..... 281
 painting labor..... 471, 479
 window..... 355
 wood flooring..... 279
- Trim & rough-in Roman tub..... 354
- Trim enamel, latex satin... 492
- Trim pack wood paneling... 252
- Trim paint..... 492
 eggshell..... 492
 flat..... 494
- Trimmers..... 75
- Trimming, trench bottom... 40
- Trine..... 436
- Triple-track storm doors..... 204-205
- Troffer fluorescent fixtures..... 258
 parabolic..... 258
 U-lamp..... 258
- Trowel
 drywall..... 250
 outside corner..... 250
- Trowel finishing, concrete... 49
- Troweling machine, rental... 39
- Trowels
 margin notch..... 291
 notched..... 291
 pointing..... 291
- Tru-Glaze 4508 epoxy gloss coating..... 496
- Trusses
 fink..... 76
 gable..... 76
 roof..... 76
- T-square, drywall..... 250
- T-straps..... 513
- T-top roof exhaust vent... 145
- Tub
 laundry..... 336
 utility laundry, kit..... 336
- Tub & shower faucet
 single control..... 360
 single-handle..... 360
 single-knob..... 360
- Tub door
 bypass..... 355
 sliding..... 356
- Tub faucet..... 360-362
 lever handle..... 361
 single-knob..... 360
- Tub, bath, removal..... 352
- Tub, laundry
 hose..... 337
 overflow tube..... 337
- Tubular skylights..... 172
- Tuf-Tex spray texture..... 246
- Tumbled tile
 marble listello..... 300
 slate..... 300
 stone..... 300
- Tumbler & toothbrush holder..... 305
- Tung oil..... 491
- Turbine vent, roof..... 91, 146
- Turned spindle deck rail... 456
- Twinfast..... 249
- Two-gang box, Super Blue, non-metallic..... 422
- Two-handle lavatory faucet..... 372
- Type X gypsum board..... 243
- Tyvec suit..... 538
- Tyvek house wrap..... 88
- U**
 U.S. Ceramic Tile..... 299, 301-303
- UF compression connector non-metallic..... 419
- UF-B sheathed cable..... 419
- U-lamp troffer fluorescent fixture..... 258
- Ultra Silent bath fan..... 379
- Ultra Touch..... 87
- Ultra-Hide
 alkyd gloss enamel..... 493
 interior latex eggshell... 492
 interior latex paint..... 492
 interior paint..... 492
- Ultrasonic, Cleaning..... 530
- Undercoater interior enamel..... 491
- Undercounter refrigerator... 316
- Underground cable, UF-B sheathed..... 419
- Underground feeder compression connector, non-metallic..... 419
- Underlay, roof..... 88
- Underlayment..... 140, 283
 cement-based..... 285
 fast-setting patch..... 285
 foam..... 283-284
 laminate flooring..... 283-284
 liquid..... 285
 roof..... 134
 tile..... 295
 tile backerboard..... 295
- Underlayment & floor patch..... 286
- Underwater tile repair mortar..... 307
- Unfaced fiberglass batt insulation..... 84
- Universal hub bolt-on A type..... 438
- Urethane roof, spray foam..... 140
- Urethane sheathing..... 86
- Urinal flush valve, Sloan Royal..... 363
- Urinals, Dover..... 364
- USG..... 245, 254
 USG Interiors..... 257, 295
- Utilatub laundry tub..... 336
- Utility access door..... 248
- Utility bowl sink..... 337
- Utility cabinets
 birch..... 317
 finished..... 320
 maple..... 321
 oak..... 319, 321
 red oak..... 318
- Utility fan thru-the-wall..... 380
 vertical discharge..... 379
- Utility laundry tub kit..... 336
- Utility sink..... 337
- V**
 V siding, pine..... 108
- Vacuum, HEPA..... 540
- Valance, cabinet..... 316, 319
- Valley flashing
 aluminum..... 141
 roll..... 143
- Valspar..... 488, 491
- ValueTest exhaust fan..... 378
- ValueTest vertical discharge bath fan..... 379
- ValuSeries pointing trowel..... 291
- Valve lines..... 374
- Valves
 angle..... 364
 flush, Sloan Royal..... 363
 flush, urinal..... 363
 toilet, remove & replace... 352
 wall stop..... 364
- Vance Industries..... 334
- Vanguard hardwood flooring..... 280
- Vanity
 Arkansas..... 375
 Charleston..... 374
 Danville..... 375
 Kingston..... 374
 maple..... 375
 Monterey..... 375
 oak..... 374-375
 solid surface sink top.... 377
 Springfield..... 374
 Virginia..... 375
 with drawer..... 375
 with marble top..... 377-378
- Vanity cabinet..... 378
 mirrored with marble top..... 378
 Vanity mirror..... 382
- Vanity top
 granite..... 377
 Neptune shell marble.... 376
 Newport cultured marble..... 376
 oval bowl cultured marble..... 376-377
 rectangular cultured marble..... 376
 shell bowl cultured marble..... 376-377
- Vanity top and bowl cultured marble..... 377
- Vapor barrier..... 40, 81, 283
 blanket insulation..... 82
 paper..... 87
 perm rating..... 82
 vapor-resistant coating... 82
- Vapor retarder..... 92
- Varathane
 exterior classic clear.... 489
 exterior clear finish..... 489
 interior classic clear.... 489
 oil-based floor finish.... 489
- Varnish, marine..... 488
- Velux..... 172-173
- Veneer base board..... 245
- Veneer plaster..... 246
- Vent
 plumbing..... 389
 soffit..... 89

Vent channel, rafter bay 88	Vinyl flooring	Wall kit	Water
Vent kit, bath 382	removal..... 278	bathtub 354	blasting 115
Vent, roof	roll..... 286-287	tile..... 355	extraction 529
dormer 144	sheet..... 286-287	tub 354	Water Claw 531
ridge 144-145	transition reducer strip... 292	Wall lantern 443	Water closet
T-top exhaust 145	Vinyl flooring tools	Wall light, opal glass 441	flange, cast iron 364
turbine 146	roller, extendable 291	Wall louvers 91	toilet 362-363
waterproofing 130	Vinyl sheet flooring 287	Wall materials	Water damage
Vented range hood 343	Vinyl siding	ceiling tile..... 236	cleanup 524
Ventilation	mounting block 96	drywall 227	contaminated flood-
attic 83	trim pieces 96	gypsum wallboard 227	water 516
crawlspace 82	Vinyl tile	lath and plaster 227	dryout 515
roof 83	adhesive 290	wood paneling 235	restorative drying 515
Ventilator, bath 382	cutter..... 291	Wall oven 342	Water damage and mold
Ventilator retrofit, heat	Vinyl tile cutter 291	double 342	remediation 515
recovery 406	Vinyl tileboard molding ... 270	Wall paint 492	insurance coverage 515
Ventilators, power 92	Vinyl wall base	eggshell 492	(OSHA) 516
Venting skylights 173	dryback 292	latex 492	personal protective
Ventlite doors	self-stick 293	Wall plate	gear 516
fiberglass exterior 201	Vinyl-clad	coaxial cable..... 433	Water damage, dryout
steel exterior 199	wood awning windows ... 160	decorator phone 433	air movers 518
Vents	wood casement	single gang Decora 435	basement 520
attic 91	windows 160	single gang plastic 435	concrete block 520
cedar 90	wood windows 159	Wall registers,	dehumidifiers 518
continuous 89		installation 397	desiccants 518
dormer 90	W	Wall stop 364	electric system 521
eave 90	Waferboard 111	Wall surround kit	floor cover 520
foundation 88	Wainscot, tile 294	bathtub 355	floors 520
gable 89-90	Wainscot paneling 253	tub 355	gas and oil appliances... 521
louvered 90	Walkway	Wall texture	hygrometer 518
redwood 90	demolition 31	Sand-Texture 493	insulation 519
ridge 90	forms 49	Wall tile, ceramic 301, 303	paneling 520
roof turbine 91	Walkway forms 43	Wallboard	plaster 519
screen 89	Walkways, concrete 49	demolition 34, 316	stucco 519
soffit 89	Wall	L-trim 248	wallboard 519
under eave 89	bathtub 354-355	mold resistant 243	wallcovering 520
VentSure ridge vent 144	braces 67, 513	painting 483-484	wood 519
Vermiculite insulation 87	fireblocks 68	primer 246	Water damage, dryout,
Vertical discharge bath	opening, breakthrough ... 72	sander 250	structural drying
fan 379	plates 67	texture spray 244	air movers 522
ValueTest 379	straightening 514	Wallboard stilts 250	ceilings 522
Vertical discharge utility	tub 354	Wallcovering, designer	hardwood flooring 523
fan 379	Wall & floor tile, ceramic ... 297	panel 252	negative air scrubbers... 523
Vibrators, rental 39	Wall and ceiling panel	Wall-mount lantern,	walls 522
Victorian base molding,	FRP 253	curved glass 443	Water dispenser 336
hardwood 259	Wall and ceiling repair 227	Wall-mounted lavatory,	Water extraction 529-531
Victorian lavatory faucet... 373	Wall base	removal 367	carpet 531
Viewer, door 214	molding 284	Walls	hard surface 531
Villeta faucet 370	rubber 292	adding 241	Water hammer 393
Vinyl	self-stick 293	concrete 47	arrester 407
bay windows 158	strip, vinyl 293	demolition 30	Water heaters 394
circular windows 159	thermoplastic 292	painting 480-485	100-gallon commercial... 405
door bottom 196	vinyl 292	partition, adding 270	Ariston 407
double-hung	Wall bracing 512	removal 239	bracing 512
replacement windows ... 157	Wall cabinets 317-319	setting with adhesive 294	connection 512
fascia 108	end panel 319	setting with mortar 294	electric 406-407
garden windows 158	finished 321	staining 485	electric, tankless 407
hopper windows 159	oak 321	tile 294	FVIR 405
jalousie windows 159	square 320	Warming system	gas 405
patch 285	washer dryer 319	ceramic tile floor 305	gas fired 405
screen doors 203	Wall cavity dryer 539	thermostat 305	gas, tankless 407
siding 107	Wall control switch 382	Wash down, manhours... 467	high altitude 405
siding removal 106	Wall demolition 31	Washer kitchen sink	oil fired 405
siding repair 105	Wall enamel, latex satin ... 492	basket strainer 336	point-of-use 407
single-hung windows 158	Wall exhaust fan	Washer dryer wall	PowerStream 407
soffit 108	chain-operated 380	cabinets 319	power-vent 405
Vinyl composition	Wall finish, demolition,	Washing	propane 405
tile 289-290	wet 532	masonry 115	propane fired 405
Vinyl drywall outside	Wall forms, concrete... 43, 47	pressure 468	tall boy 405
corner bead 248	Wall framing 57	Washing, paint prep,	Water pipe, remove &
Vinyl floor tile 288-289	Wall framing 57	manhours 467	replace 408
Vinyl floor tile,	Wall furnace, gas 404	Waste disposal 29	Water pump 540
slip-retardant 289	Wall insulation 80	Watco 488	Water resistant gypsum
			board 243

- Water Seal waterproofer... 490
 Water shield 88
 Water supply, low water pressure 393
 Water surge shock absorber 407
 Water table 38
 Water-based primer..... 493
 Water-based wood stain ... 488
 Waterblasting
 manhours 468
 masonry 115
 Waterborne sanding sealer..... 489
 Waterfall kitchen faucet... 333
 Waterproof, concrete & masonry 495
 WaterSeal..... 490
 Waterproofing
 masonry walls..... 130
 material..... 135
 membrane 305
 metal roof 135
 paint, elastomeric 494
 paper 88
 roof vent 130
 roof, remove & replace... 130
 roof, repair 129
 sealer..... 495
 wood protector..... 490
 Watertight conduit hub 430
 Watts Radiant..... 305
 Wave bath light fixture..... 441
 Wax
 bowling alley..... 491
 paste..... 491
 Wax toilet bowl gasket 364
 Weather head..... 432
 PVC 422
 Weatherproof blank cover, non-metallic 428
 Weatherproof conduit box..... 427
 Weatherproof electrical box, 2 gang 427
 Weatherproof lampholder & cover 428
 Weatherproofing 88
 Weather-resistant wood coating..... 488
 Weatherstripping
 aluminum, adjustable 196
 foam..... 196
 garage door 223
 magnetic..... 196
 vinyl, remove & replace ... 196
 window seal sets 171
 Weco 307
 Welded handy box..... 424
 Welded square box 425
 Welded wire mesh..... 45
 Western red cedar siding... 108
 Westminster Ceramics 300
 Wet location conduit box cover..... 428
 Wet location receptacle cover, GFCI 428
 Wet patch roof cement 135
 rubber 135
 Wet-Stick roof cement..... 135
 Wheel glass cutters 171
 Wheel loader, rental 28, 39
 Wheelbarrow 540
 Whirlpool bath
 Cadet Elite..... 353
 Devonshire 354
 Elite EZ-Install heater... 354
 Portrait..... 354
 Renaissance..... 353
 Williamsburg Elite..... 353
 Whirlpool tub apron 354
 White cement 114
 White Diamond bowling alley wax..... 491
 White oak strip flooring.... 281
 White wash pickling stain... 488
 Whole house fans..... 91
 Williamsburg lavatory faucet..... 372
 pedestal lavatory bowl... 366
 Roman tub filler 354
 Wilsonart counters..... 322
 Wind clips 140
 Window
 demolition, wet 534
 drip cap..... 141
 framing..... 69
 screen..... 168
 straighten opening..... 514
 Window bolt double-hung 166
 Window glass, remove & replace 170
 Window grille systems... 169
 Window guards..... 167
 Window locks
 flip lock 171
 key, sliding..... 171
 thumbscrew bar 171
 Window mullions 166
 Window openings
 closure, masonry wall.... 156
 closure, wood frame 156
 cut new 156
 Window operators
 awning 166
 jalousie 166
 Window painting labor 486-487
 Window roof covers, bay ... 164
 Window roofs..... 164-165
 Window screens 160
 patch..... 168
 spline 168
 Window shutters..... 167
 Window sill 165
 ceramic..... 301
 Window trim, bath wall ... 355
 Window wrap..... 141
 Windows
 adding or moving..... 153
 aluminum 148
 aluminum single hung 160-161
 aluminum sliding..... 161-162
 aluminum, horizontal 161
 awning 160
 awning, aluminum 162
 bay..... 158
 bay, angle 164
 building codes 148
 casement..... 160
 casement bow 164
 casement, bay 158
 caulk 157
 caulk removal 157
 circular, vinyl..... 159
 counterweighted 152
 cut new opening 156
 double-hung 157, 163
 egress window..... 172
 energy-efficiency standards 148
 escape wells..... 172
 fixed aluminum 162
 fixed octagonal 163
 garden 158
 glass setting labor 170
 glazing putty replacement 150
 grille sets, tilt sash..... 169
 heat loss and gain 147
 jalousie 159, 163
 louvered, aluminum 163
 Low-E glass..... 147
 measure & cut glass..... 170
 modern 147
 octagonal, wood 163
 picture..... 162
 removal..... 35, 156
 replacement... 155, 157-158
 sash repair..... 151, 156
 sash springs 166
 sill, ceramic..... 301
 size, reducing 156
 storm..... 149, 165
 trim removal..... 156
 vinyl bay 158
 vinyl double hung 157
 vinyl garden 158
 vinyl hopper 159
 vinyl jalousie 159
 vinyl single hung..... 158
 vinyl, custom 157
 vinyl, replacement 157
 vinyl-clad awning..... 160
 vinyl-clad casement..... 160
 vinyl-clad double-hung 159-160
 vinyl-clad wood..... 159
 weatherstripping 171
 wood 147
 wood, repair..... 149
 wood, replacement 156
 Wire
 bell..... 433
 screen..... 458
 speaker..... 433
 thermostat cable..... 433
 Type THHN copper 432
 UF cable 419
 Wire brush..... 50
 Wire mesh, welded..... 45
 Wireless door bell..... 436
 Wiring residences
 adding outlets and switches..... 414
 aluminum wiring 411
 ground wire..... 413
 knob and tube wiring 411
 low voltage wiring 414
 non-metallic sheathed cable (Romex)..... 412
 smoke detectors 416
 Wonderboard tile backerboard 295
 Wood
 shakes 137
 shingles 137
 siding removal 106
 Wood bleach kit..... 487
 Wood coating, weather-resistant..... 488
 Wood conditioner 491
 Wood deck
 patch built-up roofing.... 132
 staining 475
 Wood doors
 entry..... 193
 screen..... 203
 screen, installation..... 202
 screen, remove & replace 202
 Wood filler
 acrylic 281
 Wood finish..... 487
 penetrating 487
 Wood flooring 281
 adhesive 282
 hardwood..... 272
 installation tools 281
 laminate 274
 plank 280
 softwood 272
 strip 272
 strips 279
 tile 282
 touch-up 278
 trim..... 279
 Wood paneling trim pack... 252
 Wood preservative 463, 490-491
 copper 491
 Termin-8 490
 Wood protector
 clear..... 490
 waterproofing..... 490
 WaterSeal..... 490
 Wood shingle, patch..... 137
 Wood siding
 bevel..... 93
 board and batten 98
 bungalow 93
 clapboard..... 93
 decay 93
 horizontal..... 97
 horizontal patterns..... 97
 lap 93
 moisture damage..... 93
 painting 93
 repair 93
 vertical 97
 vertical patterns 97
 vertical tongue and groove 97
 Wood stain
 water-based..... 488
 Wood toilet seat..... 365
 Wood treatment..... 490
 Wood window repair..... 149
 Wood-burning furnace..... 404
 Woodcore storm doors.... 205
 Wool carpet 308
 Wrap
 window..... 141
X - Y - Z
 X type gypsum board 243
 Zinsser 490
 ZPW clear wood preservative..... 491

Practical References for Builders

Construction Contract Writer



Relying on a "one-size-fits-all" boilerplate construction contract to fit your jobs can be dangerous — almost as dangerous as a handshake agreement. *Construction Contract Writer* lets you draft a contract in minutes that precisely fits your needs and the particular job, and meets both state and federal requirements. You just answer a series of questions — like an interview — to

construct a legal contract for each project you take on. Anticipate where disputes could arise and settle them in the contract before they happen. Include the warranty protection you intend, the payment schedule, and create subcontracts from the prime contract by just clicking a box. Includes a feedback button to an attorney on the Craftsman staff to help should you get stumped — *No extra charge. \$149.95.* Download the *Construction Contract Writer* at: <http://www.constructioncontractwriter.com>

Construction Forms for Contractors



This practical guide contains 78 useful forms, letters and checklists, guaranteed to help you streamline your office, manage your jobsites, gather and organize records and documents, keep a handle on your subs, reduce estimating errors, administer change orders and lien issues, monitor crew productivity, track your equipment use, and more. Includes accounting forms, change order forms, forms for customers, estimating forms, field work forms, HR forms, lien forms, office forms, bids and proposals, subcontracts, and more. All are also on the CD-ROM included, in *Excel* spreadsheets, as formatted Rich Text that you can fill out on your computer, and as PDFs. **360 pages, 8½ x 11, \$48.50**

eBook (PDF) also available; \$24.25 at www.craftsman-book.com

CD Estimator

If your computer has *Windows™* and a CD-ROM drive, *CD Estimator* puts at your fingertips over 150,000 construction costs for new construction, remodeling, renovation & insurance repair, home improvement, framing & finish carpentry, electrical, concrete & masonry, painting, earthwork & heavy equipment and plumbing & HVAC. Quarterly cost updates are available at no charge on the Internet. You'll also have the *National Estimator* program — a stand-alone estimating program for *Windows™* that *Remodeling* magazine called a "computer wiz," and *Job Cost Wizard*, a program that lets you export your estimates to *QuickBooks Pro* for actual job costing. A 60-minute interactive video teaches you how to use this CD-ROM to estimate construction costs. And to top it off, to help you create professional-looking estimates, the disk includes over 40 construction estimating and bidding forms in a format that's perfect for nearly any *Windows™* word processing or spreadsheet program.

CD Estimator is \$149.50

Home Inspection Handbook

Every area you need to check in a home inspection — especially in older homes. Twenty complete inspection checklists: building site, foundation and basement, structural, bathrooms, chimneys and flues, ceilings, interior & exterior finishes, electrical, plumbing, HVAC, insects, vermin and decay, and more. Also includes information on starting and running your own home inspection business. **324 pages, 5½ x 8½, \$29.95**

eBook (PDF) also available, \$14.98 at www.craftsman-book.com

National Appraisal Estimator



An Online Appraisal Estimating Service. Produce credible single-family residence appraisals — in as little as five minutes. A smart resource for appraisers using the cost approach. Reports consider all significant cost variables and both physical and functional depreciation.

Visit www.craftsman-book.com/national-appraisal-estimator-online-software for more information.

Cabinetmaking: From Design To Finish

Every aspect of cabinetmaking, from layout, through joinery, to finishing techniques. Gives illustrated instructions for designing cabinets to fit the kitchen workcenter; create dado, mortise, tenon, lap and dowel joints; make frames and panels; construct cabinets; and install cabinet hardware. **416 pages, 5½ x 8½, \$22.00**

National Painting Cost Estimator


A complete guide to estimating painting costs for just about any type of residential, commercial, or industrial painting, whether by brush, spray, or roller. Shows typical costs and bid prices for fast, medium, and slow work, including material costs per gallon, square feet covered per gallon, square feet covered per manhour, labor, material, overhead, and taxes per 100 square feet, and how much to add for profit. Includes a free download of an electronic version of the book, with *National Estimator*, a stand-alone *Windows™* estimating program. Additional information and *National Estimator* ShowMe tutorial video is available on our website under the "Support" dropdown tab.

448 pages, 8½ x 11, \$98.00. Revised annually
eBook (PDF) also available; \$49.00 at www.craftsman-book.com

National Construction Estimator

Current building costs for residential, commercial, and industrial construction. Estimated prices for every common building material. Provides manhours, recommended crew, and gives the labor cost for installation. Includes a free download of an electronic version of the book with *National Estimator*, a stand-alone *Windows™* estimating program. Additional information and *National Estimator* ShowMe tutorial video is available on our website under the "Support" dropdown tab.

672 pages, 8½ x 11, \$97.50. Revised annually
eBook (PDF) also available; \$48.75 at www.craftsman-book.com



Roofing Construction & Estimating

Installation, repair and estimating for nearly every type of roof covering available today in residential and commercial structures: asphalt shingles, roll roofing, wood shingles and shakes, clay tile, slate, metal, built-up, and elastomeric. Covers sheathing and underlayment techniques, as well as secrets for installing leakproof valleys. Many estimating tips help you minimize waste, as well as insure a profit on every job. Troubleshooting techniques help you identify the true source of most leaks. Over 300 large, clear illustrations help you find the answer to just about all your roofing questions. **448 pages, 8½ x 11, \$38.00**

eBook (PDF) also available, \$19.00 at www.craftsman-book.com

Insurance Replacement Estimator

Insurance underwriters demand detailed, accurate valuation data. There's no better authority on replacement cost for single-family homes than the *Insurance Replacement Estimator*. In minutes you get an insurance-to-value report showing the cost of re-construction based on your specification. You can generate and save unlimited reports. Visit www.craftsman-book.com/insurance-replacement-estimator-online-software for more details.



Profits in Buying & Renovating Homes

Step-by-step instructions for selecting, repairing, improving, and selling highly profitable "fixer-uppers." Shows which price ranges offer the highest profit-to-investment ratios, which neighborhoods offer the best return, practical directions for repairs, and tips on dealing with buyers, sellers, and real estate agents. Shows you how to determine your profit before you buy, what "bargains" to avoid, and how to make simple, profitable, inexpensive upgrades. **304 pages, 8½ x 11, \$24.75**


Renovating & Restyling Older Homes

Any builder can turn a run-down old house into a showcase of perfection — if the customer has unlimited funds to spend. Unfortunately, most customers are on a tight budget. They usually want more improvements than they can afford — and they expect you to deliver. This book shows how to add economical improvements that can increase the property value by two, five or even ten times the cost of the remodel. Sound impossible? Here you'll find the secrets of a builder who has been putting these techniques to work on Victorian and Craftsman-style houses for twenty years. You'll see what to repair, what to replace and what to leave, so you can remodel or restyle older homes for the least amount of money and the greatest increase in value. **416 pages, 8½ x 11, \$33.50**

Craftsman's Construction Installation Encyclopedia

Step-by-step installation instructions for just about any residential construction, remodeling or repair task, arranged alphabetically, from *Acoustic tile* to *Wood flooring*. Includes hundreds of illustrations that show how to build, install, or remodel each part of the job, as well as manhour tables for each work item so you can estimate and bid with confidence. Also includes a CD-ROM with all the material in the book, handy look-up features, and the ability to capture and print out for your crew the instructions and diagrams for any job. **792 pages, 8½ x 11, \$65.00**
eBook (PDF) also available; \$32.50 at www.craftsman-book.com

National Electrical Estimator



This year's prices for installation of all common electrical work: conduit, wire, boxes, fixtures, switches, outlets, loadcenters, panelboards, raceway, duct, signal systems, and more. Provides material costs, manhours per unit, and total installed cost. Explains what you should know to estimate each part of an electrical system. Includes a free download of an electronic version of the book with *National Estimator*, a stand-alone *Windows™* estimating program. Additional information and *National Estimator ShowMe* tutorial video is available on our website under the "Support" dropdown tab.

552 pages, 8½ x 11, \$97.75. Revised annually
eBook (PDF) also available; \$48.88 at www.craftsman-book.com

Fences & Retaining Walls Revised eBook

Everything you need to know to run a profitable business in fence and retaining wall contracting. Takes you through layout and design, construction techniques for wood, masonry, and chain link fences, gates and entries, including finishing and electrical details. How to build retaining and rock walls. How to get your business off to the right start, keep the books, and estimate accurately. The book even includes a chapter on contractor's math. **400 pages.**
Available only as an eBook (PDF, EPUB & MOBI/Kindle); \$23.00 at www.craftsman-book.com

National Renovation & Insurance Repair Estimator

Current prices in dollars and cents for hard-to-find items needed on most insurance, repair, remodeling, and renovation jobs. All price items include labor, material, and equipment breakouts, plus special charts that tell you exactly how these costs are calculated. Includes a free download of an electronic version of the book with *National Estimator*, a stand-alone *Windows™* estimating program. Additional information and *National Estimator ShowMe* tutorial video is available on our website under the "Support" dropdown tab.

488 pages, 8½ x 11, \$99.50. Revised annually
eBook (PDF) also available; \$49.75 at www.craftsman-book.com

Plumber's Handbook Revised

This new edition explains simply and clearly, in non-technical, everyday language, how to install all components of a plumbing system to comply not only with recent changes in the International Plumbing Code and the Uniform Plumbing Code, but with the requirements of the Americans with Disabilities Act. Originally written for working plumbers to assure safe, reliable, code-compliant plumbing installations that pass inspection the first time, *Plumber's Handbook*, because of its readability, accuracy and clear, simple diagrams, has become the textbook of choice for numerous schools preparing plumbing students for the plumber's exams. Now, with a set of questions for each chapter, full explanations for the answers, and with a 200-question sample exam in the back, this handbook is one of the best tools available for preparing for almost any plumbing journeyman, master or state-required plumbing contracting exam.

384 pages, 8½ x 11, \$44.50
eBook (PDF) also available; \$22.25 at www.craftsman-book.com

Finish Carpenter's Manual

Everything you need to know to be a finish carpenter: assessing a job before you begin, and tricks of the trade from a master finish carpenter. Easy-to-follow instructions for installing doors and windows, ceiling treatments (including fancy beams, corbels, cornices and moldings), wall treatments (including wainscoting and sheet paneling), and the finishing touches of chair, picture, and plate rails. Specialized interior work includes cabinetry and built-ins, stair finish work, and closets. Also covers exterior trims and porches. Includes manhour tables for finish work, and hundreds of illustrations and photos. **208 pages, 8½ x 11, \$22.50**

National Repair & Remodeling Estimator

The complete pricing guide for dwelling reconstruction costs. Reliable, specific data you can apply on every repair and remodeling job. Up-to-date material costs and labor figures based on thousands of jobs across the country. Provides recommended crew sizes; average production rates; exact material, equipment, and labor costs; a total unit cost and a total price including overhead and profit. Separate listings for high- and low-volume builders, so prices shown are specific for any size business. Estimating tips specific to repair and remodeling work to make your bids complete, realistic, and profitable. Includes a free download of an electronic version of the book with *National Estimator*, a stand-alone *Windows™* estimating program. Additional information and *National Estimator ShowMe* tutorial video is available on our website under the "Support" dropdown tab.

512 pages, 8½ x 11, \$98.50. Revised annually
eBook (PDF) also available; \$49.25 at www.craftsman-book.com

Craftsman eLibrary

Craftsman's eLibrary license gives you immediate access to 60+ PDF eBooks in our bookstore for 12 full months! **You pay only one low price. \$129.99.** Visit www.craftsman-book.com for more details.



Builder's Guide to Accounting Revised

Step-by-step, easy-to-follow guidelines for setting up and maintaining records for your building business. This practical guide to all accounting methods shows how to meet state and federal accounting requirements, explains the new depreciation rules, and describes how the Tax Reform Act can affect the way you keep records. Full of charts, diagrams, simple directions and examples to help you keep track of where your money is going. Recommended reading for many state contractor's exams. Each chapter ends with a set of test questions, and a CD-ROM included FREE has all the questions in interactive self-test software. Use the Study Mode to make studying for the exam much easier, and Exam Mode to practice your skills.

360 pages, 8½ x 11, \$35.50
eBook (PDF) also available; \$17.75 at www.craftsman-book.com

Painter's Handbook

Loaded with "how-to" information you'll use every day to get professional results on any job: the best way to prepare a surface for painting or repainting; selecting and using the right materials and tools (including airless spray); tips for repainting kitchens, bathrooms, cabinets, eaves and porches; how to match and blend colors; why coatings fail and what to do about it. Lists 30 profitable specialties in the painting business.

320 pages, 8½ x 11, \$33.00

Insurance Restoration Contracting: Startup to Success

Insurance restoration — the repair of buildings damaged by water, fire, smoke, storms, vandalism and other disasters — is an exciting field of construction that provides lucrative work that's immune to economic downturns. And, with insurance companies funding the repairs, your payment is virtually guaranteed. But this type of work requires special knowledge and equipment, and that's what you'll learn about in this book. It covers fire repairs and smoke damage, water losses and specialized drying methods, mold remediation, content restoration, even damage to mobile and manufactured homes. You'll also find information on equipment needs, training classes, estimating books and software, and how restoration leads to lucrative remodeling jobs. It covers all you need to know to start and succeed as the restoration contractor that both homeowners and insurance companies call on first for the best jobs. **640 pages, 8½ x 11, \$69.00**
eBook (PDF) also available; \$34.50 at www.craftsman-book.com



How to Succeed With Your Own Construction Business

Everything you need to start your own construction business: setting up the paperwork, finding the jobs, advertising, using contracts, dealing with lenders, estimating, scheduling, finding and keeping good employees, keeping the books, and coping with success. If you're considering starting your own construction business, all the knowledge, tips, and blank forms you need are here. **336 pages, 8½ x 11, \$28.50**

eBook (PDF) also available, \$14.25 at www.craftsman-book.com

Home Building Mistakes & Fixes



This is an encyclopedia of practical fixes for real-world home building and repair problems. There's never an end to "surprises" when you're in the business of building and fixing homes, yet there's little published on how to deal with construction that went wrong - where out-of-square or non-standard or jerry-rigged turns what should be a simple job into a nightmare. This manual describes jaw-dropping building mistakes that actually occurred, from disas-


trous misunderstandings over property lines, through basement floors leveled with an out-of-level instrument, to a house collapse when a siding crew removed the old siding. You'll learn the pitfalls the painless way, and real-world working solutions for the problems every contractor finds in a home building or repair jobsite. Includes dozens of those "surprises" and the author's step-by-step, clearly illustrated tips, tricks and workarounds for dealing with them. **384 pages, 8½ x 11, \$52.50 eBook (PDF) also available; \$26.25 at www.craftsman-book.com**

National Plumbing & HVAC Estimator

Manhours, labor and material costs for all common plumbing and HVAC work in residential, commercial, and industrial buildings. You can quickly work up a reliable estimate based on the pipe, fittings and equipment required. Every plumbing and HVAC estimator can use the cost estimates in this practical manual. Sample estimating and bidding forms and contracts also included. Explains how to handle change orders, letters of intent, and warranties. Describes the right way to process submittals, deal with suppliers and subcontract specialty work. Includes a free download of an electronic version of the book with *National Estimator*, a stand-alone *Windows™* estimating program. Additional information and *National Estimator ShowMe* tutorial video is available on our website under the "Support" dropdown tab.

480 pages, 8½ x 11, \$98.25. Revised annually eBook (PDF) also available; \$49.13 at www.craftsman-book.com

Basic Plumbing with Illustrations, Revised



This completely-revised edition brings this comprehensive manual fully up-to-date with all the latest plumbing codes. It is the journeyman's and apprentice's guide to installing plumbing, piping, and fixtures in residential and light commercial buildings: how to select the right materials, lay out the job and do professional-quality plumbing work, use essential tools and materials, make repairs, maintain plumbing systems, install fixtures, and add to existing systems.

Includes extensive study questions at the end of each chapter, and a section with all the correct answers. **384 pages, 8½ x 11, \$44.75 eBook (PDF) also available; \$22.37 at www.craftsman-book.com**

Markup & Profit: A Contractor's Guide, Revisited



In order to succeed in a construction business, you have to be able to price your jobs to cover all labor, material and overhead expenses, and make a decent profit. But calculating markup is only part of the picture. If you're going to beat the odds and stay in business — profitably, you also need to know how to write good contracts, manage your crews, work with subcontractors and collect on your work. This book covers the business basics of running a construction company, whether you're a general or specialty contractor working in remodeling, new construction or commercial work. The principles outlined here apply to all construction-related businesses. You'll find tried and tested formulas to guarantee profits, with step-by-step instructions and easy-to-follow examples to help you learn how to operate your business successfully. Includes a link to free downloads of blank forms and checklists used in this book.

336 pages, 8½ x 11, \$52.50 eBook (EPUB, MOBI for Kindle) also available; \$39.95 at www.craftsman-book.com

Writing contracts that comply with law in your state isn't easy. A contract that doesn't comply could leave you with no way to collect.

Construction Contract Writer has you covered. Download a trial today:

www.constructioncontractwriter.com

Craftsman Book Company
6058 Corte del Cedro
Carlsbad, CA 92011

Call me.
1-800-829-8123
Fax (760) 438-0398



Name _____
e-mail address (for order tracking and special offers) _____

Company _____

Address _____

City/State/Zip _____ This is a residence

Total enclosed _____ (In California add 7.5% tax)

*Free Media Mail shipping, within the US,
when your check covers your order in full.*

10-Day Money Back Guarantee

- 44.75 Basic Plumbing with Illustrations, Revised
- 35.50 Builder's Guide to Accounting Revised
- 149.50 CD Estimator
- 22.00 Cabinetmaking: From Design to Finish
- 48.50 Construction Forms for Contractors
- 65.00 Craftsman's Construction Installation Encyclopedia
- 22.50 Finish Carpenter's Manual
- 52.50 Home Building Mistakes & Fixes
- 29.95 Home Inspection Handbook
- 28.50 How to Succeed With Your Own Construction Business
- 69.00 Insurance Restoration Contracting: Startup to Success
- 52.50 Markup & Profit: A Contractor's Guide, Revisited

In A Hurry?

We accept phone orders charged to your

Visa, MasterCard, Discover or American Express

Card# _____

Exp. date _____ CVV# _____ Initials _____

Tax Deductible: Treasury regulations make these references tax deductible when used in your work. Save the canceled check or charge card statement as your receipt.

Order online: www.craftsman-book.com
Free on the Internet! Download any of Craftsman's estimating databases for a 30-day free trial! www.craftsman-book.com/downloads

Prices subject to change without notice

- 97.50 National Construction Estimator w/FREE *Natl Estimator* Download
- 97.75 National Electrical Estimator w/FREE *Natl Estimator* Download
- 98.00 National Painting Cost Estimator w/FREE *Natl Estimator* Download
- 98.25 National Plumbing & HVAC Estimator w/FREE *Natl Estimator* Download
- 99.50 National Renovation & Ins. Repair Est. w/FREE *Natl Estimator* Download
- 98.50 National Repair & Remodeling Est. w/FREE *Natl Estimator* Download
- 33.00 Painter's Handbook
- 44.50 Plumber's Handbook, Revised
- 24.75 Profits in Buying & Renovating Homes
- 33.50 Renovating & Restyling Older Homes
- 38.00 Roofing Construction & Estimating
- 98.75 National Home Improvement Estimator w/FREE *Natl Estimator* Download