



2023 NATIONAL HOME IMPROVEMENT ESTIMATOR

\$98.75

Edited by Bilandra Chase and Richard Pray
19th Edition



**The National
Estimator Cloud**



This manual is also available as a Web app that makes it easy to compile and print estimates, bids and invoices for nearly any type of construction project. *National Estimator Cloud.*

Generate professional estimates from your internet browser. Includes 10 Craftsman cost databases. It's never been easier. No disk and no download needed!



- Turn your estimate into a bid.
- Turn your bid into a contract.
- ConstructionContractWriter.com



Craftsman Book Company
6058 Corte del Cedro, Carlsbad, CA 92011

Acknowledgments

Portions of chapters 8, 9 and 15 first appeared in the book *Renovating & Restyling Older Homes* by Lawrence Dworin. Mr. Dworin served as a resource in the development of this manuscript and contributed many valuable insights from his years of experience in the industry. Mr. Dworin is the author of both *Renovating & Restyling Older Homes* and *Profits in Buying & Renovating Homes*. Both are available from Craftsman Book Company.

Looking for other construction reference manuals?

Craftsman has the books to fill your needs. **Call toll-free 1-800-829-8123**
or visit our Web site: <http://www.craftsman-book.com>

Cover design by: *Jennifer Johnson*
Photos: *iStock by Getty Images™*
Graphics by: *Devona Quindoy and Christal Stimpson*
Production Manager: *Christine Pray*
Layout by: *Christine Pray*

© 2022 Craftsman Book Company
ISBN 978-1-57218-384-1
Published November 2022 for the year 2023.

Contents

1 Pricing Home Improvement Jobs	5	7 Roofing and Flashing.....	117
This book works two ways	8	Flashing leaks	118
Craft codes and crews.....	15	Roof repairs.....	121
Area modification factors	18	Roofing material.....	122
2 Demolition	27	<i>Cost estimates</i>	
Before you begin	27	Roof repairs	129
<i>Cost estimates</i>		Composition shingles.....	130
Equipment rental	29	Built-up roofing.....	131
Sitework demolition.....	30	Roof patching	134
Building demolition	31	Wood shingle roofing.....	137
Wood framing demolition	34	Slate and tile roofing	139
3 Foundations and Slabs	37	Roof flashing.....	141
Pre-construction checklist.....	38	Gutters and downspouts.....	146
<i>Cost estimates</i>		8 Windows	147
Equipment rental	40	Window repair	149
Concrete flatwork.....	41	Sash repair	151
Concrete finishing.....	50	Counterweighted windows	152
4 Rough Carpentry.....	53	Adding or moving a window	153
Floor beams	53	<i>Cost estimates</i>	
Wood floor repairs.....	56	Window repairs.....	156
Wall framing	57	Vinyl windows	157
Roof repairs.....	58	Aluminum windows.....	161
<i>Cost estimates</i>		Wood windows	163
Framing repairs.....	62	Storm windows.....	165
Framing room additions.....	64	Window accessories.....	165
Subflooring.....	66	Window glazing.....	169
Wall and ceiling changes	70	Skylights	172
Roof framing changes	75	9 Doors	175
5 Insulation and Moisture Control	79	Door repair and replacement	175
Ceiling insulation.....	79	Adding or moving a door.....	182
Wall and floor insulation.....	80	Hanging a slab door	184
Attic and roof ventilation	83	Door terms	188
<i>Cost estimates</i>		<i>Cost estimates</i>	
Fiberglass insulation	84	Exterior doors	191
Panel insulation	85	Prehung doors.....	197
Vapor barrier.....	87	Screen and storm doors	202
Vents and louvers.....	88	Interior doors	206
Roof ventilators.....	91	Patio doors.....	214
6 Siding and Trim.....	93	Closet doors	218
Vinyl siding installation	96	Garage doors	223
Wood siding installation	97	10 Walls and Ceilings	227
Estimating procedure for siding	104	Drywall installation	228
Masonry fireplaces	104	Wood paneling	235
<i>Cost estimates</i>		Removing partitions.....	239
Siding and soffit repairs.....	105	<i>Cost estimates</i>	
Vinyl siding	107	Drywall	242
Wood board siding	108	Textured finishes for drywall	244
Texture 1-11 plywood siding.....	111	Drywall bead and tools	247
Fiber cement siding	112	Wall paneling	251
Aluminum siding and soffit.....	113	Suspended ceilings	255
Stucco and masonry siding	114	Moldings.....	259
		Partition walls	264

11 Floors and Tile 267

Wood flooring installation	268
Ceramic tile installation.....	272
<i>Cost estimates</i>	
Wood strip and plank flooring	274
Laminate plank flooring	279
Vinyl flooring.....	282
Ceramic tile.....	289
Natural stone and slate flooring	294
Ceramic field wall tile	297
Carpet	304

12 Kitchens..... 305

Kitchen cabinet standards.....	308
<i>Cost estimates</i>	
Kitchen demolition	311
Cabinets and countertops	313
Cabinet knobs, pulls and hinges	320
Sinks and faucets.....	321
Appliances	332

13 Bathrooms 339

Bathroom additions.....	339
<i>Cost estimates</i>	
Tubs, enclosures and shower stalls	346
Tub and shower faucets	349
Toilets	350
Lavatory sinks	353
Vanity cabinets and countertops	358
Bath exhaust fans.....	362
Medicine cabinets.....	366
Bathroom accessories.....	369

14 Plumbing and HVAC 371

Heating types and considerations	371
Framing for plumbing and HVAC.....	374
<i>Cost estimates</i>	
Furnace replacement.....	376
Chimney flue components	379
Water heaters	385
DWV pipe replacement.....	387

15 Electrical..... 389

Wiring residences	391
Adding outlets and switches.....	394
<i>Cost estimates</i>	
Non-metallic cable.....	397
PVC conduit and fittings.....	400
EMT conduit and fittings	402
Flex conduit and fittings	406
Rigid and IMC conduit and fittings	409
Switches and receptacles.....	414
Distribution panels	416
Lighting.....	420
Smart home electrical mgmt. system.....	424

16 Porches and Decks 425

Adding a porch.....	426
Elevated decks	428
<i>Cost estimates</i>	
Deck lumber.....	432
Alternative deck materials	434
Porch and deck stairs.....	437
Pool replastering.....	440
Spa replastering.....	440

17 Painting and Finishing..... 441

Paint application techniques	444
<i>Cost estimates</i>	
Labor estimates for painting.....	446
Stains and finishes	467
Wood preservatives.....	470
Interior paints	472
Exterior paints	474

18 Earthquake Damage 477

Types of damage	477
What FEMA recommends.....	479
When making alterations	484
When adding a room	485
Checking for earthquake damage.....	486
Repair of foundations and floor slabs.....	487
Framing repairs	488
Cracks in plaster and stucco	489
Fireplaces and chimneys.....	490
Mechanical, electrical, and plumbing systems.....	491
<i>Cost estimates</i>	
Foundation anchors and brackets.....	492
Cripple wall bracing	492
Hold-down anchors.....	492
Bracing a water heater	492
Framing straps and braces	492
Concrete repairs	493
Straighten a frame wall	494
Straighten a window opening	494
Plaster and stucco repair	494

19 Water Damage and


Mold Remediation 495

Building Dryout	495
Mold Remediation.....	505
<i>Cost estimates</i>	
Water extraction	509, 511
Pre-drying	509
Remove appliances	510
HVAC system cleaning	510
Carpet removal	511
Drywall repairs	512
Demolition.....	512-514
Cleanup after water extraction	514
Mold inspection and remediation protocol.....	515
Containment structure.....	516
Remove mold by abrading.....	517
Encapsulation	517
Personal protection equipment	518
Air movers, dryers and drying systems.....	519
Other dryout and mold equipment	520

Index..... 521

Pricing Home Improvement Jobs

1



Estimating home improvement costs requires specialized skills. You can't price home improvement work the same way you'd price new construction. The proportion of labor expense is greater. There's far more risk because there are far more variables and unknowns. An example will make this clear.

Hanging doors in new construction is a 1-2-3 affair. You know ahead of time exactly what's required. You built the wall, installed the frame and know each door will fit right the first time. There won't be any surprises. An experienced estimator can forecast the cost of hanging a door in a new home with a high degree of confidence.

Now let's look at the same task on a home improvement project. First, remember that you may be hanging only one door. There's no chance to improve the production rate on second or later doors. Installing this one door is probably different from the last door you installed on a similar project and will be different from your next door installation.

Work starts with removing the old door. That's probably not too hard — once you break through several coats of accumulated paint on the hinges. Let's assume you work carefully and don't damage the casing or trim. The next step is to install a blind Dutchman where the original hinges were attached. If the frame's badly chewed up from years of neglect and abuse, you'll have to remove and replace the entire frame. Don't forget that the building has settled over the years. The frame has probably twisted out of plumb. More time will be needed to shim and level the frame.

Finally, the door is installed and swings smoothly. But the job still isn't finished. You still have to paint the door to match and will certainly have to haul away the old door and the debris.

Every home improvement cost estimate comes with dozens of chances to make an expensive mistake. Surprises are inevitable and nearly all surprises will add to the cost, not reduce the cost. Estimating new construction is a snap by comparison.

All home improvement has similar problems:

- ❖ No chance for economies of scale (mass production),
- ❖ Difficulty in removing just enough of the old,
- ❖ Work doesn't follow the normal (from the ground, up) sequence of construction,
- ❖ Difficulty adding new materials to deteriorated or nonstandard existing materials,
- ❖ The need to match designs, colors and textures,
- ❖ Covering up for another contractor's mistakes,
- ❖ Struggling to get access to the place where the work is to be done,
- ❖ Protecting adjacent surfaces and pathway to the work area,
- ❖ Initial uncertainty about how much work is needed.

Now notice the word *risk* in first paragraph above. There are at least two risk categories in every home improvement job. The first is risk from the unknown – work you didn’t expect and couldn’t foresee. But there’s another type of risk that’s entirely different: That the owner won’t be satisfied with what you’ve done or the way you’ve done it. Nearly all home improvement is intended to solve a problem, something the owner wants or doesn’t want. Until that problem is resolved (at least in the mind of the owner) your work is not done. That makes owner satisfaction the essence of every home improvement project. Meeting requirements of the building code is never enough. You have to satisfy the owner. Worse still, many states require a very specific set of notices and disclosures in home improvement contracts. A home improvement contract that omits any of these notices and disclosures is an “unfair act or practice” and may subject the contractor to criminal penalties.

If you’re an experienced home improvement contractor, you understand this already. Whether experienced or not, you know full well that accurate pricing is crucial to survival in the home improvement business. Unfortunately, most home improvement specialists have far less experience in pricing their work than in getting the work done. No wonder so many home improvement companies wink out after a few years.

But it doesn’t have to be that way.

The chapters that follow explain how to price each type of home improvement work. Emphasis will be on avoiding risk — pricing pitfalls that can turn any home improvement contract into a financial nightmare.

No Price Fits All Jobs

There’s no single way to arrive at the correct price for home improvement work. Neither is there a single correct price for most home improvement projects. But there are both good and bad ways to estimate prices and there are good and bad prices for any proposed job. Your task as a home improvement estimator is to produce consistently good estimates on most jobs. If you’re already doing that, congratulations. You don’t need this book. Return it where you bought it and get a refund. But if you’re not, information in the following chapters will make or save you many times what you paid for the book.

It’s accepted wisdom among home improvement specialists that salespeople need authority to quote prices when closing a sale. When trying to wrap up a deal, there’s no substitute for having current cost information at your fingertips. That’s especially true on larger jobs where you’ve prepared detailed plans and a written estimate. The owner will have questions and suggestions that change the job specs. If you want to close the sale then and there, you’d better know how much to add or subtract for each change the owner wants.

Most home improvement companies authorize salespeople to quote prices from an approved list in a price book. That simplifies the salesperson’s job, eliminates most major errors, and saves the owner of the company from approving every item in every estimate. In our opinion, quoting from a price book is the only way to

build sales volume in the home improvement business. That means every home improvement contractor needs a good price book.

Of course, the best price book for your company would be based on your actual cost experience — work done by your crews on your jobs with materials from your dealers and installed by your subcontractors. Since every contractor uses different crews, subcontractors and suppliers, every price book should be different. And, of course, prices in the company price book should be revised regularly to reflect current labor and material costs.

Having admitted that there's no substitute for developing your own price book, we'll suggest that you not bother. Most home improvement contractors don't have the time or patience to maintain current installed prices for thousands of repair and remodeling items. Even if you did, spending hundreds of hours a year keeping a price book current would be a waste of time. Prices for home improvement work are usually negotiated on site. There's little value in keeping a book of exact costs if you have to cut a special deal to close each sale.

Instead, we suggest that you let this manual serve as your company price book. Using the prices in this book (and included software download) will eliminate most of the common estimating mistakes. If your labor costs are higher or if your crews aren't as skilled as most tradesmen, you may have to increase the selling prices listed here to make a reasonable profit. And, of course, sometimes you're going to have a job with costs that exceed what any reasonable estimate could have predicted. This manual isn't a substitute for the exercise of good judgment. That's always your job.

Cost Plus Markup Equals Selling Price

The difference between your cost and your selling price is your markup. Markup varies widely from job to job, far more than either material cost or labor cost. You're the final authority on markup. You decide what markup fits best — based on market conditions, your client, and the profit you feel is reasonable. Once you decide on the "right" markup, it's easy to plug that percentage into the bid, assuming you use *National Estimator Cloud*.

Markup vs. Margin				
Hard Cost	Price at 50% Markup	Price at 70% Markup	Price at 100% Markup	Price at 150% Markup
\$50	\$75	\$85	\$100	\$125
\$100	\$150	\$170	\$200	\$250
\$200	\$300	\$340	\$400	\$500
\$300	\$450	\$510	\$600	\$750
\$400	\$600	\$680	\$800	\$1,000
\$500	\$750	\$850	\$1,000	\$1,250
\$1,000	\$1,500	\$1,700	\$2,000	\$2,500
\$2,000	\$3,000	\$3,400	\$4,000	\$5,000
\$3,000	\$4,500	\$5,100	\$6,000	\$7,500
\$4,000	\$6,000	\$6,800	\$8,000	\$10,000
\$5,000	\$7,500	\$8,500	\$10,000	\$12,500
\$6,000	\$9,000	\$10,200	\$12,000	\$15,000
\$7,000	\$10,500	\$11,900	\$14,000	\$17,500
\$8,000	\$12,000	\$13,600	\$16,000	\$20,000
\$9,000	\$13,500	\$15,300	\$18,000	\$22,500
\$10,000	\$15,000	\$17,000	\$20,000	\$25,000
\$11,000	\$16,500	\$18,700	\$22,000	\$27,500
\$12,000	\$18,000	\$20,600	\$24,000	\$30,000
\$13,000	\$19,500	\$22,100	\$26,000	\$32,500
\$14,000	\$21,000	\$23,800	\$28,000	\$35,000
\$15,000	\$22,500	\$25,500	\$30,000	\$37,500
\$16,000	\$24,000	\$27,200	\$32,000	\$40,000
\$17,000	\$25,500	\$28,900	\$34,000	\$42,500
\$18,000	\$27,000	\$30,600	\$36,000	\$45,000
\$19,000	\$28,500	\$32,300	\$38,000	\$47,500
\$20,000	\$30,000	\$34,000	\$40,000	\$50,000
\$30,000	\$45,000	\$51,000	\$60,000	\$75,000
\$40,000	\$60,000	\$68,000	\$80,000	\$100,000
\$50,000	\$75,000	\$85,000	\$100,000	\$125,000
Hard Cost	33% Margin	41% Margin	50% Margin	60% Margin

Figure 1-1

Markup (based on cost) vs. Margin (based on selling price)

Every construction contractor needs to distinguish between “markup” and “profit.” Markup is what you add to estimated labor and material costs (usually called “hard costs”) to find the selling price. Profit is what you have left when all bills have been paid. The two are very different. Profit is just the frosting on the cake.

Markup is also different from “margin.” Figure 1-1 shows percentages of markup for various levels of hard costs. For example, if your markup on a \$20,000 job is 50 percent, the selling price will be \$30,000. The margin on that job is 33 percent, \$10,000 divided by the selling price of \$30,000. (Note the bottom row in Figure 1-1.) Margin is what’s left after hard costs are recovered and includes profit.

Many successful home improvement contractors find they can stay in business if hard costs are 59 percent of selling price. Hard costs include material expense, subcontract costs and labor (including taxes and insurance). The other 41 percent of selling price (“margin”) compensates the sales staff, covers overhead, supervision and contingency, and should yield a modest profit. From Figure 1-1, you can see that markup on hard costs has to be 70 percent to yield a margin of 41 percent.

To put this formula to work in your home improvement company, add 70 percent to your hard costs to find the selling price. Of course, some jobs need more markup and others can get by on less. A smaller job with more risk done for a demanding client may require greater markup. A larger job done mostly by subcontractors can usually carry a smaller markup.

Home improvement contractors have all the overhead of any business: office rent, telephone, owner’s salary, office salaries, legal and accounting expense, insurance, auto and truck expense, and more. But unlike other contractors, home improvement specialists routinely deal with high risk, as explained earlier. Since most of what you didn’t or couldn’t anticipate will inflate your costs, you’re assuming significant risk. That’s why markups for home improvement work have to be higher than for new construction.

Naturally, competition dictates markup. If you’re not getting enough work at 70 percent markup, maybe 70 percent is too much for your area. But remember that you shouldn’t have to bid remodeling work on a level playing field. New construction usually goes to the lowest responsible bidder. A creative salesman who follows the recommendations in this book has an advantage over lowball bidders who rely on price alone to sell their services.

If you have trouble using *National Estimator Cloud*, we’ll be glad to help, and we don’t charge you for it.

Free telephone assistance is available from 8 a.m. until 5 p.m. Pacific time Monday through Friday (except holidays). Call 760-438-7828, Ext. 2.



Two Ways to Use These Estimates

This manual is also available by subscription on the Web as part of *National Estimator Cloud*. For only a few dollars a month, you get all ten of Craftsman’s 2023 construction cost estimating guides. Each has about 400 pages of current labor and material costs for construction – all neatly organized and indexed. Use these costs to build estimates, bids and invoices for nearly any type of home improvement project.

National Estimator Cloud:

- Prints estimates, bids and invoices as Word, Excel or Postscript documents.
- Runs as a secure app on the Web so you can write estimates anywhere you have a Web connection.
- Exports invoices to QuickBooks, either desktop or the online.
- Bids and invoices can show as much or as little detail as you want.
- Material costs are updated regularly as prices change.
- Costs only a few dollars a month. Cancel any time you want.

Estimates That Work Two Ways

This manual is designed for use by both the owner of a home improvement business and by company sales staff. Prices in the printed version of this manual include both hard costs (labor and material) and a recommended selling price (usually based on 70 percent markup). Sales staff will use the selling price. Prices in *National Estimator Cloud* don't include markup. *National Estimator Cloud* makes it easy to apply whatever markup percentage you select.

Figure 1-2 shows the last page of an estimate for the Stillwel room addition, including 70 percent markup. The company estimator can create an estimate like this from a job survey prepared by a sales representative. Figure 1-2 is for company use and was created with the *National Estimator Cloud*.

Figure 1-3 shows the last page of a bid for the same job. This is what the customer sees. *National Estimator Cloud* creates bids like this from your estimate. Figure 1-2, the estimate, shows 70 percent markup on hard costs.

Qty	Craft@Hours	Unit	Material	Labor	Equipment	Total
3.00	2P @ .750	Ea	5.13	16.89	-	22.02
Roll 1st coat of water base stain on rough sawn or resawn wood siding Medium 225 SF/MH, 213 SF/Gal						
17.00	2P @ 7.55	CSF	149.60	170.00	-	319.60
Roll & brush 1st finish coat of water base enamel on vanity cabinet Medium 103 SF/MH, 288 SF/Gal						
0.90	2P @ .874	CSF	6.69	19.68	-	26.37
Roll 1st coat of water base stain on rough sawn or resawn wood siding Medium 225 SF/MH, 213 SF/Gal						
17.00	2P @ 7.55	CSF	149.60	170.00	-	319.60
Add for grouting cores per linear foot of core, pumped in place 4" thick wall, (8.86 VLF per CF)						
1.00	M1 @ .011	VLF	1.31	0.64	-	1.95
Roll 2nd coat of water base stain on rough sawn or resawn wood siding Medium 275 SF/MH, 273 SF/Gal						
17.00	2P @ 6.19	CSF	116.79	139.40	-	256.19
** Subtotal: Painting						
56.8			1,607.75	1,314.17	-	2,921.92
Total Manhours, Material, Labor, and Equipment:						
406			17,719.83	9,859.62	2.56	27,582.01
Total Only (Subcontract) Costs:						
						7,292.50
Subtotal:						34,874.51
70.00% Markup						24,412.16
Estimate total:						59,286.67
8.25% Tax on Materials:						1,461.89
Grand total:						60,748.56

Figure 1-2

Estimate with a 70 percent markup shown

Description	Quantity	Rate	Amount
Roll & brush 1st finish coat of water base enamel on vanity cabinet			
Medium 103 SF/MH, 288 SF/Gal			
Material, per CSF	0.90	13.24	11.92
Labor, per CSF	0.90	37.18	33.46
Roll 1st coat of water base stain on rough sawn or resawn wood siding			
Medium 225 SF/MH, 213 SF/Gal			
Material, per CSF	17	15.69	266.73
Labor, per CSF	17	17.00	289.00
Add for grouting cores per linear foot of core, pumped in place			
4" thick wall, (8.86 VLF per CF)			
Material, per VLF	1	2.34	2.34
Labor, per VLF	1	1.09	1.09
Roll 2nd coat of water base stain on rough sawn or resawn wood siding			
Medium 275 SF/MH, 273 SF/Gal			
Material, per CSF	17	12.25	208.25
Labor, per CSF	17	13.94	236.98
*Painting subtotal			5,100.30
Total Material, Labor, and Equipment			48,352.66
Total Only (Subcontract) Costs			12,397.25
*Grand Total			60,749.91

Figure 1-3

Proposal for the same job not showing the markup

Figure 1-3, the proposal, doesn't show any markup at all. Instead, markup has been distributed proportionately throughout each cost item in the job – material, labor, equipment and subcontract. *National Estimator Cloud* does this distribution at the click of a mouse button. Notice that the total is nearly the same in both documents, \$60,749.91. (The \$1.35 difference is due to rounding when markup is distributed among hundreds of unit costs.)

National Estimator Cloud offers dozens of choices on what you show and what you hide in estimates, bids and invoices. Each can be as long (full description for everything in the estimate) or as short (only a summary of each category) as you want. You can show or hide labor and material cost detail. You can show or hide markup and profit. You can print estimates, bids and invoices in either Word (RTF), Postscript (PDF) or Excel (XLS) format.

Once work begins, you'll want to monitor job expenses to be sure actual costs remain consistent with estimated costs. If you use QuickBooks to pay bills and figure payroll, let QuickBooks do the comparisons for you. *National Estimator Cloud* exports invoices to QuickBooks -- either the full invoice for the job or just an invoice for the percentage of each task completed in the current pay period.

If you send progress invoices, *National Estimator Cloud* keeps track of what's been completed and billed and what hasn't been billed yet. When a change order increases the contract price, simply add the new item to your estimate. That item will show up on your next progress invoice at whatever percent of completion you select.

Job Survey (Scope of Work)

Of course, neither a good price book nor a computer estimating program will solve every estimating problem. Computers seldom make mistakes in addition or multiplication. But nothing prevents making an expensive estimating mistake on your own. By far the most common estimating mistake is omitting something essential to the job.

Get in the habit of completing an exhaustive job survey before beginning any estimate for home improvement work. Some of your estimates on a job may be too high. Other estimates on a job may be too low. With any luck, your over-estimates will roughly balance with your under-estimates, leaving the job total about where it should be. But the estimated price for anything omitted from a job survey is always zero. That's a 100 percent miss. It's hard to balance a complete miss with anything. A few of those can create a financial disaster.

Material Costs in This Book

Material Costs for each item are listed in the column headed "Material." These are neither retail nor wholesale prices. They are estimates of what most contractors who buy in moderate volume will pay suppliers as of early-2023. Discounts may be available for purchases in larger volumes.

Material costs can change rapidly. Material prices in *National Estimator Cloud* are revised regularly as material prices change and may be different from material prices in this manual. See the discount certificate inside the back cover of this manual for more on *National Estimator Cloud*.

Add Delivery Expense to the material cost for other than local delivery of reasonably large quantities. Cost of delivery varies with the distance from source of supply, method of transportation, and quantity to be delivered. But most material dealers absorb the delivery cost on local delivery (5 to 15 miles) of larger quantities to good customers. Add the expense of job site delivery when it's a significant part of the material cost. *National Estimator Cloud* makes it easy to add sales tax to your estimates, bids and invoices.

Add Sales Tax when sales tax will be charged to the contractor buying the materials. In some states, contractors have to collect sales tax based on the contract price. No matter what your state (or county) requires, *National Estimator Cloud* makes it easy to add sales tax to your estimates, bids and invoices.

Waste and Coverage Loss is included in the installed material cost. The cost of many materials per unit after installation is greater than the purchase price for the same unit because of waste, shrinkage or coverage loss during installation. For example, about 120 square feet of nominal 1" x 4" square edge boards will be needed to cover 100 square feet of floor or wall. There's no coverage loss with plywood sheathing, but waste due to cutting and fitting will average about 6 percent.

Costs in the Material column of this book assume normal waste and coverage loss. Small and irregular jobs may require a greater waste allowance. Materials priced without installation (with no labor cost) don't include an allowance for waste and coverage except as noted.

Labor Costs for installing the material or doing the work described are listed in the column headed Labor. The labor cost per unit is the labor cost per hour multiplied by the manhours per unit shown after the @ sign in the Craft@Hrs column. Labor cost includes the basic wage, the employer's contribution to welfare, pension, vacation and apprentice funds, and all tax and insurance charges based on wages. Hourly labor costs for the various crafts are listed on page 15.

Supervision Expense to the general contractor isn't included in the labor cost. The cost of supervision and non-productive labor varies widely from job to job. Calculate the cost of supervision and non-productive labor and add this to the estimate.

Payroll Taxes and Insurance are included in the labor cost. See page 15 for more on the "contractor's burden."

Manhours per Unit and the Craft performing the work are listed in the Craft@Hrs column. To find the units of work done per worker in an 8-hour day, divide 8 by the manhours per unit. To find the units done by a crew in an 8-hour day, multiply the units per worker per 8-hour day by the number of crew members.

Manhours include all productive labor normally associated with installing the materials described.

This will usually include tasks such as:

- ❖ Unloading and storing construction materials, tools and equipment on site.
- ❖ Moving tools and equipment from a storage area or truck on site at the beginning of the day.
- ❖ Returning tools and equipment to a storage area or truck on site at the end of the day.
- ❖ Normal time lost for work breaks.
- ❖ Planning and discussing the work to be performed.
- ❖ Normal handling, measuring, cutting and fitting.
- ❖ Keeping a record of the time spent and work done.
- ❖ Regular cleanup of construction debris.
- ❖ Infrequent correction or repairs required because of faulty installation.

Adjust the Labor Cost to the job you're figuring when your actual hourly labor cost is known or can be estimated. The labor costs listed in Figure 1-5 will apply within a few percent on many jobs. But labor costs may be much higher or much lower on the job you're estimating.

If the hourly wage rates listed in Figure 1-5 aren't accurate, divide your known or estimated cost per hour by the listed cost per hour. The result is your adjustment for any figure in the Labor column for that craft. *National Estimator Cloud* makes it easy to compile estimates using your own labor rates.

Adjust for Unusual Labor Productivity. Costs in the Labor column are for normal conditions: experienced craftsmen working on reasonably well-planned and managed home improvement projects with fair to good productivity. Labor estimates assume that materials are standard grade, appropriate tools are on hand, work done by other crafts is adequate, layout and installation are relatively uncomplicated, and working conditions don't slow progress.

Working conditions at the jobsite have a major effect on labor cost. Estimating experience and careful analysis can help you predict the effect of most changes in working conditions. Obviously, no single adjustment will apply on all jobs. But the adjustments that follow should help you produce more accurate labor estimates. More than one condition may apply on a job.

Jobsite conditions affect labor costs

- ❖ Add 10% to 15% when working temperatures are below 40 degrees or above 95 degrees.
- ❖ Add 30% to 35% when temperatures are below 20 degrees. Materials and tools are hard to handle. Bulky clothing restricts freedom of movement.
- ❖ Add 15% to 25% for work on a ladder or a scaffold, in a 36" crawl space, in a congested area, or remote from the material storage point.
- ❖ Add 50% for work in an 18" to 36" crawl space. Allow extra time for cleaning out the area before work begins.
- ❖ Add 200% if portions of the crawl space are less than 18". Allow extra time for passing tools and materials. Few contractors bid on work like this.
- ❖ Deduct 10% when the work is in an open area with excellent access and good light.
- ❖ Add 1% for each 10 feet that materials must be lifted above ground level.
- ❖ Add 5% to 50% for tradesmen with below-average skills. Deduct 5% to 25% for highly-motivated, highly-skilled tradesmen.
- ❖ Deduct 10% to 20% when an identical task is repeated many times for several days at the same site.
- ❖ Add 20% to 50% on small jobs where fitting and matching of materials is required, adjacent surfaces have to be protected and the job site is occupied during construction.
- ❖ Add 25% to 50% for work done following a major flood, fire, earthquake, hurricane or tornado while skilled tradesmen are not readily available. Material costs may also be higher after a major disaster.
- ❖ Add 10% to 35% for demanding specs, rigid inspections, unreliable suppliers, a difficult owner or an inexperienced architect.

Use an Area Modification Factor from pages 18 through 26 if your material, hourly labor or equipment costs are unknown and can't be estimated. Here's how: Use the labor and material costs in this manual without modification. Then add or deduct the percentages shown for labor, material and equipment. Area cost modifications in *National Estimator Cloud* make it easy to adjust all costs in this manual to any US zip or Canadian postal code you select.

Equipment Costs for small tools and expendable supplies (such as saws and tape) are usually considered overhead expense and are covered by your markup. Equipment costs for larger equipment (such as a compressor or backhoe) should be based on the rental rate for the period needed. Equipment rental costs are included in sections where heavy equipment may be needed.

Labor and Material Costs Change. Costs in this manual were compiled in the fall of 2022 and projected to 2023 based on recent price trends. These projections will be accurate for some materials but inaccurate for others. No one can predict material price changes accurately. Costs in *National Estimator Cloud* are revised as prices change and are likely to be different from the cost in this manual.

How Accurate Are These Figures? They're as accurate as possible considering that the estimators who compiled this book don't know your subcontractors or material suppliers, have never met the owner or been on site, have never seen the plans or specs, don't know what building code applies, and have no record of how much work your crews can handle. You wouldn't bid a job under those conditions. And we don't claim that all construction is done at these prices.

Estimating Is an Art, not a science. On many jobs the range between high and low bid will be 20 percent or more. There's room for legitimate disagreement on what the correct costs are, even when complete plans and specifications are available, the date and site are established, and labor and material costs are identical for all bidders.

No cost fits all jobs. Good estimates are custom-made for a particular project and a single contractor through judgment, analysis and experience.

This book isn't a substitute for judgment, analysis and sound estimating practice. It's an *aid* in developing an *informed opinion* of cost. If you're using this book as a sole cost authority for contract bids, you're reading more into these pages than the editors intend.

Use These Figures to compile preliminary estimates, when a "snap" bid is needed to close the deal, and when no actual costs are available. This book will reduce the chance of error or omission on bid estimates, speed "ball park" estimates, and be a good guide when there's no time to get a quote.

Where Do We Get These Figures? From the same sources all professional estimators use: material suppliers, material price services, analysis of plans, specifications, estimates and completed project costs, and both published and unpublished cost studies compiled by both private and government agencies. In addition, we conduct nationwide mail and phone surveys and have the use of several major national estimating databases.

We'll Answer Your Questions about any part of this book and explain how to apply these costs. Free telephone assistance is available from 8 a.m. until 5 p.m. Pacific time Monday through Friday except holidays. Phone 760-438-7828, Ext. 2. We don't accept collect calls and can't estimate the job for you. But if you need clarification on something in this manual, we can help.

Labor Costs and Crews

Throughout this manual you'll see a column headed *Craft@Hrs.* Letters and numbers in this column show our estimates of:

- ❖ Who will do the work (the craft code)
- ❖ An @ symbol which means at
- ❖ How long the work will take (manhours).

For example, suppose you see the following in the *Craft@Hrs* column:

B1@.016

That means we estimate the installation rate for crew B1 at 0.016 manhours per unit. That's the same as 16 manhours per 1,000 units.

Figure 1-4 is a table that defines each of the craft codes used in this book. Notice that crew B1 is composed of two craftsmen: one laborer and one carpenter.

Notice also in the table that the cost per manhour for crew B1 is listed as \$35.69. That's the average for a laborer (listed at \$31.97 per hour) and a carpenter (listed at \$39.40 per hour): \$31.97 plus 39.40 is \$71.37. Divide by 2 to get \$35.69 (\$35.685 rounded up), the average cost per manhour for crew B1.

In the table, the cost per manhour is the sum of hourly costs of all crew members divided by the number of crew members. That's the average cost per manhour.

Costs in the Labor column in this book are the product of the installation time (in manhours) multiplied by the cost per manhour. For example, if the installation rate is 0.016 manhours per unit, the installation cost is 0.016 multiplied by \$35.69, the average cost per manhour for crew B1.

Figure 1-5 shows hourly labor costs components — base wage, typical fringe benefits, payroll taxes, insurance and the total hourly cost.

Craft Codes		
Craft Code	Cost Per Manhour	Crew Composition
B1	\$35.69	1 laborer, 1 carpenter
B2	\$36.92	1 laborer, 2 carpenters
B3	\$34.45	2 laborers, 1 carpenter
B4	\$39.60	1 laborer, 1 operating engineer, 1 reinforcing iron worker
B5	\$39.17	1 laborer, 1 carpenter, 1 cement mason, 1 operating engineer, 1 reinforcing iron worker
B6	\$34.81	1 laborer, 1 cement mason
B7	\$32.63	1 laborer, 1 truck driver
B8	\$38.57	1 laborer, 1 operating engineer
B9	\$35.02	1 bricklayer, 1 bricklayer's helper
BB	\$40.19	1 bricklayer
BC	\$39.40	1 carpenter
BE	\$43.09	1 electrician
BF	\$36.40	1 floor layer
BG	\$38.20	1 glazier
BH	\$29.85	1 bricklayer's helper
BL	\$31.97	1 laborer
BR	\$38.17	1 lather
BS	\$35.38	1 marblesetter
CF	\$37.65	1 cement mason
CT	\$37.47	1 mosaic & terrazzo worker
D1	\$38.88	1 drywall installer, 1 drywall taper
DI	\$38.64	1 drywall installer
DT	\$39.12	1 drywall taper
HC	\$31.08	1 plasterer helper
OE	\$45.16	1 operating engineer
P1	\$39.03	1 laborer, 1 plumber
PM	\$46.09	1 plumber
PP	\$36.20	1 painter, 1 laborer
PR	\$39.59	1 plasterer
PT	\$40.43	1 painter
R1	\$37.85	1 roofer, 1 laborer
RI	\$41.66	1 reinforcing iron worker
RR	\$43.73	1 roofer
SW	\$44.66	1 sheet metal worker
T1	\$34.95	1 tile layer, 1 laborer
TL	\$37.92	1 tile layer
TR	\$33.29	1 truck driver

Figure 1-4

Craft codes used in this manual

Hourly Labor Cost						
	1	2	3	4	5	6
Craft	Base wage per hour	Taxable fringe benefits (5.61% of base wage)	Insurance and employer taxes (%)	Insurance and employer taxes (\$)	Non-Taxable fringe benefits (4.96% of base wage)	Total hourly cost used in this book
Bricklayer	\$29.51	\$1.66	24.27%	\$7.56	\$1.46	\$40.19
Bricklayer's Helper	21.91	1.23	24.27	5.62	1.09	29.85
Building Laborer	22.31	1.25	30.97	7.30	1.11	31.97
Carpenter	27.72	1.56	29.87	8.75	1.37	39.40
Cement Mason	28.04	1.57	22.46	6.65	1.39	37.65
Drywall Installer	28.74	1.61	22.65	6.87	1.42	38.64
Drywall Taper	29.09	1.63	22.65	6.96	1.44	39.12
Electrician	32.89	1.85	19.34	6.72	1.63	43.09
Floor Layer	26.99	1.51	23.01	6.56	1.34	36.40
Glazier	27.97	1.57	24.62	7.27	1.39	38.20
Lather	28.83	1.62	20.67	6.29	1.43	38.17
Marble Setter	26.71	1.50	20.74	5.85	1.32	35.38
Millwright	28.20	1.58	20.64	6.15	1.40	37.33
Mosaic & Terrazzo Worker	28.28	1.59	20.74	6.20	1.40	37.47
Operating Engineer	33.18	1.86	24.19	8.48	1.64	45.16
Painter	29.75	1.67	24.01	7.54	1.47	40.43
Plasterer	28.43	1.60	27.15	8.15	1.41	39.59
Plasterer Helper	22.32	1.25	27.15	6.40	1.11	31.08
Plumber	34.02	1.91	23.57	8.47	1.69	46.09
Reinforcing Ironworker	29.88	1.68	27.31	8.62	1.48	41.66
Roofer	28.40	1.59	41.11	12.33	1.41	43.73
Sheet Metal Worker	32.61	1.83	24.97	8.60	1.62	44.66
Sprinkler Fitter	33.43	1.88	24.22	8.55	1.66	45.52
Tile Layer	28.62	1.61	20.74	6.27	1.42	37.92
Truck Driver	24.27	1.36	25.19	6.46	1.20	33.29

Figure 1-5*Components of hourly labor costs*

The labor costs shown in Column 6 were used to compute the manhour costs for crews and the figures in the Labor column.

It's important that you understand what's included in the figures in each of the six columns in the table. Here's an explanation:

Column 1, the base wage per hour, is the craftsman's hourly wage. These figures are representative of what many contractors will be paying craftsmen working on home improvement jobs in 2023.

Column 2, taxable fringe benefits, includes vacation pay, sick leave and other taxable benefits. These fringe benefits average 5.61 percent of the base wage for many home improvement contractors. This benefit is in addition to the base wage.

Column 3, insurance and employer taxes in percent, shows the insurance and tax rate for construction trades. The cost of insurance in this column includes workers' compensation and contractor's casualty and liability coverage. Insurance rates

vary widely from state to state and depend on a contractor's loss experience. Note that taxes and insurance increase the hourly labor cost by 30 to 35 percent for most trades. There is no legal way to avoid these costs.

Column 4, insurance and employer taxes in dollars, shows the hourly cost of taxes and insurance for each construction trade. Insurance and taxes are paid on the costs in both columns 1 and 2.

Column 5, non-taxable fringe benefits, includes employer paid non-taxable benefits such as medical coverage and tax-deferred pension and profit sharing plans. These fringe benefits average 4.96 percent of the base wage for many home improvement contractors. The employer pays no taxes or insurance on these benefits.

Column 6, the total hourly cost in dollars, is the sum of columns 1, 2, 4 and 5.

These hourly labor costs will apply within a few percent on many jobs. But wage rates may be much higher or lower in the area where you do business. We recommend using your actual labor cost rather than national averages. That's easy with *National Estimator Cloud*. When copying and pasting costs to your estimate, adjust the assumed hourly labor cost to your actual hourly labor cost. You need do this only once for each trade. And you can make this adjustment at any time. Any change you make is applied to that trade throughout the estimate.

Abbreviations			
4WD	four-wheel drive	EPA	Environmental Protection Agency
ABS	acrylonitrile butadiene styrene	F	Fahrenheit
AC	alternating current	GFCI	ground fault circuit interrupter
ACQ	Alkaline Copper Quat	GRS	galvanized rigid steel
ADA	Americans with Disabilities Act	H	height
ANSI	American Nat. Standards Institute	HOM	higher order mode
APP	atactic polypropylene	HP	horsepower
ASTM	Amer. Society for Testing Materials	HVAC	heating, ventilating & air cond.
AWG	American Wire Gauge	ID	inside diameter
BF	board foot	IMC	intermediate metal conduit
Btr	better	KD	kiln dried
Btu(s)	British thermal unit(s)	KO	knockout
C	Celsius/Centigrade	kW	kilowatt(s)
CF	cubic foot	L	length
CFM	cubic feet per minute	Lb(s)	pound(s)
CLF	100 linear feet	LF	linear foot
CPM	cycles per minute	LS	lump sum
CSF	100 square feet	MBF	1,000 board feet
CY	cubic yard	MDF	medium density fiberboard
d	penny	mm	millimeter(s)
D	depth	Mo	month
DWV	drain, waste & vent	MPH	miles per hour
Ea	each	MSF	1,000 square feet
EMT	electric metallic tube	NEC	National Electrical Code
		NEMA	National Electrical Manufacturer's Assoc.
		OC	spacing from center to center
		OD	outside diameter
		OSB	oriented strand board
		OSHA	Occupational Safety & Health Admin.
		oz.	ounce(s)
		PSI	pounds per square inch
		PVC	polyvinyl chloride
		R	thermal resistance
		S4S	surfaced 4 sides
		SBS	styrene butadiene styrene
		SF	square foot
		SFCA	(per) square foot of contact area
		Sq	100 square feet
		Std	standard
		SY	square yard
		T	thick
		T&G	tongue & groove edge
		UL	Underwriter's Laboratory
		USDA	United States Dept. of Agriculture
		UV	ultraviolet
		W	width
		X	by or times

Figure 1-6

Abbreviations used in this manual

Area Modification Factors

Construction costs are higher in some areas than in other areas. Add or deduct the percentages shown on the following pages to adapt the costs in this book to your jobsite. Adjust your cost estimate by the appropriate percentages in this table to find the estimated cost for the site selected. Where 0% is shown, it means no modification is required. *National Estimator Cloud* will apply an area modification factor for any five-digit zip or Canadian postal code you select.

Modification factors are listed by state and province. Areas within each state are listed by the first three digits of the postal zip code. For convenience, one representative city is identified in each three-digit zip or range of zips. Percentages are based on the average of all data points in the table. Factors listed for each state and province are the average of all data in that state or province. Figures for the zips are the average of all information in that area. And figures in the Total column are the weighted average of factors for Labor, Material and Equipment.

These percentages are composites of many costs and will not necessarily be accurate when estimating the cost of any particular part of a building. But when used to modify costs for an entire structure, they should improve the accuracy of your estimates.

Area Modification Factors

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Alabama Average		-1	-4	0	-2%
Anniston	362	-3	-12	-1	-7%
Auburn	368	-1	-7	0	-4%
Bellamy	369	-2	-5	-1	-3%
Birmingham	350-352	-3	12	-1	4%
Dothan	363	-1	-5	0	-3%
Evergreen	364	-2	-7	-1	-4%
Gadsden	359	-4	-10	-1	-7%
Huntsville	358	1	13	0	7%
Jasper	355	-2	-19	-1	-10%
Mobile	365-366	-1	-4	0	-2%
Montgomery	360-361	-1	0	0	-1%
Scottsboro	357	0	5	0	2%
Selma	367	-1	-8	0	-4%
Sheffield	356	-1	-1	0	-1%
Tuscaloosa	354	0	-8	0	-4%
Alaska Average		14	15	4	14%
Anchorage	995	16	20	5	18%
Fairbanks	997	16	24	5	20%
Juneau	998	18	8	6	13%
Ketchikan	999	3	7	1	5%
King Salmon	996	16	14	5	15%

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Arizona Average		1	-9	0	-4%
Chambers	865	1	-30	0	-13%
Douglas	855	0	-20	0	-9%
Flagstaff	860	2	-19	1	-8%
Kingman	864	1	-10	0	-4%
Mesa	852	1	11	0	6%
Phoenix	850	1	11	0	6%
Prescott	863	3	-14	1	-5%
Show Low	859	2	-20	1	-8%
Tucson	856-857	0	-9	0	-4%
Yuma	853	0	10	0	5%
Arkansas Average		-2	-14	0	-7%
Batesville	725	0	-19	0	-9%
Camden	717	-4	-13	-1	-8%
Fayetteville	727	0	-9	0	-4%
Fort Smith	729	-1	-15	0	-7%
Harrison	726	-1	-28	0	-13%
Hope	718	-3	-17	-1	-9%
Hot Springs	719	-2	-27	-1	-13%
Jonesboro	724	-1	-6	0	-3%
Little Rock	720-722	-1	-4	0	-2%
Pine Bluff	716	-4	-23	-1	-13%

Area Modification Factors

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Russellville	728	0	3	0	1%
West Memphis	723	-3	-12	-1	-7%
California Average		2	17	1	9%
Alhambra	917-918	3	17	1	9%
Bakersfield	932-933	0	-2	0	-1%
El Centro	922	1	-2	0	0%
Eureka	955	1	-6	0	-2%
Fresno	936-938	0	-3	0	-1%
Herlong	961	2	-1	1	1%
Inglewood	902-905	3	16	1	9%
Irvine	926-927	3	29	1	15%
Lompoc	934	3	11	1	7%
Long Beach	907-908	3	20	1	11%
Los Angeles	900-901	3	14	1	8%
Marysville	959	1	2	0	1%
Modesto	953	1	3	0	2%
Mojave	935	0	11	0	5%
Novato	949	3	29	1	15%
Oakland	945-947	3	39	1	20%
Orange	928	3	26	1	14%
Oxnard	930	3	6	1	4%
Pasadena	910-912	4	16	1	9%
Rancho Cordova	956-957	2	21	1	11%
Redding	960	1	4	0	2%
Richmond	948	2	46	1	22%
Riverside	925	1	7	0	4%
Sacramento	958	1	23	0	11%
Salinas	939	3	2	1	3%
San Bernardino	923-924	0	7	0	3%
San Diego	919-921	3	12	1	7%
San Francisco	941	3	69	1	33%
San Jose	950-951	3	45	1	22%
San Mateo	943-944	4	53	1	26%
Santa Barbara	931	3	4	1	3%
Santa Rosa	954	3	14	1	8%
Stockton	952	2	14	1	8%
Sunnyvale	940	3	52	1	26%
Van Nuys	913-916	3	14	1	8%
Whittier	906	3	16	1	9%
Colorado Average		2	2	1	2%
Aurora	800-801	3	19	1	10%
Boulder	803-804	3	12	1	7%
Colorado Springs	808-809	2	2	1	2%
Denver	802	3	23	1	12%
Durango	813	1	-12	0	-5%
Fort Morgan	807	2	-4	1	-1%
Glenwood Springs	816	2	7	1	4%
Grand Junction	814-815	1	-10	0	-4%
Greeley	806	3	12	1	7%
Longmont	805	3	6	1	4%
Pagosa Springs	811	0	-11	0	-5%
Pueblo	810	-1	-6	0	-3%
Salida	812	2	-8	1	-3%

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Connecticut Average		1	16	0	8%
Bridgeport	066	0	18	0	8%
Bristol	060	1	22	0	11%
Fairfield	064	2	19	1	10%
Hartford	061	0	20	0	9%
New Haven	065	1	14	0	7%
Norwich	063	0	8	0	4%
Stamford	068-069	4	25	1	14%
Waterbury	067	1	13	0	7%
West Hartford	062	1	6	0	3%
Delaware Average		1	6	0	3%
Dover	199	1	-2	0	0%
Newark	197	2	11	1	6%
Wilmington	198	0	10	0	5%
District of Columbia					
Washington	200-205	2	21	1	11%
Florida Average		0	-7	0	-3%
Altamonte Springs	327	-1	-3	0	-2%
Bradenton	342	0	-11	0	-5%
Brooksville	346	0	-11	0	-5%
Daytona Beach	321	-2	-17	-1	-9%
Fort Lauderdale	333	3	3	1	3%
Fort Myers	339	0	-11	0	-5%
Fort Pierce	349	-2	-13	-1	-7%
Gainesville	326	-1	-14	0	-7%
Jacksonville	322	-1	0	0	-1%
Lakeland	338	-3	-12	-1	-7%
Melbourne	329	-2	-10	-1	-6%
Miami	330-332	2	4	1	3%
Naples	341	3	-7	1	-2%
Ocala	344	-3	-18	-1	-10%
Orlando	328	0	1	0	0%
Panama City	324	-2	-14	-1	-8%
Pensacola	325	-1	-13	0	-7%
Saint Augustine	320	-1	-4	0	-2%
Saint Cloud	347	0	-4	0	-2%
St Petersburg	337	0	-4	0	-2%
Tallahassee	323	0	-7	0	-3%
Tampa	335-336	-1	1	0	0%
West Palm Beach	334	1	5	0	3%
Georgia Average		-1	2	0	0%
Albany	317	-2	-11	-1	-6%
Athens	306	0	0	0	0%
Atlanta	303	3	40	1	20%
Augusta	308-309	-2	2	-1	0%
Buford	305	0	-2	0	-1%
Calhoun	307	-1	0	0	-1%
Columbus	318-319	-1	-5	0	-3%
Dublin/Fort Valley	310	-3	-13	-1	-8%
Hinesville	313	-2	8	-1	3%
Kings Bay	315	-2	-19	-1	-10%

Area Modification Factors

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Macon	312	-2	6	-1	2%
Marietta	300-302	1	13	0	7%
Savannah	314	-1	-3	0	-2%
Statesboro	304	-2	14	-1	5%
Valdosta	316	-1	-6	0	-3%

Hawaii Average 17 21 6 18%

Aliamanu	968	17	25	6	21%
Ewa	967	17	19	6	18%
Halawa Heights	967	17	19	6	18%
Hilo	967	17	19	6	18%
Honolulu	968	17	25	6	21%
Kailua	968	17	25	6	21%
Lualualei	967	17	19	6	18%
Millilani Town	967	17	19	6	18%
Pearl City	967	17	19	6	18%
Wahiawa	967	17	19	6	18%
Waianae	967	17	19	6	18%
Wailuku (Maui)	967	17	19	6	18%

Idaho Average 0 -17 0 -8%

Boise	837	1	-2	0	0%
Coeur d'Alene	838	0	-14	0	-6%
Idaho Falls	834	-1	-19	0	-9%
Lewiston	835	0	-28	0	-13%
Meridian	836	0	-14	0	-6%
Pocatello	832	-1	-21	0	-10%
Sun Valley	833	0	-18	0	-8%

Illinois Average -1 8 0 4%

Arlington Heights	600	1	25	0	12%
Aurora	605	2	28	1	14%
Belleville	622	-2	10	-1	4%
Bloomington	617	1	-2	0	0%
Carbondale	629	-3	-14	-1	-8%
Carol Stream	601	2	26	1	13%
Centralia	628	-3	-10	-1	-6%
Champaign	618	-1	-3	0	-2%
Chicago	606-608	2	26	1	13%
Decatur	623	-2	-7	-1	-4%
Galesburg	614	-2	-7	-1	-4%
Granite City	620	-3	5	-1	1%
Green River	612	-1	2	0	0%
Joliet	604	0	25	0	12%
Kankakee	609	-2	2	-1	0%
Lawrenceville	624	-4	0	-1	-2%
Oak Park	603	3	29	1	15%
Peoria	615-616	-1	19	0	8%
Peru	613	0	7	0	3%
Quincy	602	3	25	1	13%
Rockford	610-611	-2	12	-1	4%
Springfield	625-627	-2	0	-1	-1%
Urbana	619	-3	-3	-1	-3%

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
----------	-----	------	------	--------	-----------------

Indiana Average -2 -5 -1 -4%

Aurora	470	-1	-15	0	-7%
Bloomington	474	1	-10	0	-4%
Columbus	472	0	-5	0	-2%
Elkhart	465	-2	-5	-1	-3%
Evansville	476-477	-2	-3	-1	-2%
Fort Wayne	467-468	-3	0	-1	-2%
Gary	463-464	-4	16	-1	5%
Indianapolis	460-462	-1	11	0	5%
Jasper	475	-2	-13	-1	-7%
Jeffersonville	471	-1	-10	0	-5%
Kokomo	469	-2	-14	-1	-8%
Lafayette	479	-2	-2	-1	-2%
Muncie	473	-4	-16	-1	-9%
South Bend	466	-4	-5	-1	-4%
Terre Haute	478	-4	-8	-1	-6%

Iowa Average -2 -5 -1 -3%

Burlington	526	0	-8	0	-4%
Carroll	514	-3	-10	-1	-6%
Cedar Falls	506	-1	-4	0	-2%
Cedar Rapids	522-524	0	5	0	2%
Cherokee	510	-2	1	-1	-1%
Council Bluffs	515	-2	-6	-1	-4%
Creston	508	-3	-6	-1	-4%
Davenport	527-528	-1	1	0	0%
Decorah	521	-2	-10	-1	-6%
Des Moines	500-503	-2	9	-1	3%
Dubuque	520	-2	-1	-1	-2%
Fort Dodge	505	-2	-1	-1	-2%
Mason City	504	0	-7	0	-3%
Ottumwa	525	0	-22	0	-10%
Sheldon	512	-1	-1	0	-1%
Shenandoah	516	-3	-23	-1	-12%
Sioux City	511	-2	3	-1	0%
Spencer	513	-1	-5	0	-3%
Waterloo	507	-4	-4	-1	-4%

Kansas Average -2 -13 -1 -7%

Colby	677	-1	-10	0	-5%
Concordia	669	-1	-31	0	-15%
Dodge City	678	-2	-12	-1	-7%
Emporia	668	-3	-20	-1	-11%
Fort Scott	667	-2	-9	-1	-5%
Hays	676	-2	-22	-1	-11%
Hutchinson	675	-3	-14	-1	-8%
Independence	673	-3	-1	-1	-2%
Kansas City	660-662	0	8	0	4%
Liberal	679	-2	-22	-1	-11%
Salina	674	-3	-15	-1	-8%
Topeka	664-666	-3	-7	-1	-5%
Wichita	670-672	-2	-8	-1	-5%

Area Modification Factors

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Kentucky Average		-1	-12	0	-6%
Ashland	411-412	-4	-6	-1	-5%
Bowling Green	421	0	-9	0	-4%
Campton	413-414	-1	-28	0	-13%
Covington	410	-1	9	0	4%
Elizabethtown	427	-1	-13	0	-7%
Frankfort	406	1	-18	0	-8%
Hazard	417-418	-2	-27	-1	-13%
Hopkinsville	422	-2	-9	-1	-5%
Lexington	403-405	1	4	0	2%
London	407-409	-1	-24	0	-12%
Louisville	400-402	-1	1	0	0%
Owensboro	423	-2	-16	-1	-8%
Paducah	420	-2	-12	-1	-7%
Pikeville	415-416	-3	-20	-1	-11%
Somerset	425-426	0	-22	0	-10%
White Plains	424	-3	-4	-1	-3%

Louisiana Average		-1	4	-1	1%
Alexandria	713-714	-3	-13	-1	-8%
Baton Rouge	707-708	0	29	0	13%
Houma	703	-2	18	-1	7%
Lafayette	705	0	9	0	4%
Lake Charles	706	-2	19	-1	8%
Mandeville	704	-1	14	0	6%
Minden	710	-2	-16	-1	-8%
Monroe	712	-2	-18	-1	-9%
New Orleans	700-701	0	14	0	6%
Shreveport	711	-2	-12	-1	-7%

Maine Average		0	-10	0	-5%
Auburn	042	-1	-9	0	-5%
Augusta	043	-1	-9	0	-5%
Bangor	044	-1	-4	0	-2%
Bath	045	1	-13	0	-5%
Brunswick	039-040	1	0	0	1%
Camden	048	-1	-18	0	-9%
Cutler	046	-1	-21	0	-10%
Dexter	049	-1	-12	0	-6%
Northern Area	047	-2	-16	-1	-8%
Portland	041	2	5	1	3%

Maryland Average		1	5	0	3%
Annapolis	214	4	14	1	9%
Baltimore	210-212	-1	14	0	6%
Bethesda	208-209	3	24	1	13%
Church Hill	216	2	-9	1	-3%
Cumberland	215	-4	-15	-1	-9%
Elkton	219	2	6	1	4%
Frederick	217	1	9	0	5%
Laurel	206-207	2	15	1	8%
Salisbury	218	1	-14	0	-6%

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Massachusetts Average		2	24	1	12%
Ayer	015-016	1	15	0	7%
Bedford	017	3	39	1	20%
Boston	021-022	3	55	1	27%
Brockton	023-024	3	41	1	20%
Cape Cod	026	2	10	1	6%
Chicopee	010	1	9	0	5%
Dedham	019	2	30	1	15%
Fitchburg	014	2	28	1	14%
Hingham	020	3	39	1	20%
Lawrence	018	2	36	1	18%
Nantucket	025	3	22	1	12%
New Bedford	027	1	19	0	9%
Northfield	013	2	6	1	4%
Pittsfield	012	1	-4	0	-1%
Springfield	011	-1	8	0	3%

Michigan Average		-2	5	-1	1%
Battle Creek	490-491	-3	1	-1	-1%
Detroit	481-482	0	17	0	8%
Flint	484-485	-3	2	-1	-1%
Grand Rapids	493-495	-2	13	-1	5%
Grayling	497	1	-13	0	-5%
Jackson	492	-3	-1	-1	-2%
Lansing	488-489	-1	3	0	1%
Marquette	498-499	-1	-3	0	-2%
Pontiac	483	-3	24	-1	9%
Royal Oak	480	-2	19	-1	8%
Saginaw	486-487	-2	0	-1	-1%
Traverse City	496	-1	-3	0	-2%

Minnesota Average		-1	4	0	2%
Bemidji	566	-1	6	0	2%
Brainerd	564	-1	1	0	0%
Duluth	556-558	-2	2	-1	0%
Fergus Falls	565	-1	-12	0	-6%
Magnolia	561	-1	-13	0	-7%
Mankato	560	0	3	0	1%
Minneapolis	553-555	1	27	0	13%
Rochester	559	0	0	0	0%
St Cloud	563	-1	22	0	10%
St Paul	550-551	1	20	0	10%
Thief River Falls	567	0	-6	0	-3%
Willmar	562	-1	-2	0	-1%

Mississippi Average		-2	0	-1	-1%
Clarksdale	386	-3	3	-1	0%
Columbus	397	-1	-3	0	-2%
Greenville	387	-4	-5	-1	-4%
Greenwood	389	-3	-1	-1	-2%
Gulfport	395	-2	4	-1	1%
Jackson	390-392	-3	9	-1	3%
Laurel	394	-3	6	-1	1%

Area Modification Factors

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
McComb	396	-2	-7	-1	-4%
Meridian	393	-2	0	-1	-1%
Tupelo	388	-1	-4	-1	-2%
Missouri Average		-1	-8	0	-4%
Cape Girardeau	637	-2	-8	-1	-5%
Caruthersville	638	-1	-11	0	-6%
Chillicothe	646	-2	-15	-1	-8%
Columbia	652	1	-7	0	-3%
East Lynne	647	-1	-8	0	-4%
Farmington	636	-3	-18	-1	-10%
Hannibal	634	0	-19	0	-9%
Independence	640	-1	10	0	4%
Jefferson City	650-651	1	-10	0	-4%
Joplin	648	-2	-9	-1	-5%
Kansas City	641	-2	12	-1	4%
Kirksville	635	0	-25	0	-12%
Knob Noster	653	0	-18	0	-8%
Lebanon	654-655	-2	-27	-1	-13%
Poplar Bluff	639	-1	-20	0	-10%
Saint Charles	633	1	1	0	1%
Saint Joseph	644-645	-3	21	-1	8%
Springfield	656-658	-2	-15	-1	-8%
St Louis	630-631	-2	20	-1	8%
Montana Average		0	-5	0	-2%
Billings	590-591	0	1	0	0%
Butte	597	1	3	0	2%
Fairview	592	-1	8	0	3%
Great Falls	594	-1	1	0	0%
Havre	595	-1	-14	0	-7%
Helena	596	0	-7	0	-3%
Kalispell	599	1	-12	0	-5%
Miles City	593	-1	-14	0	-7%
Missoula	598	1	-11	0	-5%
Nebraska Average		-1	-15	0	-7%
Alliance	693	-1	-27	0	-13%
Columbus	686	-1	-10	0	-5%
Grand Island	688	0	-18	0	-8%
Hastings	689	0	-10	0	-5%
Lincoln	683-685	0	-9	0	-4%
McCook	690	1	-20	0	-9%
Norfolk	687	-3	-10	-1	-6%
North Platte	691	0	-19	0	-9%
Omaha	680-681	-1	1	0	0%
Valentine	692	-2	-25	-1	-13%
Nevada Average		2	0	1	1%
Carson City	897	2	-10	1	-4%
Elko	898	1	2	0	1%
Ely	893	2	-11	1	-4%
Fallon	894	2	7	1	4%
Las Vegas	889-891	2	4	1	3%
Reno	895	2	7	1	4%

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
New Hampshire Average		1	4	0	2%
Charlestown	036	0	-8	0	-4%
Concord	034	1	0	0	1%
Dover	038	1	20	0	10%
Lebanon	037	2	-7	1	-2%
Littleton	035	-1	-12	0	-6%
Manchester	032-033	0	15	0	7%
New Boston	030-031	1	23	0	11%
New Jersey Average		1	22	0	11%
Atlantic City	080-084	-2	14	-1	5%
Brick	087	2	4	1	3%
Dover	078	1	23	0	11%
Edison	088-089	1	32	0	15%
Hackensack	076	3	27	1	14%
Monmouth	077	3	23	1	12%
Newark	071-073	1	21	0	10%
Passaic	070	2	23	1	12%
Paterson	074-075	2	18	1	9%
Princeton	085	-2	28	-1	12%
Summit	079	3	33	1	17%
Trenton	086	-3	23	-1	9%
New Mexico Average		0	-21	0	-10%
Alamogordo	883	-1	-25	0	-12%
Albuquerque	870-871	2	-7	1	-2%
Clovis	881	-2	-35	-1	-17%
Farmington	874	2	-9	1	-3%
Fort Sumner	882	-3	-3	-1	-3%
Gallup	873	1	-30	0	-13%
Holman	877	2	-25	1	-10%
Las Cruces	880	-1	-23	0	-11%
Santa Fe	875	3	-14	1	-5%
Socorro	878	1	-41	0	-18%
Truth or Consequences	879	-2	-22	-1	-11%
Tucumcari	884	-1	-21	0	-10%
New York Average		0	14	0	7%
Albany	120-123	-1	18	0	8%
Amityville	117	2	19	1	10%
Batavia	140	-3	4	-1	0%
Binghamton	137-139	-3	6	-1	1%
Bronx	104	2	24	1	12%
Brooklyn	112	3	11	1	7%
Buffalo	142	-4	6	-1	1%
Elmira	149	-4	-2	-1	-3%
Flushing	113	3	28	1	14%
Garden City	115	3	25	1	13%
Hicksville	118	3	23	1	12%
Ithaca	148	-4	-7	-1	-5%
Jamaica	114	3	25	1	13%
Jamestown	147	-4	-9	-1	-6%
Kingston	124	0	-5	0	-2%
Long Island	111	3	65	1	31%

Area Modification Factors

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Montauk	119	1	19	0	9%
New York (Manhattan)	100-102	3	67	1	32%
New York City	100-102	3	67	1	32%
Newcomb	128	-1	7	0	3%
Niagara Falls	143	-4	-10	-1	-7%
Plattsburgh	129	1	4	0	2%
Poughkeepsie	125-126	1	1	0	1%
Queens	110	4	31	1	16%
Rochester	144-146	-3	5	-1	1%
Rockaway	116	3	16	1	9%
Rome	133-134	-3	-6	-1	-4%
Staten Island	103	3	16	1	9%
Stewart	127	-1	27	0	12%
Syracuse	130-132	-3	7	-1	2%
Tonawanda	141	-4	1	-1	-2%
Utica	135	-4	-6	-1	-5%
Watertown	136	-2	-7	-1	-4%
West Point	109	1	8	0	4%
White Plains	105-108	3	22	1	12%

North Carolina Average

Asheville	287-289	1	-13	0	-5%
Charlotte	280-282	1	12	0	6%
Durham	277	2	10	1	6%
Elizabeth City	279	1	-17	0	-7%
Fayetteville	283	-1	-12	0	-6%
Goldsboro	275	1	6	0	3%
Greensboro	274	1	3	0	2%
Hickory	286	-1	-8	0	-4%
Kinston	285	-1	-16	0	-8%
Raleigh	276	3	9	1	6%
Rocky Mount	278	-1	-10	0	-5%
Wilmington	284	1	-9	0	-4%
Winston-Salem	270-273	0	-1	0	0%

North Dakota Average

Bismarck	585	-1	2	0	0%
Dickinson	586	-1	20	0	9%
Fargo	580-581	0	1	0	0%
Grand Forks	582	0	-5	0	-2%
Jamestown	584	-1	-8	0	-4%
Minot	587	-1	-1	0	-1%
Nekoma	583	-1	-37	0	-18%
Williston	588	-1	30	0	13%

Ohio Average

Akron	442-443	-2	6	-1	2%
Canton	446-447	-3	4	-1	0%
Chillicothe	456	-2	-9	-1	-5%
Cincinnati	450-452	-1	10	0	4%
Cleveland	440-441	-3	9	-1	3%
Columbus	432	-1	14	0	6%
Dayton	453-455	-3	5	-1	1%

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Lima	458	-3	-4	-1	-3%
Marietta	457	-2	-12	-1	-7%
Marion	433	-3	-4	-1	-3%
Newark	430-431	-1	12	0	5%
Sandusky	448-449	-1	4	0	1%
Steubenville	439	-3	-3	-1	-3%
Toledo	434-436	-1	9	0	4%
Warren	444	-4	-6	-1	-5%
Youngstown	445	-5	0	-2	-3%
Zanesville	437-438	-2	1	-1	-1%

Oklahoma Average

Adams	739	-2	-11	-1	-6%
Ardmore	734	-3	-14	-1	-8%
Clinton	736	-3	-11	-1	-7%
Durant	747	-4	-13	-1	-8%
Enid	737	-4	-18	-1	-10%
Lawton	735	-3	-23	-1	-12%
McAlester	745	-4	-9	-1	-6%
Muskogee	744	-2	-11	-1	-6%
Norman	730	-2	-5	-1	-3%
Oklahoma City	731	-2	-2	-1	-2%
Ponca City	746	-3	-10	-1	-6%
Poteau	749	-2	-23	-1	-12%
Pryor	743	-2	-14	-1	-8%
Shawnee	748	-4	-12	-1	-8%
Tulsa	740-741	-1	-6	0	-3%
Woodward	738	-4	-20	-1	-11%

Oregon Average

Adrian	979	-1	-30	0	-14%
Bend	977	1	5	0	3%
Eugene	974	2	-9	1	-3%
Grants Pass	975	2	-12	1	-4%
Klamath Falls	976	2	-19	1	-8%
Pendleton	978	0	-7	0	-3%
Portland	970-972	2	22	1	11%
Salem	973	2	-4	1	-1%

Pennsylvania Average

Allentown	181	-2	7	-1	2%
Altoona	166	-3	-16	-1	-9%
Beaver Springs	178	-3	-12	-1	-7%
Bethlehem	180	-1	15	0	6%
Bradford	167	-4	-18	-1	-10%
Butler	160	-4	3	-1	-1%
Chambersburg	172	-1	-11	0	-6%
Clearfield	168	2	7	1	4%
DuBois	158	-2	-20	-1	-10%
East Stroudsburg	183	0	-12	0	-6%
Erie	164-165	-3	-16	-1	-9%
Genesee	169	-4	-16	-1	-9%
Greensburg	156	-4	-2	-1	-3%
Harrisburg	170-171	-2	1	-1	-1%

Area Modification Factors

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Hazleton	182	-3	-5	-1	-4%
Johnstown	159	-4	-17	-1	-10%
Kittanning	162	-4	-11	-1	-7%
Lancaster	175-176	-2	4	-1	1%
Meadville	163	-4	-25	-1	-14%
Montrose	188	-3	-9	-1	-6%
New Castle	161	-4	4	-1	0%
Philadelphia	190-191	-3	24	-1	9%
Pittsburgh	152	-4	9	-1	2%
Pottsville	179	-4	-7	-1	-5%
Punxsutawney	157	-4	-8	-1	-6%
Reading	195-196	-4	7	-1	1%
Scranton	184-185	-2	-3	-1	-2%
Somerset	155	-4	-17	-1	-10%
Southeastern	193	0	21	0	10%
Uniontown	154	-4	-14	-1	-9%
Valley Forge	194	-3	37	-1	15%
Warminster	189	-1	23	0	10%
Warrendale	150-151	-4	13	-1	4%
Washington	153	-4	4	-1	0%
Wilkes Barre	186-187	-3	-2	-1	-3%
Williamsport	177	-3	-9	-1	-6%
York	173-174	-3	4	-1	0%

Rhode Island Average		1	7	0	4%
Bristol	028	1	7	0	4%
Coventry	028	1	7	0	4%
Cranston	029	1	8	0	4%
Davisville	028	1	7	0	4%
Narragansett	028	1	7	0	4%
Newport	028	1	7	0	4%
Providence	029	1	8	0	4%
Warwick	028	1	7	0	4%

South Carolina Average		-1	-3	0	-1%
Aiken	298	0	5	0	2%
Beaufort	299	-1	-7	0	-4%
Charleston	294	-1	7	0	3%
Columbia	290-292	0	-3	0	-1%
Greenville	296	0	2	0	1%
Myrtle Beach	295	0	-12	0	-6%
Rock Hill	297	-1	-8	0	-4%
Spartanburg	293	-2	-4	-1	-3%

South Dakota Average		-1	-15	0	-7%
Aberdeen	574	-1	-15	0	-7%
Mitchell	573	-1	-15	0	-7%
Mobridge	576	-2	-20	-1	-10%
Pierre	575	-2	-25	-1	-13%
Rapid City	577	-2	-10	-1	-6%

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Sioux Falls	570-571	0	-2	0	-1%
Watertown	572	-1	-15	0	-7%

Tennessee Average		0	3	0	1%
Chattanooga	374	-1	9	0	4%
Clarksville	370	1	19	0	9%
Cleveland	373	-1	6	0	2%
Columbia	384	-1	-13	0	-7%
Cookeville	385	0	-8	0	-4%
Jackson	383	-1	11	0	5%
Kingsport	376	0	-7	0	-3%
Knoxville	377-379	-1	2	0	0%
McKenzie	382	-1	-20	0	-10%
Memphis	380-381	-1	13	0	5%
Nashville	371-372	1	21	0	10%

Texas Average		-2	-1	-1	-1%
Abilene	795-796	-4	-8	-1	-6%
Amarillo	790-791	-2	-6	-1	-4%
Arlington	760	-1	17	0	7%
Austin	786-787	1	20	0	10%
Bay City	774	-1	22	0	10%
Beaumont	776-777	-3	8	-1	2%
Brownwood	768	-3	-18	-1	-10%
Bryan	778	0	-5	0	-2%
Childress	792	-3	-12	-1	-7%
Corpus Christi	783-784	-2	4	-1	1%
Dallas	751-753	-1	18	0	8%
Del Rio	788	-3	-22	-1	-12%
El Paso	798-799	-3	-21	-1	-11%
Fort Worth	761-762	-1	17	0	7%
Galveston	775	-3	19	-1	7%
Giddings	789	0	-1	0	0%
Greenville	754	-3	11	-1	3%
Houston	770-772	-1	21	0	9%
Huntsville	773	-2	17	-1	7%
Longview	756	-2	-12	-1	-7%
Lubbock	793-794	-3	-10	-1	-6%
Lufkin	759	-3	-16	-1	-9%
McAllen	785	-3	-23	-1	-12%
Midland	797	-3	15	-1	5%
Palestine	758	-2	-9	-1	-5%
Plano	750	0	18	0	8%
San Angelo	769	-3	-13	-1	-8%
San Antonio	780-782	-2	2	-1	0%
Texarkana	755	-3	-17	-1	-9%
Tyler	757	-1	-15	0	-7%
Victoria	779	-2	-3	-1	-2%
Waco	765-767	-3	-5	-1	-4%
Wichita Falls	763	-3	-12	-1	-7%
Woodson	764	-3	-7	-1	-5%

Area Modification Factors

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Utah Average		1	-10	1	-4%
Clearfield	840	2	0	1	1%
Green River	845	1	-22	0	-10%
Ogden	843-844	0	-15	0	-7%
Provo	846-847	2	-14	1	-5%
Salt Lake City	841	2	3	1	2%
Vermont Average		1	-11	0	-5%
Albany	058	1	-15	0	-6%
Battleboro	053	1	-14	0	-6%
Beecher Falls	059	1	-18	0	-8%
Bennington	052	-1	-16	0	-8%
Burlington	054	3	3	1	3%
Montpelier	056	2	-9	1	-3%
Rutland	057	-1	-17	0	-8%
Springfield	051	-1	-13	0	-7%
White River Junction	050	1	-4	0	-1%
Virginia Average		0	-6	0	-3%
Abingdon	242	-2	-15	-1	-8%
Alexandria	220-223	3	23	1	12%
Charlottesville	229	1	-8	0	-3%
Chesapeake	233	-1	-1	0	-1%
Culpeper	227	1	-11	0	-5%
Farmville	239	-2	-18	-1	-9%
Fredericksburg	224-225	1	-9	0	-4%
Galax	243	-2	-20	-1	-10%
Harrisonburg	228	1	-12	0	-5%
Lynchburg	245	-2	-15	-1	-8%
Norfolk	235-237	0	2	0	1%
Petersburg	238	-2	-1	-1	-2%
Radford	241	-2	-16	-1	-8%
Reston	201	3	19	1	10%
Richmond	232	-1	5	0	2%
Roanoke	240	-1	-6	0	-3%
Staunton	244	0	-12	0	-6%
Tazewell	246	-3	-25	-1	-13%
Virginia Beach	234	0	-2	0	-1%
Williamsburg	230-231	0	2	0	1%
Winchester	226	0	-11	0	-5%
Washington Average		1	0	1	1%
Clarkston	994	0	-12	0	-6%
Everett	982	2	7	1	4%
Olympia	985	2	-1	1	1%
Pasco	993	0	1	0	0%
Seattle	980-981	3	27	1	14%
Spokane	990-992	0	-7	0	-3%
Tacoma	983-984	2	9	1	5%
Vancouver	986	2	4	1	3%

Location	Zip	Mat.	Lab.	Equip.	Total Wtd. Avg.
Wenatchee	988	1	-12	0	-5%
Yakima	989	0	-13	0	-6%
West Virginia Average		-2	-13	-1	-7%
Beckley	258-259	1	-8	0	-3%
Bluefield	247-248	-1	-28	0	-13%
Charleston	250-253	1	5	0	3%
Clarksburg	263-264	-3	-3	-1	-3%
Fairmont	266	0	-32	0	-15%
Huntington	255-257	-1	-5	0	-3%
Lewisburg	249	-2	-29	-1	-14%
Martinsburg	254	-1	-16	0	-8%
Morgantown	265	-3	-7	-1	-5%
New Martinsville	262	-2	-20	-1	-10%
Parkersburg	261	-3	-13	-1	-8%
Romney	267	-4	-18	-1	-10%
Sugar Grove	268	-3	-22	-1	-12%
Wheeling	260	-3	13	-1	4%
Wisconsin Average		-1	3	0	1%
Amery	540	0	0	0	0%
Beloit	535	0	7	0	3%
Clam Lake	545	-1	-11	0	-6%
Eau Claire	547	-1	0	0	-1%
Green Bay	541-543	0	5	0	2%
La Crosse	546	-2	-1	-1	-2%
Ladysmith	548	-2	11	-1	4%
Madison	537	2	11	1	6%
Milwaukee	530-534	0	13	0	6%
Oshkosh	549	-1	13	0	5%
Portage	539	0	3	0	1%
Prairie du Chien	538	-2	-5	-1	-3%
Wausau	544	-1	-3	0	-2%
Wyoming Average		0	-12	0	-6%
Casper	826	-2	-11	-1	-6%
Cheyenne/Laramie	820	1	-1	0	0%
Gillette	827	-1	-5	0	-3%
Powell	824	0	-19	0	-9%
Rawlins	823	0	-13	0	-6%
Riverton	825	-1	-17	0	-8%
Rock Springs	829-831	0	-2	0	-1%
Sheridan	828	1	-14	0	-6%
Wheatland	822	0	-25	0	-12%
UNITED STATES TERRITORIES					
Guam		53	-21	-5	18%
Puerto Rico		2	-47	-5	-21%
VIRGIN ISLANDS (U.S.)					
St. Croix		18	-15	-4	2%
St. John		52	-15	-4	20%
St. Thomas		23	-15	-4	5%

Canadian Area Modification Factors


To find the cost in Canada in Canadian dollars, increase the costs in this book by the appropriate percentage listed below. These figures convert costs to Canadian dollars based on \$1.00 Canadian to \$0.76 U.S.

Location	Mat.	Lab.	Equip.	Total Wtd. Avg.
Alberta Average	26	-1	7	13%
Calgary	26	1	7	14%
Edmonton	25	2	7	14%
Fort McMurray	28	-7	7	12%
British Columbia Average	26	-15	7	7%
Fraser Valley	26	-16	7	6%
Okanagan	27	-18	7	6%
Vancouver	26	-11	7	9%
Manitoba Average	20	-22	5	0%
North Manitoba	20	-22	5	0%
Selkirk	20	-22	5	0%
South Manitoba	20	-22	5	0%
Winnipeg	20	-22	5	0%
New Brunswick	16	-47	3	-13%
Moncton	16	-47	3	-13%

Location	Mat.	Lab.	Equip.	Total Wtd. Avg.
Newfoundland/Labrador	19	-29	4	-3%
Nova Scotia Average	17	-36	4	-8%
Amherst	16	-36	3	-8%
Nova Scotia	17	-35	4	-7%
Sydney	17	-37	4	-8%
Ontario Average	22	-11	5	7%
London	22	-10	5	7%
Thunder Bay	24	-14	6	6%
Toronto	21	-9	5	7%
Quebec Average	19	-24	4	-1%
Montreal	19	-24	4	-1%
Quebec City	19	-24	4	-1%
Saskatchewan Average	23	-18	5	4%
La Ronge	24	-21	6	3%
Prince Albert	22	-20	5	2%
Saskatoon	22	-14	5	5%

Demolition

2



Nearly all home improvement projects require some breaking out and removing of existing materials and disposal of debris. Most will require protection of adjacent surfaces, taking safety precautions (such as setting up barricades), closing off doorways or windows, and normal cleanup. The demolition figures in this chapter include these tasks and will apply on most home improvement jobs that don't involve unusual conditions or complications. Costs will be higher when access to the work is limited, when your crew doesn't have complete control of the construction site, or when debris must be moved longer distances or around obstacles. All figures assume that debris is piled on site or in a bin. Add the cost of hauling to the nearest disposal site and tippage charges, if required. No salvage value is assumed except as noted.

Many of the following chapters include estimated costs to remove the old and replace with new materials of a similar description. For example, you'll find costs for removing shingles and replacing shingles in the roofing chapter. That's appropriate because they're part of the same task and usually performed by the same contractor. The estimates in this chapter are for demolition only and don't consider the cost of replacing what has been removed.

Of all construction tasks, demolition is probably the most difficult to estimate with any certainty. You're never sure what's in a wall to be demolished until the job begins. That's why it's best to exclude from your demolition bid what isn't in your estimate. Use the checklist to the right to help identify potential problems before they develop.

Demolition Checklist

- ☐ Can you anticipate any problem getting a demolition permit for this job?
- ☐ Is there a noise ordinance which will limit hours of operation or selection of equipment?
- ☐ Can the debris box be located close to the work?
- ☐ Can a trencher get to the job site?
- ☐ Is the site accessible to wheeled equipment?
- ☐ Will the debris have to be hand-carried to the roll-off box or gondola?
- ☐ Is there a direct route from the demolition site to the debris box?
- ☐ Will you need to re-route any plumbing, electrical, phone or gas lines?
- ☐ Will you need to remove and replace lawn sprinklers?
- ☐ Will you need to cut back or remove any bushes or trees?
- ☐ Will you have to remove and re-install a fence or gate?
- ☐ Does a septic tank or drain field extend into the site of construction?
- ☐ Can (must) materials generated from your project be recycled or salvaged?

Some classes of waste require special treatment. For example, paint cans with liquid paint may have to be delivered to an approved paint disposal facility. Brick and broken concrete delivered to a recycling company may have salvage value. Hot embers should not be removed from the site. Most public dumps and waste pickup services won't accept hazardous materials such as asbestos, explosives, pesticides, contaminated soils, absorbents, fuel oil or medical waste. State law may prohibit mixing of toxic minerals (such as mercury) with other waste materials. Wood, plaster, insulation, styrofoam, tile, and drywall are routinely accepted by most waste disposal companies. If you anticipate problems disposing of debris, get advice from an office of your local county government before bidding the job.

Online Preview

	Day	Week	Month
Equipment Rental for Demolition.			
Air compressors, wheel-mounted			
16 CFM, shop type, electric	80.10	188.00	560.00
30 CFM, shop type, electric	85.70	257.00	771.00
80 CFM, shop type, electric	100.00	305.00	911.00
100 CFM, gasoline unit	134.00	399.00	1,120.00
125 CFM, gasoline unit	168.00	508.00	1,520.00
Paving breakers (no bits included) hand-held, pneumatic			
To 40 lb	56.00	179.00	395.00
41 - 55 lb	83.00	297.00	624.00
56 - 70 lb	75.00	258.00	510.00
71 - 90 lb	129.00	305.00	653.00
Paving breakers jackhammer bits			
Moil points, 15" to 18"	6.00	14.00	30.00
Chisels, 3"	7.00	17.00	44.00
Clay spades, 5-1/2"	10.00	23.00	62.00
Asphalt cutters, 5"	8.00	24.00	51.00
Pneumatic chippers, medium weight, 10 lb	38.00	110.00	307.00
Air hose rental, 50 LF section			
5/8" air hose	11.00	21.00	50.00
3/4" air hose	13.00	27.00	63.00
1" air hose	16.00	37.00	76.00
1-1/2" air hose	25.00	72.00	186.00
Dump truck rental rate plus mileage			
3 CY	464.00	1,220.00	2,380.00
5 CY	491.00	1,300.00	3,750.00
Hammer rental			
Electric brute breaker	65.00	260.00	780.00
Gas breaker	96.00	387.00	1,050.00
Demolition hammer, electric	58.00	232.00	696.00
Roto hammer, 7/8", electric	66.00	264.00	792.00
Roto hammer, 1-1/2", electric	67.00	268.00	648.00
Stump grinder, 9 HP	165.00	660.00	1,980.00
Brush chipper, trailer-mounted 40 HP	332.00	971.00	2,420.00
Chain saw, 18", gasoline	72.00	289.00	837.00
Chop saw, 14", electric	42.00	167.00	488.00
Backhoe/loader, wheel-mounted, diesel or gasoline			
1/2 CY bucket capacity, 55 HP	264.00	812.00	1,880.00
1 CY bucket capacity, 65 HP	245.00	755.00	2,280.00
1-1/4 CY bucket capacity, 75 HP	239.00	803.00	2,220.00
1-1/2 CY bucket capacity, 100 HP	425.00	1,170.00	3,000.00
Wheel loader, front-end load and dump, diesel			
3/4 CY bucket, 4WD, articulated	219.00	747.00	2,130.00
1 CY bucket, 4WD, articulated	387.00	1,120.00	3,150.00
2 CY bucket, 4WD, articulated	630.00	1,780.00	4,710.00

	Craft@Hrs	Unit	Material	Labor	Total	Sell
Sitework Demolition						
Debris disposal and removal. Tipping charges for solid waste disposal at the dump vary from \$30 to \$120 per ton. For planning purposes, estimate waste disposal at \$75 per ton, plus the hauling cost. Call the dump or trash disposal company for actual charges. Typical costs are shown below.						
Dumpster, 3 CY trash bin, emptied weekly	—	Mo	—	—	420.00	—
Dumpster, 40 CY solid waste bin (lumber, drywall, roofing)						
Hauling cost, per load	—	Ea	—	—	297.00	—
Add to per load charge, per ton	—	Ton	—	—	72.80	—
Low-boy, 14 CY solid waste container (asphalt, dirt, masonry, concrete)						
Hauling cost, per load (7 CY maximum load)	—	Ea	—	—	286.00	—
Add to per load charge, per ton	—	Ton	—	—	72.80	—
Recycler fees. Recycling construction waste materials can substantially reduce disposal costs. Recycling charges vary from \$95 to \$120 per load, depending on the type of material and the size of the load. Add the cost of hauling to a recycling facility.						
Greenwaste	—	Ton	—	—	39.20	—
Asphalt, per load (7 CY)	—	Ea	—	—	123.00	—
Concrete, masonry or rock, per load (7 CY)	—	Ea	—	—	121.00	—
Dirt, per load (7 CY)	—	Ea	—	—	118.00	—
Mixed loads, per load (7 CY)	—	Ea	—	—	127.00	—
Bush and tree removal. Includes cutting into manageable pieces with power hand tools and dumping debris in a trash bin on site. Add the cost of power equipment rental, if needed.						
Shrubs and bushes, including stump removal.						
4' high, per each	BL@.750	Ea	—	24.00	24.00	40.80
Tree removal. Costs will vary widely depending on the condition, size, location and accessibility of the tree. Small quantities. Includes cutting into manageable pieces with power hand tools and dumping debris in a trash bin or chipper on site. Does not include stump removal or grinding. Add the cost of power equipment rental, bucket truck, and other specialized equipment if needed. Large shade tree removal may require a crew of 5 or more. Use \$2,000 as a minimum job charge for trees with a 26" diameter trunk and larger.						
8" to 12" diameter trunk	B8@5.00	Ea	—	193.00	193.00	328.00
13" to 18" diameter trunk	B8@7.00	Ea	—	270.00	270.00	459.00
19" to 24" diameter trunk	B8@11.0	Ea	—	424.00	424.00	721.00
25" to 36" diameter trunk	B8@14.0	Ea	—	540.00	540.00	918.00
Stump grinding, using a 9 HP wheel-mounted stump grinder						
6" to 10" diameter stump	B8@.800	Ea	—	30.90	30.90	52.50
11" to 14" diameter stump	B8@1.04	Ea	—	40.10	40.10	68.20
15" to 18" diameter stump	B8@1.30	Ea	—	50.10	50.10	85.20
19" to 24" diameter stump	B8@1.50	Ea	—	57.90	57.90	98.40
Fencing demolition. Remove chain link fence and cemented posts for disposal. These figures assume fencing is removed by cutting ties at posts and rails and rolling the fabric. These rolls can be heavy. A larger crew will be needed on larger jobs.						
To 6' high	BL@.100	LF	—	3.20	3.20	5.44
Remove chain link fence and cemented posts for salvage,						
To 6' high	BL@.120	LF	—	3.84	3.84	6.53
Remove board fence and cemented posts for disposal,						
To 6' high	BL@.100	LF	—	3.20	3.20	5.44

	Craft@Hrs	Unit	Material	Labor	Total	Sell
--	-----------	------	----------	-------	-------	------

Building Demolition

Single-story room demolition. Includes breaking out a concrete or masonry foundation using pneumatic tools, breaking materials into manageable pieces with hand tools and handling debris to a trash bin on site. Includes the cost of erecting a temporary vapor barrier to seal the wall opening in the existing structure. Add the cost of wall patching on the remaining structure. Add the cost of equipment rental.

Demolish a wood-frame addition built on a concrete slab, including grade beams. Use these figures to estimate the cost of demolishing an attached garage.

Per square foot of floor area demolished	BL@.100	SF	—	3.20	3.20	5.44
--	---------	----	---	------	------	------

Demolish a wood-frame addition built on a conventional foundation, including wood deck, stairs to grade, and the concrete or concrete block foundation.

Per square foot of floor area demolished	BL@.120	SF	—	3.84	3.84	6.53
--	---------	----	---	------	------	------

Detached garage demolition. Includes breaking materials into manageable pieces with hand tools and handling debris to a trash bin on site. No slab or foundation demolition included. No salvage of materials assumed.

Frame garage with wood or aluminum siding

One-car garage, to 10' wide by 22' deep	BL@16.5	Ea	—	528.00	528.00	898.00
---	---------	----	---	--------	--------	--------

Two-car garage, to 20' wide by 28' deep	BL@23.0	Ea	—	735.00	735.00	1,250.00
---	---------	----	---	--------	--------	----------

Frame garage with stucco siding

One-car garage to 12' wide by 22' deep	BL@23.5	Ea	—	751.00	751.00	1,280.00
--	---------	----	---	--------	--------	----------

One-car to 16' wide by 22' deep	BL@28.5	Ea	—	911.00	911.00	1,550.00
---------------------------------	---------	----	---	--------	--------	----------

Two-car garage to 22' wide by 28' deep	BL@42.5	Ea	—	1,360.00	1,360.00	2,310.00
--	---------	----	---	----------	----------	----------

Brick or block garage

One-car garage to 12' wide by 22' deep	BL@23.0	Ea	—	735.00	735.00	1,250.00
--	---------	----	---	--------	--------	----------

One-car garage to 16' wide by 22' deep	BL@28.0	Ea	—	895.00	895.00	1,520.00
--	---------	----	---	--------	--------	----------

Two-car garage to 20' wide by 22' deep	BL@33.0	Ea	—	1,060.00	1,060.00	1,800.00
--	---------	----	---	----------	----------	----------

Gutting a building. Interior finish stripped back to the structural walls. Building structure to remain. No allowance for salvage value. These costs include loading and hauling up to 6 miles but no dump fees. Costs are per square foot of floor area based on 8' ceiling height. Add the cost of equipment rental. Figures in parentheses show the approximate "loose" volume of materials after demolition.

Residential building (125 SF per CY)	BL@.100	SF	—	3.20	3.20	5.44
--------------------------------------	---------	----	---	------	------	------

Building Component Demolition. Itemized costs for demolition of building components when building is being remodeled, repaired or rehabilitated and not completely demolished. Costs include protecting adjacent areas and normal clean-up. Costs are to break out the items listed and pile debris on site or in a bin.

Brick wall demolition. Cost per square foot removed measured on one face. Removed using a pneumatic breaker. Add the cost of equipment rental. Figures in parentheses show the volume before and after demolition and weight of the materials after demolition.

4" thick walls

(60 SF per CY and 36 lbs. per SF)	BL@.061	SF	—	1.95	1.95	3.32
-----------------------------------	---------	----	---	------	------	------

8" thick walls

(30 SF per CY and 72 lbs. per SF)	BL@.110	SF	—	3.52	3.52	5.98
-----------------------------------	---------	----	---	------	------	------

	Craft@Hrs	Unit	Material	Labor	Total	Sell
Brick sidewalk demolition. Cost per square foot removed. Add the cost of Bobcat rental. Larger jobs will require a crew of 2 or more. Figures in parentheses show the volume before and after demolition and weight of materials after demolition.						
2-1/2" thick brick on sand base, no mortar bed, removed using hand tools (100 SF per CY and 28 lbs. per SF)	BL@.020	SF	—	25.60	25.60	43.50
Brick pavers up to 4-1/2" thick with mortar bed, removed using a pneumatic breaker (55 SF per CY and 50 lbs. per SF)	BL@.050	SF	—	1.60	1.60	2.72
Concrete masonry wall demolition. Cost per square foot of wall removed measured on one side. Removed using a pneumatic breaker. Add the cost of equipment rental. Figures in parentheses show the volume before and after demolition and weight of materials after demolition.						
4" thick walls (60 SF per CY and 19 lbs. per SF)	BL@.066	SF	—	2.11	2.11	3.59
6" thick walls (40 SF per CY and 28 lbs. per SF)	BL@.075	SF	—	2.40	2.40	4.08
8" thick walls (30 SF per CY and 34 lbs. per SF)	BL@.098	SF	—	3.13	3.13	5.32
12" thick walls (20 SF per CY and 46 lbs. per SF)	BL@.140	SF	—	4.48	4.48	7.62
Reinforced or grouted walls add	—	%	—	—	50.0	—
Concrete foundation demolition (footings). Steel reinforced, removed using a pneumatic breaker. Add the cost of equipment rental. Figures in parentheses show the volume before and after demolition.						
Cost per CY (.75 CY per CY)	BL@3.96	CY	—	127.00	127.00	216.00
Cost per LF with width and depth as shown						
6" W x 12" D (35 LF per CY)	BL@.075	LF	—	2.40	2.40	4.08
8" W x 12" D (30 LF per CY)	BL@.098	LF	—	3.13	3.13	5.32
8" W x 16" D (20 LF per CY)	BL@.133	LF	—	4.25	4.25	7.23
8" W x 18" D (18 LF per CY)	BL@.147	LF	—	4.70	4.70	7.99
10" W x 12" D (21 LF per CY)	BL@.121	LF	—	3.87	3.87	6.58
10" W x 16" D (16 LF per CY)	BL@.165	LF	—	5.28	5.28	8.98
10" W x 18" D (14 LF per CY)	BL@.185	LF	—	5.91	5.91	10.00
12" W x 12" D (20 LF per CY)	BL@.147	LF	—	4.70	4.70	7.99
12" W x 16" D (13 LF per CY)	BL@.196	LF	—	6.27	6.27	10.70
12" W x 20" D (11 LF per CY)	BL@.245	LF	—	7.83	7.83	13.30
12" W x 24" D (9 LF per CY)	BL@.294	LF	—	9.40	9.40	16.00
Concrete sidewalk demolition. To 4" thick, cost per SF removed. Figures in parentheses show the volume before and after demolition.						
Non-reinforced, removed by hand with sledge (60 SF per CY)	BL@.050	SF	—	1.60	1.60	2.72
Reinforced with wire mesh. Mesh cut into manageable pieces, then removed using pneumatic breaker. Add the cost of equipment rental. (55 SF per CY)	BL@.060	SF	—	1.92	1.92	3.26

	Craft@Hrs	Unit	Material	Labor	Total	Sell
Porch and deck demolition. Includes breaking materials into manageable pieces with hand tools and handling debris to a trash bin on site.						
Demolish an enclosed wood-frame porch. Includes breaking out the concrete or masonry pier foundation. Per square foot of floor.						
One story	BL@.250	SF	—	7.99	7.99	13.60
Two story	BL@.225	SF	—	7.19	7.19	12.20
Three story	BL@.196	SF	—	6.27	6.27	10.70
Demolish a screened porch built on a concrete slab. Includes demolition of one concrete or wood frame step to grade. Per square foot of floor area.						
Porch and one step (no slab demolition)	BL@.100	SF	—	3.20	3.20	5.44
Demolish a wood deck with railing or kneewall. Includes demolition of the wood deck and up to 7 steps to grade.						
Deck to 150 SF	BL@18.5	Ea	—	591.00	591.00	1,000.00
Add per SF for deck over 150 SF	BL@.100	SF	—	3.20	3.20	5.44
Concrete slab demolition. Break up and remove concrete slab using a compressor and pneumatic hammer. Includes loosening concrete with a pick and handling debris to a trash bin on site. Costs for demolition of reinforced concrete slab include burning off rebars with an acetylene torch. Add the rental cost of a compressor, pneumatic hammer and a torch, as required. Figures in parentheses show the volume before and after demolition.						
4" non-reinforced concrete (60 SF per CY)	BL@.057	SF	—	1.82	1.82	3.09
4" reinforced concrete (60 SF per CY)	BL@.071	SF	—	2.27	2.27	3.86
6" non-reinforced concrete (45 SF per CY)	BL@.083	SF	—	2.65	2.65	4.51
6" reinforced concrete (45 SF per CY)	BL@.103	SF	—	3.29	3.29	5.59
8" non-reinforced concrete (30 SF per CY)	BL@.109	SF	—	3.48	3.48	5.92
8" reinforced concrete (30 SF per CY)	BL@.122	SF	—	3.90	3.90	6.63
Asphalt pavement demolition. Asphaltic concrete (bituminous) 3" thick, removed using a pneumatic spade. Add the cost of equipment rental and dump fees. Figures in parentheses show the volume before and after demolition and weight of debris.						
Break up and shovel on to a truck (4 SY per CY and 660 lbs. per SY)	BL@.140	SY	—	4.48	4.48	7.62
Concrete wall demolition. Steel reinforced, removed using a compressor and pneumatic breaker. Add the cost of equipment rental. Figures in parentheses show the volume before and after demolition.						
Cost per CY (1.33 CY per CY)	BL@4.76	CY	—	152.00	152.00	258.00
Cost per SF with thickness as shown						
3" wall thickness (80 SF per CY)	BL@.045	SF	—	1.44	1.44	2.45
4" wall thickness (55 SF per CY)	BL@.058	SF	—	1.85	1.85	3.15
5" wall thickness (45 SF per CY)	BL@.075	SF	—	2.40	2.40	4.08
6" wall thickness (40 SF per CY)	BL@.090	SF	—	2.88	2.88	4.90
8" wall thickness (30 SF per CY)	BL@.120	SF	—	3.84	3.84	6.53
10" wall thickness (25 SF per CY)	BL@.147	SF	—	4.70	4.70	7.99
12" wall thickness (20 SF per CY)	BL@.176	SF	—	5.63	5.63	9.57

	Craft@Hrs	Unit	Material	Labor	Total	Sell
Wood Framing Demolition. Typical costs for demolition of wood frame structural components using hand tools. Normal center-to-center spacing (12" thru 24" OC) is assumed. Includes breaking materials into manageable pieces with hand tools and handling debris to a trash bin on site. Costs include removal of Romex cable as necessary, protecting adjacent areas, and normal clean-up. Costs do not include temporary shoring to support structural elements above or adjacent to the work area. (Add for demolition of flooring, roofing, sheathing, etc.) Figures in parentheses give the approximate "loose" volume and weight of the materials after being demolished.						
Ceiling joist demolition. Per in-place SF of ceiling area removed.						
2" x 4" (720 SF per CY and 1.18 lbs. per SF)	BL@.009	SF	—	.29	.29	.49
2" x 6" (410 SF per CY and 1.76 lbs. per SF)	BL@.013	SF	—	.42	.42	.71
2" x 8" (290 SF per CY and 2.34 lbs. per SF)	BL@.018	SF	—	.58	.58	.99
2" x 10" (220 SF per CY and 2.94 lbs. per SF)	BL@.023	SF	—	.74	.74	1.26
2" x 12" (190 SF per CY and 3.52 lbs. per SF)	BL@.027	SF	—	.86	.86	1.46
Floor joist demolition. Per in-place SF of floor area removed.						
2" x 6" (290 SF per CY and 2.04 lbs. per SF)	BL@.016	SF	—	.51	.51	.87
2" x 8" (190 SF per CY and 2.72 lbs. per SF)	BL@.021	SF	—	.67	.67	1.14
2" x 10" (160 SF per CY and 3.42 lbs. per SF)	BL@.026	SF	—	.83	.83	1.41
2" x 12" (120 SF per CY and 4.10 lbs. per SF)	BL@.031	SF	—	.99	.99	1.68
Rafter demolition. Per in-place SF of actual roof area removed.						
2" x 4" (610 SF per CY and 1.42 lbs. per SF)	BL@.011	SF	—	.35	.35	.60
2" x 6" (360 SF per CY and 2.04 lbs. per SF)	BL@.016	SF	—	.51	.51	.87
2" x 8" (270 SF per CY and 2.68 lbs. per SF)	BL@.020	SF	—	.64	.64	1.09
2" x 10" (210 SF per CY and 3.36 lbs. per SF)	BL@.026	SF	—	.83	.83	1.41
2" x 12" (180 SF per CY and 3.94 lbs. per SF)	BL@.030	SF	—	.96	.96	1.63
Stud wall demolition. Interior or exterior, includes allowance for plates and blocking, per in-place SF of wall area removed, measured on one face.						
2" x 3" (430 SF per CY and 1.92 lbs. per SF)	BL@.013	SF	—	.42	.42	.71
2" x 4" (310 SF per CY and 2.58 lbs. per SF)	BL@.017	SF	—	.54	.54	.92
2" x 6" (190 SF per CY and 3.74 lbs. per SF)	BL@.025	SF	—	.80	.80	1.36
Stud wall demolition, salvage condition. Remove wall cover (nailed hardboard or fiberboard) from partition wall and salvage the stud framing. Per linear foot of stud wall.						
2" x 4" x 8', 16" on center	BL@.156	LF	—	4.99	4.99	8.48
Roof cover demolition. Includes breaking materials into manageable pieces with hand tools and handling debris to a trash bin on site. Cost per Sq or "square". (1 square = 100 square feet.) Figures in parentheses show the approximate "loose" volume and weight of materials after being demolished.						
Built-up, 5 ply						
(2.5 Sq per CY and 250 lbs per Sq)	BL@1.50	Sq	—	48.00	48.00	81.60
Shingles, asphalt, single layer						
(2.5 Sq per CY and 240 lbs per Sq)	BL@1.33	Sq	—	42.50	42.50	72.30
Shingles, asphalt, double layer						
(1.2 Sq per CY and 480 lbs per Sq)	BL@2.00	Sq	—	63.90	63.90	109.00
Shingles, slate. Weight ranges from 600 lbs. to 1,200 lbs. per Sq						
(1 Sq per CY and 900 lbs per Sq)	BL@1.79	Sq	—	57.20	57.20	97.20

	Craft@Hrs	Unit	Material	Labor	Total	Sell
Shingles, wood (1.7 Sq per CY and 400 lbs per Sq)	BL@2.02	Sq	—	64.60	64.60	110.00
Clay or concrete tile (.70 Sq per CY)	BL@1.65	Sq	—	52.80	52.80	89.80
Remove gravel stop or flashing	BL@.070	LF	—	2.24	2.24	3.81

Interior and exterior finish demolition. Includes breaking materials into manageable pieces with hand tools and handling debris to a trash bin on site. Figures in parentheses show the approximate "loose" volume and weight of the materials after being demolished. Demolition for disposal. No salvage of materials included.

Plywood sheathing, up to 1" thick, cost per in-place SF

(200 SF per CY and 2 lbs. per SF) BL@.017 SF — .54 .54 .92

Wood board sheathing

(250 SF per CY and 2 lbs. per SF) BL@.030 SF — .96 .96 1.63

Metal siding, using hand tools

(200 SF per CY and 2 lbs. per SF) BL@.027 SF — .86 .86 1.46

Stucco on walls or soffits, cost per in-place SF, removed using hand tools

(150 SF per CY and 8 lbs. per SF) BL@.036 SF — 1.15 1.15 1.96

Wallboard 1/2" thick, cost per in-place SF, removed using hand tools. Add 50% to labor costs for 1" wallboard.

Gypsum, walls or ceilings

(250 SF per CY and 2.3 lbs. per SF) BL@.010 SF — .32 .32 .54

Including strip furring BL@.015 SF — .48 .48 .82

Plywood or insulation board

(200 SF per CY and 2 lbs. per SF) BL@.018 SF — .58 .58 .99

Insulation, fiberglass batts or rolls, cost per square foot removed

(500 SF per CY and .3 lb per SF) BL@.003 SF — .10 .10 .17

Plaster on walls, cost per square foot removed by hand

(150 SF per CY and 8 lbs. per SF) BL@.015 SF — .48 .48 .82

Remove baseboard molding

Single member base, no salvage BL@.022 LF — .70 .70 1.19

Base and base shoe, no salvage BL@.038 LF — 1.21 1.21 2.06

Remove and salvage single member base BL@.025 LF — .80 .80 1.36

Remove and salvage base and base shoe BL@.044 LF — 1.41 1.41 2.40

Ceiling demolition. Knock down with hand tools at heights to 9' and handle debris to a trash bin on site. Building structure to remain. No allowance for salvage value. Costs shown are per square foot of ceiling. Figures in parentheses show the approximate "loose" volume after demolition.

Plaster ceiling (typically 175 to 200 SF per CY)

Including lath and furring BL@.025 SF — .80 .80 1.36

Including suspended grid BL@.020 SF — .64 .64 1.09

Acoustic tile ceiling (typically 200 to 250 SF per CY)

Including suspended grid BL@.010 SF — .32 .32 .54

Including grid in salvage condition BL@.019 SF — .61 .61 1.04

Tile glued or stapled to ceiling BL@.015 SF — .48 .48 .82

Tile on strip furring, including furring BL@.025 SF — .80 .80 1.36

Drywall ceiling (typically 250 to 300 SF per CY)

Nailed or attached with screws
to joists BL@.010 SF — .32 .32 .54

Floor cover demolition. Includes breaking materials into manageable pieces with hand tools and handling debris to a trash bin on site. Cost per square yard of floor removed. (1 square yard = 9 square feet.) Figures in parentheses show the approximate "loose" volume and weight of the materials after demolition.

Ceramic tile (25 SY per CY and 34 lbs. per SY)	BL@.263	SY	—	8.41	8.41	14.30
Hardwood, nailed (25 SY per CY and 18 lbs. per SY)	BL@.290	SY	—	9.27	9.27	15.80
Hardwood, glued (25 SY per CY and 18 lbs. per SY)	BL@.503	SY	—	16.10	16.10	27.40
Linoleum, sheet (30 SY per CY and 3 lbs. per SY)	BL@.056	SY	—	1.79	1.79	3.04
Resilient tile (30 SY per CY and 3 lbs. per SY)	BL@.300	SY	—	9.59	9.59	16.30
Terrazzo (25 SY per CY and 34 lbs. per SY)	BL@.286	SY	—	9.14	9.14	15.50
Carpet on tack strip (40 SY per CY and 5 lbs. per SY)	BL@.028	SY	—	.90	.90	1.53
Glue-down carpet with rubber backing (35 SY per CY and 1.7 lbs. per SY)	BL@.160	SY	—	5.12	5.12	8.70
Add for each LF of room perimeter	BL@.008	LF	—	.26	.26	.44
Carpet pad (35 SY per CY and 1.7 lbs. per SY)	BL@.014	SY	—	.45	.45	.77

Removal of interior items. Includes breaking materials into manageable pieces with hand tools and handling debris to a trash bin on site. Items removed in salvageable condition do not include an allowance for salvage value. Figures in parentheses give the approximate "loose" volume of the materials after demolition. Removed in non-salvageable condition (demolished) except as noted.

Windows, typical cost to remove window, frame and hardware, cost per SF of window						
Metal (36 SF per CY)	BL@.058	SF	—	1.85	1.85	3.15
Wood (36 SF per CY)	BL@.063	SF	—	2.01	2.01	3.42
Wood stairs, cost per in-place SF or LF						
Risers (25 SF per CY)	BL@.116	SF	—	3.71	3.71	6.31
Landings (50 SF per CY)	BL@.021	SF	—	.67	.67	1.14
Handrails (100 LF per CY)	BL@.044	LF	—	1.41	1.41	2.40
Posts (200 LF per CY)	BL@.075	LF	—	2.40	2.40	4.08
Hollow metal door and frame in a masonry wall. (2 doors per CY)						
Single door to 4' x 7'	BL@1.00	Ea	—	32.00	32.00	54.40
Two doors, per opening to 8' x 7'	BL@1.50	Ea	—	48.00	48.00	81.60
Wood door and frame in a wood frame wall (2 doors per CY)						
Single door to 4' x 7'	BL@.500	Ea	—	16.00	16.00	27.20
Two doors, per opening to 8' x 7'	BL@.750	Ea	—	24.00	24.00	40.80
Metal door and frame in masonry wall, salvage condition						
Hollow metal door to 4' x 7'	BL@2.00	Ea	—	63.90	63.90	109.00
Wood door to 4' x 7'	BL@1.00	Ea	—	32.00	32.00	54.40

Index

- A**
- Abbreviations..... 17
 - ABS pipe 388
 - DWV 388
 - Absorber, shock
 - water surge 387
 - ABTCO 251
 - AC cable 399
 - AC quiet rocker switch
 - Decora 414
 - AC quiet toggle switch..... 414
 - Access door..... 248
 - Access doors
 - foundation..... 88
 - Accessories, ridge vents ... 90
 - Acid cleaning
 - masonry..... 115
 - wash 51, 115
 - Acid wash, manhours 446
 - Acknowledgments 2
 - Acoustic ceiling texture
 - labor 449
 - Acoustic roll-on..... 473
 - Acoustic tile
 - demolition..... 35, 311
 - Acoustical ceiling
 - demolition..... 254
 - panel..... 255-257
 - patch..... 245
 - suspended..... 256
 - texture touch-up kit..... 244
 - tile adhesive 254
 - Acrylic
 - latex paint..... 472
 - mirrored sheet..... 171
 - mortar admix 303
 - paint, concrete..... 41
 - roof coating 137
 - sheet..... 171
 - skylights..... 173
 - stain..... 467
 - suspended lighting
 - panel 258
 - tape 287
 - wood filler 277
 - Actuating devices,
 - garage doors 225
 - Adapter, box 401
 - Additive
 - feather edge 282
 - resilient flooring 281
 - Additives
 - coloring..... 48
 - concrete..... 48
 - perlite paint texturing... 473
 - Adhesive
 - acoustical ceiling tile ... 254
 - bond 133
 - cold process 133
 - cove base..... 286
 - field..... 134
 - flooring..... 278
 - marble & granite..... 302
 - modified bitumen..... 133
 - nozzle 287
 - primer 278
 - resilient tile 286
 - sheet flooring..... 286
 - spray..... 249
 - tile..... 289-290
 - vinyl tile 286
 - white silicone..... 171
 - wood flooring..... 278
 - Adhesive caulk
 - ceramic tile 303
 - Adhesive remover 278
 - flooring..... 281
 - Admix, acrylic mortar..... 303
 - Admixtures
 - coloring..... 48
 - concrete..... 48
 - Aggregate
 - base..... 41, 47
 - roofing 132
 - Aggregate sealer..... 475
 - Air compressor, rental 29
 - Air conditioner 377
 - Air gap 327
 - cover 327
 - Air hose, rental 29
 - Air mover 519
 - Air scrubber 519
 - Alkyd gloss enamel 473
 - All-season storm
 - doors 204-205
 - All-season storm doors,
 - triple-track..... 204
 - Alpine ceiling panel 257
 - Aluminum
 - door bottom..... 196
 - drip edge 141
 - fascia 114
 - foil..... 88
 - patio cover..... 439
 - patio doors 215
 - roll flashing 141
 - roof coating 137
 - screen rolls..... 168
 - siding 113
 - siding removal..... 106
 - siding repair..... 105
 - soffit..... 114
 - storm windows 165
 - thermal door sill..... 195
 - windows, fixed 162
 - Aluminum conduit
 - threaded..... 411
 - Aluminum siding 93
 - painting..... 462
 - Aluminum wiring 391
 - Amber shellac..... 470
 - American Flexible
 - Conduit..... 399
 - American Marazzi..... 292-294, 299
 - American Molding..... 262
 - American Shower &
 - Bath 330
 - American Standard..... 323,
 - ... 326-327, 331, 354-356, 369
 - Anchor clip..... 438
 - Anchor, foundation 492
 - Anchor, hold-down 492
 - Andersen 214, 216
 - Angle
 - flashing..... 142
 - Angle bay windows..... 164
 - Angle valve 351
 - Ann Arbor birch paneling ... 252
 - Anti-fracture
 - membrane kit 303
 - membrane
 - waterproofing 301
 - tile membrane 301
 - Antimicrobial..... 516
 - Anti-siphon toilet fill valve... 351
 - Appliance receptacle..... 415
 - Appliance removal..... 510
 - Appliances
 - connect..... 397
 - disconnect 397
 - kitchen, removal..... 311
 - new connection 397
 - remove & replace cable ... 397
 - Apron
 - roof 143
 - whirlpool tub 347
 - Aqua Mix 303
 - Aqua-Tough tile
 - underlayment..... 291
 - Arch, bullnose drywall 247
 - Architectural laminate
 - shingles 130
 - Architectural shingles 131
 - Area modification factors... 18
 - Area modification factors,
 - Canadian 26
 - Area walls, sheet metal ... 370
 - Ariston 387
 - Arlington Industries..... 402
 - Armstrong..... 255-257, 281-287, 289
 - Asceri Hi-Arc lavatory
 - faucet..... 357
 - Ashland sink 322
 - Asphalt
 - base..... 52
 - fiberglass shingles ... 130-131
 - paving..... 52
 - paving, demolition ... 33, 52
 - recycling 30
 - Asphalt roofing 132
 - built-up..... 132
 - emulsion..... 133
 - fabric..... 131
 - saturated cotton roof
 - patch 136
 - SEBS..... 135
 - Asphalt shingles
 - fiberglass..... 131
 - repair 130
 - Astragal, T 194
 - Attachments
 - skid steer equipment..... 40
 - Attic conversions 57
 - Attic fans
 - belt drive..... 91
 - Attic ventilation 83
 - Attic vents..... 91
 - Avenite counters..... 318
 - Awning
 - remove and replace 106
 - Awning windows
 - aluminum..... 162
 - operators 166
 - vinyl-clad wood..... 160

B

 - Bacharach kitchen
 - faucet..... 324
 - Backer, tile..... 245
 - Backer tape, tile..... 249
 - Backerboard
 - ceramic tile 291
 - RhinoBoard 291
 - tile 291
 - Wonderboard..... 291
 - Backfill
 - concrete excavation 41
 - Backhoe
 - rental 29
 - Backing
 - carpentry 73
 - Backsplash 318
 - Baffle
 - sound..... 333
 - Baffle light kit..... 420
 - Balance, sash..... 166
 - Ballista range hood..... 336
 - Baluster 435
 - deck rail 436
 - Balustrade
 - deck..... 436
 - Bamboo
 - flooring trim 276
 - hardwood flooring..... 276
 - plank flooring..... 276
 - Banner 322
 - Bar doors..... 209
 - Bar faucet..... 331
 - single handle 331
 - two-handle..... 331-332
 - Bar kit
 - QO load center ground 420
 - Bar light fixture 421
 - Bar sink
 - composite 331
 - Manchester composite ... 331
 - polycast 331
 - single bowl 330
 - stainless steel..... 331
 - Bar, towel 301, 356, 369
 - Barn & fence paint..... 476
 - Barrier, foil..... 88
 - Base
 - adhesive 286
 - asphalt..... 52
 - ceramic tile 291
 - lavatory..... 352
 - rubber wall..... 288
 - self-stick wall 289
 - slab..... 50
 - vinyl wall..... 288, 289
 - Base cabinets..... 314
 - end panel 313
 - finished..... 316-317
 - oak..... 316
 - unfinished birch 313
 - unfinished oak 314
 - Base cap molding
 - primed finger joint..... 260
 - Base corner molding
 - MDF primed 261
 - Base molding..... 263
 - colonial 263
 - MDF colonial 261
 - paperwrap colonial..... 263
 - polystyrene colonial..... 263
 - primed finger joint..... 260
 - Victorian hardwood 259
 - Base plate cover, toilet.... 351
 - Base sheet
 - fiberglass..... 133
 - Base shoe molding
 - primed finger joint..... 260
 - Base, wall
 - thermoplastic..... 288
 - Baseboard
 - demolition..... 35
 - painting labor..... 448

Baseboard heater, electric.....	384	enameled steel.....	346	Blank cover		non-metallic round conduit.....	408
Baseboard molding MDF.....	261	Freestanding.....	346	2 gang.....	408	rectangular weatherproof.....	407
Basement doors.....	226	removal.....	346	handy box.....	404	Super Blue non-metallic three gang.....	402
Basement HVAC restoration.....	92	Walk-in.....	347	weatherproof.....	408	Super Blue non-metallic two gang.....	402
Basement post removal.....	63	wall surround kit.....	347	Blasting dry ice.....	517	welded square.....	405
Basement storm windows.....	165	Bathtub & shower units ..	348	Bleach kit wood.....	467	Box adapter.....	401
Basin strainer remove & replace.....	346	Bathtub door bypass.....	347	Blinds painting.....	461-462	Box cover.....	406
Basket strainer garbage disposal.....	328	Bathtub filler.....	347	Block Furniture.....	509	blank handy.....	404
junior.....	331	Bathtub framing.....	375	Block masonry painting.....	456	finished.....	405
kitchen sink.....	328-329	Bathtub wall.....	347	Block molding corner.....	262	square surface.....	405
Basket strainer washer kitchen sink.....	329	Bathtub, wall kit three-piece.....	347	corner rosette.....	259	Box for ceiling fan.....	405
Basswood molding.....	259	Batt insulation.....	84	Blocking fire.....	66	pancake.....	405
Bath accessories.....	369	Batten tileboard.....	251	fireblocks.....	68	Box room contents.....	509
ceramic tile.....	290	Bay vent channel rafter.....	88	Blow-in cellulose insulation.....	85	Boxes cardboard.....	518
Bath accessory set porcelain.....	301	Bay window roof.....	164	Blue Board insulation.....	85	Brace plate installation.....	92
Bath cabinet framed.....	366	Bay windows.....	158, 164	Blueboard.....	245	Braces wall.....	493
stainless steel.....	366	Bead bullnose corner.....	247	Board blue.....	245	Bracing carpentry.....	67
storage.....	367	corner.....	248	forming.....	45	cripple wall.....	492
swing door.....	367	drywall.....	248	sheathing.....	66	temporary.....	67
top lighted.....	367	drywall corner.....	247	Board insulation.....	80, 85	Bracket foundation.....	492
Bath ceiling blower.....	362	glazing.....	170	fire resistance.....	80	non-metallic low voltage mounting.....	402
Bath fan.....	362-364	inside corner.....	247	polystyrene.....	80	Bracket, hanger lavatory.....	353
ceiling.....	365	L-trim.....	248	polyurethane.....	80	Brass storm doors.....	205
ceiling & wall.....	362	metal J-trim.....	248	Board siding cedar.....	108	Brass Craft.....	327, 350-351
ceiling or wall.....	363	outside corner.....	247	pine.....	108	Breaker arc fault, HomeLine.....	417
chain-operated.....	364	plastic.....	248	repair.....	105	GFCI.....	417
Designer Series.....	365	tape on.....	247	Board, cement.....	245	ground fault interrupter plug-on circuit.....	420
exhaust.....	364	Bead molding.....	263	Bobcats.....	40	HomeLine.....	417
exhaust with heater.....	365	primed finger joint.....	260	Boiler hydronic heating system.....	378	main circuit.....	418
exhaust with light.....	364	Bead, corner spray adhesive.....	249	Boiler breeching.....	381-383	QO miniature circuit.....	419
Heat-A-Lamp.....	365	Beaded Cape Cod plank.....	252	Bolt bolt kit.....	320	tandem circuit.....	419
QuieTTTest.....	364	Beaded paneling.....	251	foundation.....	492	Breaker box ground bar kit.....	420
solitaire.....	365	Beams ceiling.....	68	toilet tank.....	352	Breaker, paving rental.....	29
timer switch.....	366	collar.....	75	Bolt-on A type universal hub.....	418	Brick cleaning.....	115
Ultra Silent.....	363	grade.....	49	Bolts double-hung window ..	166	demolition.....	31
vertical discharge.....	363	needle.....	62	Bond adhesive permanent.....	133	painting.....	457-458
with heater, infrared.....	365	Bed molding.....	263	Bonding mortar.....	301-302	pointing.....	115
with light.....	364-365	Bedding mortar CustomFloat.....	302	flexible.....	302	repainting.....	115
Bath heater exhaust fan.....	365	Behr.....	467, 470, 472-475	Bonding primer concrete.....	473	Brick masonry painting labor.....	456
Heat-A-Lamp.....	365	Bell wire.....	413	Bookcase painting labor.....	448	Brick molding.....	195
infrared bulb.....	365	Berm.....	510	Boone International.....	289	Brick molding set primed finger joint.....	260
Bath light bar.....	421	Bestview Ltd.....	294	Bosch.....	387	Brick paver tile.....	296
Bath vent kit.....	366	Bevel siding cedar.....	108	Boston polish.....	471	Bridging carpentry.....	65
Bathrobe hook.....	369	pine.....	108	Bottle jacks.....	62	Broan Manufacturing.....	337, 362-366
Bathroom accessories ceramic tile soap dish ..	300	western red cedar.....	108	Bow window roof.....	164-165	Brookfield cast iron kitchen sink.....	323
towel bar, ceramic.....	301	Beveled mirror bath bar...	421	Bowl sink utility.....	330	Brookstone birch paneling.....	252
Bathroom sink drop-in.....	353	Bidet hot & cold.....	350	Bowling alley wax.....	471	Broom finish, concrete.....	50
Bathroom vanity top.....	360	Bidet faucet set.....	350	Box 2 gang weatherproof electrical.....	407	Brown coat plaster.....	114
Bathrooms additions.....	339	Bi-fold doors.....	219-221	drawn 2-device switch ..	405	Bruce.....	274, 278
conversions.....	340	hardware.....	221	drawn handy.....	404		
exterior additions.....	342	Metal.....	220	drawn octagon.....	405		
floor plans.....	343	mirrored.....	221	multi gang switch.....	405		
in basements.....	341	Bilco.....	226	non-metallic old work switch.....	402		
in garages.....	342	Bin, trash.....	30				
naming conventions.....	339	Biocidal coating.....	92				
space minimums.....	344	Birch doors.....	192, 206-207, 210				
Bathtub alcove steel.....	346	Birch paneling.....	252				
Drop-in.....	347	Birdstop.....	140				
		Bitumen adhesive, modified.....	133				
		Bitumen cold process adhesive, modified.....	133				
		Bituminous roofing.....	132				

- Brush
 painting labor..... 448
 wire..... 51
- Brush chipper
 rental..... 29
- Brushes
 crow's foot..... 250
 drywall texture..... 250
- Bubble wrap..... 518
- Buggies
 rental..... 40
- Building dryout, interior work
 appliances..... 496
 basement..... 497
 ceiling..... 496
 flooring..... 496
 furniture..... 496
 heavy items..... 497
 lamps..... 496
 mud and debris..... 497
 outlets..... 496
 securing valuables..... 496
 vents and registers..... 497
 wall switches..... 496
 walls..... 496
- Building paper..... 87, 134
- Building wire
 type THHN..... 412
- Built-up girders
 carpentry..... 62
- Built-up roofing..... 132, 134
- Cold-Ap cement..... 133
- demolition..... 34
- insulation..... 131-132
- patch..... 131
- tear-off..... 129
- torch and mop system..... 134
- Bulb heater & fan
 Heat-A-Lamp..... 365
- Bulkhead light fixture
 outdoor..... 423
- Bull float
 rental..... 40
- Bullnose
 ceramic tile..... 297
 corner bead..... 247
 corner tile..... 298
 drywall arch..... 247
 outside corner..... 247
 plastic corner..... 247
- Bulls Eye shellac..... 470
- Bumper
 garage door..... 225
- Buried cable..... 399
- Burn off paint labor..... 446
- Bush removal..... 30
- Bushing
 insulated metallic
 grounding..... 410
 non-metallic reducer..... 400
 rigid or IMC reducing..... 410
 thermoplastic insulating..... 410
- Butcher's..... 471
- BX cable
 flexible armored..... 399
- Bypass door
 accessories..... 219
 bathtub..... 347
 beveled mirror..... 218
 closet..... 218
 hardware..... 222
 mirrored..... 218-219
- C**
- Cabinet
 demolition, wet..... 514
- Cabinet door..... 312
- Cabinet drawer front..... 312
- Cabinet hinge
 overlay..... 320
 self-closing..... 321
 semi-concealed..... 321
- Cabinet knobs..... 320
- Cabinet trim..... 316
- Cabinets
 base..... 313-314, 316-317
 bath..... 366-367
 bathroom vanity..... 358-359
 corner..... 367
 door trim..... 312
 end panel..... 312-314
 filler strip..... 314-315
 finished..... 316
 frameless..... 367
 kitchen,
 unfinished birch..... 313
 medicine..... 366-368
 oak..... 316-317
 painting labor..... 449
 pantry..... 315-317
 removal..... 311
 trim..... 316
 trim, finished..... 318
 utility..... 313-317
 utility..... 317
 vanity..... 362
 wall..... 313-317
- Cable
 AC..... 399
 appliance connection..... 397
 appliance re-connect..... 397
 appliance, remove &
 replace..... 397
 BX..... 399
 coaxial..... 413
 data communication..... 413
 fish through stud wall..... 397
 flexible armored BX..... 399
 thermostat..... 413
 Type NM-B Romex
 sheathed..... 397-398
 Type UF-B sheathed..... 399
 underground..... 399
- Cable coupling
 EMT to non-metallic
 sheathed..... 404
- Cable snake flat wire
 fish tape..... 397
- Cadet Series bar faucet..... 331
- Cafe doors..... 209
- Calcium chloride..... 48
- Cambray vinyl sheet
 flooring..... 283
- Cambria countertop..... 319
- Can
 ceiling light..... 420
- Canopy
 remove and replace..... 106
- Cant strips..... 137
- roofing..... 86
- Cap..... 146
 ceramic surface..... 298
 chimney..... 146
 PVC service entrance..... 402
 service entrance..... 412
- Cap sheet
 roofing..... 133
- Cap, post..... 436-437
- Cape Cod plank..... 252
- Carbon monoxide alarm,
 battery powered..... 416
- Carborundum rub..... 51
- Cardboard boxes..... 518
- Carflex liquid-tight
 conduit fitting..... 407
 flexible conduit..... 407
- Carlson..... 400-402, 407-408
- Carol Cable..... 413
- Carpentry
 backing and nailers..... 73
 beams and girders..... 62
 bridging or blocking..... 65
 ceiling beams..... 68
 ceiling joists..... 73
 door openings..... 69
 dormer studs..... 76
 fascia board..... 76
 fireblocks..... 68
 floor joists..... 64-65
 floor repairs..... 62
 furring..... 72
 plates..... 67
 posts..... 63
 rafters..... 75
 roof sheathing..... 77
 roof trusses..... 76
 room additions..... 64
 sheathing..... 70
 sill plates..... 64
 studs..... 66
 subflooring..... 66
 wall assemblies..... 70
 wall framing..... 66
 window openings..... 69
- Carpet..... 304
 cleaning..... 512
 demolition..... 36
 removal..... 274, 511
 roller, extendable..... 287
 transition strip..... 288
 water extraction..... 511
- Cartridge
 disposal..... 333
- Casement windows..... 164
 lock handle..... 166
 operator handle..... 166
 vinyl-clad wood..... 160
- Casing..... 263
 aluminum siding..... 114
 colonial..... 260
 colonial door..... 195
 door..... 191, 206
 paperwrap colonial..... 263
 polystyrene..... 264
 ranch..... 260, 263
- Casing, MDF..... 261
- Caspian sheet vinyl
 flooring..... 282
- Cast iron
 pipe, remove & replace..... 388
 radiator, remove &
 replace..... 378
 water closet flange..... 351
- Cast iron kitchen sink..... 322-323
- Cast molding..... 262
- chair rail..... 262
- Cast-in-place concrete..... 48
- Cat doors..... 216
- Catalina Lighting..... 423
- Caulk
 ceramic tile..... 303
 ceramic tile adhesive..... 303
 removal..... 157
 roof..... 136
 window exterior..... 157
- Caulking
 manhours..... 446
- Cedar
 panels, sidewall shingle..... 113
 roofing..... 137
 shingles..... 138
 siding..... 108-109
- Cedar louvered vents..... 90
- Cedar mill..... 112
- Ceiling
 beams..... 68
 demolition..... 242
 demolition, wet..... 513
 joists..... 73
 painting..... 450
 painting manhours..... 449-450
 repair..... 244
 staining manhours..... 450
 texture manhours..... 449
 tile adhesive..... 254
 touch-up kit..... 244
- Ceiling and wall panel
 FRP..... 253
- Ceiling fan
 bath..... 362
 bath heater & fan..... 365
 gazebo..... 424
 QuietTest..... 364
 San Marino..... 424
- Ceiling fan box..... 405
 non-metallic..... 402
 pancake..... 405
- Ceiling fixture..... 420
 drum..... 421
 fluorescent..... 421
 flush mount..... 421
 glass globe..... 422
 incandescent flush
 mount..... 422
 mushroom flush mount..... 422
 remove & replace..... 421
 Sunburst flush mount..... 422
 swirl dome light..... 422
- Ceiling insulation
 batt and roll blanket..... 79
 Kraft-faced..... 79
 loose-fill..... 79
 R-value..... 79
- Ceiling latex paint..... 472
- Ceiling lighting panel
 acrylic..... 258
 styrene..... 258
- Ceiling panel..... 256
 acoustical..... 256
 classic fine-textured..... 256
 fiberglass..... 256
 Firecode Fifth Avenue..... 257
 fissured..... 257
 fissured fire guard..... 256
 Grenoble..... 256
 gypsum lay-in..... 257
 mineral fiber..... 257
 plain white..... 256
 Prestige..... 256
 random textured..... 255
 Sahara..... 256
 suspended..... 255-257
 textured..... 257

Ceiling repair	245	toilet tissue holder	300	main.....	418	Cobra Rigid ridge vent	145
Ceiling texture	246	tool.....	287	main, all-in-one.....	418	Cofair Products.....	135
patch.....	245	toothbrush & tumbler		QO miniature.....	419	Coffer dam.....	92
popcorn patch	245	holder	301	tandem	419	Coil, kickplate	439
spray.....	244-245	wall	297, 299	Circular windows		Cold process adhesive	
touch-up kit.....	244	window sill.....	297	half circle, vinyl.....	159	modified bitumen.....	133
Ceiling tile.....	254	Ceramic tile definitions ...	272	Civic Square	286	Cold process cement.....	133
acoustical	253	Ceramic tile flooring.....	272	Clamp		Collar beams	
tin design.....	254	Ceramic tile flooring,		ground rod.....	412	carpentry	75
wood fiber.....	254	tips on.....	273	Snap Strap PVC		Collar ties	75
Ceiling tile grid system		Chain link fence		conduit.....	400	Colonial base molding	263
zero-clearance tile grid ...	255	demolition	30	wood floor.....	277	MDF.....	261
Ceiling tile, wet.....	513	Chain saw		Clamp connector		paperwrap	263
Ceiling wire hanging kit ...	255	rental	29	two-piece.....	399	polystyrene	263
Ceiling, suspended		Chain-operated wall		Classic faucet handle	354	Colonial casing	
cross tee.....	255	exhaust fan.....	364	Clay roofing tile.....	139	finger jointed.....	260
installation	254	Chair rail		Cleaning		paperwrap	263
main beam	255	cast polyurethane.....	262	after water extraction....	514	Colonial door casing.....	195
wall molding	255	MDF.....	261	antimicrobial	516	Colonial storm doors,	
CeilingMAX.....	255	paperwrap	264	brick.....	115	triple-track	205
Ceilings, suspended.....	237	polymer.....	263	carpet.....	512	Colonnade kitchen	
Cellar doors, steel	194	prefinished.....	264	HVAC.....	510	faucet.....	325
Cement		primed finger joint.....	260	masonry.....	115	Colorant	
board	245	Chalk line, self chalking...	287	pressure wash.....	448	grout.....	303
coloring.....	48	Chandelier	422	stone.....	115	Coloring agents	
joint compound.....	245	Channel		terra cotta.....	115	concrete.....	48, 50
mixer, rental	40	vent, rafter bay	88	Ultrasonic	510	Column, porch	435
siding.....	113	Chesapeake floor tile.....	285	Clear cedar siding.....	108	Combination coupling.....	404
soffit, fiber.....	112	Chime kit, door	416	Clear wood		Combination service	
tile.....	139	Chimney	379-383	preservative.....	471	entrance device.....	418
underlayment.....	281	A vent.....	382-383	protector.....	470	Combination service	
white	114	all fuels.....	382-383	Clearshield.....	468	entrance load center	417
Cement, roofing		aluminum.....	379-380	Clip, anchor	438	Commercial Electric	420
cold process	133	B vent.....	381	Clips & screws.....	322	Communication cable	
flashing	135	base tee	380-382	Clips, drywall repair.....	249	category 5E	413
Kool Patch.....	135	C vent.....	379-380	Closers		Composite kitchen sink ...	331
lap roof.....	133	cap.....	146	door	217	60/40 bowl.....	324
rubber wet patch	135	double wall	381-382	Closet		bar	331
Wet Stick.....	135	double wall		painting labor.....	450	Beaumont.....	324
Center		insulated	382-383	Closet doors	210	double bowl	323
HomeLine indoor main		elbow	380-383	bi-fold.....	219-220	Forsyth	323
lug load	417	flue.....	379-383	bypass.....	218	Greenwich	323
Central air conditioning....	377	flue rain cap.....	379	mirrored bypass ...	218-219	single bowl	323
Central air filtration retrofit,		gas or propane	379-382	Closet pole molding.....	263	Composition tile	
HEPA.....	378	L vent.....	381-382	Closure strips, horizontal...	141	vinyl	285-286
Central humidifier	377	liner.....	379	CMU		Compound	
Ceramic		liner (flue)		painting.....	457	glazing.....	170
floor & wall.....	293	aluminum.....	379	CO/ALR duplex		latex glazing	170
Ceramic tile		liner rain cap.....	379	receptacle.....	415	Compression conduit	
accessories	300	masonry,		coal furnace.....	384	coupling, rigid or IMC	410
accessory set	301	repair.....	104	Coated glass fabric.....	136	Compression connector	
adhesive.....	289	rain cap	380-383	yellow resin	136	EMT.....	403
adhesive caulk	303	repairing earthquake		Coating		EMT-to-box offset.....	404
backer.....	291	damage	490	elastomeric roof.....	137	non-metallic UF	399
backerboard	291	roof flashing.....	380-383	fibered roof	137	Compression faucet	
bullnose	297	single wall.....	379-380	floor, epoxy.....	475	repair	346
bullnose corner.....	298	stack.....	381-382	foundation and roof	129	Compression inlet	
caulk.....	303	storm collar.....	380-383	roof	137	dishwasher connector...	334
demolition	36, 311	supports & brackets	383	roof and foundation	129	Compressor	
floor	291-294	termination		weather-resistant.....	468	rental	29
floor warming system ...	301	assembly.....	380-383	wood	468	Concrete	
glazed.....	299	Chlorinated rubber paint...	476	Coating kit		additives	48
installation	289	C-hook		seam.....	287	architectural.....	48
mosaic accent	300	garage door.....	225	Coatings		bonding primer	473
mosaic octagon.....	300	Chop saw		concrete.....	475	coatings	475
Natura.....	292	rental	29	corrosion.....	92	coloring.....	48
removal.....	274	Chrome light fixture	421	epoxy gloss	476	curb	45
Saltillo.....	295	Circuit breaker		epoxy primer	476	delivery charges	47
sink rail.....	298	arc fault, HomeLine	417	specialty	476	driveways	47
soap dish.....	300	GFCI.....	417	Coaxial cable	413	embossed finish	51
surface cap.....	298	ground fault interrupter		wall plate	413	enamel.....	475
surface cap corner	298	plug-on	420	Coaxial F-connector		epoxy floor coating	475
threshold.....	297	HomeLine.....	417	for RG6.....	413	expansion joints	47

exposed aggregate	50	removal, rigid.....	409	Copper pipe		Cove and corner molding	
finishing	51	Schedule 40 PVC.....	400	DWV	388	inside.....	264
flatwork	41	Schedule 80 PVC.....	400	water.....	388	paperwrap	264
floor painting labor... 454-455		Conduit body	401	Copper step flashing	142	Cove base	
footings, demolition	32	PVC Type T.....	401	Copper wire		adhesive.....	286
form stripping	44	threaded aluminum	411	Type THHN	412-413	adhesive nozzle	287
forms	43-49	Conduit box		Copper wood preservative... 471		Cover	
foundations.....	49	adapter	401	Cord		faucet hole.....	328
grade beams	49	cover, steel.....	404, 406	disposal accessory kit... 333		patio, aluminum.....	439
granite aggregate.....	47	installation	404	Corian countertops	318	Covers	
grinding.....	493	non-metallic round.....	408	Cork		2 gang blank.....	408
grout mix	47	steel.....	405	roll.....	289	blank handy box.....	404
grouting	51	three-gang non-metallic... 402		tile flooring	271	dual weatherproof	
high early strength.....	48	two-gang non-metallic... 402		tile, natural.....	289	lampholder.....	408
joints.....	47	Conduit bushing		Corner		GFCI wet location	
keyway	49	rigid.....	410	MDF primed base.....	261	receptacle.....	408
lightweight	47	Conduit clamp		plastic bullnose.....	247	horizontal duplex	
mix.....	47	Snap Strap PVC.....	400	Corner and cove molding		weatherproof	
patching.....	51	Conduit connector		inside.....	264	receptacle	408
planing.....	493	90-degree.....	406	paperwrap	264	receptacle.....	408
plasticized.....	48	flex.....	407	Corner bead		steel conduit box... 404, 406	
protective coating.....	475	Conduit coupling		bullnose	247	switch.....	408
pump mix	47	rigid.....	409-410	drywall	247	weatherproof blank.....	408
pumping.....	40	Conduit elbow		flex.....	248	Crack filler,	
ready-mix.....	47	45-degree rigid steel 409		inside	247	siliconizer.....	136
recycling	30	rigid or IMC steel.....	409	outside.....	248	Crack repair.....	493
reinforcing steel.....	45	Conduit fitting		spray adhesive	249	mesh.....	248
repair.....	493	Carflex.....	407	Corner block		Craft codes.....	15
retaining walls	48	non-metallic.....	401	polyurethane.....	262	Crawlspace ventilation	
sawing.....	51	Conduit hub		Corner cabinet,		free circulation area..... 82	
sealer.....	475	watertight.....	410	frameless	367	Cribbing	62
shingles	140	Conduit installation		Corner molding		Cripple wall.....	492
sidewalk.....	50	confined area	409	inside	264	Cross bridging	65
slab demolition	33	Conduit locknut.....	410	paperwrap outside.....	264	Cross head cast molding ... 262	
slabs	50	Conduit nipple	411	polystyrene outside	264	Crow's foot brush	250
specialty finishes	51	Conduit sill plate		Corner shelf, ceramic	300	Crown molding	259, 263
stain.....	475	service entrance.....	412	Corner tape,		cabinet.....	316, 318
stamped finish.....	51	Conduit strap.....	411	flexible metal	249	MDF ultralite.....	262
tile.....	139	Connector		Corner trowel.....	250	primed finger joint.....	261
tile roofing.....	140	90-degree flexible.....	406	Cornices,		Crystalite countertop	319
topping.....	51	dishwasher	333-334	painting.....	460	Curb mount fixed	
walks	50	EMT compression	403	Corrosion coatings	92	skylights.....	173
wall demolition.....	33	EMT offset screw	403	Corrugated		Curbs,	
wall form.....	44	EMT set screw	403	fiberglass.....	140	concrete.....	45
walls	48	EMT-to-box offset		metal roofing	138	Cure-Seal concrete	
waterproof	475	compression.....	404	metal siding	113	sealer.....	475
waterproofing sealer..... 475		flex screw-in	406	CorStone	323-324	Curing and sealing	
Concrete & masonry		flex squeeze	407	Cost plus markup equals		compound.....	50
waterproof	475	non-metallic UF		selling price	7	Curved glass wall	
Concrete block		compression	399	Cotton insulation.....	87	lantern	423
demolition.....	32	two-piece clamp	399	Cotton roof patch		Custom Building	
painting.....	456-458	Containment		asphalt saturated.....	136	Products	301-303
Concrete conveyor		dust.....	516	Counterflashing	144	CustomBlend Thin-Set	
rental	40	mold.....	516	Countertops.....	318	Mortar	302
Concrete deck		Contents	3	Corian	318	CustomFloat bedding	
patch built-up roofing... 131		Continuous vents.....	89	granite	319	mortar.....	302
Concrete pier replacement... 63		Contractors, state license		laminated plastic ... 319-320		Cutter	
Concrete saws		dryout	495	marble vanity.....	360	glass	171
rental	40	mold remediation.....	495	miter bolt kit.....	320	vinyl tile	287
Conditioner		Control switch		plastic laminate	319	Cutting	
wood.....	471	fan	366	setting with adhesive... 290		slabs.....	51
Conduit		Convection heating,		setting with mortar	290		
Carflex liquid-tight	407	baseboard	378	solid surface	318		
EMT	402, 406	Cooktop		stone, engineered	319		
EMT, removal.....	402	electric.....	335	tile.....	291		
ENT	407	electric ceramic glass... 335		Coupling			
flex appliance		gas.....	335	combination	404		
connection.....	397	Cooling system, patio	438	EMT to non-metallic			
flexible aluminum	406	Copper		sheathed cable.....	404		
flexible steel	406	formed flashing.....	142	non-metallic standard... 401			
galvanized IMC	409	roll flashing	141	rigid conduit.....	409		
GRS.....	409	window roofs	164	rigid or IMC compression			
IMC.....	409			conduit.....	410		
installation, rigid	409						

D

Dado partition	
demolition.....	312
Dal-Tile	293, 299-300
Danco	329
Danish Oil.....	468
DAP	170
Data communication cable	
category 5E	413

Deadbolts	202	sidewalks	32	Door		birch	192, 210
Debris removal	30, 509	skylight, poly dome	172	cabinet	312	birch, prehung	197
Deck		slab	31	demolition, wet	514	bypass, closet	218
demolition	432	stairs	36	framing	69	bypass, mirrored ...	218-219
lumber	433	suspended ceiling ...	254, 311	hinges, brass	196	cafe	209
lumber	432	wall	264	kick plates	213	camber top	199
lumber	434	wall cover	312	knockers	213	casing	195
lumber, Fiberon	434	walls	31-32	openers	225	cellar	194
lumber, Thompsonized ..	434	wet materials	512	painting labor	451-453	closers	217
misting system	438	windows	36, 156	peep sights	214	closet	186, 210, 218-219
painting	455	wood framing	31	pull plates	213	closet, bypass	218
post & beam	432	DensArmor gypsum		push plates	213	demolition	36
post cap	437	board	243	Door accessories		Douglas fir	193
posts	433, 436	DensShield tile backer ..	245	bypass	219	entrance	194
railing	435-436	Dentil cast molding	262	Door bar	226	entry	193, 198-200
railing, turned spindle ..	436	Dentil chair rail	262	Door bell		entry, decorative fan ..	200
repair	432	Designer panel		wireless	416	entry, decorative	
roof	435	wallcovering	252	Door bottom		half lite	200
screws	439	Designer Series bath fan ..	365	aluminum & vinyl	196	exterior ...	192-193, 197-198
staining	455	Detaching membrane	304	drip cap	196	exterior fan lite	197
stairs	438	Detector		Door casing	191, 206	exterior flush	197
Deck & siding stain	467	dual-ionization smoke ...	416	colonial	195, 260	exterior prehung ...	197-199
Deck Plus stain	467	smoke	416	ranch	195	exterior prehung,	
Deck, roof		Devoe Coatings	476	ranch, pine	195	with mini-blind	198
removal	129	DeWalt	249	Door chime builder's kit ..	416	exterior, installation	191
repair	129	De-watering	509	Door closers	217	fiberglass	200-201
walking	140	DeWitts	135	hinge pin	217	fir	193
Deck, roofing		Difficulty factors, painting		hydraulic	217	fire	192
patching built-up ...	131-132	manhours	446	installation	217	fire-rated	197
Decora AC quiet rocker		overhang	460	pneumatic	217	flush	219
switch	414	Diffuser fixture		Door frame		flush closet	219
Decora wall plate,		fluorescent	421	painting labor	451	flush closet, lauan	219
single gang	415	Diffusers		Door frames	194	folding, accordion	217
Deflect-O	366	duct, installation	377	fire-rated	194	foundation access	88
Dehumidifiers	518	Dimmer		pocket	222	French	193
Delta ... 325-326, 354, 356-357		illuminated slide	416	removal	197	French, interior	208
Demolition		incandescent slide	416	Door grille	216	garage	223-224
acoustic tile ceiling	311	Dirt, recycling	30	Door handles, patio	216	garage,	
acoustical ceiling ...	254, 311	Disconnect		Door hangers	222	extension spring	225
asphalt paving	52	appliances	397	Door hardware	216	garage, jamb hinge	224
baseboard	35	distribution panel	417	track	222	handle sets	202
brick sidewalk	32	Dish, soap	300	Door hinge, remove	196	hanging slab doors	184
brick wall	31	Dishwasher	334	Door installation		hardboard	192, 209
building components	31	compression inlet	334	interior	191, 206, 209	hardware	221
carpet	36	connector	333-334	removal	206	hardware, exit	226
ceiling	35, 242	removal	311	Door jambs		hemlock	197
checklist	27	Dispenser		exterior	194	installation	
concrete block	32	hot water	329	garage	224	interior ...	191, 197, 206, 209
concrete sidewalk	32	soap	328	interior	209	interior ...	207-208, 211-212
concrete slab	33	Disposal		patio door	216	interior cafe	209
concrete wall	33	basket strainer	328	pocket	222	interior slab	206
decks, wood	33, 432	batch feed	332	remove & replace ...	191, 206	interior, birch	206
doors	36	cartridge	333	Door kit	222	interior, colonial	211
drywall	242	food waste	332-333	Door lever,		interior, colonist	211
drywall ceiling	311	mounting assembly	333	privacy	213	interior, fir	208
equipment rental	29	septic system	332	Door locks	217	interior, French	212-213
estimating	27	sink flange	333	patio	216	interior, full louver, pine ...	212
fence	30	sink stopper	333	Door locksets ...	183, 201, 202	interior, hardboard	207
floor cover	311	waste	30	Door push bar	226	interior, hardboard,	
flooring	274	Disposer		Door roller	216	colonist	207
framing	34	garbage	332-333	Door stop	213	interior, lauan	206-207
garage	31	cord		Door threshold	216	interior, oak ...	206, 208, 212
guardrail	30	accessory kit	333	Door track hardware	222	interior, pine	208
joists	34	sink stopper	333	Door trim	194	interior, pine louver	212
kitchen cabinets	311	Distribution box		painting labor	451	interior, prehung ...	209-210
kitchen fixtures	311	electric	520	Doors		interior, prehung,	
masonry	31	Distribution panel		4-panel	193	knotty alder	212
molding	35	disconnect & remove ...	417	6-panel	192	interior, solid core	207
panelling	252	Ditching	42	adding or removing	182	lauan	210
plaster	242	Ditra	304	bar	209	lever latchset	213
plaster ceiling	311	Dock & fence post		basement	226	lockset repair	201
porch	33, 432	preservative	470	bi-fold	219-221	metal, reversible	194
shower stall	348	Dome light ceiling fixture ..	422	bi-fold, louvered	220-221	mirrored	221

- mobile home..... 222
 molded face..... 207-208
 oak..... 210
 pantry..... 212
 patio..... 214
 patio grille..... 216
 patio handle..... 216
 patio lock..... 216
 patio roller..... 216
 patio threshold..... 216
 patio, aluminum..... 215
 patio, double..... 215
 patio, fiberglass..... 215
 patio, gliding..... 214
 patio, hinged..... 214
 patio, sliding..... 214
 patio, sliding, aluminum..... 215
 patio, steel..... 215
 patio, swinging..... 214-215
 patio, vinyl..... 215
 pet..... 216
 pet, cat..... 216
 pocket..... 222
 prehung..... 186, 197
 red oak..... 192
 removal..... 36, 197
 repair..... 175, 191
 replacement..... 175
 replacement procedure..... 185
 screen..... 203
 screen, installation..... 202
 screen, metal..... 203
 screen, pine..... 203
 screen,
 replacement..... 203, 216
 screen, steel..... 203
 screen, vinyl..... 203
 screen, wood..... 203
 security..... 205
 security, Paradise-style..... 205
 security, with screen,
 heavy-duty..... 205
 setting trim..... 184
 shower..... 349
 sidelites..... 198
 slab..... 192-193
 solid core..... 192, 197
 steel..... 198
 steel exterior..... 199
 steel, 6-panel..... 198
 steel, entry..... 198
 steel, exterior..... 199
 steel, prehung..... 198
 steel, prehung, with
 mini-blind..... 198
 stile & rail..... 208
 storm..... 204-205
 storm, all-season..... 204
 storm, aluminum..... 204
 storm, aluminum and
 wood..... 204
 storm, removal..... 204
 storm, self-storing..... 204
 storm, triple-track..... 204
 storm, woodcore..... 205
 terms..... 188
 weatherstripping..... 196
 Doors, entry..... 175
 antiquing..... 176
 reassembling..... 179
 rebuilding..... 178
 refinishing..... 176
 repairing holes..... 177
 Doors, exterior
 framing and replacing..... 179
 Doors, interior..... 181
 Dormer
 studs..... 75-76
 vent..... 144
 vents..... 90
 Double bowl kitchen sink..... 322
 cast iron..... 322
 stainless steel..... 321
 Double cylinder
 door handle..... 202
 Double doors..... 211-212
 Double oven
 wall..... 335
 Double-hung windows
 insulated..... 159
 replacement..... 157
 screens..... 160
 vinyl-clad..... 159
 wood..... 163
 Double-track storm
 windows..... 165
 Downlight
 ceiling fixture..... 420
 Downspouts
 acid wash..... 446
 galvanized steel..... 146
 painting labor..... 456
 remove and replace..... 106
 residential..... 146
 Drain connector
 garbage disposal to
 dishwasher..... 334
 Drain stopper..... 329
 flat sink..... 329
 Drain, waste and vent lines,
 plumbing for..... 373
 Drainboards, countertops..... 291
 Drawer front
 cabinet..... 312
 Drawer pulls..... 320
 Drawn box
 2-device switch..... 405
 handy..... 404
 octagon..... 405
 Drip cap..... 141
 door bottom seal..... 196
 molding, wood..... 114
 Drip edge..... 142
 aluminum..... 141
 Driveway forms..... 44, 50
 Driveways,
 concrete..... 50
 Drop ceiling
 panel..... 255-257
 soffit..... 312
 Drum mushroom ceiling
 fixture..... 421
 Dry ice blasting..... 517
 Dry rot remediation..... 92
 Dry tile grout
 non-sanded..... 303
 Dryback vinyl wall base..... 288
 Dryer
 wall cavity..... 519
 Dry-out..... 509
 Emergency..... 509
 Drywall
 arch, bullnose..... 247
 ceiling, demolition..... 311
 ceilings..... 232
 corner bead..... 247
 corner tape..... 249
 demolition..... 35, 242, 312
 demolition, wet..... 512
 dustless sanding
 system..... 251
 finish..... 244
 fire code type X..... 243
 fire-resistant..... 243
 flexible..... 244
 greenboard..... 244
 hand sander..... 250
 hanging..... 228
 installation..... 242, 244
 J-bead..... 248
 joint compound..... 245-246
 joint tape..... 246
 J-trim..... 248
 L-trim..... 248
 mildew resistant..... 243
 moisture resistant..... 243
 moisture-resistant..... 243
 mold resistant..... 243
 nails..... 249
 outside corner trowel..... 250
 painting..... 463-464
 panel lift..... 250
 patch..... 242
 primer..... 246
 repair..... 242
 repair clips..... 249
 repair kit..... 248
 repair patch..... 248
 repair sheet..... 244
 repairing..... 234
 sander kit..... 250
 sanding respirator..... 250
 sanding sponge..... 250
 screws..... 249
 sound deadening..... 243
 spray texture..... 244
 tape..... 246
 taping and finishing..... 230
 texture..... 244
 texture spray..... 244
 textured finishes..... 232
 topping compound..... 246
 vinyl outside corner
 bead..... 248
 Drywall tape, white,
 fiberglass..... 246
 Drywall tools
 electronic stud sensor..... 249
 hammer..... 250
 sander..... 251
 screw gun,
 battery-powered..... 249
 screwdriver..... 249
 screwdriver bit..... 250
 screws, collated..... 249
 stilts..... 250
 texture brush..... 250
 trowel..... 250
 trowel, corner..... 250
 T-square..... 250
 Dual sensing smoke
 alarm..... 416
 Dual weatherproof
 lampholder & cover..... 408
 Dual-ionization smoke
 detector..... 416
 Duct
 heating, removal..... 376
 runs, installation..... 377
 Duct tape..... 518
 Dumont kitchen sink..... 322
 Dump fees..... 30
 Dump trucks
 rental..... 29
 Dumpster..... 518
 rental..... 30
 trash..... 30
 Duplex receptacle
 CO/ALR..... 415
 commercial grade..... 415
 handy box cover..... 404
 straight blade..... 414
 waterproof cover..... 408
 Duratemp
 panel siding..... 111
 Durock backerboard..... 291
 Durock cement board..... 245
 Dust control..... 516
 Dustless drywall sanding
 system..... 251
 DWV pipe
 remove & replace..... 388
- ## E
- E.L. Mustee..... 329
 Earthquake anchor..... 492
 Earthquake damage
 (IBC) seismic safety
 standards..... 477
 (IPMC) seismic safety
 standards..... 477
 (IRC) seismic safety
 standards..... 477
 structural
 improvements..... 478
 structural improvements,
 (IRC)..... 478
 structural improvements,
 permits for..... 478
 Earthquake damage
 prevention
 anchors, hold-down..... 480
 bracing hillside homes..... 482
 bracing, cripple walls..... 480
 bracing, open front..... 481
 foundation bolting..... 479
 masonry chimneys,
 anchoring..... 483
 tension ties on split-level
 homes..... 483
 Earthquake damage
 prevention, FEMA
 recommendations..... 479
 bracing hillside homes..... 482
 cripple wall bracing..... 480
 foundation bolting..... 479
 hold-down anchors..... 480
 masonry chimneys,
 anchoring..... 483
 open front bracing..... 481
 tension ties on split-level
 homes..... 483
 Earthquake damage repair
 chimneys..... 490
 concrete cracks..... 487
 cracks in plaster and
 stucco..... 489
 drywall..... 490
 electrical systems..... 491
 epoxy injection..... 487
 fireplaces..... 490
 floors out of level..... 488

foundations and slabs... 487	Electric water heater... 386-387	Entry doors..... 193, 198-200	Exterior trim, painting 443
framing 488	PowerStar™ 387	deco fan lite..... 193	Exterior wall assemblies.... 71
gypsum drywall 490	tankless 387	fiberglass 200-201	Exterior window shutters... 167
mechanical systems 491	Electrical management	oak..... 194	Extraction
plaster..... 489	system	Epoxy crack repair..... 493	Water..... 509
plumbing systems 491	Smart home..... 424	Epoxy floor coating..... 475	Extruded polymer
stucco 489	Electrical non-metallic	Epoxy gloss coating 476	molding..... 263
Earthquake damage,	tubing conduit..... 407	Epoxy mortar 302	Eyeball trim light kit 420
checking for	Electrical systems	Epoxy primer 476	
before making repairs... 486	licensing and code	Equipment costs..... 13	F
jobsite walk..... 486	compliance..... 390	Equipment rental	F channel..... 439
structural engineer 486	National Electrical Code	demolition 29	F connector
Earthquake damage,	(NEC) 390	foundations and slabs ... 40	for RG6 coaxial cable... 413
cosmetic 477	power shortfall 389	Escape window 172	Fabback acrylic mirrored
Earthquake damage,	repairing earthquake	Estimating home	sheet..... 171
increased risk	damage 491	improvement costs	Fabric
when adding a room ... 484	service upgrade..... 390	hanging doors 5	asphalt roofing..... 131
when making	Eliane ceramic tile 293	price book..... 6	polyester stress-block ... 136
alterations..... 484	Eljer 322	problems..... 5	Factors
when removing	Elkay Manufacturing... 321, 331	Estwing 250	high time painting 446
wall bracing 485	Embossed basswood	Eternit 139	painting difficulty..... 460
Earthquake damage,	molding..... 259	Excavation..... 42	Fairfax faucet
structural..... 477	Embossed concrete..... 51	backfilling 41	two-handle..... 358
Easysills..... 165	Embossed decorative	fine grading 41	Fairfax kitchen faucet 326
Eave closure..... 140	molding..... 259	footings..... 41	Fan
Eave vents..... 90	Embossed tileboard..... 251	rock..... 41	ceiling 424
Decomesh 89	Embossing leveler 281	spreading..... 42	gazebo..... 424
Eaves	Emergency dry-out	tamping..... 42	outdoor ceiling..... 424
painting..... 460	service..... 509	topsoil..... 42	Fan lite doors..... 197, 201
Edeck..... 432	Emser International 294	Excelon vinyl composition	Fans
Edge	EMT conduit 402, 406	tile..... 285-286	attic exhaust..... 91
drip 141-142	45-degree elbow 403	Exhaust fan 364	bath 362-365
flashing, roof..... 143	90-degree elbow 403	bath 362-365	bath exhaust... 362, 364-365
Edge forms, concrete... 41, 44	combination coupling 404	bath, vertical discharge... 363	bath exhaust & heater... 365
Edge protection tile..... 299	compression connector... 403	ceiling..... 363	bath exhaust,
Edge pulls..... 222	coupling..... 404	QuieTTest..... 364	timer switch 366
Edge V-plank..... 252	offset compression	utility, vertical discharge... 363	ValueTest with light..... 364
Efficiency cast iron kitchen	connector..... 404	vertical discharge 363	vertical discharge 363
sink..... 322	offset screw connector... 403	wall 363	bath, premium 363
Egg & dart cast molding... 262	set screw connector 403	with heater..... 365	SensAire control switch ... 366
Egg knob locksets 202	strap..... 404	with infrared heater 365	utility exhaust, vertical
Eggshell wall paint,	EMT conduit, removal 402	Exhauster, roof 145	discharge..... 363
latex..... 472	EMT strap..... 404	Exit bar 226	utility, thru-the-wall 364
Elastocaulk 136	Emulsion	Expansion bolt..... 492	wall exhaust,
Elastomastic..... 136	asphalt..... 133	Expansion joints	chain-operated 364
Elastomeric roof coat... 137	Enamel	concrete..... 47	Fascia
Elastomeric waterproofing	floor & porch..... 475	Exposed aggregate finish ... 50	aluminum..... 114
paint..... 474	interior & exterior..... 473	Exposed aggregate	board 76
Elastotape..... 136	latex..... 472	sealer..... 475	staining 453
Elbow	oil-based..... 476	Exposed round conduit box	vinyl 108
45-degree plain end..... 401	painting..... 463-464	non-metallic..... 408	Fashion Series 252
90-degree..... 403	wall & trim..... 472	Extendable roller 287	Fasteners..... 438-439
90-degree standard	Enamel undercoater	Extension kit	deck screws 439
radius 401	interior 471	jamb..... 216	Fast-setting patch..... 281
EMT 45-degree 403	Encapsulate mold..... 517	Exterior & interior stain	Faucet hole cover..... 328
EMT 90-degree 403	Encapsulated fiberglass roll	acrylic..... 467	Faucets
pulling..... 403	insulation 85	Exterior clear finish..... 469	bar 331
rigid or IMC steel	Enclosure, shower	Exterior door jambs 194	bar, single handle..... 331
conduit..... 409	pivot door 349	Exterior doors 193	bar, two-handle 331-332
rigid steel conduit 409	End panel	fir 192	bidet..... 350
rigid steel conduit 409	base cabinets..... 313	flush..... 192	compression, repair..... 346
service entrance..... 412	cabinet..... 312, 314	prehung 197	kitchen 324-326
Electric baseboard	wall cabinets..... 315	Exterior jambs	kitchen,
heaters 384	Energy-efficient electrical	kerfed 194	two-handle..... 326-327
Electric cooktop 335	upgrades 424	Exterior paint	kitchen, two-handle,
Electric metallic tube	ENT conduit..... 407	satin flat..... 474	with spray 327
conduit..... 402, 406	Entertainment sink..... 331	Exterior painting 446	laundry, two-handle..... 330
Electric metallic tube	Entrance cap	Exterior sanding	lavatory..... 354-356
conduit removal..... 402	PVC..... 402	manhours 447	lavatory,
Electric service panel 419		Exterior stain 467	adjustable center..... 358
Electric space heaters 372		Plus 10 467	lavatory, center set... 355-358
Electric wall oven..... 335			lavatory, infrared 355

- lavatory, two-handle 356
 Roman tub 347
 supply 358
 tub & shower 349-350
 Feather edge additive 282
 Federal Emergency Management Agency (FEMA)
 recommendations 479
 structural improvements 478
 Fees
 recycling 30
 Felt
 roofing 133
 roofing, glass fiber 134
 scribing 287
 Fence
 demolition 30
 staining labor 454
 Fence & barn paint 476
 Fence post preservative 470
 Fernco 334
 Fiber cement
 lap siding 112
 siding 113
 siding panel 112
 soffit 112
 trim for siding 112
 Fiber-cement
 roofing 139
 Fiberglass aluminum roof
 coating 137
 Fiberglass roof coating 137
 Fiberglass
 base sheet 133
 panels 140
 reinforcing membrane 136
 screen rolls 168
 window trim, bath 347
 Fiberglass asphalt
 shingles 131
 Fiberglass ceiling
 panel 256-257
 Fiberglass doors
 entry 200-201
 Fiberglass insulation
 batt 84
 Kraft-faced 84
 roll 84-85
 unfaced 84
 Fiberglass mat roof patch 135
 Fiberglass reinforced plastic
 panels 253
 Fiberon 432, 434
 Field adhesive
 SBS 134
 Field tile
 setting with adhesive 290
 setting with mortar 290
 Fill
 excavation 41
 Filler
 crack 136
 Filler strip 313-315
 oak 317
 wood 138
 Film
 polyethylene 87
 Finish carpentry
 countertops 318
 siding 107
 Finish sealer
 high-gloss 303
 Finished box cover 405
 Finishes
 exterior clear 469
 flat latex 472
 floor, oil-based 469
 interior classic clear 469
 log home gloss 469
 rust-resistant 476
 stain gel, non-wood 468
 wood 467
 Finishing
 concrete 50-51
 Finishing compound
 wallboard 246
 Finishing putty
 Pergo 279
 Fink truss 76
 Fir doors 192-193
 Fire doors 192
 Fireblocks 68
 Firebrick 115
 Fireplaces
 demolition 115
 masonry, repair 104
 prefabricated 116
 repairing earthquake damage 490
 Fire-rated door frames 194
 Fire-rated doors 197
 Fire-resistant drywall 243
 Fish tape 393
 cable snake 397
 Fissured ceiling
 panel 256-257
 Fixed shower door 349
 Fixed skylights 172-173
 Fixture removal 510
 Fixture gasket removal 346
 Fixture supply lines 358
 Fixture valve lines 358
 Fixture, light
 ceiling 422
 chandelier 422
 chrome bath bar 421
 fluorescent ceiling 421
 flush mount ceiling 421
 jelly jar 423
 motion sensing 423
 mushroom flush mount 422
 outdoor bulkhead 423
 outdoor wall lantern 423
 remove & replace 421
 wave bath 421
 Fixtures
 troffer fluorescent 258
 U-lamp troffer fluorescent 258
 Flange kit
 load center 417
 Flashing
 aluminum roll 141
 aluminum siding 113
 angle 142
 copper formed 142
 counterflash 144
 galvanized 142
 gravel stop 142
 lead 143, 145
 patch 135
 pipe 143, 145
 removal 129
 repair 129
 roll valley 141, 143
 roof 134
 roof edge 143-144
 roof, removal 134
 roof-to-wall 144
 service entrance roof 412
 shingle 144
 step 144
 w-valley 144
 Flashing cement
 pro-grade 135
 Flashing leaks 118
 Flashing paper
 roof 88
 Flashing, pipe
 tile roof 145
 Flat masonry &
 stucco paint 474
 Flat paint 472
 exterior, satin 474
 interior 472
 latex 474
 Flat sink drain stopper 329
 Flex conduit
 appliance connection 397
 Flex screw-in connector 406
 FlexBond bonding
 mortar 302
 Flexible aluminum
 conduit 406
 Flexible armored BX
 cable 399
 Flexible bonding mortar 302
 Flexible connector
 90-degree 406
 90-degree insulated 406
 Flexible metal corner
 tape 249
 Flexible steel conduit 406
 Flip locks
 window 171
 Float
 carpet 511
 Float finish
 concrete 50
 Floating floor
 installation kit 276
 Flood abatement 511
 Flood Company, The 470
 Flooding, effects of 495
 Floor
 beam 62
 beam, shimming 62
 clamp 277
 decking, subflooring 66
 demolition 36
 furring 72
 joists 64-65
 repairs, framing 62
 slab, concrete 50
 staining 455
 Floor & porch enamel 475
 Floor & porch oil gloss 475
 Floor & wall tile
 ceramic 293
 Floor beams
 decay 53
 reinforcement with jack posts 55
 repair 53
 Floor coating
 epoxy 475
 Floor covering
 tile, resilient 267
 wood 267
 Floor drying system 519
 Floor enamel 475
 Floor finish
 oil-based 469
 Floor furnace, gas 384
 Floor insulation 80
 Floor jacks 54
 Floor joist
 demolition 34
 repair 54-55
 Floor molding
 hardwood 274
 Floor plank choices for
 porches and decks 430
 Floor primer 281
 Floor tile
 ceramic 291-294
 granite 295
 marble 294
 natural stone 295
 parquet 278
 Place n Press 285
 Saltillo ceramic 295
 slate 295
 travertine 295
 vinyl 284-285
 vinyl, slip-retardant 285
 wood 278
 Floor trim
 wood 275
 Floor warming system 301
 thermostat 301
 Flooring
 adhesive for rubber tile 286
 adhesive for vinyl sheet 286
 adhesive for vinyl tile 286
 adhesive for wood 278
 adhesive remover 281
 bamboo plank 276
 carpet 304
 ceramic tile 290
 demolition 36, 274, 311
 demolition, wet 513
 hardwood plank 276
 hardwood, sanding 277
 heart pine plank 276
 Hevea parquet 278
 installation spacer 279
 laminate floor
 underlayment 280
 laminate strip 280
 maple hardwood 275
 maple strip, unfinished 277
 molding, laminate 280
 molding, wood laminate 279
 Northwoods hardwood 274
 oak 275
 oak parquet 278
 oak self-stick parquet 278
 oak, solid hardwood 274
 Pergo 279
 Pergo underlayment 279
 red oak, strip 277
 removal 274
 repairs 62
 rustic oak plank 276
 sealant, laminate 279
 setting with adhesive 290
 setting with mortar 290
 sheet vinyl 282-283
 strips, natural wood 275

surface preparation	280	Flush valve urinal, Sloan Royal.....	351	partitions, wood	66-67	locks	225
teak.....	275	Flute & reed molding	261	repairs	62	low headroom kit.....	225
TrafficMaster laminate	280	Foam insulation	85	room additions.....	64	operators	225
transition reducer strip	288	Foam underlayment... 279-280		straightening.....	494	raised panel.....	223
transition strip.....	288	Foam weatherstripping... 196		wall studs	66	replacement.....	223
trim, hardwood	277	Foamular XAE	85	Framing lumber	432	steel.....	223
underlayment.....	281	Foil		Framing straps	492	steel, non-insulated	224
underlayment & patch... 282		aluminum.....	88	French doors	193, 208	torsion spring.....	223
underlayment skimcoat... 282		barrier.....	88	interior, double	212-213	trolleys, installation.....	223
vinyl roll	282-283	Folding doors		painting labor.....	451-452	weather seal	224
vinyl sheet	283	accordion.....	217	Frenchwood.....	214, 216	Garage slabs	43
vinyl wall base.....	289	locks	217	Frieze cast molding	262	Garbage disposal	
water extraction	511	Footings.....	49	FRP panel molding.....	253	basket strainer.....	328
white oak strip	277	concrete.....	47, 49	FRP wall and ceiling		connector, dishwasher	
wood.....	277	continuous.....	49	panel.....	253	drain	334
wood laminate	279	demolition	32	Full-view storm doors	205	Garbage disposer	332-333
wood plank	276	excavation	41	Fungicide.....	92	cord kit.....	333
wood, installation tools... 277		keyway	49	Furnace		mounting assembly	333
Flooring installation system		Forced air furnace	377	coal.....	384	mounting gasket.....	333
laminate floor.....	280	Forced-air heating	371	counterflow, gas	377	removal.....	311
Flooring over concrete..... 272		Formica countertops..... 318		flue.....	379-383	sink flange	333
Flooring trim	280	Forms		gas, duct.....	376	sink stopper	333
bamboo	276	board	44	gas, floor	384	switch, sink top.....	333
heart pine	277	concrete.....	49	gas, thru-wall.....	384	Garden windows.....	158
Flooring, resilient		curb	45	gas, wall	384	Gardner	135-136
sheet vinyl	270	footings.....	45	horizontal flow, gas	377	Gas breaker	
Flooring, tile		foundation.....	44-45	low boy, gas	376	rental	29
ceramic.....	272	keyway	45	oil fired	377	Gas cooktop	335
ceramic, tips on	273	plywood	44	remove & replace.....	378	Gas furnace	
cork.....	271	stripping	45	wood burning.....	384	counterflow	377
granite	271	wall	44	Furniture		exterior wall duct	376
marble	271	Formwork		Blocking	509	horizontal flow	377
Flooring, wood		stripping	45	Moving.....	509	interior wall duct	376
hardwood.....	268	Forsyth composite sink... 323		Furniture pad	518	low boy	376
laminate.....	270	Foundation		Furring		Gas water heater.....	385
softwood.....	268	access doors	88	floor	72	power vent.....	387
strip.....	268	anchor	492	wood.....	72	tankless	387
Floors, sagging.....	54	bracket.....	492	G		Gasket	
Floors, wood		crack repair	493	Gable		fixture, remove &	
fixing squeaks	56	demolition	32	truss.....	76	replace	346
Flue		vent.....	88	Gable louver, metal	90	mounting.....	333
chimney	379	vents.....	88	Gable vents	89	wax, toilet bowl.....	351
chimney, aluminum	379	Foundation and roof coating		metal.....	90	Gates	
furnace	379-383	non-fibered	129	power attic.....	92	security	205
Fluidmaster.....	351-352	Foundation and slab pre-		redwood	90	Gazebo ceiling fan.....	424
Fluorescent ceiling fixture .. 421		construction checklist.... 38		Gabrielle Comfort Height		GE Appliances.....	334-335
Fluorescent diffuser fixture		Foundation bolt.....	492	toilet.....	351	Gel stain	468
low profile	421	Foundation insulation	86	GAF	131, 134, 145	General requirements..... 30	
Fluorescent fixtures		Foundations		GAFGLAS		Generator	520
parabolic troffer	258	concrete.....	47-48	ply 4 glass felt	134	Genesis kitchen faucet... 325	
U-lamp troffer	258	cracks (active or		Torch and Mop System... 134		Georgetown lavatory	
Flush doors.....	219	dormant).....	37	Galvanized		faucet.....	357
bi-fold closet	219	equipment rental	40	bullnose corner bead... 247		Georgia-Pacific... 245, 251, 253	
birch exterior	192, 197	footings.....	49	Galvanized flashing	142	GFCI circuit breaker	417
birch interior... 206-207, 210		forms	44	Galvanized rigid steel		plug-on	420
fire-rated	192	leaky basement walls.... 37		conduit.....	409	GFCI receptacle	405, 415
hardboard	192	repair	37	Galvanized roofing	138	duplex waterproof.....	408
hardboard exterior..... 197		Frame		louver	145	hospital grade.....	415
hardboard		painting labor.....	451	Galvanized steel		vertical	408
interior	206-207, 209	sink	327	rain gutters	146	wet location cover	408
hardboard, interior..... 207		Frame wall		Garage		GFI plug-on circuit	
hardwood exterior... 192, 197		aligning.....	494	demolition	31	breaker	420
lauan exterior	192	Frameless corner		Garage doors	223	Girders	
lauan interior... 206-207, 210		cabinet.....	367	bonded steel.....	224	carpentry.....	62
oak entry	194	Frames		bottom seal.....	223	Glacier Bay	
oak interior	206, 210	door	194	extension springs	225	324, 326, 330, 354-356	
painting labor.....	451-452	Framing		hardware	225	Glacier Extensa kitchen	
red oak interior	210	cut window opening..... 156		installation	223	faucet.....	325
steel exterior.....	198-199	damage	53	insulated	224	Glaslock interlocking	
steel utility	198	demolition	34, 264	jamb hinge.....	224	shingles	130
Flush mount ceiling		estimating, problems				Glass	
fixture.....	421-422	with	53			jalousie	169
Flush mount light fixture... 422		interior doors	206, 209			measure & cut.....	170

Glass block mortar mix 302	Guardrail demolition 30	Hardware bi-fold door 221	Hinged Shower door 349
Glass cutters 171	Gutters acid wash 446	door, patio 216	Hinges door 196
Glass felt ply 4 134	aluminum 146	garage door 224-225	cabinet 321
Glass globe ceiling fixture 422	flashing cement 135	pocket door 222	cabinet, Euro 320
Glazing bead 170	galvanized steel 146	screen door 203	garage door 224
Glazing compound 170	painting labor 456	Hardwood flooring demolition 311	solid brass 196
latex 170	patching material 135	molding, embossed 259	Hip and ridge shingles 130
Glazing points 170	remove and replace 106	molding, Victorian base 259	Hip shingles 131
Glazing putty remove and replace 170	roof caulk 136	paneling 251	Hold-down anchor 492
Glazing tool 171	vinyl 146	Hardwood doors 192	Hole cover faucet 328
Glidden 472-475	Gutting, demolition 31	fire-rated 192	Hollow core doors 207
Gloss polyurethane oil 475	Gypboard painting 463-464	prehung 197	Hollow metal doors 194
Gloss & seal, tile 304	Gypsum demolition 35	Hardwood flooring demolition 36	Homax 473
Gloss enamel alkyd 473	greenboard 71	maple 275	HomeLine circuit breaker 417
Gloss finish, log home 469	type X 71	molding 274, 276	indoor main lug load center 417
Glue Pergo laminate floor 279	Gypsum base Imperial 245	oak 274-275	HomeStyle 256
Grade beams concrete 49	Gypsum board DensArmor 243	removal 274	HomeStyle suspended ceiling 256
formwork 45	Gypsum lay-in ceiling panel 257	rosewood 275	Hood range 336-337
Granite aggregate concrete 47	Gypsum panel lift 250	sanding 277	range, quiet 336
countertop 319	Gypsum wallboard demolition 242	strip 274	range, vented 336
floor tile 295	fire code 243	TapTight 276	Hooks bathrobe 369
mortar mix 302	flexible 244	trim 277	Hopper gun ceiling finish 244
setting adhesive 302	installation 242, 244	Hardwood molding Bruce parquet 274	Hopper vinyl window 159
tile flooring 271	joint cement 246	Harris-Tarkett 274, 276-277	Hospital grade receptacle GFCI 415
tile, natural 295	joint tape 246	HazMat protection 518	Hot mix, spreading 52
vanity top 361	mold resistant 243	Headers carpentry 68	Hot water dispenser 329
Granules roofing 136	primer 246	Headroom kit 225	Hot water heating systems 372
Gravel stop 142	repair 242	Heart pine flooring trim 277	Hotmopping roofing 132
Gravity heating 371	spray texture 244	plank flooring 276	House wrap 88
Gray Board insulation 85	water resistant 243	Heat recovery ventilator retrofit 386	Hub bolt-on A type universal 418
Grecian cast molding 262	H	Heat-A-Lamp bulb heater & fan 365	watertight conduit 410
Greek key chair rail 262	Hammer drywall 250	Heat-A-Ventlite heater 366	Humidifier, central 377
Greenboard 71	Hampton Bay™ 421, 423-424	Heaters baseboard, electric 384	HVAC central air conditioning 377
Greenhouse panels 140	Hand sander drywall 250	Heat-A-Ventlite 366	cleaning 510
Greenwaste recycling 30	Handle sets double cylinder 202	water, gas 385	component removal 376
Greenwich kitchen sink 323	entry door 202	whirlpool bath 347	hydronic heating 378
Grilles door, patio 216	Handrail painting 461	Heating duct removal 376	hydronic heating system 378
Ground bar kit breaker box 420	patio deck 435	Heating system component removal 376	radiator, cast iron 378
QO load center 420	Handy box cover, blank 404	Heating systems electric space heaters 372	removal of components 376
Ground fault interrupter plug-on circuit breaker 420	drawn 404	hot water, radiant heating 372	restoration 92
Ground rod clamp 412	welded 404	Heating systems, warm air forced-air 371	Hydraulic door closers 217
Grounding bushing insulated metallic 410	Hanger bracket lavatory 353	gravity 371	Hydraulic jacks 62
Grout colorant 303	Hangers pocket door 222	Heating, hydronic 378	Hydronic heating 378
Saltito 303	Harbour Collection 285	Helmman spar urethane 468	Hydro-X Vacuum 511
sanded 303	Hardboard lap siding 112	Hemlock doors 212	Hygienist industrial 515
sealer 304	panel siding 111	Henry 133, 135-137, 254, 281-282, 286	I
tile 290	Hardboard doors 192, 207, 209	HEPA central air filtration retrofit 378	Ice dam shield 88
tile, non-sanded dry 303	fire-rated 197	HEPA vacuum 520	Illuminated incandescent slide dimmer 416
Grout mix concrete 47	Hardboard siding 100	Hevea parquet flooring 278	IMC conduit 409
Grouting concrete 51	Hardibacker 291	High boy threshold, oak 195	body 411
GRS conduit removal 409	Hardie 112	High early strength concrete 48	bushing 410
Guard window 167	Hardipanel 112	High time factors 446	coupling 409-410
	Hardiplank 112	High-gloss enamel 473	elbow 409
	Hardisoffit 112	High-gloss finish sealer 303	

hub	410	birch, flush	206-207	pocket door	222	polycast	323
nipple	411	cafe	209	Jameco	328	single bowl	321
service entrance elbow	412	fir	208	James Hardie	112, 291	stainless steel	321
strap	411	fire-rated	211	Jasco	470-471, 475	Kitchen sink basket	
Imperial		flush	209-210	J-bead		strainer	328-329
gypsum base	245	flush	207	metal	248	Spin-N-Lock	328
Incandescent ceiling		half louver	208	plastic	248	washer	329
fixture	422	hardboard	207	J-channel		Kitchens	
Incandescent slide		hardboard, colonist	207	thermoplastic	108	appliances	309
dimmer	416	hardboard, flush	206-207	vinyl	107	cabinets and counters	306
Indoor & outdoor cable		heater closet	210	Jeffrey Court	296	cabinets and counters,	
type NM-B Romex		hemlock, prehung	212	Jelly jar fixture	423	costs	307
sheathed	397-398	knotty alder	212	Job survey		cabinets and counters,	
Indoor main lug load		lauan	207	(scope of work)	11	custom-made	308
center	418	lauan, flush	206-207	Joint cement		cabinets and counters,	
Homeline	417	oak	208	lightweight	245	refinishing	307
Industrial hygienist	515	oak	212	Joint compound	246	design	305
Infiltration barrier	88	oak, flush	206	Joint repair		electrical service	
Infrared bulb heater &		pine	208, 212	concrete	493	checklist	310
fan	365	pine louver	212	Joint tape, drywall	246	remodeling checklist	309
Ingenium Flushing		prehung	211-212	Joints		work triangle	306
System	351	Interior flat paint	472	expansion	47	Klean-Strip	467
Innovations lavatory		Interior latex		Joists		Knob and tube wiring	391
faucet	357	eggshell	472	bridging	65	Knobs	
Inside corner bead		flat finish	472	ceiling	73	cabinet	320
metal	247	paint, semi-gloss	473	demolition	34	Knockdown ceiling	245
Inside corner molding		Interior paint	472	floor	64-65	Knockdown door	
polystyrene	264	Interior painting		TJI	65	frames	194
In-Sink-Erator	329, 332-333	labor	446	J-trim		Knockdown drywall	
Ins-X	476	Interior sanding		metal	248	texture	244
Installation kit		labor	446	Jubilee White Ice beaded		Knockdown stucco	473
floating floor	276	Interior trim		paneling	251	Knockers, door	213
Pergo	279	baseboard	238	junction box	404	Kohler	321-323,
Installation system		casing	238	Junior basket strainer	331	325-326, 351, 355, 358	
laminate flooring	280	molding	238			Kool Patch	
Insulated grounding		Interior wall assemblies	70			acrylic roof patching	
bushing, metallic	410	Interlocking shingles	130			cement	135
Insulating bushing		Intermatic	416			Kool Seal	135
high-impact		Intermediate metal				Kraft-faced	
thermoplastic	410	conduit	409			fiberglass roll insulation	84
Insulation		International					
blow-in cellulose	85	Thermocast	324, 331				
board	80, 85	In-wall spring wound					
board, demolition	35, 312	timer	416				
built-up roofing,		Island sink					
patch	131, 132	polycast	331				
ceiling	79						
FBX	86						
fiberglass	84-85						
fiberglass batt	84						
fiberglass, unfaced	84						
floor	80						
foam	85						
foundation	86						
masonry	87						
natural fiber	87						
polystyrene	85						
pouring	87						
R-Gard	86						
rockwool	86-87						
roof, perlite	86						
SAFB	87						
sill gasket	86						
sound control	86						
vapor barrier	81						
vermiculite	87						
wall	80						
Interior							
pressure wash	510						
Interior & exterior stain							
acrylic	467						
Interior acrylic latex paint	472						
Interior doors	212-213						

trim	451	Laminate shingles architectural.....	130	LB conduit body PVC, Type LB	401	HomeLine indoor main lug	417
painting exterior French door.....	451	Laminated plastic countertops.....	318-319	LDR Industries.....	328	indoor main lug.....	418
painting exterior louver door.....	451	Laminated plastic countertop	320	Lead flashing	143, 145	outdoor	419
painting exterior panel (entry) door	451	Lampholder & cover dual weatherproof	408	Leak Sentry toilet fill valve	351	Loading trucks	41
painting exterior plaster for stucco	460-461	Lantern		Leak Stopper rubberized roof patch ...	135	Locknut	
painting flush exterior door.....	451	curved glass wall.....	423	Leads		steel sealing conduit....	410
painting gutters & downspouts.....	456	motion sensing	423	roof penetrations	120	Locks	
painting gypsum drywall ceiling.....	464	outdoor wall.....	423	LED fixtures troffer	258	deadbolt.....	202
painting gypsum drywall walls	463	Lap		LED lighting system retrofit	424	door, folding	217
painting interior flush door.....	451-452	cement.....	133	Ledgers.....	73	garage door.....	225
painting interior French door	452	Lap siding		Leg set		installation	201
painting interior louver door	452	fiber cement	112	pedestal lavatory	352	patio door	216
painting interior panel door	452-453	hardboard.....	112	Lenape.....	300-301	sash	166
painting molding or trim ..	459	OSB.....	111	Let-in bracing.....	67	sliding window	171
painting roof overhang	459, 460	spruce.....	110	Let-in ribbons.....	73	window flip.....	171
painting shutters or blinds.....	461-462	textured	111	Leveler		Locksets	
painting smooth brick masonry	457	Lascoat.....	348	embossing	281	and deadbolt	202
painting tongue & groove ceiling.....	449-450	Latch		Lever locksets	202	colonial knob	202
painting windows ..	466-467	knob passage	213	Leviton	414-415	egg knob	202
painting wood deck or floor	455	Latchsets		Lexan XL-10	171	installation	201
painting wood paneled walls	465	privacy lever	213	L-flashing	143	keyed entry.....	201-202
pressure washing (waterblasting).....	448	privacy, egg knob.....	213	Lift sash.....	166	lever.....	202
repaint home exterior ..	446	Latex glazing compound ..	170	Light bar		Log cabin siding	110
repaint home interior ..	446	Latex paint		beveled	368	Log home gloss finish	469
sandblasting	447	eggshell.....	472	medicine cabinet ...	368-369	Log lap siding	110
sanding, exterior.....	447	enamel.....	472-473	Light fixture		Longstrip oak flooring.....	275
sanding, interior.....	446	exterior	474	ceiling	420	Louver	
staining fascia	453	flat finish, interior.....	472	chandelier.....	422	gable.....	90
staining picket fence.....	454	masonry & stucco.....	474	chrome bath bar.....	421	roof	145
staining rough wood siding.....	462	semi-gloss	473	drum, mushroom	421	roofing	145
staining tongue & groove ceiling.....	450	waterproofing.....	474	jelly jar	423	Louver doors	
staining wood deck or floor	455	Latex primer		mushroom flush mount.....	422	painting	451-452
staining wood paneled walls	465	PVA	471	outdoor bulkhead.....	423	Louver windows	163
wash down	447	resilient flooring	281	remove & replace	421	Louvered doors	212
waterblasting (pressure washing).....	448	Lauan doors	206-207, 210	wave bath	421	Louvered exterior window shutters.....	167
Lag screws		flush.....	192	Light kit		Louvered vents.....	90
drill tip suspension.....	255	Laundry faucet		mini can	420	Louvers	
Laminate flooring		two-handle.....	330	mini can recessed		midget.....	91
finishing putty	279	wall mount.....	330	eyeball.....	420	roof	91
glue.....	279	Laundry tub		recessed.....	420	wall	91
installation spacer	279	double bowl.....	330	recessed non-IC baffle.....	420	Low voltage wiring.....	394
installation system	280	overflow tube.....	330	slot aperture	420	Low-Boy toilet kit	351
molding	280	single bowl	329	Light-emitting diodes	424	Low-boy, trash disposal....	30
Pergo Presto	279	Utilatub	329	Lighting		Low-sound bath fan	
Pergo Presto molding...	279	utility kit	329	motion sensor.....	423	QuietTest.....	364
sealant.....	279	Lavatory		recessed	420	Low-voltage light kit.....	420
strip.....	280	Pedestal	352	Lighting fixtures		L-straps.....	492
TrafficMaster	280	Lavatory base.....	352	soffit, kitchen	312	L-trim	
trim	280	Lavatory faucet		Lighting panel		drywall	248
underlayment.....	279-280	adjustable center	358	acrylic	258	Lug load center	
		decorator	357	styrene.....	258	HomeLine indoor	417
		hands free	355	Lights		Lumber	
		hi-arc	357	suspended troffer fixture ..	258	alternative building materials.....	437
		single-handle.....	354-355	Lightweight concrete	47	deck.....	433-434
		single-handle, zinc	354	Linoleum, sheet		pressure treated	432
		two-handle	355-358	demolition	36	recycled plastic.....	437
		two-handle, acrylic	355	Liquid underlayment	281	Thompsonized.....	434
		two-lever.....	355	Liquid-tight flexible conduit		Luna ceiling panel	257
		Lavatory hanger bracket ..	353	Carflex	407		
		Lavatory leg set	352	Listello		M	
		Lavatory sink	353	tumbled marble tile.....	296	Magna.....	251
		drop-in	353	Litex	473	Magnetic weatherstrip	196
		removal.....	353	Lithonia Lighting	421	Magnolia Brick and Tile ..	296
		Lavatory trap		Load center		Mahogany doors.....	193
		remove & replace.....	346	combination ring type ...	417	Main circuit breaker.....	418
		Lay-in ceiling panel		flange kit.....	417	Main load center	
		gypsum.....	257	ground bar kit	420	combination	417

534 National Home Improvement Estimator

Main lug load center.....	419	lighted.....	367	Moisturbloc polyethylene	280	wall base.....	280
HomeLine indoor.....	417	mirrored.....	367	film.....	280	wall, suspended ceiling...	255
indoor.....	418	octagonal.....	367	Moisture barrier.....	280	Molding set	
Mallet, rubber.....	287	oval.....	367	Moisture-resistant drywall...	243	brick.....	260
Man-O-War marine spar		single door.....	367	Mold		Molding, crown.....	261
varnish.....	468	sliding door.....	367	abrading.....	517	Molding, hardwood.....	275
Maple plank flooring.....	276	swing door.....	367	blasting.....	517	rosewood.....	275
Maple hardwood		tri-view.....	368	containment structure...	516	Monticello lavatory	
flooring, solid.....	275	Medium density fiberboard		encapsulation.....	517	faucet.....	357
molding.....	275	molding.....	261	protective equipment...	518	Mop, roof.....	136
Maple strip flooring.....	277	Megatrade.....	293	removal.....	517	Mortar	
Marble		Melard.....	352	sampling.....	515	acrylic admix.....	303
countertop.....	360	Membrane		testing.....	515	bedding.....	302
floor tile.....	294	anti-fracture.....	301	Mold and mildew		bonding.....	301-302
listello tumbled tile.....	296	fiberglass reinforcing....	136	sanitizer.....	511	CustomBlend thin-set...	302
mortar mix.....	302	polyethylene.....	304	Mold inspection.....	515	epoxy.....	302
setting adhesive.....	302	tile, anti-fracture.....	301	Mold remediation.....	515	flexible bonding.....	302
threshold.....	296	Mesh		by job size.....	506	porcelain.....	302
tile.....	294	crack repair.....	248	cleaning methods.....	508	thin-set.....	302
tile flooring.....	271	Metal conduit		industrial hygienist.....	506	thin-set tile.....	289
Margin notch trowel.....	287	flexible.....	406	insurance coverage.....	505	tile.....	290
Marine varnish.....	468	galvanized.....	409	protocol.....	515	tile repair.....	302
Markup vs. margin.....	7	Metal corner bead ..	247, 249	sampling and protocol...	507	underwater tile repair...	303
Masco.....	356-357	Metal doors.....	194	Mold Retarder.....	92	Mortar mix	
Mask		bi-fold.....	220	Molded face closet		glass block.....	302
safety.....	250	Metal primer.....	476	doors.....	220	marble & granite.....	302
Masonite Corp.....	253	rust converting.....	476	Molding		Mosaic ceramic tile.....	300
Masonry		Metal screen doors.....	203	base.....	263	Motion sensor	
chimneys, repair.....	104	Metallic grounding bushing		base cap.....	260	security light.....	423
cleaning.....	115	insulated.....	410	base shoe.....	260	heavy-duty.....	423
demolition.....	31	Meter main load center ..	417	bead.....	260	lantern.....	423
fireplace demolition.....	115	Meter socket.....	417	brick.....	195	Moulding	
fireplaces.....	115	Metro sheet vinyl flooring...	283	casing.....	263	hardwood.....	259
fireplaces, repair.....	104	Microwave oven		cast.....	262	Mount Vernon paneling...	251
furring.....	72	Advantium.....	335	chair rail.....	260, 262	Mounting assembly	
insulation.....	87	over-the-range.....	335	chair rail paperwrap.....	264	disposal.....	333
joints.....	115	Midget louvers.....	91	chair rail prefinished....	264	Mounting bracket	
painting labor.....	456-458	Milban.....	511	crown.....	259	non-metallic low	
pointing.....	115	Milban 1-2-3.....	516	demolition.....	35	voltage.....	402
protective coating.....	475	Mildew resistant drywall...	243	embossed basswood ..	259	Mounting kit	
recycling.....	30	Mineral fiber ceiling		embossed decorative		sink.....	327
repointing.....	115	panel.....	257	hardwood.....	259	Mud	
veneer.....	103	Mineral siding.....	93	extruded polymer.....	263	joint cement.....	245
walls, waterproofing.....	130	asbestos cement.....	94	hardwood.....	259, 276	wallboard.....	246
Masonry & concrete		asbestos testing.....	94	hardwood floor.....	274	Mullions	
waterproof.....	475	Mineral surface roll		hardwood parquet.....	278	window.....	166
Masonry & stucco paint...	474	roofing.....	133	heart pine.....	277	Multi gang switch box.....	405
Masterchem.....	472, 474	Mini can recessed		inside corner.....	264	Mushroom light fixture...	422
Mastic		light kit.....	420	inside corner & cove			
tile.....	290	Miniature circuit breaker		paperwrap.....	264		
Material costs.....	11	QO.....	419	lamine flooring.....	280		
Mayfield sink.....	322	Minwax.....	467-469, 471	MDF colonial base.....	261		
Maytag.....	335	pickling stain.....	468	MDF ultralite crown.....	262		
MDF		Polycrylic.....	469	medium density			
casing.....	261	Polyshades.....	468	fiberboard.....	261		
chair rail.....	261	polyurethane.....	469	oak, unfinished.....	277		
paneling.....	251	spar urethane.....	468	outside corner.....	264		
MDF molding		Miracle Sealants Co.....	303	paperwrap.....	264		
base corner.....	261	Mirror bath light bar.....	421	polystyrene.....	264		
colonial base.....	261	Mirrored doors		painting labor.....	459		
plinth block.....	262	bi-fold.....	221	panel.....	253		
ultralite crown.....	262	bypass.....	218	paperwrap.....	263		
Mechanical systems		Mirrored sheet.....	171	polystyrene.....	263		
repairing earthquake		Mirrors		primed finger			
damage.....	491	frosted.....	366	joint base.....	260		
Medicine cabinet		oval.....	366	quarter round.....	261		
beveled edge.....	367-368	vanity.....	366	reversible flute & reed...	261		
bi-view.....	368	Mission tile roofing.....	139	rosette block.....	259		
etched glass.....	367	Miter bolt kit.....	320	round edge stop.....	261		
framed.....	367	Mobile home doors.....	222	stop.....	195		
framed door.....	366	Modified bitumen		stucco.....	196		
frameless.....	367-368	adhesive.....	133	T-astragal.....	194		
light bar.....	368-369	Moen.....	325, 354, 357-358	Victorian hardwood			
				base.....	259		
				vinyl tileboard.....	264		

N

Nail plate, stud.....	399
Nailer strip, carpentry.....	73
Nailers.....	73
Nailite siding.....	107
Nails	
drywall.....	249
vinyl siding.....	107
National Electrical Code	
(NEC).....	390
National Estimator Cloud....	8
Natural Images floor tile...	285
Natural stone floor tile.....	295
Needle beams.....	62
Negative air scrubber.....	519
Neptune.....	321
Neptune marble	
countertop.....	360
New wood treatment.....	470
Nipple	
rigid conduit.....	411

- NM-B Romex sheathed cable
 indoor & outdoor..... 398
 NM-B Romex sheathed
 indoor cable..... 397
 Non-fibered roof and
 foundation coating..... 129
 Non-metallic
 ceiling fan box..... 402
 conduit fitting..... 401
 low voltage device
 mounting bracket..... 402
 old work switch box..... 402
 reducer bushing..... 400
 sheathed cable..... 398
 standard coupling..... 401
 UF compression
 connector..... 399
 Non-metallic cable..... 397
 Non-metallic sheathed cable
 (Romex)..... 392
 Northwoods hardwood
 flooring..... 274
 Notched trowels..... 287
 NuTone..... 336, 362-366
 Nylon carpet..... 304
 Nylon paneling rivets..... 253
- O**
- Oak
 hardwood flooring..... 274
 molding, unfinished..... 277
 parquet flooring..... 278
 plank flooring..... 276
 strip flooring..... 274, 277
 Oak doors..... 192, 206, 210
 entry..... 194
 Oak fill strip..... 317
 Oak threshold..... 195
 OakCrest Products..... 278
 Octagon box
 drawn..... 405
 Octagonal windows..... 163
 Offset compression
 connector..... 404
 EMT-to-box..... 404
 Offset screw connector
 EMT..... 403
 Oil
 Danish..... 468
 oil fired furnace..... 377
 oil gloss
 polyurethane..... 475
 oil, teak..... 471
 oil, tung..... 471
 oil-based enamel..... 476
 oil-based floor finish
 Varathane..... 469
 oil-based primer sealer..... 473
 oil-fired water heater..... 385
 Old work switch box
 non-metallic..... 402
 Olefin carpet..... 304
 Opal glass wall light..... 421
 Open light kit..... 420
 Openers, garage door..... 225
 Opening,
 breakthrough wall..... 72
 Operators, window..... 166
 Orange peel
 ceiling..... 245
 drywall texture..... 244
- Oriental carpet
 hang dry..... 511
 Oriented strand board
 siding..... 111
 OSB
 roof sheathing..... 77
 shear wall..... 492
 sheathing..... 66, 70
 siding..... 111
 subfloor..... 66
 Outdoor ceiling fan..... 424
 Outdoor wall lantern..... 423
 Outlet box
 connecting appliance..... 397
 re-connect appliance..... 397
 Outside corner bead,
 drywall..... 248
 Outside corner
 molding..... 263-264
 colonial..... 264
 paperwrap..... 264
 polystyrene..... 264
 Outside corner trowel,
 drywall..... 250
 Oval light fixture
 outdoor bulkhead..... 423
 Oven
 double wall..... 335
 microwave..... 335
 microwave,
 above range..... 335
 wall..... 335
 Overhang
 painting..... 459-460
 Overhang painting,
 difficulty..... 460
 Overhead doors..... 223
 Owens Corning..... 130, 144
- P**
- Pad
 furniture..... 518
 Paint
 acrylic latex..... 472
 alkyd..... 473
 barn & fence..... 476
 ceiling..... 472
 elastomeric..... 474
 flat..... 472, 474
 floor & porch..... 475
 gloss..... 473
 house & trim..... 474
 interior..... 472
 latex..... 474
 latex ceiling..... 472
 latex interior..... 472
 masonry & stucco..... 474
 polyurethane oil gloss..... 475
 satin flat..... 474
 semi-gloss..... 473
 semi-gloss latex..... 473
 swimming pool..... 476
 texture..... 473
 wall & trim..... 472-473
 waterproofing..... 474
 Paint additive
 Perlite texturing..... 473
 Paint seal removal..... 156
 Paint stripping
 labor..... 447
- Painting
 burn off, manhours..... 446
 high-time difficulty
 factors..... 446
 Painting and finishing
 application methods..... 444
 exterior trim..... 443
 paint color and gloss..... 442
 penetrating stains..... 443
 recoating..... 441
 surface preparation..... 441
 wood preservatives..... 443
 Painting labor, manhours
 acid wash..... 446
 baseboard..... 448
 blinds..... 461-462
 bookcases..... 448
 brick masonry..... 457
 burn off paint..... 446
 cabinets..... 449
 caulking..... 446
 ceiling texture..... 449
 ceilings..... 449-450
 closet shelf and pole..... 450
 concrete floor..... 454-455
 concrete masonry
 units..... 457-458
 cutting-in..... 446
 door frame and trim..... 451
 drywall ceiling..... 464
 drywall walls..... 463
 eaves and cornices..... 460
 entry doors..... 451
 exterior doors..... 451
 French doors..... 451-452
 gutters and
 downspouts..... 456
 handrail..... 461
 house exterior..... 446
 house interior..... 446
 interior doors..... 451-453
 louver doors..... 451
 masking..... 446
 molding..... 459
 paneled walls..... 465
 plaster or stucco..... 460-461
 pressure washing..... 448
 roof overhang..... 459-460
 shutters..... 461-462
 siding..... 462
 stripping paint..... 447
 trim..... 459
 windows..... 466-467
 wood deck..... 455
 Paling, rail..... 435
 Pan
 shower..... 348
 Pancake box
 ceiling fan..... 405
 Panel molding
 FRP..... 253
 Panel siding..... 98
 cedar shingle..... 113
 fiber cement siding..... 112
 fiber-overlaid plywood..... 99
 hardboard..... 98, 111
 MDO..... 99
 OSB..... 111
 particleboard..... 98
 plywood..... 98, 111
 Panel wallcovering
 designer..... 252
- Panel, ceiling..... 253
 acoustical..... 256
 lay-in..... 257
 lighting..... 258
 suspended..... 255-257
 Panel, distribution
 disconnect & remove..... 417
 Panel, electric service..... 419
 Paneling
 beaded..... 251
 birch..... 252
 demolition..... 252
 fiberboard..... 251
 FRP..... 253
 hardboard..... 251
 hardwood..... 252
 hardwood plank..... 251-252
 MDF..... 251
 oak print..... 251
 pine plank..... 252-253
 plywood..... 251-253
 prefinished..... 252
 rivets..... 253
 tileboard..... 251-252
 trim pack..... 252-253
 wainscot..... 253
 Panelized shingles..... 113
 Panels
 fiberglass..... 140
 greenhouse..... 140
 sun..... 140
 Panic bar
 door..... 226
 Panic door hardware..... 226
 Pantry
 cabinet..... 315
 cabinets..... 316-317
 Pantry doors..... 212
 Paper
 Aquabar..... 87
 building..... 134
 Moistop..... 88
 Pyro-Kure..... 88
 roof flashing..... 88
 roof underlay..... 88
 Seekure..... 88
 vapor barrier..... 87
 Paper holder
 toilet tissue..... 300
 Paper-faced metal trim..... 247
 Paperwrap molding
 base..... 263
 casing..... 263
 chair rail..... 264
 inside corner & cove..... 264
 outside corner..... 264
 Parabolic troffer
 fluorescent fixture..... 258
 Parisa faucet..... 354
 Parks Corporation..... 469
 Parquet
 molding..... 278
 Parquet floor tile..... 278
 Parquet flooring
 Hevea..... 278
 oak..... 278
 oak, self-stick..... 278
 Partition walls
 adding..... 265
 removal..... 70
 Pass &
 Seymour/Legrand..... 415
 Passage latch, knob..... 213
 Paste wax..... 471

Patch		Pergo	279	Plaster of Paris	246	Points	
built-up roofing	131-132	finishing putty	279	Plastering		glazing	170
drywall	248	flooring	279	pool	440	Pole sander	251
Elastocaulk roof patch	136	flooring sealant	279	spa	440	Polish	
Elastomastic roof patch	136	flooring underlayment	279	Plastic		Boston	471
flashing	135	installation	279	conduit	400	Poly bags	518
Kool Patch cement	135	installation kit	279	gutters	146	Poly sheeting	516
PondPatch	136	laminate glue	279	lumber	437	Polyblend	
popcorn	245	Presto floor molding	279	siding	107	ceramic tile caulk	303
roof caulk	136	Presto laminate flooring	279	Plasticized concrete	48	Polycarbonate sheet	171
roof cement	135	Pergola patio cover	439	Plate		Polycast kitchen sink	323
roofing	134-135	Perimeter berm	510	service entrance conduit		Polycrylic	
roofing, cotton	136	Perimeter wall insulation	86	sill	412	protective finish	469
roofing, wood shingle	137	Perlite texturing paint		single gang Decora		Polyester	
underlayment	281-282	additive	473	wall	415	stress-block fabric	136
vinyl	281	Permanent Bond		single gang plastic		Polyester carpet	304
Wet Patch roof cement	135	Adhesive	133	wall	415	Polyethylene film	41, 87
Wet Stick roof cement	135	Perma-Shield	216	stud nail	399	moisture barrier	280
Patching		Pet doors	216	Plate cover, toilet base	351	Polyethylene membrane	
cement, roof	135	Pet doors, cat	216	Plate straps	493	Schluter Ditra	304
concrete	51	Phone wall plate	413	Plate, splash	337	Polymer molding	263
Patio cover		Picket fence		Plates		Polyshades polyurethane	
aluminum, embossed	439	staining labor	454	carpentry	64	stain	468
aluminum, standard	439	Pickling stain		carpentry piecework		Polystyrene casing	
Patio doors	214-215	white wash	468	rates	67	reversible	264
aluminum	214-215	Picture windows	162	Platinum lavatory faucet	357	Polystyrene insulation	85-86
aluminum, double	214	Pier, concrete	63	Plexiglas	171	Polystyrene molding	
fiberglass, swinging	215	Pine		Plinth	435	base	263
gliding, vinyl	214	door casing	195	Plinth block	259	outside corner	264
grille	216	door casing, fluted	195	MDF primed	262	Polyurethane	
handles	216	flooring trim	277	Plug		fast-drying	469
hardware	216	plank flooring	276	connecting appliance	397	oil gloss	475
hinged, vinyl-clad	214	screen doors	203	Plug-on circuit breaker		stain	468
installation	214	siding	108-110	ground fault interrupter	420	Polyurethane cast	
jamb extension kit	216	Pine doors	208	Plumb bob	287	molding	262
locks	216	Pine jamb sets	209	Plumb Shop	329, 334	chair rail	262
roller	216	Pine planking	252-253	Plumbing and HVAC		corner block	262
screen	216	Pine square rosette		bath tub framing	375	cross head	262
screen & track	216	molding	259	framing for		frieze	262
swinging, double	214	Pipe		improvements	374	rope	262
threshold	216	ABS	388	repairs, cutting		PondPatch	136
vinyl	215	ABS replacement of		floor joists	374	Pool paint	476
Patio roof	435	cast iron	388	repairs, pricing	374	Pool replastering	440
Patio screens		copper replacement of	388	repairs, utility walls	375	Popcorn ceiling	
replacement	216	copper replacement of		Plumbing drain, waste and		patch	245
Pavement		galvanized	388	vent lines	373	spray	244
concrete	47, 50	PVC DWV	388	Plumbing systems		spray texture	244
demolition	33	PVC replacement of		repairing earthquake		Porcelain	
Paver tile	295	cast iron	388	damage	491	bath accessory set	301
brick	296	Pipe flashing	143, 145	Plumbing vent	370	mortar	302
Paving		tile roof	145	relocate	370	towel bar	301
asphalt	52	Pitch pan	129	Plus 10 Exterior Stain	467	Porcelain, glazed	
concrete	47, 50	Pitch pocket	129	Ply 4 glass felt	134	floor tile	292
demolition	33	Pits, excavation	41	Plywood		Porch	
Paving breaker		Place n Press floor tile	285	roof sheathing	77	columns	435
rental	29	Plain end 45-degree		sheathing	66, 70	columns, aluminum	435
Pea gravel		elbow	401	siding	111	demolition	432
concrete	47	Planing concrete	493	siding, T 1-11	111	enclosure screen	438
Pedestal lavatory		Plank floor clamp	277	subfloor	66	misting system	438
combo	352	Plank flooring		Plywood cap molding	263	repair	432
leg set	352	bamboo	276	Plywood siding	99	roof framing	435
removal	353	heart pine	276	pre-finished	99	screen frame	438
Pedestal Sink		rustic oak	276	Pneumatic breaker		support posts	435
Top	353	wood	276	rental	29	Porch & floor enamel	475
Peel & Patch		Plank paneling	252-253	Pocket doors		Porches	
waterproofing	135	beaded	252	edge pull	222	additions	426
Peep sights	214	Edge-V	252	hangers	222	balustrades	428
Pellets		Plaster		hardware	222	columns and posts	427
dry ice	517	demolition	35, 242, 312	jamb	222	elevated decks	428
Penetrating stains	443	demolition, wet	513	kit, converging	222	Porches and decks	
Penetrating wood finish		painting	460-461	Pointing trowel	287	choices in floor plank	430
Preserva-Wood	467	repair	494	Pointing, masonry	115	inspecting for decay	425
		veneer	246			maintenance	431

Portland cement stucco..... 114	base cap..... 260	PVC pipe..... 388	RCA..... 413
Post	base shoe..... 260	DWV..... 388	Ready-mix concrete..... 47
base, plinth..... 435	bead..... 260	PVC service	Rebar..... 45
Posts	brick..... 260	entrance cap..... 402	Rebond..... 304
basement..... 63	chair rail..... 260	Pyro-Kure paper..... 88	Receptacle
cap..... 436-437	crown..... 261		appliance flush mount... 415
carpentry..... 63	flute and reed..... 261	Q	CO/ALR duplex..... 415
deck..... 432-433, 436	quarter round..... 261	QO circuit breaker	duplex..... 415
jack posts..... 63	Primed tilt double-hung	GFI plug-on..... 420	duplex straight blade... 414
porch..... 432, 435	windows..... 163	main..... 418	GFCI..... 415
wood..... 435	Primer	miniature..... 419	GFCI, hospital grade... 415
Pouring	adhesive..... 278	tandem..... 419	remove..... 414
insulation..... 87	bonding..... 473	QO load center ground	side-wired single..... 415
Power attic gable vents..... 92	clean metal..... 476	bar kit..... 420	Receptacle cover
Power distribution box..... 520	concrete..... 473	QO main lug load	GFCI, wet location..... 408
Power massage	epoxy..... 476	center..... 418-419	horizontal duplex
shower head..... 350	flooring..... 281	Quarry tile..... 295	weatherproof..... 408
Power vent	gypsum wallboard..... 246	Quarrybasics..... 295	Recessed light kit..... 420
gas water heater..... 387	latex..... 471	Quarter round	Recessed lighting..... 420
Power ventilators	metal..... 476	bamboo..... 276	Recoating..... 441
attic gable..... 92	resilient flooring..... 281	floor molding.. 274-276, 280	Rectangular weatherproof
roof-mount..... 92	rusty metal..... 476	molding..... 263	box..... 407
Power washing..... 448	water-based..... 472	primed finger joint..... 261	Recycler fees..... 30
PowerStar..... 387	Primer sealer..... 474	Quick Roof..... 135	Red cedar
PowerStream..... 387	oil-based..... 473	QuickBooks..... 10	western, siding..... 108
Power-vent	stainblocker..... 474	QuietTest bath fan..... 364	Red Dot..... 407-408
water heater..... 385	Privacy latchset,	Quietzone..... 86	Red oak
PPE..... 518	egg knob..... 213	Quik-Tape..... 248	plank flooring..... 276
Pre-drying..... 509	Pro Finisher..... 469	Quik-Gard..... 420	strip flooring..... 274, 277
Prefinished molding	Propane water heater..... 385		Red rosin sheathing..... 87
chair rail..... 264	Propane-fired water	R	RedGard waterproofing
Prefinished paneling..... 252	heater..... 385	RACO..... 404-406	membrane..... 301
Prehung doors..... 209-211	Protection	RADAR Illusion	Reducer
double..... 212	tile edge..... 299	ceiling panel..... 257	bamboo..... 276
exterior..... 198	Protector..... 470	Radiant heating systems... 372	carpet..... 280
fire-rated..... 197, 211	ProtectoWrap..... 303	Radiator	floor molding..... 274-275
French..... 212-213	Protocol	cast iron..... 378	laminate flooring..... 280
hardboard..... 197	mold remediation..... 515	Rafter	Reducer floor
heater closet..... 210	Provisa range hood..... 336	bay vent channel..... 88	molding..... 275-276
installation..... 197	P-trap	spacing..... 88	Reducer strip
interior..... 212	remove & replace..... 346	Rafters	tile..... 300
oak..... 212	Pull bar..... 277	demolition..... 34	vinyl flooring..... 288
pantry..... 212	Pull plates, door..... 213	rough carpentry..... 75	Reducing
patio, steel..... 215	Pulling elbow, 90-degree... 403	Ragione..... 292	window opening size.... 156
steel..... 199-200	Pulls	Rail	Reducing bushing
steel, exterior, with	Drawer..... 320	deck..... 436	non-metallic..... 400
mini-blind..... 198	edge, pocket door..... 222	painting..... 461	rigid or IMC..... 410
steel, half lite..... 198	Pump	sink..... 298	Redwood
steel, installation..... 197	water..... 520		siding..... 109
Prelude..... 255	Pump mix concrete..... 47	Rail molding	vents..... 90
Premium Plus..... 475	Pumps	paperwrap..... 264	Reed & flute molding..... 261
interior flat paint..... 472	sewer..... 370	prefinished chair..... 264	Refinishing in-ground
primer sealer..... 473	Purlins	Railing	spa..... 440
satin flat exterior paint... 474	carpentry..... 76	patio deck..... 435	Reinforcing
Preserva products..... 467	Push bar	Rain cap, chimney..... 380	bars..... 45
Preservative	door..... 226	Rain gutters..... 146	membrane, fiberglass... 136
dock & fence post..... 470	Push plates, door..... 213	aluminum..... 146	slab..... 48
wood..... 470-471	Pushbutton	galvanized steel..... 146	steel..... 45
Preserva-Wood penetrating	garage door..... 225	Ranch casing..... 195	steel, galvanized..... 46
finish..... 467	Putty	Clearwood PS..... 263	Remediation
Pressure wash	finishing..... 279	primed finger joint..... 260	dry rot..... 92
interior..... 510	PVA latex primer..... 471	Ranch door casing	mold..... 515
Pressure washer..... 520	PVC	primed finger joint..... 195	Removal
Pressure washing	faucet supply..... 358	Random textured ceiling	Appliance..... 510
manhours..... 448	PVC conduit	panel..... 255	Carpet..... 511
Price Pfister..... 325-326, 330,	coupling..... 401	Range hood..... 336	Fixture..... 510
..... 354-355, 357	elbow..... 401	Ballista..... 336	glazing putty..... 170
Primed finger joint casing	Schedule 40..... 400	custom..... 337	skylight..... 172
colonial..... 260	Schedule 80..... 400	Provisa..... 336	window..... 156
ranch..... 260	PVC conduit body..... 401	vented..... 336	window glass..... 170
Primed finger joint molding	PVC conduit clamp		windows..... 156
base..... 260	Snap Strap..... 400		

Remover		Ring type meter socket ...	417	Roof cement	135	sheets	138
adhesive	278	Rings		wet patch	135	shingle remover	136
flooring adhesive	281	towel	369	Wet-Stick	135	shingle starter strip	131
Rental		Rivets	255	Roof coating		shingles,	
air mover	519	paneling	253	acrylic	137	algae-resistant	130
dehumidifiers	518	Robe hook	369	aluminum	137	shingles, architectural ...	131
dry ice blaster	517	Roberts	278	elastomeric	137	shingles,	
floor drying system	519	Rock		fibered	137	asphalt fiberglass... 130-131	
generator	520	recycling	30	silicone	137	shingles, hip and ridge... 131	
gypsum panel lift	250	Rocker switch		Snow Roof	137	slate	139
negative air scrubber... 519		Decora AC quiet	414	Roof covers	164	tar	132
remediation equipment . 518		Rockwool insulation	87	Roof deck		tear-off	129
wall cavity dryer	519	Rod clamp		removal	129	tile	140
Repainting a home	446	ground	412	repair	129	tile, clay	139
Repair		Roll		walking	140	tools	136
shingles, tin	144	screen	168	Roof edge flashing ... 143-144		Roofing cement	133
Repair clips, drywall	249	Roll flashing		Roof exhaust vent		built-up	133
Repair kit		aluminum	141	T-top	145	Roofing fabric	
drywall	248	copper	141	Roof flashing		asphalt	131
toilet	352	Roll roofing	134	chimney	380-381	Roofing louver	
Repair mesh		mineral surface	133	service entrance	412	galvanized	145
crack	248	Roll valley		Roof framing	75	Roofing material	
Repair patch, drywall	248	flashing	143	jacking	75	built-up	127
Repairs		Roller		Roof jack	145	modified bitumen	
door	191	extendable	287	rubber	145	(APP and SBS)	127
Replace-A-Vent	89	painting labor	448	Roof loading	140	new roof	122
Replacement screen		Roller spline tool	168	Roof openings		shingles, asphalt-	
doors	203	Rollers		cut for skylights	172	fiberglass (composition) ... 124	
Replacement windows		door, patio	216	Roof overhang		shingles, wood	123
vinyl	157	Roll-on		adding	61	Roofing materials, life	
vinyl double-hung	157	texture, acoustic	473	painting	459-460	expectancy	121
vinyl single-hung	158	texture, stucco	473	Roof patch		Roof-mount	
Replastering		Rollup doors		cotton	136	power ventilator	92
pool	440	garage	223	rubberized	135	Roofs	
spa	440	Roman tub		Roof patching cement		flashing leaks	118
Resilient flooring		filler	347	white	135	how to measure	
sheet vinyl	270	Romex	392	Roof repair	58	roof area	128
Resilient tile		Romex sheathed cable		Roof sheathing	60	repairs	121
adhesive	286	indoor	397-398	Roof turbine vent	146	source of leaks	117
demolition	36	indoor & outdoor	398	Roof turbine vents	91	Roof-to-wall flashing	144
removal	274	Roof		Roof vent		Rope cast molding	262
Resin siding	107	bay window	164	repair, waterproofing ... 130		Rope crown cast molding ... 262	
Respirator	518	bow window	164	waterproofing	130	Roppe	288-289
sanding drywall	250	built-up	132	Roof vent kit		Rosette molding	259
Retaining wall forms	48	cant strips	86	bath	366	square	259
Reversible doors	194	deck	435	Roof ventilation	83	Rosette set	195
Reversible flute & reed		demolition	34	Roof waterproofing	135	Rosewood	
molding		flashing	88	repair	129	flooring trim	275
primed finger joint	261	flashing, removal	134	replace	130	hardwood flooring	275
Reversible polystyrene		flashing, self-adhesive.. 134		Roofing		Roto hammer	
casing	264	insulation	86	asphalt	132	rental	29
R-Gard insulation	86	louver	91, 145	base sheet	133	Rough carpentry	53
RhinoBoard	291	membrane	132	broom with scraper	136	backing and nailers	73
Ribbands	73	patch	135	built-up	132, 134	bracing	67
Ribbons, carpentry	73	patch, shingle	137	built-up, patch	131-132	ceiling joists	73
Ridge and hip shingles... 130		patio	435	built-up, tear-off	129	ceilings and joists	73
Ridge shingles	131	patio cover	439	cement trowel	136	collar beams	75
Ridge vent	144	sagging ridge board	59	clay tile	139	collar ties	75
aluminum	90	sheathing, OSB	70, 77	concrete tile	140	curbs	75
Cobra Rigid	145	sheathing, plywood	77	demolition	34	dormer studs	75
coil	90	silicone coating	141	felt	133	floor joists	64
rigid	145	tile, clay	139	fiber-cement slate	139	floor trusses	65
shingle-over	145	tile, concrete	140	fiberglass panels	140	furring	72
VentSure	144	trusses	76	flashing, removal	134	girders	62
Rigid conduit		trusses, repair	76	flashing, self-adhesive ... 134		joists	68
coupling	409	trusses, rough carpentry... 76		galvanized	138	ledger strips	73
strap	411	underlay	88	granules	136	plates	67
Rigid insulation	85	urethane spray foam ... 140		gravel	132	posts	63
Rigid steel conduit		Roof and foundation coating		membrane	132	purlins	76
elbow	409	non-fibered	129	mop	136	rafters	75
galvanized	409	Roof apron	143	patch	135	ribbons	73
installation	409	Roof caulk	136	roll	133-134	roof trusses	76
removal	409			sheet metal	138	sill plates	64

- studding..... 66-67
 subflooring..... 66
 trimmers..... 75
 wall openings..... 72
 wall studs..... 66
 window openings..... 72
 Round conduit box
 non-metallic..... 408
 Round edge stop
 molding..... 261
 Royal Mouldings..... 264
 Royelle vinyl sheet
 flooring..... 283
 Rub, carborundum..... 51
 Rubber
 mallet..... 287
 roof jack..... 145
 wall base..... 288
 wet patch roof cement... 135
 Rubber studded tile..... 286
 Rubber tile adhesive..... 286
 Rubberized
 roof patch..... 135
 Rust resistant finish..... 476
 Rustic oak plank flooring... 276
 Rustic siding
 pine..... 108, 110
 Rust-Oleum..... 468-469, 476
- S**
- Sack finish..... 51
 Saddle & sill..... 296
 Safety
 respirator mask..... 250
 Safety Zone vinyl floor
 tile..... 285
 Sahara ceiling panels..... 256
 Saltillo
 ceramic floor tile..... 295
 grout mix..... 303
 Salvage, demolition..... 36
 Sampling
 mold..... 515
 San Marino ceiling fan..... 424
 Sand
 fill..... 41, 50
 Sand & Kleen..... 251
 Sandblasting
 manhours..... 447
 masonry..... 115
 Sanded grout..... 303
 Sander
 drywall..... 250
 gypsum wallboard..... 251
 Sanding
 hardwood floor..... 277
 Sanding sealer
 waterborne..... 469
 Sanding sponge..... 250
 Sanding system
 drywall..... 251
 dustless..... 251
 Sanding, paint prep
 manhours..... 446-447
 Sand-Texture wall texture... 473
 Sash
 balance..... 166
 cord repair..... 156
 lift..... 166
 locks..... 166
 springs, wood window... 166
 window, repair..... 156
- Saturated cotton roof patch
 asphalt..... 136
 Savannah lavatory faucet... 357
 Sawing
 concrete slab..... 51
 SBS field adhesive..... 134
 ScapeWel window..... 172
 Schedule 40 PVC
 conduit..... 400
 Schedule 80 PVC
 conduit..... 400
 Schluter Ditra polyethylene
 membrane..... 304
 Schluter Systems.....
 299-300, 304
 Scotchgard..... 512
 Scratch coat, plaster..... 114
 Screed
 rental..... 40
 Screen
 aluminum rolls..... 168
 fiberglass rolls..... 168
 frame kit..... 167
 patch..... 168
 porch enclosure..... 438
 spline..... 168, 439
 window..... 168
 Screen doors
 hardware..... 203
 installation..... 202-203
 metal..... 203
 pine..... 203
 replacement..... 203
 security, steel..... 203
 steel, replacement..... 203
 vinyl..... 203
 wood..... 203
 Screen frame..... 438
 Screen vents..... 89
 Screen wire..... 438
 Screens
 patio door..... 216
 window..... 160
 Screw gun, drywall..... 249
 Screwdriver, drywall..... 249
 Screwdriver bit, drywall... 250
 Screw-in connector, flex... 406
 Screws
 deck..... 439
 drywall..... 249
 drywall to steel..... 249
 drywall to wood..... 249
 lag, drill tip..... 255
 self-tapping..... 141
 Screws & clips,
 sink mount..... 322
 Scribing felt..... 287
 Scrubber
 negative air..... 519
 Seal
 garage door..... 223
 Seal & tile gloss..... 304
 Sealant
 laminated flooring..... 279
 Sealer
 concrete..... 475
 exposed aggregate..... 475
 grout..... 304
 high-gloss finish..... 303
 oil-based..... 473
 painting..... 463-464
 primer..... 473
 sanding..... 469
- sill..... 86
 tile..... 304
 tile & stone..... 303
 water-based..... 472
 waterproofing..... 475
 Sealer primer
 stainblocker..... 474
 water-base..... 474
 Sealer's Choice 15 Gold... 303
 Sealing conduit locknut
 steel..... 410
 Seal-Krete..... 475
 Seam coating kit..... 287
 Seats
 toilet, plastic..... 352
 toilet, wood..... 352
 SEBS styrene-ethylene-
 butylene-styrene
 asphalt..... 135
 Security doors..... 205
 heavy-duty..... 205
 Security doors,
 Paradise-style..... 205
 Security gates, folding..... 205
 Security light
 motion sensor..... 423
 Security storm doors..... 205
 Seekure paper..... 88
 Seismic safety standards,
 earthquakes..... 477
 Self-stick
 parquet flooring, oak.... 278
 vinyl wall base..... 289
 wall base..... 289
 Self-storing storm doors... 204
 Self-tapping screws..... 141
 Semco..... 301
 Semi-gloss
 latex paint..... 473
 wall enamel..... 472
 Senco..... 249
 SensAire wall control
 switch..... 366
 Sentinel Products..... 281
 Sentinel sheet vinyl
 flooring..... 283
 Septic disposal cartridge... 333
 Sequentia..... 253
 Service entrance
 cap..... 412
 cap, PVC..... 402
 device, combination..... 418
 elbow..... 412
 meter main load center... 417
 roof flashing..... 412
 Service entrance conduit
 sill plate..... 412
 Service panel
 electric..... 419
 Set screw connector
 EMT..... 403
 Setting adhesive
 marble & granite stone... 302
 Shake felt..... 137
 Shakertown siding..... 113
 Shakes
 cedar..... 137
 siding, replacement..... 105
 Shank nut
 sink strainer..... 329
 Shaping slopes..... 42
 Shaw HardSurfaces..... 280
 Shear wall..... 492
- Sheathed cable
 indoor..... 398
 indoor & outdoor
 Romex..... 398
 Type NM-B Romex... 397-398
 Sheathing
 board..... 66, 70
 carpentry..... 66
 demolition..... 35
 insulated..... 85
 plywood..... 70, 77
 roof..... 70, 77
 T 1-11..... 111
 Sheathing paper..... 87
 Sheet
 acrylic..... 171
 mirrored..... 171
 Plexiglas..... 171
 Sheet flooring
 adhesive..... 286
 removal..... 274
 vinyl..... 282-283
 Sheet metal
 gutters, downspouts..... 146
 roofing..... 138
 Sheetrock
 ceiling panel..... 257
 demolition..... 242
 fire code..... 243
 flexible..... 244
 installation..... 242, 244
 painting..... 463-464
 repair..... 242
 water resistant..... 243
 Sheets, roofing..... 138
 Shelf
 bath, with glass..... 369
 corner..... 300
 painting..... 448
 Shellac
 amber..... 470
 ShellGard RTU..... 92
 Shelves
 painting labor..... 448
 Sherwin-Williams..... 470
 Shield, ice & water..... 88
 Shim shingles..... 138
 Shims
 flooring..... 62
 stud..... 67
 Shingle
 flashing..... 144
 Shingle and shake siding... 100
 furring, estimating..... 100
 Shingle panels..... 113
 Shingle siding..... 113
 cedar..... 113
 Shingle starter strip..... 131
 Shingles
 algae-resistant..... 130
 architectural..... 131
 asphalt..... 130
 asphalt, repair..... 130
 cedar..... 138
 demolition..... 34
 fiberglass asphalt..... 131
 hip and ridge..... 131
 interlocking..... 130
 laminated..... 130
 paneled..... 113
 roofing..... 130
 siding..... 113
 siding, replacement..... 105

slate.....	139	T 1-11 plywood.....	111	entertainment	331	Soffits	
tin repair	144	thermoplastic	107	kitchen	322-324	aluminum.....	114
wood	137	touch up paint.....	108	kitchen, basket strainer...	328	demolition	35
wood, repair	137	trim	114	mounting clips	322	fiber cement	112
ShockWave	516	vinyl	96, 107	polycast	323	kitchen	312
Shower		western red cedar	108	Silhouette polycast	323	pendent lighting	312
stall kit	348	wood	93	single bowl	321, 323	refrigerator,	
stall kit, add-on.....	350	wood, diagonal	97	stainless steel.....	321-322	under counter.....	312
Shower & bathtub units...	348	wood, horizontal	97	stainless steel kitchen...	321	removal.....	106
Shower & tub faucet		wood, vertical	97	stainless steel single		stucco	114
single control	349	Siding & deck stain.....	467	bowl	321	vinyl	108
Shower curtain rod,		Siding and roofing		utility	330	Soil compaction	42
permanent	370	metal.....	247	Skid steer loaders		Solar lens	172
Shower door		Siding installation		rental	40	Solid core doors	
fixed	349	removing old siding	95	Skimcoat patch &		birch exterior	192, 197
hinged.....	349	Siding,		underlayment.....	282	entry	193
pivot.....	349	estimating procedure.....	104	Skylight removal	172	fir entry	193
sliding	349	Signature kitchen faucet...	325	Skylights		hardboard exterior... 192, 197	
swinging	349	SilentStep	279	acrylic	173	hardboard interior	207
Shower faucet	349-350	Silestone countertop.....	319	cut roof opening	172	hardwood exterior	192
Shower head		Silhouette polycast kitchen		fixed	172-173	luan exterior	192
power massage.....	350	sink	323	trimmers	75	prehung exterior	197
remove & replace	346	Silicone		tubular	172	red oak	192
sunflower	350	roof coating	141	venting	173	red oak exterior	192
Shower pan	348	Silicone roof coating.....	137	Slab doors... 192-194, 206-207		Solid surface countertop ... 318	
Shower stall		Silicone sealant		installation	191	Solitaire bath fan	365
demolition	348	window caulk	157	Slab leveling	493	Sound baffle, removable ... 333	
Showers.....	348	Siliconized roof coat	137	Slabs		Sound control	86
Shutters		Siliconizer		base	50	Soundbloc foam	
painting.....	461-462	crack filler	136	calculating area	43	underlayment.....	279
remove and replace	106	Sill		concrete	47	Southern yellow pine	
window	167	door, thermal	195	finishes	50	siding	109-110
Sidelites, steel door	198	window	165	forms	44	Spa replastering	440
Sidewalk, demolition.....	32	window, ceramic.....	297	garage	43	Spacer, laminate flooring ... 279	
Sidewalks, concrete	47, 50	Sill & saddle.....	296	on grade	50	Spacing, rafter	88
Side-wired receptacle,		Sill plate		repair	37	Spanish tile roofing.....	139
single	415	service entrance		Slate		Spar urethane	
Siding.....	107, 112	conduit.....	412	floor tile, natural.....	295	Helmsman	468
accessories, mounting... 107		Sill plate gasket.....	86	roofing	139	Spar varnish, marine	468
aluminum.....	93, 114	Sill plates	64	tile, tumbled	296	Spatter ceiling.....	245
aluminum corrugated ... 113		Sill removal.....	63	Sleepers, carpentry	73	Spatter drywall texture.....	244
cedar	108	Sill sealer	86	Slide dimmer		Speaker wire	413
cedar T&G.....	109	Single bowl kitchen sink		illuminated	416	Speed-Wall	
corrugated	113	stainless steel.....	321	incandescent	416	interior latex enamel..... 473	
demolition	35	Single gang wall plate	415	Sliding		PVA latex primer	471
fiber cement	112	Single receptacle		shower door	349	Spider box	
fiber cement shingles ... 113		side-wired	415	Sliding windows.....	161-162	electric.....	520
hardboard	100	Single-hung		Sloan Royal flush valve... 351		Spin-N-Lock sink strainer... 328	
hardboard lap	112	windows.....	158, 160-161	Slopes, shaping.....	42	Splash plate.....	337
hardboard panel	111	Single-texture drywall		Slot aperture light kit	420	Spline	
lap	110	brush	250	Smart home electrical		screen, porch	439
log cabin	110	Sink		management system..... 424		tool.....	168
mineral	93-94	bathroom	353	Smoke alarm,		window screen	168
mounting block, fixture... 107		frame	327	dual sensing	416	Split system, remove	378
Nailite	107	hardware	322	Smoke and CO Alarm	416	Sponge	
OSB	111	lavatory.....	353	Smoke detector	396	sanding, drywall	250
painting.....	462	mounting kit.....	327	basic	416	Spray adhesive.....	249
panel	98	removal.....	311	dual sensing	416	Spray painting	
paneled shingles.....	113	strainer shank nut.....	329	dual-ionization	416	labor	448
pine	108	undermount	353	Snap Strap PVC conduit		Spray texture	244-246
pine rustic.....	108, 110	wall-mount.....	353	clamp	400	ceiling	244
pine shiplap	110	Sink rail, ceramic.....	298	Soap dish		wallboard	244
plywood	99, 111	Sink trap		ceramic.....	300	Spreading soil.....	42
redwood	109	remove & replace	346	porcelain.....	301	Spring wound timer	
removal.....	106	Sinks		Soap dispenser	328	in-wall	416
repair	105	bar	330-331	Soffit		Springs	
resin	107	bowl	330	painting.....	459-460	garage door.....	223
shingle	113	Breckenridge	324	wood	73	garage, extension.....	225
shingle and shake	100	Cambridge.....	324	Soffit vents		window sash.....	166
shingles, replacement... 105		cast iron	322-323	louvered.....	89	Spruce	
southern yellow		composite	323-324, 331			lap siding	110
pine	109-110	double bowl	321, 323				
staining	462	double bowl composite... 324					

Square box	Stilts, drywall	250	Strips	Suspended ceiling panel	256
surface cover	Stone		asphalt roofing starter	Suspended ceiling	
welded	base	50	cant	systems	255
Square D	cleaning	115	shingle starter	Suspended ceilings	237
Square rosette molding	countertops	319	Structoglas	Sweep, door	196
Squeeze connector, flex	floor tile	295	Stucco	Swimming pool paint	476
Stain	roofing	139	knockdown	refinishing	440
acrylic interior &	sealer	303	molding, redwood	Switch	
exterior	setting adhesive	302	paint	AC quiet toggle	414
concrete	slate	139	painting	Decora AC quiet rocker	414
deck	tile, travertine	294	plastering	remove	414
deck & siding	tile, tumbled	296	portland cement	sink top	333
Deck Plus	Stonit	139	removal	Switch & cover	408
exterior	Stop fixture supply	351	repair	Switch box	
gel	Stop gravel	142	soffit vents	drawn 2-device	405
Plus 10	Stop molding	195	texture	multi gang	405
polyurethane	round edge	261	wall assembly,	non-metallic old work	402
siding	Stopper, drain	329	wood framed	Switches	
white wash	Stops Rust	476	Stud sensor	fan control	366
wood	Storage		electronic	timer, exhaust fan	366
Stainblocker	off site	518	Stud straightening		
primer sealer	Storage cabinet		Stud wall		
water-based	bath	367	demolition		
Staining labor, manhours	etched glass	367	Studding		
ceiling	Store-in-Door	204	Studs		
fascia	Storm collar		carpentry piecework		
paneled walls	chimney	380-381	rates		
picket fence	Storm doors	204-205	dormer		
siding	aluminum	205	straps		
wood deck	full-view	205	wall assemblies		
Stainless steel sink	removal	204	Stump grinder		
double bowl	security	205	rental		
single bowl	self-storing	204	Stump grinding		
Stair nose	triple-track	204	Stylistik II floor tile		
bamboo	woodcore	205	Styrene suspended lighting		
molding	Storm windows	149, 165	panel		
Stair stringers, basement	remove and replace	106	Styrene-ethylene-butylene-		
Stairs	StormGuard	88	styrene		
basement	Straight blade receptacle		asphalt		
deck	duplex	414	Subfloor		
demolition	Straightening		board sheathing		
porch	framing	494	OSB		
stringers	Strainer		plywood		
Stall kit, shower	junior basket	331	Subflooring		
add-on	sink shank nut	329	installation		
Stamped concrete	Strainer, basin		piecework rates		
Stanadyne	remove & replace	346	Sump pump		
Standard coupling	Strap		Sundial vinyl sheet		
non-metallic	EMT	404	flooring		
Standard radius elbow	rigid conduit	411	Sunflower shower head		
Starter strip	Straps		Supply lines		
Starter strip,	framing	492	supply lines, toilet		
aluminum siding	hardware	493	Supply stop		
Steam cleaning, masonry	T	493	Surface box cover,		
Steel conduit	tie	493	square		
elbow	Stress-block fabric		Surface preparation		
elbow, rigid or IMC	polyester	136	flooring		
galvanized rigid	Stretch wrap	518	labor		
Steel doors	Stringers		manhours		
entry	deck stair	438	Surface preparation for		
exterior	Strip		painting or finishing		
exterior, with mini-blind	transition	288	Surround kit		
frames	Strip flooring		bathtub		
garage	laminate	280	tub wall		
installation	maple, unfinished	277	Suspended ceiling		
screen	natural wood	275	demolition		
Steel octagon box cover	red oak	277	installation		
Steel sealing conduit	white oak	277	installation kit		
locknut	Stripping		light kit		
Stem wall	forms	45	lighting panel		
Step flashing	soil	42	panel		
copper	Stripping paint		panel, acoustical		
Stile & rail doors	labor	447			

Texture, drywall.....	244	gloss & seal.....	304	Tileboard molding		Towel ring.....	369
ceiling.....	245	granite.....	295	vinyl.....	264	Track, patio door.....	216
spray.....	244, 246	granite floor.....	295	Tilt double-hung windows...	163	TrafficMaster laminate	
Textured ceiling panels...	257	grout.....	290	Timberline Ultra.....	131	flooring.....	280
Textured lap siding.....	111	grout, sanded.....	303	Timbertex.....	131	Transit mix concrete.....	47
Texturing paint additive		installation.....	289	Timer		Transition reducer strip	
Perlite.....	473	marble.....	294	in-wall, spring wound....	416	vinyl flooring.....	288
The Association of Bay Area		marble floor.....	294	Timer switch.....	366	Transition strip	
Governments.....	480	mortar.....	302	Tin		carpet to tile.....	288
Themes sheet vinyl		mosaic ceramic.....	300	repair shingles.....	144	oak to tile.....	288
flooring.....	283	natural cork.....	289	TJI		Trap, lavatory	
Thermal expansion tank....	386	non-sanded dry grout....	303	joists.....	65	remove & replace.....	346
Thermal sill.....	195	parquet floor.....	278	T-molding.....	276	Trash	
Thermoplastic siding.....	107	paver.....	295	bamboo.....	276	bins.....	30
Thermostat		Place n Press floor.....	285	hardwood.....	275	Trash compactor	
floor warming system...	301	polyethylene membrane...	304	wood floor.....	275	removal.....	311
Thermostat cable.....	413	quarry.....	295	Toggle switch		Trash pump.....	520
THHN copper wire		reducer strip.....	300	AC quiet.....	414	Travertine	
gauge.....	412	repair, mortar.....	302	Toilet base plate cover....	351	floor tile.....	295
Thin-set mortar.....	302	resilient, demolition.....	36	Toilet bowl		stone tile.....	294
CustomBlend.....	302	roofing.....	140	gasket.....	351	Treads	
Thompson's.....	470	rubber studded.....	286	reset.....	346	concrete, finishing.....	50
Thompsonized decking		Saltillo ceramic floor....	295	Toilet fill valve		Treatment	
lumber.....	434	sealer.....	303	anti-siphon.....	351	wood.....	470
Thoro.....	475	sealer, high-gloss.....	303	remove & replace.....	346	Tree removal.....	30
Thorseal protective		setting with adhesive....	290	Toilet flange		Trenchers	
coating.....	475	setting with mortar.....	290	cast iron.....	351	rental.....	40
Threaded conduit body....	411	slate floor.....	295	Toilet paper holder.....	369	Trenching.....	42
Three gang box		thin-set mortar.....	289	Toilet repair kit.....	352	hand.....	41
Super Blue,		travertine floor.....	295	Toilet seat		Trim	
non-metallic.....	402	travertine stone.....	294	molded wood.....	352	aluminum siding.....	114
Threshold		tumbled marble listello..	296	plastic open-front.....	352	bamboo flooring.....	276
ceramic.....	297	tumbled slate.....	296	wood.....	352	door.....	194
high boy.....	195	tumbled stone.....	296	Toilet supply line.....	351	fiber cement siding.....	112
marble.....	296	vinyl composition....	285-286	Toilet tank bolt kit.....	352	hardwood flooring.....	277
patio door.....	216	vinyl floor.....	284-285	Toilet tissue paper		heart pine flooring.....	277
Thru-the-wall utility fan...	364	wall.....	299	holder.....	300-301	painting labor.....	451, 459
Thrutone.....	139	wall, ceramic.....	299	Toilets		window.....	347
Thru-wall furnace, gas....	384	wood flooring.....	278	Comfort Height.....	351	wood flooring.....	275
Tie straps.....	493	Tile accessory set		dual flush.....	350	Trim enamel	
Ties		porcelain.....	301	hook-up kit for low-boy...	351	latex satin.....	472
collar.....	75	Tile adhesive		one-piece.....	350	Trim pack	
Tile		ceramic.....	289	two-piece.....	350	wood paneling.....	252
accessories, ceramic....	300	resilient.....	286	urinals.....	351	Trim paint.....	472
accessories,		rubber.....	286	wall-mount.....	351	eggshell.....	472
toilet tissue holder.....	300	stone.....	302	Tongue and groove siding		flat.....	474
accessories,		thin-set.....	302	cedar.....	109	Trimmers.....	75
toothbrush holder.....	301	vinyl.....	286	Tools		Trimming, trench bottom...	41
accessories, towel bar...	301	Tile adhesive caulk		ceramic tile.....	287	Trine.....	416
acoustic, demolition.....	35	ceramic.....	303	drywall.....	249-251	Triple-track storm	
anti-fracture membrane...	301	Tile backer.....	245	glazing.....	171	doors.....	204-205
anti-fracture membrane		Tile backer tape.....	249	roof repair.....	136	Troffer fluorescent fixtures	
kit.....	303	Tile backerboard.....	291	spline.....	168	LED.....	258
backerboard.....	291	Tile cutter		Toothbrush & tumbler		parabolic.....	258
bullnose, ceramic....	297-298	vinyl.....	287	holder.....	301	U-lamp.....	258
carpet.....	304	Tile flooring		Toothbrush holder.....	369	Trowel	
ceiling.....	254	cork.....	271	porcelain.....	301	drywall.....	250
ceiling, acoustical.....	253	Tile Perfect.....	303	Top		outside corner.....	250
ceiling, tin design.....	254	Tile repair		laminated plastic ...	319-320	Trowel finishing, concrete...	50
ceiling, wood fiber.....	254	mortar.....	302	Topping compound		Troweling machine	
ceramic caulk.....	303	mortar, underwater.....	303	wallboard.....	246	rental.....	40
ceramic floor.....	291-294	Tile tool		Topping, concrete.....	51	Trowels	
ceramic floor & wall.....	293	ceramic.....	287	Topsoil, excavation.....	42	margin notch.....	287
ceramic wall.....	297, 299	Tile tub wall.....	347	Torsion springs.....	223	notched.....	287
ceramic, demolition.....	36	Tile underlayment		Touch control lavatory		pointing.....	287
clay, roofing.....	139	Aqua-Tough.....	291	faucet.....	355	Tru-Glaze 4508 epoxy gloss	
concrete roof.....	140	Tile, ceiling		Touch-up kit		coating.....	476
demolition.....	311	zero clearance grid		spray texture.....	244	Trusses	
edge protection.....	299	system.....	255	wood floor.....	274	fink.....	76
finish.....	303	Tileboard		Towel bar.....	369	gable.....	76
floor.....	295	batten.....	251	ceramic.....	301	roof.....	76
glazed ceramic.....	299	embossed.....	251	porcelain.....	301	T-square	
glazed porcelain.....	292					drywall.....	250

T-straps	493	Underlayment & floor patch	282	Vanity cabinet	362	screen	89
T-top roof exhaust vent	145	Undermount sink	353	mirrored with marble top	362	soffit	89
Tub		Underwater tile repair mortar	303	Vanity mirror	366	under eave	89
laundry	329	Unfaced fiberglass batt insulation	84	Vanity top		VentSure ridge vent	144
utility laundry, kit	329	Universal hub bolt-on A type	418	granite	361	Vermiculite insulation	87
Tub & shower faucet single control	349	Urethane roof, spray foam	140	Neptune shell marble	360	Vertical discharge bath fan	363
Tub door bypass	347	Urinals		Newport cultured marble	360	ValueTest	363
Tub faucet	349-350	Dover	351	oval bowl cultured marble	360-361	Vertical discharge utility fan	363
Tub, bath removal	346	USG	245, 254	rectangular cultured marble	360	Vibrators rental	40
Tub, laundry hose	330	USG Interiors	257, 291	shell bowl cultured marble	360-361	Victorian base molding hardwood	259
overflow tube	330	Utilatub laundry tub	329	Vanity top and bowl cultured marble	361	Victorian lavatory faucet	357
Tubular skylights	172	Utility access door	248	Vapor barrier	41, 81, 279	Viewer door	214
Tuf-Tex spray texture	246	Utility bowl sink	330	blanket insulation	82	Villeta faucet	354
Tumbled tile		Utility cabinets		paper	87	Vinyl	
marble listello	296	birch	313	perm rating	82	bay windows	158
slate	296	finished	316	vapor-resistant coating	82	circular windows	159
stone	296	maple	317	Vapor retarder	92	door bottom	196
Tumbler & toothbrush holder	301	oak	315, 317	Varathane		double-hung replacement windows	157
Tung oil	471	red oak	314	exterior classic clear	469	fascia	108
Turbine vent roof	91, 146	Utility fan thru-the-wall	364	exterior clear finish	469	garden windows	158
Turned spindle deck rail	436	vertical discharge	363	interior classic clear	469	hopper windows	159
Twinfast	249	Utility laundry tub kit	329	oil-based floor finish	469	jalousie windows	159
Two-gang box		Utility sink	330	Varnish		patch	281
Super Blue, non-metallic	402	Utility tub kit	329	marine spar	468	screen doors	203
Two-handle lavatory faucet	356			Velux	172-173	siding	107
Type X gypsum board	243			Veneer base board	245	siding removal	106
Tyvec suit	518			Veneer plaster	246	siding repair	105
Tyvek house wrap	88			Vent		single-hung windows	158
		V		plumbing	370	soffit	108
		V siding		soffit	89	Vinyl composition tile	285-286
		pine	108	Vent channel		Vinyl drywall	
		Vacuum		rafter bay	88	outside corner bead	248
		HEPA	520	Vent kit		Vinyl floor tile	284-285
		Valance		bath	366	Vinyl floor tile, slip-retardant	285
		cabinet	312, 315	Vent, roof		Vinyl flooring	
		Valley flashing		dormer	144	removal	274
		aluminum	141	ridge	144-145	roll	282-283
		roll	143	T-top exhaust	145	sheet	282-283
		Valspar	468, 471	turbine	146	transition reducer strip	288
		ValueTest exhaust fan	362	waterproofing	130	Vinyl flooring tools	
		ValueTest vertical discharge bath fan	363	Vented range hood	336	roller, extendable	287
		ValuSeries		Ventilation		Vinyl sheet flooring	283
		pointing trowel	287	attic	83	Vinyl siding	
		Valve lines	358	crawl space	82	mounting block	96
		Valves		roof	83	trim pieces	96
		angle	351	Ventilator		Vinyl tile	
		flush, Sloan Royal	351	bath	366	adhesive	286
		toilet, remove & replace	346	Ventilator retrofit		cutter	287
		wall stop	351	heat recovery	386	Vinyl tile cutter	287
		Vance Industries	327	Ventilators		Vinyl tileboard molding	264
		Vanguard hardwood flooring	276	power	92	Vinyl wall base	
		Vanity		Venting skylights	173	dryback	288
		Arkansas	359	Ventlite doors		self-stick	289
		Charleston	358	fiberglass exterior	201	Vinyl-clad	
		Danville	359	steel exterior	199	wood awning windows	160
		Kingston	358	Vents		wood casement windows	160
		maple	359	attic	91	wood windows	159
		Monterey	359	cedar	90		
		oak	358-359	continuous	89		
		solid surface sink top	361	dormer	90		
		Springfield	358	eave	90		
		Virginia	359	foundation	88		
		with drawer	359	gable	89-90		
		with marble top	361-362	louvered	90		
				redwood	90		
				ridge	90		
				roof turbine	91		
						W	
						Waferboard	111
						Wainscot	
						tile	290
						Wainscot paneling	253

Walkway demolition..... 32	Wall tile ceramic..... 297, 299	hygrometer..... 498	Watertight conduit hub.... 410
forms..... 50	Wallboard demolition..... 35, 312	insulation..... 499	Watts Radiant..... 301
Walkway forms..... 44	L-trim..... 248	paneling..... 500	Wave bath light fixture.... 421
Walkways concrete..... 50	mold resistant..... 243	plaster..... 499	Wax bowling alley..... 471
Wall braces..... 67, 493	painting..... 463-464	stucco..... 499	paste..... 471
fireblocks..... 68	primer..... 246	wallboard..... 499	Wax toilet bowl gasket ... 351
opening, breakthrough ... 72	sander..... 250	wallcovering..... 500	Weather head..... 412
plates..... 67	texture spray..... 244	wood..... 499	PVC..... 402
straightening..... 494	Wallboard stilts..... 250	Water damage, dryout, structural drying	Weatherproof blank cover
tub..... 347	Wallcovering designer panel..... 252	air movers..... 502	non-metallic..... 408
Wall & floor tile ceramic..... 293	Wall-mount sink..... 353	ceilings..... 502	Weatherproof conduit box... 407
Wall and ceiling panel FRP..... 253	Wall-mount lantern curved glass..... 423	hardwood flooring..... 503	Weatherproof electrical box 2 gang..... 407
Wall and ceiling repair.... 227	Wall-mounted lavatory removal..... 353	negative air scrubbers... 503	Weatherproof lampholder & cover..... 408
Wall base molding..... 280	Walls adding..... 241	walls..... 502	Weatherproofing..... 88
rubber..... 288	concrete..... 48	Water dispenser..... 329	Weather-resistant wood coating..... 468
self-stick..... 289	demolition..... 31	Water extraction..... 511	WeatherSide siding..... 113
strip, vinyl..... 289	painting... 460-461, 463-465	carpet..... 511	Weatherstripping aluminum, adjustable ... 196
thermoplastic..... 288	partition, adding..... 265	hard surface..... 511	foam..... 196
vinyl..... 288	removal..... 239	Water Extraction..... 509	garage door..... 223
Wall bracing..... 492	setting with adhesive..... 290	Water hammer..... 373	magnetic..... 196
Wall cabinets..... 313-315	setting with mortar..... 290	arrester..... 387	vinyl, remove & replace... 196
end panel..... 315	staining..... 465	Water heater..... 374	window seal sets..... 172
finished..... 317	tile..... 290	100-gallon commercial... 385	Weco..... 303
oak..... 317	Warming system ceramic tile floor..... 301	Ariston..... 387	Welded handy box..... 404
square..... 316	thermostat..... 301	bracing..... 492	Welded square box..... 405
washer dryer..... 315	Wash down manhours..... 447	connection..... 492	Welded wire mesh..... 46
Wall cavity dryer..... 519	Washer kitchen sink basket strainer..... 329	electric..... 386-387	Western red cedar siding..... 108
Wall control switch..... 366	Washer dryer wall cabinets..... 315	electric, tankless..... 387	Westminster Ceramics ... 296
Wall demolition..... 32	Washing masonry..... 115	FVIR..... 385	Wet location conduit box cover..... 408
Wall enamel latex satin..... 472	pressure..... 448	gas..... 385	Wet location receptacle cover GFCI..... 408
Wall exhaust fan chain-operated..... 364	Washing, paint prep manhours..... 447	gas fired..... 385	Wet patch roof cement... 135
Wall finish demolition, wet..... 512	Waste disposal..... 30	gas, tankless..... 387	rubber..... 135
Wall forms, concrete.... 44, 48	Watco..... 468	high altitude..... 385	Wet-Stick roof cement.... 135
Wall framing..... 57	Water blasting..... 115	oil fired..... 385	Wheel glass cutters..... 171
Wall furnace, gas..... 384	extraction..... 509	point-of-use..... 387	Wheel loader rental..... 29, 40
Wall insulation..... 80	Water Claw..... 511	PowerStream..... 387	Wheelbarrow..... 520
Wall kit bathtub..... 347	Water closet flange, cast iron..... 351	power-vent..... 385	Whirlpool bath heater..... 347
Wall lantern..... 423	toilet..... 350	propane..... 385	Whirlpool tub apron..... 347
Wall light opal glass..... 421	Water damage cleanup..... 504	propane fired..... 385	White cement..... 114
Wall louvers..... 91	contaminated floodwater..... 496	tall boy..... 385	White Diamond bowling alley wax..... 471
Wall materials ceiling tile..... 236	dryout..... 495	Water pipe remove & replace..... 388	White oak strip flooring..... 277
drywall..... 227	restorative drying..... 495	Water pump..... 520	White wash pickling stain... 468
gypsum wallboard..... 227	Water damage and mold remediation..... 495	Water resistant gypsum board..... 243	Whole house fans..... 91
lath and plaster..... 227	insurance coverage..... 495	Water Seal waterproofer... 470	Williamsburg lavatory faucet..... 356
wood paneling..... 235	(OSHA)..... 496	Water shield..... 88	Wilsonart counters..... 318
Wall oven..... 335	personal protective gear..... 496	Water supply, low water pressure..... 373	Wind clips..... 140
double..... 335	Water damage, dryout air movers..... 498	Water surge shock absorber..... 387	Window demolition, wet..... 514
Wall paint..... 472	basement..... 500	Water table..... 38	drip cap..... 141
eggshell..... 472	concrete block..... 500	Water-based primer..... 473	framing..... 69
latex..... 472	dehumidifiers..... 498	Water-based wood stain ... 468	screen..... 168
Wall plate coaxial cable..... 413	dessicants..... 498	Waterblasting manhours..... 448	straighten opening..... 494
decorator phone..... 413	electric system..... 501	masonry..... 115	Window bolt double-hung..... 166
single gang Decora..... 415	floor cover..... 500	Waterborne sanding sealer..... 469	Window glass remove & replace..... 170
single gang plastic..... 415	floors..... 500	Waterfall kitchen faucet... 326	Window grille systems.... 169
Wall registers, installation..... 377	gas and oil appliances... 501	Waterproofing concrete & masonry..... 475	Window guards..... 167
Wall stop..... 351		Waterproofing masonry walls..... 130	Window locks flip lock..... 171
Wall surround kit bathtub..... 347		material..... 135	key, sliding..... 171
tub..... 347		membrane..... 301	thumbscrew bar..... 171
Wall texture Sand-Texture..... 473		metal roof..... 135	
		paint, elastomeric..... 474	
		paper..... 88	
		roof vent..... 130	
		roof, remove & replace... 130	
		roof, repair..... 129	
		sealer..... 475	
		wood protector..... 470	

Window mullions	166	fixed aluminum	162	Wire brush	51	touch-up	274
Window openings		fixed octagonal	163	Wire mesh, welded	46	trim	275
closure, masonry wall ...	156	garden	158	Wireless door bell	416	Wood paneling trim pack ...	252
closure, wood frame	156	glass setting labor	170	Wiring residences		Wood preservative	
cut new	156	glazing putty		adding outlets and		443, 470-471	
Window operators		replacement	150	switches	394	copper	471
awning	166	grille sets, tilt sash	169	aluminum wiring	391	Termin-8	470
jalousie	166	heat loss and gain	147	ground wire	393	Wood protector	
Window painting		jalousie	159, 163	knob and tube wiring	391	clear	470
labor	466-467	louvered, aluminum	163	low voltage wiring	394	Wood shingle	
Window roof covers, bay ...	164	Low-E glass	147	non-metallic sheathed		patch	137
Window roofs	164-165	measure & cut glass	170	cable (Romex)	392	Wood siding	
Window screens	160	modern	147	smoke detectors	396	bevel	93
patch	168	octagonal, wood	163	Wonderboard tile		board and batten	98
spline	168	picture	162	backerboard	291	bungalow	93
Window shutters	167	removal	36, 156	Wood		clapboard	93
Window sill	165	replacement ... 155, 157	158	shakes	137	decay	93
ceramic	297	sash repair	151, 156	shingles	137	horizontal	97
Window trim		sash springs	166	siding removal	106	horizontal patterns	97
bath wall	347	sill, ceramic	297	Wood bleach kit	467	lap	93
Window wrap	141	size, reducing	156	Wood coating		moisture damage	93
Windows		storm	149, 165	weather-resistant	468	painting	93
adding or moving	153	trim removal	156	Wood conditioner	471	repair	93
aluminum	148	vinyl bay	158	Wood deck		vertical	97
aluminum single		vinyl custom	157	patch built-up roofing	132	vertical patterns	97
hung	160-161	vinyl double hung	157	staining	455	vertical tongue and	
aluminum sliding	161-162	vinyl garden	158	Wood doors		groove	97
aluminum, horizontal ...	161	vinyl hopper	159	entry	193	Wood stain	
awning	160	vinyl jalousie	159	screen	203	water-based	468
awning, aluminum	162	vinyl single hung	158	screen, installation	202	Wood toilet seat	352
bay	158	vinyl, replacement	157	screen, remove &		Wood treatment	470
bay, angle	164	vinyl-clad awning	160	replace	202	Wood window repair	149
building codes	148	vinyl-clad casement	160	Wood filler		Wood-burning furnace	384
casement	160	vinyl-clad		acrylic	277	Woodcore storm doors ...	205
casement bay	158	double- hung	159-160	Wood finish	467	Wool carpet	304
casement bow	164	vinyl-clad wood	159	penetrating	467	Wrap	
caulk	157	weatherstripping	172	Wood flooring	277	window	141
caulk removal	157	wood	147	adhesive	278		
circular, vinyl	159	wood, repair	149	hardwood	268		
counterweighted	152	wood, replacement	156	installation tools	277		
cut new opening	156	Wire		lamine	270		
double-hung	157, 163	bell	413	plank	276		
egress window	172	screen	438	softwood	268		
energy-efficiency		speaker	413	strip	268		
standards	148	thermostat cable	413	strips	275		
escape wells	172	type THHN copper	412	tile	278		
		UF cable	399				

X - Y - Z

X type gypsum board	243
Zinsser	470
ZPW clear wood	
preservative	471

Practical References for Builders

National Estimator Cloud



Generate professional construction estimates for all residential and commercial construction from your internet browser. Includes 10 Craftsman construction cost databases, over 40,000 labor and material costs for construction, in an easy-to-use format. Cost estimates are well-organized and thoroughly indexed to speed and simplify writing estimates for nearly any residential or light commercial construction project – new construction, improvement or repair. Convert the bid to an invoice – in either QuickBooks Desktop or QuickBooks Online. Access your estimates from anywhere and on any device with a Web browser. Monthly and one-time billing options available.

Visit <http://craftsman-book.com/national-estimator-cloud> for more details.

Construction Contract Writer



Relying on a “one-size-fits-all” boilerplate construction contract to fit your jobs can be dangerous — almost as dangerous as a handshake agreement. *Construction Contract Writer* lets you draft a contract in minutes that precisely fits your needs and the particular job, and meets both state and federal requirements. You just answer a series of questions — like an interview — to construct a legal contract for each project you take on. Anticipate where disputes could arise and settle them in the contract before they happen. Include the warranty protection you intend, the payment schedule, and create subcontracts from the prime contract by just clicking a box. Includes a feedback button to an attorney on the Craftsman staff to help should you get stumped. **No extra charge. \$149.95.** Download the *Construction Contract Writer* at <http://www.constructioncontractwriter.com>

Construction Forms for Contractors



This practical guide contains 78 useful forms, letters and checklists, guaranteed to help you streamline your office, manage your jobsites, gather and organize records and documents, keep a handle on your subs, reduce estimating errors, administer change orders and lien issues, monitor crew productivity, track your equipment use, and more. Includes accounting forms, change order forms, forms for customers, estimating forms, field work forms, HR forms, lien forms, office forms, bids and proposals, subcontracts, and more. All are also on the CD-ROM included, in Excel spreadsheets, as formatted Rich Text that you can fill out on your computer, and as PDFs.

360 pages, 8½ x 11, \$48.50

eBook (PDF) also available; \$24.25 at www.craftsman-book.com

Home Inspection Handbook

Every area you need to check in a home inspection — especially in older homes. Twenty complete inspection checklists: building site, foundation and basement, structural, bathrooms, chimneys and flues, ceilings, interior & exterior finishes, electrical, plumbing, HVAC, insects, vermin and decay, and more. Also includes information on starting and running your own home inspection business. **324 pages, 5½ x 8½, \$39.95**

eBook (PDF) also available, \$19.98 at www.craftsman-book.com

Craftsman eLibrary



Craftsman's eLibrary license gives you immediate access to 60+ PDF eBooks in our bookstore for 12 full months! **You pay only one low price. \$129.99.** Visit www.craftsman-book.com for more details.

Cabinetmaking: From Design To Finish

Every aspect of cabinetmaking, from layout, through joinery, to finishing techniques. Gives illustrated instructions for designing cabinets to fit the kitchen workcenter; create dado, mortise, tenon, lap and dowel joints; make frames and panels; construct cabinets; and install cabinet hardware. **416 pages, 5½ x 8½, \$22.00**

National Appraisal Estimator



An Online Appraisal Estimating Service. Produce credible single-family residence appraisals – in as little as five minutes. A smart resource for appraisers using the cost approach. Reports consider all significant cost variables and both physical and functional depreciation.

Visit www.craftsman-book.com/national-appraisal-estimator-online-software for more information.

National Painting Cost Estimator

A complete guide to estimating painting costs for just about any type of residential, commercial, or industrial painting, whether by brush, spray, or roller. Shows typical costs and bid prices for fast, medium, and slow work, including material costs per gallon, square feet covered per gallon, square feet covered per manhour, labor, material, overhead, and taxes per 100 square feet, and how much to add for profit.

448 pages, 8½ x 11, \$98.00. Revised annually

eBook (PDF) also available; \$49.00 at www.craftsman-book.com

National Construction Estimator

Current building costs for residential, commercial, and industrial construction. Estimated prices for every common building material. Provides manhours, recommended crew, and gives the labor cost for installation.

672 pages, 8½ x 11, \$97.50. Revised annually

eBook (PDF) also available; \$48.75 at www.craftsman-book.com



Roofing Construction & Estimating

Detailed, step-by-step instructions, with photographs and diagrams, for installing, repairing and estimating nearly every type of roof covering available today for residential and commercial structures: asphalt shingles, roll roofing, wood shingles and shakes, clay tile, slate, metal, built-up, elastomeric, TPO and more. Provides guidance on sheathing, synthetic and felt underlayment, as well as tips and tricks from an experienced pro for dealing with those difficult points on a roof that are prone to leaks, such as valleys and roof penetrations. For each roofing type, instructions are provided for estimating material quantities and labor costs, with formulas, easy-to-follow examples and sample estimates for you to test your skill. Use these methods to create reliable estimates that will help insure a profit on every job you take. **448 pages, 8½ x 11, \$62.50**

eBook (PDF) also available, \$31.25 at www.craftsman-book.com



Profits in Buying & Renovating Homes

Step-by-step instructions for selecting, repairing, improving, and selling highly profitable “fixer-uppers.” Shows which price ranges offer the highest profit-to-investment ratios, which neighborhoods offer the best return, practical directions for repairs, and tips on dealing with buyers, sellers, and real estate agents. Shows you how to determine your profit before you buy, what “bargains” to avoid, and how to make simple, profitable, inexpensive upgrades. **304 pages, 8½ x 11, \$24.75**



National Electrical Estimator


This year's prices for installation of all common electrical work: conduit, wire, boxes, fixtures, switches, outlets, loadcenters, panelboards, raceway, duct, signal systems, and more. Provides material costs, manhours per unit, and total installed cost. Explains what you should know to estimate each part of an electrical system.

552 pages, 8½ x 11, \$97.75. Revised annually

eBook (PDF) also available; \$48.88 at www.craftsman-book.com



Renovating & Restyling Older Homes



Any builder can turn a run-down old house into a showcase of perfection — if the customer has unlimited funds to spend. Unfortunately, most customers are on a tight budget. They usually want more improvements than they can afford — and they expect you to deliver. This book shows how to add economical improvements that can increase the property value by two, five or even ten times the cost of the remodel. Sound impossible? Here you'll find the secrets of a builder who has been putting these techniques to work on Victorian and Craftsman-style houses for twenty years. You'll see what to repair, what to replace and what to leave, so you can remodel or restyle older homes for the least amount of money and the greatest increase in value. **416 pages, 8½ x 11, \$33.50**

Craftsman's Construction Installation Encyclopedia

Step-by-step installation instructions for just about any residential construction, remodeling or repair task, arranged alphabetically, from *Acoustic tile* to *Wood flooring*. Includes hundreds of illustrations that show how to build, install, or remodel each part of the job, as well as manhour tables for each work item so you can estimate and bid with confidence. Also includes a CD-ROM with all the material in the book, handy look-up features, and the ability to capture and print out for your crew the instructions and diagrams for any job. **792 pages, 8½ x 11, \$65.00**

eBook (PDF) also available; \$32.50 at www.craftsman-book.com

Fences & Retaining Walls Revised eBook

Everything you need to know to run a profitable business in fence and retaining wall contracting. Takes you through layout and design, construction techniques for wood, masonry, and chain link fences, gates and entries, including finishing and electrical details. How to build retaining and rock walls. How to get your business off to the right start, keep the books, and estimate accurately. The book even includes a chapter on contractor's math.

Available only as an eBook (PDF, EPUB & MOBI/Kindle); \$23.00 at www.craftsman-book.com

Plumber's Handbook Revised

This new edition explains simply and clearly, in non-technical, everyday language, how to install all components of a plumbing system to comply not only with recent changes in the International Plumbing Code and the Uniform Plumbing Code, but with the requirements of the Americans with Disabilities Act. Originally written for working plumbers to assure safe, reliable, code-compliant plumbing installations that pass inspection the first time, *Plumber's Handbook*, because of its readability, accuracy and clear, simple diagrams, has become the textbook of choice for numerous schools preparing plumbing students for the plumber's exams. Now, with a set of questions for each chapter, full explanations for the answers, and with a 200-question sample exam in the back, this handbook is one of the best tools available for preparing for almost any plumbing journeyman, master or state-required plumbing contracting exam. **384 pages, 8½ x 11, \$44.50**

eBook (PDF) also available; \$22.25 at www.craftsman-book.com

Finish Carpenter's Manual

Everything you need to know to be a finish carpenter: assessing a job before you begin, and tricks of the trade from a master finish carpenter. Easy-to-follow instructions for installing doors and windows, ceiling treatments (including fancy beams, corbels, cornices and moldings), wall treatments (including wainscoting and sheet paneling), and the finishing touches of chair, picture, and plate rails. Specialized interior work includes cabinetry and built-ins, stair finish work, and closets. Also covers exterior trim and porches. Includes manhour tables for finish work, and hundreds of illustrations and photos. **208 pages, 8½ x 11, \$32.50**

National Renovation & Insurance Repair Estimator



Current prices in dollars and cents for hard-to-find items needed on most insurance, repair, remodeling, and renovation jobs. All price items include labor, material, and equipment breakouts, plus special charts that tell you exactly how these costs are calculated. **488 pages, 8½ x 11, \$99.50. Revised annually**

eBook (PDF) also available; \$49.75 at www.craftsman-book.com

National Repair & Remodeling Estimator

The complete pricing guide for dwelling reconstruction costs. Reliable, specific data you can apply on every repair and remodeling job. Up-to-date material costs and labor figures based on thousands of jobs across the country. Provides recommended crew sizes; average production rates; exact material, equipment, and labor costs; a total unit cost and a total price including overhead and profit. Separate listings for high- and low-volume builders, so prices shown are specific for any size business. Estimating tips specific to repair and remodeling work to make your bids complete, realistic, and profitable.

528 pages, 8½ x 11, \$98.50. Revised annually

eBook (PDF) also available; \$49.25 at www.craftsman-book.com

Builder's Guide to Accounting Revised

Step-by-step, easy-to-follow guidelines for setting up and maintaining records for your building business. This practical guide to all accounting methods shows how to meet state and federal accounting requirements, explains the new depreciation rules, and describes how the Tax Reform Act can affect the way you keep records. Full of charts, diagrams, simple directions and examples to help you keep track of where your money is going. Recommended reading for many state contractor's exams. Each chapter ends with a set of test questions, and a CD-ROM included FREE has all the questions in interactive self-test software. Use the Study Mode to make studying for the exam much easier, and Exam Mode to practice your skills. **360 pages, 8½ x 11, \$43.00**

eBook (PDF) also available; \$21.50 at www.craftsman-book.com

Insurance Restoration Contracting: Startup to Success

Insurance restoration — the repair of buildings damaged by water, fire, smoke, storms, vandalism and other disasters — is an exciting field of construction that provides lucrative work that's immune to economic downturns. And, with insurance companies funding the repairs, your payment is virtually guaranteed. But this type of work requires special knowledge and equipment, and that's what you'll learn about in this book. It covers fire repairs and smoke damage, water losses and specialized drying methods, mold remediation, content restoration, even damage to mobile and manufactured homes. You'll also find information on equipment needs, training classes, estimating books and software, and how restoration leads to lucrative remodeling jobs. It covers all you need to know to start and succeed as the restoration contractor that both homeowners and insurance companies call on first for the best jobs. **640 pages, 8½ x 11, \$69.00**

eBook (PDF) also available; \$34.50 at www.craftsman-book.com

National Plumbing & HVAC Estimator

Manhours, labor and material costs for all common plumbing and HVAC work in residential, commercial, and industrial buildings. You can quickly work up a reliable estimate based on the pipe, fittings and equipment required. Every plumbing and HVAC estimator can use the cost estimates in this practical manual. Sample estimating and bidding forms and contracts also included. Explains how to handle change orders, letters of intent, and warranties. Describes the right way to process submittals, deal with suppliers and subcontract specialty work.

480 pages, 8½ x 11, \$98.25. Revised annually

eBook (PDF) also available; \$49.13 at www.craftsman-book.com

Basic Plumbing with Illustrations, Revised eBook

This completely-revised edition brings this comprehensive manual fully up-to-date with all the latest plumbing codes. It is the journeyman's and apprentice's guide to installing plumbing, piping, and fixtures in residential and light commercial buildings: how to select the right materials, lay out the job and do professional-quality plumbing work, use essential tools and materials, make repairs, maintain plumbing systems, install fixtures, and add to existing systems. Includes extensive study questions at the end of each chapter, and a section with all the correct answers.

Available only as an eBook (PDF) \$22.37 at www.craftsman-book.com

How to Succeed With Your Own Construction Business

Everything you need to start your own construction business: setting up the paperwork, finding the jobs, advertising, using contracts, dealing with lenders, estimating, scheduling, finding and keeping good employees, keeping the books, and coping with success. If you're considering starting your own construction business, all the knowledge, tips, and blank forms you need are here. **336 pages, 8½ x 11, \$28.50**

eBook (PDF) also available, \$14.25 at www.craftsman-book.com

Home Building Mistakes & Fixes



This is an encyclopedia of practical fixes for real-world home building and repair problems. There's never an end to "surprises" when you're in the business of building and fixing homes, yet there's little published on how to deal with construction that went wrong - where out-of-square or non-standard or jerry-rigged turns what should be a simple job into a nightmare. This manual describes jaw-dropping building mistakes that actually occurred, from disastrous misunderstandings over property lines, through basement floors leveled with an out-of-level instrument, to a house collapse when a siding crew removed the old siding. You'll learn the pitfalls the painless way, and real-world working solutions for the problems every contractor finds in a home building or repair jobsite. Includes dozens of those "surprises" and the author's step-by-step, clearly illustrated tips, tricks and workarounds for dealing with them. **384 pages, 8½ x 11, \$52.50**

eBook (PDF) also available; \$26.25 at www.craftsman-book.com

Painter's Handbook

Loaded with "how-to" information you'll use every day to get professional results on any job: the best way to prepare a surface for painting or repainting; selecting and using the right materials and tools (including airless spray); tips for repainting kitchens, bathrooms, cabinets, eaves and porches; how to match and blend colors; why coatings fail and what to do about it. Lists 30 profitable specialties in the painting business. **320 pages, 8½ x 11, \$33.00**

Markup & Profit: A Contractor's Guide, Revised

In order to succeed in a construction business, you have to be able to price your jobs to cover all labor, material and overhead expenses, and make a decent profit. But calculating markup is only part of the picture. If you're going to beat the odds and stay in business — profitably, you also need to know how to write good contracts, manage your crews, work with subcontractors and collect on your work. This book covers the business basics of running a construction company, whether you're a general or specialty contractor working in remodeling, new construction or commercial work. The principles outlined here apply to all construction-related businesses. You'll find tried and tested formulas to guarantee profits, with step-by-step instructions and easy-to-follow examples to help you learn how to operate your business successfully. Includes a link to free downloads of blank forms and checklists used in this book. **336 pages, 8½ x 11, \$52.50**

eBook (EPUB, MOBI for Kindle) also available; \$39.95 at www.craftsman-book.com



Writing contracts that comply with law in your state isn't easy. A contract that doesn't comply could leave you with no way to collect.

Construction Contract Writer has you covered. Download a trial today:

www.constructioncontractwriter.com



Craftsman Book Company
6058 Corte del Cedro
Carlsbad, CA 92011

Call me
1-800-829-8123
Fax (760) 438-0398

In A Hurry?

We accept phone orders charged to your

☐ Visa, ☐ MasterCard, ☐ Discover or ☐ American Express

Card# _____

Exp. date _____ CVV# _____ Initials _____

Tax Deductible: Treasury regulations make these references tax deductible when used in your work. Save the canceled check or charge card statement as your receipt.

Order online: www.craftsman-book.com

Name _____
e-mail address (for order tracking and special offers) _____
Company _____
Address _____
City/State/Zip _____ ☐ This is a residence
Total enclosed _____ (In California add 7.5% tax)

*Free Media Mail shipping, within the US,
when your check covers your order in full.*

10-Day Money Back Guarantee

Prices subject to change without notice

- | | |
|---|--|
| ☐ 43.00 Builder's Guide to Accounting Revised | ☐ 97.75 National Electrical Estimator |
| ☐ 22.00 Cabinetmaking: From Design to Finish | ☐ 98.00 National Painting Cost Estimator |
| ☐ 48.50 Construction Forms for Contractors | ☐ 98.25 National Plumbing & HVAC Estimator |
| ☐ 65.00 Craftsman's Construction Installation Encyclopedia | ☐ 99.50 National Renovation & Insurance Repair Estimator |
| ☐ 32.50 Finish Carpenter's Manual | ☐ 98.50 National Repair & Remodeling Estimator |
| ☐ 52.50 Home Building Mistakes & Fixes | ☐ 33.00 Painter's Handbook |
| ☐ 39.95 Home Inspection Handbook | ☐ 44.50 Plumber's Handbook, Revised |
| ☐ 28.50 How to Succeed With Your Own Construction Business | ☐ 24.75 Profits in Buying & Renovating Homes |
| ☐ 69.00 Insurance Restoration Contracting: Startup to Success | ☐ 33.50 Renovating & Restyling Older Homes |
| ☐ 52.50 Markup & Profit: A Contractor's Guide, Revisited | ☐ 62.50 Roofing Construction & Estimating |
| ☐ 97.50 National Construction Estimator | ☐ 98.75 National Home Improvement Estimator |